Instructor's Manual

for

C++ How to Program, 3/e

Deitel, Deitel & Nieto

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

C++ How to Program: Third Edition
Instructor's Manual Contents

	Preface	iii
Chapter 1	Introduction to Computers and C++ Programming: Solutions	1
Chapter 2	Control Structures: Solutions	15
Chapter 3	Functions: Solutions	66
Chapter 4	Arrays Solutions:	120
Chapter 5	Pointers and Strings: Solutions	170
Chapter 6	Classes and Data Abstraction: Solutions	235
Chapter 7	Classes: Part II: Solutions	264
Chapter 8	Operator Overloading: Solutions	276
Chapter 9	Inheritance: Solutions	299
Chapter 10	Virtual Functions and Polymorphism: Solutions	318
Chapter 11	C++ Stream Input/Output: Solutions	333
Chapter 12	Templates: Solutions	348
Chapter 13	Exception Handling: Solutions	359
Chapter 14	File Processing: Solutions	370
Chapter 15	Data Structures: Solutions	390
Chapter 16	Bits, Characters, Strings and Structures: Solutions	498
Chapter 17	The Preprocessor: Solutions	524
Chapter 18	C Legacy Code Topics: Solutions	531
Chapter 19	Class `string` and String Stream Processing: Solutions	541
Chapter 20	Standard Template Library (STL): Solutions	559
Chapter 21	Standard C++ Language Additions: Solutions	565
Appendix	C++ Multimedia Cyber Classroom Solutions Provided on CD	573

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Preface

Thank you for considering and/or adopting our text *C++ How to Program: Third Edition.* If you have not read the preface to *C++ How to Program: Third Edition*, please do so. The preface contains a careful walkthrough of the book's key features, including our new Unified Modeling Language™ (UML™) case study, which carefully introduces the reader to the UML and object-oriented design (OOD). Students are presented with a detailed problem statement and guided through a simplified, UML-based object-oriented design process. The complete 1000-line C++ program solution for the case study is presented in the book and provided on the CD-ROM in the back of the textbook.

We have worked hard to produce a textbook and ancillaries that we hope you and your students will find valuable. The following ancillary resources are available:

- *C++ How to Program: Third Edition's 250 program examples* are included on the CD-ROM in the back of the textbook. This helps instructors prepare lectures faster and helps students master C++. The examples are also available for download at **www.deitel.com**. When extracting the source code from the ZIP file, you must use a ZIP-file reader such as WinZip (**www.winzip.com**) or PKZIP (**www.pkware.com**) that understands directories. The file should be extracted into a separate directory (e.g., **cpphtp3e_examples**).
- *Microsoft Visual C++ 6 Introductory Edition software* is provided on the textbook's CD-ROM. This software allows students to edit, compile and debug C++ programs. We have provided at no charge a short Visual C++ 6 tutorial (in Adobe PDF format) on our Web site (**www.deitel.com**).
- This *C++ How to Program: Third Edition Instructor's Manual* on CD contains answers to most of the exercises in the textbook. The programs are separated into directories by chapter and exercise number.
- The optional *C++ Multimedia Cyber Classroom: Third Edition* is an interactive multimedia CD version of the book for Windows. Its features include audio walkthroughs of programs, section review questions (which are available only on the *C++ Multimedia Cyber Classroom: Third Edition*), a text-search engine, the ability to execute example programs, and more. The *Cyber Classroom* helps students get more out of their courses. The *Cyber Classroom* is also useful for students who miss a lecture and have to catch up quickly. The *Cyber Classroom* is available as a stand-alone product (see the last few pages of the textbook for the ISBN number) or bundled with the textbook (at a discount) in a product called *The Complete C++ Training Course: Third Edition* (ISBN# 0-13-089563-6).
- *Companion Web site* (**www.prenhall.com/deitel**) provides instructor and student resources. Instructor resources include textbook appendices (e.g., Appendix D, "C++ Internet and Web Resources") and a syllabus manager for lesson planning. Student resources include chapter objectives, true/false questions, chapter highlights, reference materials and a message board.
- Customizable *Powerpoint Instructor Lecture Notes*, with many complete features including source code, and key discussion points for each program and major illustration. These lecture notes are available for instructors and students at no charge at our Web site **www.deitel.com**.
- *Lab Manual* (available Spring 2001)—a for-sale item containing closed-lab sessions.

We would sincerely appreciate your questions, comments, criticisms and corrections addressed to us at:

deitel@deitel.com

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

We will respond immediately. Please read the latest copy of the *Deitel Buzz* (published every April and November) for information on forthcoming Deitel publications, ancillaries, product options and ordering information. To receive the *Deitel Buzz*, please contact Jennie Burger (**jennie_burger@prenhall.com**).

Watch our Deitel & Associates, Inc. Web site (**www.deitel.com**) and our Prentice Hall Web site (**www.prenhall.com/deitel**) for the latest publication updates.

We would like to thank the extraordinary team of publishing professionals at Prentice Hall who made *C++ How to Program: Third Edition* and its ancillaries possible. Our Computer Science editor, Petra Recter, worked closely with us to ensure the timely availability and professional quality of these ancillaries.

We would also like to thank two of our student interns—Aftab Bukhari (a Computer Science major at Boston University) and Jason Rosenfeld (a Computer Science major at Northwestern University) for their assistance in preparing this Instructor's Manual.

Harvey M. Deitel
Paul J. Deitel

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

1

Introduction to Computers and C++ Programming Solutions

SOLUTIONS

1.10 Categorize each of the following items as either hardware or software:

a) CPU

ANS: hardware.

b) C++ compiler

ANS: software.

c) ALU

ANS: hardware.

d) C++ preprocessor

ANS: software.

e) input unit

ANS: hardware.

f) an editor program

ANS: software.

1.11 Why might you want to write a program in a machine-independent language instead of a machine-dependent language? Why might a machine-dependent language be more appropriate for writing certain types of programs?

ANS: Machine independent languages are useful for writing programs to be executed on multiple computer platforms. Machine dependent languages are appropriate for writing programs to be executed on a single platform. Machine dependent languages tend to exploit the efficiencies of a particular machine.

1.12 Fill in the blanks in each of the following statements:

a) Which logical unit of the computer receives information from outside the computer for use by the computer? _____.

ANS: input unit.

b) The process of instructing the computer to solve specific problems is called _____.

ANS: computer programming.

c) What type of computer language uses English-like abbreviations for machine language instructions? _____.

ANS: high-level language.

d) Which logical unit of the computer sends information that has already been processed by the computer to various devices so that the information may be used outside the computer? _____.

ANS: output unit.

e) Which logical unit of the computer retains information? _____.

ANS: memory unit and secondary storage unit.

f) Which logical unit of the computer performs calculations? _____.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS: arithmetic and logical unit.

g) Which logical unit of the computer makes logical decisions? _____.

ANS: arithmetic and logical unit.

h) The level of computer language most convenient to the programmer for writing programs quickly and easily is _____.

ANS: high-level language.

i) The only language that a computer can directly understand is called that computer's _____.

ANS: machine language.

j) Which logical unit of the computer coordinates the activities of all the other logical units? _____.

ANS: central processing unit.

1.13 Discuss the meaning of each of the following objects:

a) **`cin`**

ANS: This object refers to the standard input device that is normally connected to the keyboard.

b) **`cout`**

ANS: This object refers to the standard output device that is normally connected to the computer screen.

c) **`cerr`**

ANS: This object refers to the standard error device that is normally connected to the computer screen.

1.14 Why is so much attention today focused on object-oriented programming in general and C++ in particular?

ANS: Object-oriented programming enables the programmer to build reusable software components that model items in the real world. Building software quickly, correctly, and economically has been an elusive goal in the software industry. The modular, object-oriented design and implementation approach has been found to increase productivity 10 to 100 times over conventional programming languages while reducing development time, errors, and cost. C++ is extremely popular because it is a superset of the widely used C programming language. Programmers already familiar with C have an easier time learing C++.

1.15 Fill in the blanks in each of the following:

a) _____ are used to document a program and improve its readability.

ANS: comments

b) The object used to print information on the screen is _____.

ANS: **`cout`**

c) A C++ statement that makes a decision is _____.

ANS: **`if`**

d) Calculations are normally performed by _____ statements.

ANS: assignment

e) The _____ object inputs values from the keyboard.

ANS: **`cin`**

1.16 Write a single C++ statement or line that accomplishes each of the following:

a) Print the message **`"Enter two numbers"`**.

ANS:
```
cout << "Enter two numbers";
```

b) Assign the product of variables **`b`** and **`c`** to variable **`a`**.

ANS:
```
a = b * c;
```

c) State that a program performs a sample payroll calculation (i.e., use text that helps to document a program).

ANS:
```
// Sample Payroll Calculation Program
```

d) Input three integer values from the keyboard and into integer variables **`a`**, **`b`** and **`c`**.

ANS:
```
cin >> a >> b >> c;
```

1.17 State which of the following are *true* and which are *false*. If *false*, explain your answers.

a) C++ operators are evaluated from left to right.

ANS: False. Some operators are evaluated from left to right, while other operators are evaluated right to left.

b) The following are all valid variable names: **`_under_bar_`**, **`m928134`**, **`t5`**, **`j7`**, **`her_sales`**, **`his_account_total`**, **`a`**, **`b`**, **`c`**, **`z`**, **`z2`**.

ANS: True. All variables begin with an underscore or letter.

c) The statement **`cout << "a = 5;"`**; is a typical example of an assignment statement.

ANS: False. The statement is an output statement. **`a = 5;`** is output to the screen.

d) A valid C++ arithmetic expression with no parentheses is evaluated from left to right.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS: False. Arithmetic operators can appear in any order in an expression. Since multiplication, division, and modulus have higher precendence than addition and subtraction the statement cannot be true.

e) The following are all invalid variable names: **`3g`**, **`87`**, **`67h2`**, **`h22`**, **`2h`**.

ANS: False. **`h22`** is a valid variable name.

1.18 Fill in the blanks in each of the following:

a) What arithmetic operations are on the same level of precedence as multiplication? _____.

ANS: division and modulus.

b) When parentheses are nested, which set of parentheses is evaluated first in an arithmetic expression? _____.

ANS: innermost.

c) A location in the computer's memory that may contain different values at various times throughout the execution of a program is called a _____.

ANS: variable.

1.19 What, if anything, prints when each of the following C++ statements is performed? If nothing prints, then answer "nothing." Assume **`x = 2`** and **`y = 3`**.

a) **`cout << x;`**

ANS: `2`

b) **`cout << x + x;`**

ANS: `4`

c) **`cout << "x=";`**

ANS: `x=`

d) **`cout << "x = " << x;`**

ANS: `x = 2`

e) **`cout << x + y << " = " << y + x;`**

ANS: `5 = 5`

f) **`z = x + y;`**

ANS: nothing.

g) **`cin >> x >> y;`**

ANS: 23.

h) **`// cout << "x + y = " << x + y;`**

ANS: nothing.

i) **`cout << "\n";`**

ANS: A newline is output which positions the cursor at the beginning of the next line on the screen.

1.20 Which of the following C++ statements contain variables whose values are replaced?

a) **`cin >> b >> c >> d >> e >> f;`**

b) **`p = i + j + k + 7;`**

c) **`cout << "variables whose values are destroyed";`**

d) **`cout << "a = 5";`**

ANS: Parts (a) and (b).

1.21 Given the algebraic equation $y = ax^3 + 7$, which of the following, if any, are correct C++ statements for this equation?

a) **`y = a * x * x * x + 7;`**

b) **`y = a * x * x * ( x + 7 );`**

c) **`y = ( a * x ) * x * ( x + 7 );`**

d) **`y = (a * x) * x * x + 7;`**

e) **`y = a * ( x * x * x ) + 7;`**

f) **`y = a * x * ( x * x + 7 );`**

ANS: Parts (a), (d) and (e).

1.22 State the order of evaluation of the operators in each of the following C++ statements and show the value of **`x`** after each statement is performed.

a) **`x = 7 + 3 * 6 / 2 - 1;`**

ANS: `*, /, +, -, =, 15`

b) **`x = 2 % 2 + 2 * 2 - 2 / 2;`**

ANS: `%, *, /, +, -, =, 3`

c) **`x = ( 3 * 9 * ( 3 + ( 9 * 3 / ( 3 ) ) ) );`**

ANS: `*, /, +, *, *, 324`

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

1.23 Write a program that asks the user to enter two numbers, obtains the two numbers from the user and prints the sum, product, difference, and quotient of the two numbers.

```
// Exercise 1.23 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int num1, num2;  // declare variables

   cout << "Enter two integers: ";  // prompt user
   cin >> num1 >> num2;             // read values from keyboard

   // output the results
   cout << "The sum is " << num1 + num2
        << "\nThe product is " << num1 * num2
        << "\nThe difference is " << num1 - num2
        << "\nThe quotient is " << num1 / num2 << endl;

   return 0;  // indicate successful termination
}
```

```
Enter two integers: 8 22
The sum is 30
The product is 176
The difference is -14
The quotient is 0
```

1.24 Write a program that prints the numbers 1 to 4 on the same line with each pair of adjacent numbers separated by one space. Write the program using the following methods:

a) Using one output statement with one stream insertion operator.
b) Using one output statement with four stream insertion operators.
c) Using four output statements.

```
// Exercise 1.24 Solution
#include <iostream>

using std::cout;
using std::endl;

int main ()
{
   // Part A
   cout << "1 2 3 4\n";

   // Part B
   cout << "1 " << "2 " << "3 " << "4\n";

   // Part C
   cout << "1 ";
   cout << "2 ";
   cout << "3 ";
   cout << "4" << endl;

   return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
22  }
```

```
1 2 3 4
1 2 3 4
1 2 3 4
```

1.25 Write a program that asks the user to enter two integers, obtains the numbers from the user, then prints the larger number followed by the words "**is larger**." If the numbers are equal, print the message "**These numbers are equal**."

```
1  // Exercise 1.25 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int main()
9  {
10    int num1, num2;   // declaration
11
12    cout << "Enter two integers: ";  // prompt
13    cin >> num1 >> num2;             // input to numbers
14
15    if ( num1 == num2 )
16       cout << "These numbers are equal." << endl;
17
18    if ( num1 > num2 )
19       cout << num1 << " is larger." << endl;
20
21    if ( num2 > num1 )
22       cout << num2 << " is larger." << endl;
23
24    return 0;
25 }
```

```
Enter two integers: 22 8
22 is larger.
```

1.26 Write a program that inputs three integers from the keyboard and prints the sum, average, product, smallest and largest of these numbers. The screen dialogue should appear as follows:

```
Input three different integers: 13 27 14
Sum is 54
Average is 18
Product is 4914
Smallest is 13
Largest is 27
```

```
1  // Exercise 1.26 Solution
2  #include <iostream>
3
4  using std::cout;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
using std::endl;
using std::cin;

int main()
{
   int num1, num2, num3, smallest, largest;  // declaration

   cout << "Input three different integers: ";  // prompt
   cin >> num1 >> num2 >> num3;                 // input

   largest = num1;  // assume first number is largest

   if ( num2 > largest )  // is num2 larger?
      largest = num2;

   if ( num3 > largest )  // is num3 larger?
      largest = num3;

   smallest = num1;  // assume first number is smallest

   if ( num2 < smallest )
      smallest = num2;

   if ( num3 < smallest )
      smallest = num3;

   cout << "Sum is " << num1 + num2 + num3
        << "\nAverage is " << (num1 + num2 + num3) / 3
        << "\nProduct is " << num1 * num2 * num3
        << "\nSmallest is " << smallest
        << "\nLargest is " << largest << endl;

   return 0;
}
```

```
Input three different integers: 13 27 14
Sum is 54
Average is 18
Product is 4914
Smallest is 13
Largest is 27
```

1.27 Write a program that reads in the radius of a circle and prints the circle's diameter, circumference and area. Use the constant value 3.14159 for π. Do these calculations in output statements. (Note: In this chapter, we have discussed only integer constants and variables. In Chapter 3 we will discuss floating-point numbers, i.e., values that can have decimal points.)

```
// Exercise 1.27 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int radius;  // declaration

   cout << "Enter the circle radius: ";  // prompt
   cin >> radius;                        // input
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
14
15    cout << "Diameter is " << radius * 2.0
16         << "\nCircumference is " << 2 * 3.14159 * radius
17         << "\nArea is " << 3.14159 * radius * radius << endl;
18
19    return 0;
20 }
```

```
Enter the circle radius: 8
Diameter is 16
Circumference is 50.2654
Area is 201.062
```

1.28 Write a program that prints a box, an oval, an arrow and a diamond as follows:

```
*********          ***             *             *
*       *        *     *          ***           * *
*       *       *       *        *****         *   *
*       *       *       *          *          *     *
*       *       *       *          *         *       *
*       *       *       *          *          *     *
*       *       *       *          *           *   *
*       *        *     *           *            * *
*********          ***             *             *
```

```
1  // Exercise 1.28 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  main()
8  {
9     cout << "*********      ***         *         *\n"
10         << "*       *    *   *      *      ***       * *\n"
11         << "*       *   *     *     *****     *    *\n"
12         << "*       *   *     *       *      *     *\n"
13         << "*       *   *     *       *     *       *\n"
14         << "*       *   *     *       *      *     *\n"
15         << "*       *    *   *        *       *   *\n"
16         << "*       *     * *         *        * *\n"
17         << "*********      ***         *         *" << endl;
18
19    return 0;
20 }
```

1.29 What does the following code print?

```
cout << "*\n**\n***\n****\n*****\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS:

```
*
**
***
****
*****
```

1.30 Write a program that reads in five integers and determines and prints the largest and the smallest integers in the group. Use only the programming techniques you learned in this chapter.

```
// Exercise 1.30 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int num1, num2, num3, num4, num5, largest, smallest;

   cout << "Enter five integers: ";
   cin >> num1 >> num2 >> num3 >> num4 >> num5;

   largest = num1;
   smallest = num1;

   if ( num1 > largest )
      largest = num1;

   if ( num2 > largest )
      largest = num2;

   if ( num3 > largest )
      largest = num3;

   if ( num4 > largest )
      largest = num4;

   if ( num5 > largest )
      largest = num5;

   if ( num1 < smallest )
      smallest = num1;

   if ( num2 < smallest )
      smallest = num2;

   if ( num3 < smallest )
      smallest = num3;

   if ( num4 < smallest )
      smallest = num4;

   if ( num5 < smallest )
      smallest = num5;

   cout << "Largest is " << largest
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
         << "\nSmallest is " << smallest << endl;

   return 0;
}
```

```
Enter five integers: 88 22 8 78 21
Largest is 88
Smallest is 8
```

1.31 Write a program that reads an integer and determines and prints whether it is odd or even. (Hint: Use the modulus operator. An even number is a multiple of two. Any multiple of two leaves a remainder of zero when divided by 2.)

```
// Exercise 1.31 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int num;

   cout << "Enter a number: ";
   cin >> num;

   if ( num % 2 == 0 )
      cout << "The number " << num << " is even." << endl;

   if ( num % 2 != 0 )
      cout << "The number " << num << " is odd." << endl;

   return 0;
}
```

```
Enter a number: 73
The number 73 is odd.
```

1.32 Write a program that reads in two integers and determines and prints if the first is a multiple of the second. (Hint: Use the modulus operator.)

```
// Exercise 1.32 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int num1, num2;

   cout << "Enter two integers: ";
   cin >> num1 >> num2;

   if ( num1 % num2 == 0 )
      cout << num1 << " is a multiple of " << num2 << endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
17
18     if ( num1 % num2 != 0 )
19        cout << num1 << " is not a multiple of " << num2 << endl;
20
21     return 0;
22  }
```

```
Enter two integers: 22 8
22 is not a multiple of 8
```

1.33 Display a checkerboard pattern with eight output statements, then display the same pattern with as few output statements as possible.

```
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
```

```
1  // Exercise 1.33 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     // Eight output statements
10    cout << "* * * * * * * *\n";
11    cout << " * * * * * * * *\n";
12    cout << "* * * * * * * *\n";
13    cout << " * * * * * * * *\n";
14    cout << "* * * * * * * *\n";
15    cout << " * * * * * * * *\n";
16    cout << "* * * * * * * *\n";
17    cout << " * * * * * * * *\n\n";
18
19    // One output statement; 3 parts
20    cout << "* * * * * * * *\n * * * * * * * *\n* * * * * * * *\n"
21         << " * * * * * * * *\n* * * * * * * *\n  * * * * * * * *\n"
22         << "* * * * * * * *\n * * * * * * * *\n";
23
24    cout << endl;   // ensure everything is displayed
25
26    return 0;
27 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 * * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *

* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
  * * * * * * * *
* * * * * * * *
 * * * * * * * *
```

1.34 Distinguish between the terms fatal error and non–fatal error. Why might you prefer to experience a fatal error rather than a non–fatal error?

ANS: A fatal error causes a program to terminate prematurely. A nonfatal error occurs when the logic of the program is incorrect, and the program does not work properly. A fatal error is preferred for debugging purposes. A fatal error immediately lets you know there is a problem with the program, whereas a nonfatal error can be subtle and possibly go undetected.

1.35 Here is a peek ahead. In this chapter you learned about integers and the type **int**. C++ can also represent uppercase letters, lowercase letters and a considerable variety of special symbols. C++ uses small integers internally to represent each different character. The set of characters a computer uses and the corresponding integer representations for those characters is called that computer's *character set.* You can print a character by simply enclosing that character in single quotes as with

```
cout << 'A';
```

You can print the integer equivalent of a character using **static_cast** as follows:

```
cout << static_cast< int >( 'A' );
```

This is called a *cast* operation (we formally introduce casts in Chapter 2). When the preceding statement executes, it prints the value 65 (on systems that use the *ASCII character set*). Write a program that prints the integer equivalents of some uppercase letters, lowercase letters, digits and special symbols. At a minimum, determine the integer equivalents of the following: **A B C a b c 0 1 2 $ * + /** and the blank character.

```
1  // Exercise 1.35 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int main()
9  {
10    char symbol;
11
12    cout << "Enter a character: ";
13    cin >> symbol;
14
15    cout << symbol << "'s integer equivalent is "
16         << static_cast< int > ( symbol ) << endl;
17
18    return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}
```

```
Enter a character: A
A's integer equivalent is 65
```

1.36 Write a program that inputs a five-digit number, separates the number into its individual digits and prints the digits separated from one another by three spaces each. (Hint: Use the integer division and modulus operators.) For example, if the user types in **42339** the program should print

```
4   2   3   3   9
```

```
// Exercise 1.36 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int num;

   cout << "Enter a five-digit number: ";
   cin >> num;

   cout << num / 10000 << "   ";
   num = num % 10000;
   cout << num / 1000 << "   ";
   num = num % 1000;
   cout << num / 100 << "   ";
   num = num % 100;
   cout << num / 10 << "   ";
   num = num % 10;
   cout << num << endl;

   return 0;
}
```

```
Enter a five-digit number: 42339
4   2   3   3   9
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

1.37 Using only the techniques you learned in this chapter, write a program that calculates the squares and cubes of the numbers from 0 to 10 and uses tabs to print the following table of values:

```
number  square  cube
0       0       0
1       1       1
2       4       8
3       9       27
4       16      64
5       25      125
6       36      216
7       49      343
8       64      512
9       81      729
10      100     1000
```

```
1  // Exercise 1.37 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     int num;
10
11    num = 0;
12    cout << "\nnumber\tsquare\tcube\n"
13         << num << '\t' << num * num << '\t' << num * num * num << "\n";
14
15    num = num + 1;
16    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
17
18    num = num + 1;
19    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
20
21    num = num + 1;
22    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
23
24    num = num + 1;
25    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
26
27    num = num + 1;
28    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
29
30    num = num + 1;
31    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
32
33    num = num + 1;
34    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
35
36    num = num + 1;
37    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
38
39    num = num + 1;
40    cout << num << '\t' << num * num << '\t' << num * num * num << "\n";
41
42    num = num + 1;
43    cout << num << '\t' << num * num << '\t' << num * num * num << endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
44
45      return 0;
46   }
```

1.38 Give a brief answer to each of the following "object think" questions:

a) Why does this text choose to discuss structured programming in detail before proceeding with an in-depth treatment of object-oriented programming?

ANS: Objects are composed in part by structured program pieces.

b) What are the typical steps (mentioned in the text) of an object-oriented design process?

ANS: (1) Determine which objects are needed to implement the system. (2) Determine's each object's attributes. (3) Determine each object's behaviors. (4) Determine the interaction between the objects.

c) How is multiple inheritance exhibited by human beings?

ANS: Children. A child receives genes from both parents.

d) What kinds of messages do people send to one another?

ANS: People send messages through body language, speech, writings, email, telephones, etc.

e) Objects send messages to one another across well-defined interfaces. What interfaces does a car radio (object) present to its user (a person object)?

ANS: Dials and buttons that allow the user to select a station, adjust the volume, adjust bass and treble, play a CD or tape, etc.

1.39 You are probably wearing on your wrist one of the world's most common types of objects—a watch. Discuss how each of the following terms and concepts applies to the notion of a watch: object, attributes, behaviors, class, inheritance (consider, for example, an alarm clock), abstraction, modeling, messages, encapsulation, interface, information hiding, data members and member functions.

ANS: The entire watch is an object that is composed of many other objects (such as the moving parts, the band, the face, etc.) Watch attributes are time, color, band, style (digital or analog), etc. The behaviors of the watch include setting the time and getting the time. A watch can be considered a specific type of clock (as can an alarm clock). With that in mind, it is possible that a class called **`Clock`** could exist from which other classes such as watch and alarm clock can inherit the basic features in the clock. The watch is an abstraction of the mechanics needed to keep track of the time. The user of the watch does not need to know the mechanics of the watch in order to use it; the user only needs to know that the watch keeps the proper time. In this sense, the mechanics of the watch are encapsulated (hidden) inside the watch. The interface to the watch (its face and controls for setting the time) allows the user to set and get the time. The user is not allowed to directly touch the internal mechanics of the watch. All interaction with the internal mechanics is controlled by the interface to the watch. The data members stored in the watch are hidden inside the watch and the member functions (looking at the face to get the time and setting the time) provide the interface to the data.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Control Structures Solutions

Solutions

Exercises 2.14 through 2.38 correspond to Sections 2.1 through 2.12.
Exercises 2.39 through 2.63 correspond to Sections 2.13 through 2.21.

2.14 Identify and correct the error(s) in each of the following:

a)
```
if ( age >= 65 );
   cout << "Age is greater than or equal to 65" << endl;
else
   cout << "Age is less than 65 << endl";
```
ANS: The semicolon at the end of the `if` should be removed. The closing double quote after the second `endl` should be placed after `65`.

b)
```
if ( age >= 65 )
   cout << "Age is greater than or equal to 65" << endl;
else;
   cout << "Age is less than 65 << endl";
```
ANS: The semicolon after the `else` should be removed. The closing double quote after the second `endl` should be placed after `65`.

c)
```
int x = 1, total;
while ( x <= 10 ) {
   total += x;
   ++x;
}
```
ANS: Variable `total` should be initialized to `0`.

d)
```
While ( x <= 100 )
   total += x;
   ++x;
```
ANS: The `W` in `while` should be lowercase. The `while`'s body should be enclosed in braces `{}`.

e)
```
while ( y > 0 ) {
   cout << y << endl;
   ++y;
}
```
ANS: The variable `y` should be decremented (i.e., `--y;`) not incremented (`++y;`).

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.15 What does the following program print?

```
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   int y, x = 1, total = 0;

   while ( x <= 10 ) {
      y = x * x;
      cout << y << endl;
      total += y;
      ++x;
   }

   cout << "Total is " << total << endl;
   return 0;
}
```

```
1
4
9
16
25
36
49
64
81
100
Total is 385
```

For Exercises 2.16 to 2.19, perform each of these steps:

a) Read the problem statement.
b) Formulate the algorithm using pseudocode and top-down, stepwise refinement.
c) Write a C++ program.
d) Test, debug and execute the C++ program.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.16 Drivers are concerned with the mileage obtained by their automobiles. One driver has kept track of several tankfuls of gasoline by recording miles driven and gallons used for each tankful. Develop a C++ program that will input the miles driven and gallons used for each tankful. The program should calculate and display the miles per gallon obtained for each tankful. After processing all input information, the program should calculate and print the combined miles per gallon obtained for all tankfuls.

```
Enter the gallons used (-1 to end): 12.8
Enter the miles driven: 287
The miles / gallon for this tank was 22.421875

Enter the gallons used (-1 to end): 10.3
Enter the miles driven: 200
The miles / gallon for this tank was 19.417475

Enter the gallons used (-1 to end): 5
Enter the miles driven: 120
The miles / gallon for this tank was 24.000000

Enter the gallons used (-1 to end): -1

The overall average miles/gallon was 21.601423
```

ANS:

Top:

Determine the average miles/gallon for each tank of gas, and the overall miles/gallons for an arbitrary number of tanks of gas.

First refinement:

Initialize variables.
Input the gallons used and the miles driven, and calculate and print the miles/gallon for each tank of gas. Keep track of the total miles and total gallons.
Calculate and print the overall average miles/gallon.

Second refinement:

Initialize totalGallons to zero
Initialize totalMiles to zero

Input the gallons used for the first tank

While the sentinel value (-1) has not been entered for the gallons
    Add gallons to the running total in totalGallons
    Input the miles driven for the current tank
    Add miles to the running total in totalMiles
    Calculate and print the miles/gallon
    Input the gallons used for thenext tank

Print the average miles/gallon

```
1  // Exercise 2.16 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
int main()
{
   double gallons, miles, totalGallons = 0.0,
          totalMiles = 0.0, average;

   cout << "Enter the gallons used (-1 to end): ";
   cin >> gallons;

   while ( gallons != -1.0 ) {
      totalGallons += gallons;

      cout << "Enter the miles driven: ";
      cin >> miles;
      totalMiles += miles;

      cout << "The Miles / Gallon for this tank was "
           << miles / gallons
           << "\n\nEnter the gallons used (-1 to end): ";
      cin >> gallons;
   }

   average = totalMiles / totalGallons;
   cout << "\nThe overall average Miles/Gallon was "
        << average << endl;

   return 0;
}
```

```
Enter the gallons used (-1 to end): 16
Enter the miles driven: 220
The Miles / Gallon for this tank was 13.75

Enter the gallons used (-1 to end): 16.5
Enter the miles driven: 272
The Miles / Gallon for this tank was 16.4848

Enter the gallons used (-1 to end): -1

The overall average Miles/Gallon was 15.1385
```

2.17 Develop a C++ program that will determine if a department store customer has exceeded the credit limit on a charge account. For each customer, the following facts are available:

a) Account number (an integer)
b) Balance at the beginning of the month
c) Total of all items charged by this customer this month
d) Total of all credits applied to this customer's account this month
e) Allowed credit limit

The program should input each of these facts, calculate the new balance (= beginning balance + charges – credits) and determine if the new balance exceeds the customer's credit limit. For those customers whose credit limit is exceeded, the program should display the customer's account number, credit limit, new balance and the message “Credit limit exceeded”.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter account number (-1 to end): 100
Enter beginning balance: 5394.78
Enter total charges: 1000.00
Enter total credits: 500.00
Enter credit limit: 5500.00
Account:      100
Credit limit: 5500.00
Balance:      5894.78
Credit Limit Exceeded.

Enter account number (-1 to end): 200
Enter beginning balance: 1000.00
Enter total charges: 123.45
Enter total credits: 321.00
Enter credit limit: 1500.00

Enter account number (-1 to end): 300
Enter beginning balance: 500.00
Enter total charges: 274.73
Enter total credits: 100.00
Enter credit limit: 800.00

Enter account number (-1 to end): -1
```

ANS:

Top:

Determine if each of an arbitrary number of department store customers has exceeded the credit limit on a charge account.

First refinement:

Input the account number, beginning balance, total charges, total credits, and credit limit for a customer, calculate the customer's new balance and determine if the balance exceeds the credit limit. Then process the next customer.

Second refinement:

Input the first customer's account number

While the sentinel value (-1) has not been entered for the account number
    Input the customer's beginning balance
    Input the customer's total charges
    Input the customer's total credits
    Input the customer's credit limit
    Calculate the customer's new balance

    If the balance exceeds the credit limit
        Print the account number
        Print the credit limit
        Print the balance
        Print "Credit Limit Exceeded"

    Input the next customer's account number

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 2.17 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setprecision;
using std::setiosflags;

int main()
{
   int accountNumber;
   double balance, charges, credits, limit;

   cout << "Enter account number (-1 to end): "
        << setiosflags(ios::fixed | ios::showpoint);
   cin >> accountNumber;

   while ( accountNumber != -1 ) {
      cout << "Enter beginning balance: ";
      cin >> balance;
      cout << "Enter total charges: ";
      cin >> charges;
      cout << "Enter total credits: ";
      cin >> credits;
      cout << "Enter credit limit: ";
      cin >> limit;
      balance += charges - credits;

      if ( balance > limit )
         cout << "Account:      " << accountNumber
              << "\nCredit limit: " << setprecision( 2 ) << limit
              << "\nBalance:      " << setprecision( 2 ) << balance
              << "\nCredit Limit Exceeded.\n";

      cout << "\nEnter account number (-1 to end): ";
      cin >> accountNumber;
   }

   cout << endl;  // ensure all output is displayed

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter account number (-1 to end): 88
Enter beginning balance: 900.57
Enter total charges: 324.78
Enter total credits: 100
Enter credit limit: 1500

Enter account number (-1 to end): 89
Enter beginning balance: 2789.65
Enter total charges: 1540.55
Enter total credits: 25
Enter credit limit: 1500
Account:      89
Credit limit: 1500.00
Balance:      4305.20
Credit Limit Exceeded.

Enter account number (-1 to end): -1
```

2.18 One large chemical company pays its salespeople on a commission basis. The salespeople receive $200 per week plus 9 percent of their gross sales for that week. For example, a salesperson who sells $5000 worth of chemicals in a week receives $200 plus 9 percent of $5000, or a total of $650. Develop a C++ program that will input each salesperson's gross sales for last week and calculate and display that salesperson's earnings. Process one salesperson's figures at a time.

```
Enter sales in dollars (-1 to end): 5000.00
Salary is: $650.00

Enter sales in dollars (-1 to end): 6000.00
Salary is: $740.00

Enter sales in dollars (-1 to end): 7000.00
Salary is: $830.00

Enter sales in dollars (-1 to end): -1
```

ANS:

Top:

For an arbitrary number of salespeople, determine each salesperson's earnings for the last week.

First refinement:

Initialize variables

Input the salesperson's sales for the week, calculate and print the salesperson's wages for the week then process the next salesperson.

Second refinement:

Input the first salesperson's sales in dollars

While the sentinel value (-1) has not been entered for the sales
    Calculate the salesperson's wages for the week
    Print the salesperson's wages for the week
    Input the next salesperson's sales in dollars

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
1  // Exercise 2.18 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6  using std::ios;
7
8  #include <iomanip>
9
10 using std::setprecision;
11 using std::setiosflags;
12
13 int main()
14 {
15    double sales, wage;
16
17    cout << "Enter sales in dollars (-1 to end): "
18         << setiosflags( ios::fixed | ios::showpoint );
19    cin >> sales;
20
21    while ( sales != -1.0 ) {
22       wage = 200.0 + 0.09 * sales;
23       cout << "Salary is: $" << setprecision( 2 ) << wage
24            << "\n\nEnter sales in dollars (-1 to end): ";
25       cin >> sales;
26    }
27
28    return 0;
29 }
```

```
Enter sales in dollars (-1 to end): 7000
Salary is: $830.00

Enter sales in dollars (-1 to end): 500
Salary is: $245.00

Enter sales in dollars (-1 to end): -1
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.19 Develop a C++ program that will determine the gross pay for each of several employees. The company pays "straight-time" for the first 40 hours worked by each employee and pays "time-and-a-half" for all hours worked in excess of 40 hours. You are given a list of the employees of the company, the number of hours each employee worked last week and the hourly rate of each employee. Your program should input this information for each employee and should determine and display the employee's gross pay.

```
Enter hours worked (-1 to end): 39
Enter hourly rate of the worker ($00.00): 10.00
Salary is $390.00

Enter hours worked (-1 to end): 40
Enter hourly rate of the worker ($00.00): 10.00
Salary is $400.00

Enter hours worked (-1 to end): 41
Enter hourly rate of the worker ($00.00): 10.00
Salary is $415.00

Enter hours worked (-1 to end): -1
```

ANS:

Top:

Determine the gross pay for an arbitrary number of employees

Second refinement:

Input the hours worked for the first employee

While the sentinel value (-1) has not been entered for the hours
    Input the employee's hourly rate

    If the hours input is less than or equal to 40
        Calculate gross pay by multiplying hours worked by hourly rate
    Else
        Calculate gross pay by multiplying hours worked above forty by 1.5 times the hourly rate and adding 40 hours worked by the hourly rate.
    Display the employee's gross pay.
    Input the hours worked for thenext employee

Print the average miles/gallon

```
1  // Exercise 2.19 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6  using std::ios;
7
8  #include <iomanip>
9
10 using std::setprecision;
11 using std::setiosflags;
12
13 int main()
14 {
15    double hours, rate, salary;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
16
17     cout << "Enter hours worked (-1 to end): "
18          << setiosflags( ios::fixed | ios::showpoint );
19     cin >> hours;
20
21     while ( hours != -1.0 ) {
22        cout << "Enter hourly rate of the worker ($00.00): ";
23        cin >> rate;
24
25        if ( hours <= 40 )
26           salary = hours * rate;
27        else
28           salary = 40.0 * rate + ( hours - 40.0 ) * rate * 1.5;
29
30        cout << "Salary is $" << setprecision( 2 ) << salary
31             << "\n\nEnter hours worked (-1 to end): ";
32        cin >> hours;
33     }
34
35     return 0;
36  }
```

```
Enter hours worked (-1 to end): 40
Enter hourly rate of the worker ($00.00): 10
Salary is $400.00

Enter hours worked (-1 to end): 50
Enter hourly rate of the worker ($00.00): 10
Salary is $550.00

Enter hours worked (-1 to end): -1
```

2.20 The process of finding the largest number (i.e., the maximum of a group of numbers) is used frequently in computer applications. For example, a program that determines the winner of a sales contest would input the number of units sold by each salesperson. The salesperson who sells the most units wins the contest. Write a pseudocode program, then a C++ program that inputs a series of 10 numbers, and determines and prints the largest of the numbers. Hint: Your program should use three variables, as follows:

counter:	A counter to count to 10 (i.e., to keep track of how many numbers have been input and to determine when all 10 numbers have been processed).
number:	The current number input to the program.
largest:	The largest number found so far.

```
1  // Exercise 2.20 solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int main()
9  {
10    int counter = 0, number, largest;
11
12    cout << "Enter the first number: ";
13    cin >> largest;
14
15    while ( ++counter < 10 ) {
16       cout << "Enter the next number : ";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cin >> number;

      if ( number > largest )
         largest = number;
   }

   cout << "Largest is " << largest << endl;

   return 0;
}
```

```
Enter the first number: 78
Enter the next number : 19
Enter the next number : 99
Enter the next number : 33
Enter the next number : 22
Enter the next number : 10
Enter the next number : 8
Enter the next number : 88
Enter the next number : 22
Enter the next number : 34
Largest is 99
```

2.21 Write a C++ program that utilizes looping and the tab escape sequence **\t** to print the following table of values:

```
N       10*N    100*N   1000*N

1       10      100     1000
2       20      200     2000
3       30      300     3000
4       40      400     4000
5       50      500     5000
```

```
// Exercise 2.21 Solution
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   int n = 0;

   cout << "N\t10 * N\t100 * N\t1000 * N\n\n";

   while ( ++n <= 5 )
      cout << n << '\t' << 10 * n << '\t' << 100 * n
           << '\t' << 1000 * n << '\n';

   cout << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
N       10 * N  100 * N 1000 * N

1       10      100     1000
2       20      200     2000
3       30      300     3000
4       40      400     4000
5       50      500     5000
```

2.22 Using an approach similar to Exercise 2.20, find the *two* largest values among the 10 numbers. Note: You must input each number only once.

```
1  // Exercise 2.22 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int main()
9  {
10    int counter = 0, number, largest, secondLargest = 0;
11
12    cout << "Enter the first number: ";
13    cin >> largest;
14
15    while ( ++counter < 10 ) {
16       cout << "Enter next number: ";
17       cin >> number;
18
19       if ( number > largest ) {
20          secondLargest = largest;
21          largest = number;
22       }
23       else if ( number > secondLargest )
24          secondLargest = number;
25    }
26
27    cout << "\nLargest is " <<  largest
28         << "\nSecond largest is " << secondLargest << endl;
29
30    return 0;
31 }
```

```
Enter the first number: 77
Enter next number: 33
Enter next number: 44
Enter next number: 73
Enter next number: 79
Enter next number: 45
Enter next number: 2
Enter next number: 22
Enter next number: 21
Enter next number: 8

Largest is 79
Second largest is 77
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.23 Modify the program in Fig. 2.11 to validate its inputs. On any input, if the value entered is other than 1 or 2, keep looping until the user enters a correct value.

```
// Exercise 2.23 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int passes = 0, failures = 0, student = 0, result;

   while ( ++student <= 10 ) {
      cout << "Enter result (1=pass, 2=fail): ";
      cin >> result;

      while ( result != 1 && result != 2 ) {
         cout << "Invalid result"
              << "\nEnter result (1=pass, 2=fail): ";
         cin >> result;
      }

      if ( result == 1 )
         ++passes;
      else
         ++failures;
   }

   cout << "Passed: " << passes
        << "\nFailed: " << failures;

   if ( passes >= 8 )
      cout << "\nRaise tuition\n";

   cout << endl;

   return 0;
}
```

```
Enter result (1=pass, 2=fail): 1
Enter result (1=pass, 2=fail): 4
Invalid result
Enter result (1=pass, 2=fail): 1
Enter result (1=pass, 2=fail): 1
Enter result (1=pass, 2=fail): 5
Invalid result
Enter result (1=pass, 2=fail): 2
Enter result (1=pass, 2=fail): 1
Enter result (1=pass, 2=fail): 1
Enter result (1=pass, 2=fail): 1
Enter result (1=pass, 2=fail): 2
Enter result (1=pass, 2=fail): 2
Enter result (1=pass, 2=fail): 2
Passed: 6
Failed: 4
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.24 What does the following program print?

```
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   int count = 1;

   while ( count <= 10 ) {
      cout << (count % 2 ? "*****" : "++++++++")
           << endl;
      ++count;
   }

   return 0;
}
```

```
****
++++++++
****
++++++++
****
++++++++
****
++++++++
****
++++++++
```

2.25 What does the following program print?

```
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   int row = 10, column;

   while ( row >= 1 ) {
      column = 1;

      while ( column <= 10 ) {
         cout << ( row % 2 ? "<" : ">" );
         ++column;
      }

      --row;
      cout << endl;
   }

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
>>>>>>>>>>
<<<<<<<<<<
>>>>>>>>>>
<<<<<<<<<<
>>>>>>>>>>
<<<<<<<<<<
>>>>>>>>>>
<<<<<<<<<<
>>>>>>>>>>
<<<<<<<<<<
```

2.26 *(Dangling Else Problem)* Determine the output for each of the following when **x** is **9** and **y** is **11** and when **x** is **11** and **y** is **9**. Note that the compiler ignores the indentation in a C++ program. Also, the C++ compiler always associates an **else** with the previous **if** unless told to do otherwise by the placement of braces **{}**. Because, on first glance, the programmer may not be sure which **if** an **else** matches, this is referred to as the "dangling else" problem. We have eliminated the indentation from the following code to make the problem more challenging. (Hint: Apply indentation conventions you have learned.)

a)
```
if ( x < 10 )
   if ( y > 10 )
   cout << "******" << endl;
   else
   cout << "#####" << endl;
   cout << "$$$$$" << endl;
```

ANS: x = 9, y = 11

```
*****
$$$$$
```

b)
```
if ( x < 10 ) {
   if ( y > 10 )
   cout << "******" << endl;
   }
   else {
   cout << "#####" << endl;
   cout << "$$$$$" << endl;
   }
```

ANS: x = 11, y = 9

```
#####
$$$$$
```

2.27 *(Another Dangling Else Problem)* Modify the following code to produce the output shown. Use proper indentation techniques. You must not make any changes other than inserting braces. The compiler ignores indentation in a C++ program. We have eliminated the indentation from the following code to make the problem more challenging. Note: It is possible that no modification is necessary.

```
if ( y == 8 )
if ( x == 5 )
cout << "@@@@@" << endl;
else
cout << "#####" << endl;
cout << "$$$$$" << endl;
cout << "&&&&&" << endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

a) Assuming `x = 5` and `y = 8`, the following output is produced.

```
@@@@@
$$$$$
&&&&&
```

ANS:

```
1  if ( y == 8 )
2     if ( x == 5 )
3        cout << "@@@@@\n";
4     else
5        cout << "#####\n";
6
7  cout << "$$$$$\n";
8  cout << "&&&&&\n";
```

b) Assuming `x = 5` and `y = 8`, the following output is produced.

```
@@@@@
```

ANS:

```
1  if ( y == 8 )
2     if ( x == 5 )
3        cout << "@@@@@\n";
4     else {
5        cout << "#####\n";
6        cout << "$$$$$\n";
7        cout << "&&&&&\n";
8     }
```

c) Assuming `x = 5` and `y = 8`, the following output is produced.

```
@@@@@
&&&&&
```

ANS:

```
1  if ( y == 8 )
2     if ( x == 5 )
3        cout << "@@@@@\n";
4     else {
5        cout << "#####\n";
6        cout << "$$$$$\n";
7     }
8
9  cout << "&&&&&\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

d) Assuming `x = 5` and `y = 7`, the following output is produced. Note: The last three output statements after the `else` are all part of a compound statement.

```
#####
$$$$$
&&&&&
```

ANS:

```
if ( y == 8 ) {
   if ( x == 5 )
      cout << "@@@@@\n";
}
else {
   cout << "#####\n";
   cout << "$$$$$\n";
   cout << "&&&&&\n";
}
```

2.28 Write a program that reads in the size of the side of a square and then prints a hollow square of that size out of asterisks and blanks. Your program should work for squares of all side sizes between 1 and 20. For example, if your program reads a size of 5, it should print

```
*****
*   *
*   *
*   *
*****
```

```
// Exercise 2.28 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int side, rowPosition, size;

   cout << "Enter the square side: ";
   cin >> side;

   size = side;

   while ( side > 0 ) {
      rowPosition = size;

      while ( rowPosition > 0 ) {

         if ( size == side || side == 1 || rowPosition == 1 ||
             rowPosition == size )

            cout << '*';
         else
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
            cout << ' ';

         --rowPosition;
      }

      cout << '\n';
      --side;
   }

   cout << endl;

   return 0;
}
```

```
Enter the square side: 8
********
*      *
*      *
*      *
*      *
*      *
*      *
********
```

2.29 A palindrome is a number or a text phrase that reads the same backwards as forwards. For example, each of the following five-digit integers is a palindrome: 12321, 55555, 45554 and 11611. Write a program that reads in a five-digit integer and determines whether it is a palindrome. (Hint: Use the division and modulus operators to separate the number into its individual digits.)

```
// Exercise 2.29 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int number, firstDigit, secondDigit, fourthDigit, fifthDigit;

   cout << "Enter a five-digit number: ";
   cin >> number;

   firstDigit = number / 10000;
   secondDigit = number % 10000 / 1000;
   fourthDigit = number % 10000 % 1000 % 100 / 10;
   fifthDigit = number % 10000 % 1000 % 10;

   if ( firstDigit == fifthDigit && secondDigit == fourthDigit )
      cout << number << " is a palindrome" << endl;
   else
      cout << number << " is not a palindrome" << endl;

   return 0;
}
```

```
Enter a five-digit number: 57475
57475 is a palindrome
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.30 Input an integer containing only 0s and 1s (i.e., a "binary" integer) and print its decimal equivalent. (Hint: Use the modulus and division operators to pick off the "binary" number's digits one at a time from right to left. Just as in the decimal number system where the rightmost digit has a positional value of 1 and the next digit left has a positional value of 10, then 100, then 1000, etc., in the binary number system, the rightmost digit has a positional value of 1, the next digit left has a positional value of 2, then 4, then 8, etc. Thus the decimal number 234 can be interpreted as 4 * 1 + 3 * 10 + 2 * 100. The decimal equivalent of binary 1101 is 1 * 1 + 0 * 2 + 1 * 4 + 1 * 8 or 1 + 0 + 4 + 8, or 13.)

```
1  // Exercise 2.30 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int main()
9  {
10    int binary, number, decimal = 0, highBit = 16, factor = 10000;
11
12    cout << "Enter a binary number (5 digits maximum): ";
13    cin >> binary;
14
15    number = binary;
16
17    while ( highBit >= 1 ) {
18       decimal += binary / factor * highBit;
19       highBit /= 2;
20       binary %= factor;
21       factor /= 10;
22    }
23
24    cout << "The decimal equivalent of "
25         << number << " is " << decimal << endl;
26
27    return 0;
28 }
```

```
Enter a binary number (5 digits maximum): 10010
The decimal equivalent of 10010 is 18
```

2.31 Write a program that displays the following checkerboard pattern

```
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Your program must use only three output statements, one of each of the following forms:

```
cout << "* ";
cout << ' ';
cout << endl;
```

```
1  // Exercise 2.31 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     int side = 8, row;
10
11    while ( side-- > 0 ) {
12       row = 8;
13
14       if ( side % 2 == 0 )
15          cout << ' ';
16
17       while ( row-- > 0 )
18          cout << "* ";
19
20       cout << '\n';
21    }
22
23    cout << endl;
24
25    return 0;
26 }
```

```
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
* * * * * * * *
 * * * * * * * *
```

2.32 Write a program that keeps printing the multiples of the integer 2, namely 2, 4, 8, 16, 32, 64, etc. Your loop should not terminate (i.e., you should create an infinite loop). What happens when you run this program?

```
1  // Exercise 2.32 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     int multiple = 1;
10
11    while ( multiple *= 2 )
12       cout << multiple << "\n";
13
14    cout << endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
15
16    return 0;
17 }
```

```
2
4
...
32768
65536
131072
262144
524288
1048576
2097152
4194304
8388608
16777216
33554432
67108864
134217728
268435456
536870912
1073741824
-2147483648
```

2.33 Write a program that reads the radius of a circle (as a **double** value) and computes and prints the diameter, the circumference and the area. Use the value 3.14159 for π.

```
1  // Exercise 2.33 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int main()
9  {
10    double radius, pi = 3.14159;
11
12    cout << "Enter the radius: ";
13    cin >> radius;
14
15    cout << "The diameter is " << radius * 2.0
16         << "\nThe circumference is " << 2.0 * pi * radius
17         << "\nThe area is " << pi * radius * radius << endl;
18
19    return 0;
20 }
```

```
Enter the radius: 5
The diameter is 10
The circumference is 31.4159
The area is 78.5397
```

2.34 What's wrong with the following statement? Provide the correct statement to accomplish what the programmer was probably trying to do.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
cout << ++( x + y );
```

ANS: The **++** operator must be used in conjuction with variables. The programmer probably intended to write the statement: **cout << x + y + 1;**.

2.35 Write a program that reads three nonzero **double** values and determines and prints if they could represent the sides of a right triangle.

```
// Exercise 2.35 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   double a, b, c;

   cout << "Enter three floating point numbers: ";
   cin >> a >> b >> c;

   if ( c * c == a * a + b * b )
      cout << "The three numbers could"
           << " be sides of a right triangle" << endl;
   else
      cout << "The three numbers probably"
           << " are not the sides of a right triangle" << endl;

   return 0;
}
```

```
Enter three floating point numbers: 4.5 7.7 6.6
The three numbers probably are not the sides of a right triangle
```

2.36 Write a program that reads three nonzero integers and determines and prints if they could be the sides of a right triangle.

```
// Exercise 2.36 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
  int a, b, c;

  do {
     cout << "Enter three integers: ";
     cin >> a >> b >> c;
  } while ( a <= 0 || b <= 0 || c <= 0 );

  if ( c * c == a * a + b * b )
     cout << "The three integers are the"
          << " sides of a right triangle\n";
  else
     cout << "The three integers are not the"
          << " sides of a right triangle\n";

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
24     cout << endl;
25
26     return 0;
27  }
```

```
Enter three integers: 3 4 5
The three integers are the sides of a right triangle
```

2.37 A company wants to transmit data over the telephone, but they are concerned that their phones may be tapped. All of their data are transmitted as four-digit integers. They have asked you to write a program that encrypts their data so that it can be transmitted more securely. Your program should read a four-digit integer and encrypt it as follows: Replace each digit by *(the sum of that digit plus 7) modulus 10*. Then, swap the first digit with the third, swap the second digit with the fourth and print the encrypted integer. Write a separate program that inputs an encrypted four-digit integer and decrypts it to form the original number.

```
1  // Exercise 2.37 Part A Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int main()
9  {
10    int first, second, third, fourth, digit, temp;
11    int encryptedNumber;
12
13    cout << "Enter a four digit number to be encrypted: ";
14    cin >> digit;
15
16    first = ( digit / 1000 + 7 ) % 10;
17    second = ( digit % 1000 / 100 + 7 ) % 10;
18    third = ( digit % 1000 % 100 / 10 + 7 ) % 10;
19    fourth = ( digit % 1000 % 100 % 10 + 7 ) % 10;
20
21    temp = first;
22    first = third * 1000;
23    third = temp * 10;
24
25    temp = second;
26    second = fourth * 100;
27    fourth = temp * 1;
28
29    encryptedNumber = first + second + third + fourth;
30    cout << "Encrypted number is " << encryptedNumber << endl;
31
32    return 0;
33 }
```

```
Enter a four digit number to be encrypted: 1009
Encrypted number is 7687
```

```
1  // Exercise 2.37 Part B Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 7
 8  int main()
 9  {
10     int first, second, third, fourth, decrypted, temp, num;
11
12     cout << "Enter a four digit encrypted number: ";
13     cin >> num;
14
15     first = num / 1000;
16     second = num % 1000 / 100;
17     third = num % 1000 % 100 / 10;
18     fourth = num % 1000 % 100 % 10;
19
20     temp = ( first + 3 ) % 10;
21     first = ( third + 3 ) % 10;
22     third = temp;
23
24     temp = ( second + 3 ) % 10;
25     second = ( fourth + 3 ) % 10;
26     fourth = temp;
27
28     decrypted = first * 1000 + second * 100 + third * 10 + fourth;
29     cout << "Decrypted number is " << decrypted << endl;
30
31     return 0;
32  }
```

```
Enter a four digit encrypted number: 7687
Decrypted number is 1009
```

2.38 The factorial of a nonnegative integer n is written $n!$ (pronounced "n factorial") and is defined as follows:

$n! = n \cdot (n - 1) \cdot (n - 2) \cdot \ldots \cdot 1$ (for values of n greater than or equal to 1)

and

$n! = 1$ (for $n = 0$).

For example, $5! = 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1$, which is 120.

a) Write a program that reads a nonnegative integer and computes and prints its factorial.

b) Write a program that estimates the value of the mathematical constant e by using the formula:

$$e = 1 + \frac{1}{1!} + \frac{1}{2!} + \frac{1}{3!} + \ldots$$

c) Write a program that computes the value of e^x by using the formula

$$e^x = 1 + \frac{x}{1!} + \frac{x^2}{2!} + \frac{x^3}{3!} + \ldots$$

```
 1  // Exercise 2.38 Part A Solution
 2  #include <iostream>
 3
 4  using std::cout;
 5  using std::endl;
 6  using std::cin;
 7
 8  int main()
 9  {
10     int n = 0, number;
11     unsigned factorial = 1;
12
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
13     do {
14        cout << "Enter a positive integer: ";
15        cin >> number;
16     } while ( number < 0 );
17
18     while ( n++ < number )
19        factorial *= n == 0 ? 1 : n;
20
21     cout << number << "! is " << factorial << endl;
22
23     return 0;
24  }
```

```
Enter a positive integer: 8
8! is 40320
```

```
1   // Exercise 2.38 Part B Solution
2   #include <iostream>
3
4   using std::cout;
5   using std::endl;
6
7   int main()
8   {
9      int n = 0, fact = 1, accuracy = 10;
10     double e = 1;
11
12     while ( ++n < accuracy ) {
13        fact *= n;
14        e += 1.0 / fact;
15     }
16
17     cout << "e is " << e << endl;
18
19     return 0;
20  }
```

```
e is 2.71828
```

```
1   // Exercise 2.38 Part C Solution
2   #include <iostream>
3
4   using std::cout;
5   using std::endl;
6   using std::cin;
7   using std::ios;
8
9   #include <iomanip>
10  using std::setw;
11  using std::setprecision;
12  using std::setiosflags;
13
14  int main()
15  {
16     int n = 0, accuracy = 15, x = 3.0, times = 0, count;
17     double e = 1.0, exp = 0.0, fact = 1.0;
18
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   while ( n++ <= accuracy ) {
      count = n;
      fact *= n == 0 ? 1.0 : n;

      while ( times < count ) {

         if ( times == 0 )
            exp = 1.0;

         exp *= x;
         ++times;
      }

      e += exp / fact;
    }

   cout << setiosflags( ios::fixed | ios::showpoint )
        << "e raised to the " << x << " power is "
        << setprecision( 4 ) << e << endl;

   return 0;
}
```

```
e raised to the 3 power is 20.0855
```

2.39 Find the error(s) in each of the following:

a)
```
For ( x = 100, x >= 1, x++ )
   cout << x << endl;
```
ANS: `For` should be `for`. The commas should be semicolons. The `++` should be a decrement such as `--`.

b) The following code should print whether integer `value` is odd or even:
```
switch ( value % 2 ) {
   case 0:
      cout << "Even integer" << endl;
   case 1:
      cout << "Odd integer" << endl;
}
```
ANS: `case 0` needs a `break` statement.

c) The following code should output the odd integers from 19 to 1:
```
for ( x = 19; x >= 1; x += 2 )
   cout << x << endl;
```
ANS: `+=` should be `-=`.

d) The following code should output the even integers from 2 to 100:
```
counter = 2;
do {
   cout << counter << endl;
   counter += 2;
} While ( counter < 100 );
```
ANS: `While` should be `while`. Operator `<` should be `<=`.

2.40 Write a program that sums a sequence of integers. Assume that the first integer read specifies the number of values remaining to be entered. Your program should read only one value per input statement. A typical input sequence might be

```
5 100 200 300 400 500
```

where the `5` indicates that the subsequent `5` values are to be summed.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 2.40 Solution
#include <iostream>


using std::cout;
using std::endl;
using std::cin;

int main()
{
   int sum = 0, number, value;

   cout << "Enter the number of values to be processed: ";
   cin >> number;

   for ( int i = 1; i <= number; i++ ) {
      cout << "Enter a value: ";
      cin >> value;
      sum += value;
   }

   cout << "Sum of the " << number << " values is "
        << sum << endl;

   return 0;
}
```

```
Enter the number of values to be processed: 3
Enter a value: 7
Enter a value: 8
Enter a value: 9
Sum of the 3 values is 24
```

2.41 Write a program that calculates and prints the average of several integers. Assume the last value read is the sentinel **9999**. A typical input sequence might be

```
10 8 11 7 9 9999
```

indicating that the average of all the values preceding **9999** is to be calculated.

```
// Exercise 2.41 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int value, count = 0, total = 0;

   cout << "Enter an integer (9999 to end): ";
   cin >> value;

   while ( value != 9999 ) {
      total += value;
      ++count;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
18         cout << "Enter next integer (9999 to end): ";
19         cin >> value;
20      }
21
22      if ( count != 0 )
23         cout << "\nThe average is: "
24              << static_cast< double > ( total ) / count << endl;
25      else
26         cout << "\nNo values were entered." << endl;
27
28      return 0;
29   }
```

```
Enter an integer (9999 to end): 88
Enter next integer (9999 to end): 65
Enter next integer (9999 to end): 77
Enter next integer (9999 to end): 43
Enter next integer (9999 to end): 90
Enter next integer (9999 to end): 45
Enter next integer (9999 to end): 76
Enter next integer (9999 to end): 2
Enter next integer (9999 to end): 9999

The average is: 60.75
```

2.42 What does the following program do?

```
1   #include <iostream>
2
3   using std::cout;
4   using std::cin;
5   using std::endl;
6
7   int main()
8   {
9      int x, y;
10
11     cout << "Enter two integers in the range 1-20: ";
12     cin >> x >> y;
13
14     for ( int i = 1; i <= y; i++ ) {
15
16        for ( int j = 1; j <= x; j++ )
17           cout << '@';
18
19        cout << endl;
20     }
21
22     return 0;
23  }
```

```
Enter two integers in the range of 1-20: 3 4
@@@
@@@
@@@
@@@
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.43 Write a program that finds the smallest of several integers. Assume that the first value read specifies the number of values remaining and that the first number is not one of the integers to compare.

```
// Exercise 2.43 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   int number, value, smallest;

   cout << "Enter the number of integers to be processed: ";
   cin >> number;
   cout << "Enter an integer: ";
   cin >> smallest;

   for ( int i = 2; i <= number; i++ ) {
      cout << "Enter next integer: ";
      cin >> value;

      if ( value < smallest )
         smallest = value;
   }

   cout << "\nThe smallest integer is: " << smallest << endl;

   return 0;
}
```

```
Enter the number of integers to be processed: 5
Enter an integer: 5
Enter next integer: 4
Enter next integer: 3
Enter next integer: 1
Enter next integer: 8

The smallest integer is: 1
```

2.44 Write a program that calculates and prints the product of the odd integers from 1 to 15.

```
// Exercise 2.44 Solution
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   long product = 1;

   for ( long i = 3; i <= 15; i += 2 )
      product *= i;

   cout << "Product of the odd integers from 1 to 15 is: "
        << product << endl;

}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   return 0;
}
```

```
Product of the odd integers from 1 to 15 is: 2027025
```

2.45 The *factorial* function is used frequently in probability problems. The factorial of a positive integer *n* (written *n!* and pronounced "n factorial") is equal to the product of the positive integers from 1 to *n*. Write a program that evaluates the factorials of the integers from 1 to 5. Print the results in tabular format. What difficulty might prevent you from calculating the factorial of 20?

```
// Exercise 2.45 Solution
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   int factorial;

   cout << "X\tFactorial of X\n";

   for ( int i = 1; i <= 5; ++i ) {
      factorial = 1;

      for ( int j = 1; j <= i; ++j )
         factorial *= j;

      cout << i << '\t' << factorial << '\n';
   }

   cout << endl;
   return 0;
}
```

```
X       Factorial of X
1       1
2       2
3       6
4       24
5       120
```

2.46 Modify the compound interest program of Section 2.15 to repeat its steps for interest rates of 5 percent, 6 percent, 7 percent, 8 percent, 9 percent and 10 percent. Use a **for** loop to vary the interest rate.

```
// Exercise 2.46 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
13  using std::setiosflags;
14
15  #include <cmath>
16
17  int main()
18  {
19     double amount, principal = 1000.00;
20
21     cout << setiosflags( ios::fixed | ios::showpoint );
22
23     for ( int rate = 5; rate <= 10; rate++ ) {
24        cout << "Interest Rate: " << setprecision( 2 ) << rate / 100.0
25             << "\nYear\tAmount on deposit\n";
26
27        for ( int year = 1; year <= 10; year++ ) {
28           amount = principal * pow( 1 + ( rate / 100.0 ), year );
29           cout << year << '\t' << setprecision( 2 ) << amount << '\n';
30        }
31
32        cout << '\n';
33     }
34
35     cout << endl;
36
37     return 0;
38  }
```

```
...
Interest Rate: 0.10
Year    Amount on deposit
1       1100.00
2       1210.00
3       1331.00
4       1464.10
5       1610.51
6       1771.56
7       1948.72
8       2143.59
9       2357.95
10      2593.74
```

2.47 Write a program that prints the following patterns separately one below the other. Use **`for`** loops to generate the patterns. All asterisks (**`*`**) should be printed by a single statement of the form **`cout << '*';`** (this causes the asterisks to print side by side). Hint: The last two patterns require that each line begin with an appropriate number of blanks. Extra credit: Combine your code from the four separate problems into a single program that prints all four patterns side by side by making clever use of nested **`for`** loops.

```
(A)             (B)             (C)                 (D)
*               **********      **********              *
**              *********       *********             **
***             ********        ********            ***
****            *******         *******           ****
*****           ******          ******          *****
******          *****           *****         ******
*******         ****            ****        *******
********        ***             ***       ********
*********       **              **      *********
**********      *               *     **********
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 2.47 Solution
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   // Pattern A
   for ( int row = 1; row <= 10; ++row ) {

      for ( int col = 1; col <= row; ++col )
         cout << '*';

      cout << '\n';
   }

   cout << '\n';

   // Pattern B
   for ( row = 10; row >= 1; --row ) {

      for ( int col = 1; col <= row; ++col )
         cout << '*';

      cout << '\n';
   }

   cout << '\n';

   // Pattern C
   for ( row = 10; row >= 1; --row ) {

      for ( int space = 1; space <= 10 - row; ++space )
         cout << ' ';

      for ( int col = 1; col <= row; ++col )
         cout << '*';

      cout << '\n';
   }

   cout << '\n';

   // Pattern D
   for ( row = 1; row <= 10; ++row ) {

      for ( int space = 1; space <= 10 - row; ++space )
         cout << ' ';

      for ( int col = 1; col <= row; ++col )
         cout << '*';

      cout << '\n';
   }

   cout << endl;

   return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
60 }
```

```
*
**
***
****
*****
******
*******
********
*********
**********

**********
*********
********
*******
******
*****
****
***
**
*

**********
 *********
  ********
   *******
    ******
     *****
      ****
       ***
        **
         *

         *
        **
       ***
      ****
     *****
    ******
   *******
  ********
 *********
**********
```

```
1  // Exercise 2.47 Extra Credit Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     int row, column, space;
10
11    for ( row = 1; row <= 10; ++row ) {
12
13       // part a
14       for ( column = 1; column <= row; ++column )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
         cout << '*';

      for ( space = 1; space <= 10 - row; ++space )
         cout << ' ';

      cout << '\t';

      // part b
      for ( column = 10; column >= row; --column )
         cout << '*';

      for ( space = 1; space < row; ++space )
         cout << ' ';

      cout << '\t';

      // part c
      for ( space = 10; space > row; --space )
         cout << ' ';

      for ( column = 1; column <= row; ++column )
         cout << '*';

      cout << '\t';

      // part d
      for ( space = 1; space < row; ++space )
         cout << ' ';

      for ( column = 10; column >= row; --column )
         cout << '*';

      cout << endl;
   }

   return 0;
}
```

```
*               **********               *       **********
**              *********               **        *********
***             ********               ***         ********
****            *******               ****          *******
*****           ******               *****           ******
******          *****               ******            *****
*******         ****               *******             ****
********        ***               ********              ***
*********       **               *********               **
**********      *               **********               *
```

2.48 One interesting application of computers is drawing graphs and bar charts (sometimes called "histograms"). Write a program that reads five numbers (each between 1 and 30). For each number read, your program should print a line containing that number of adjacent asterisks. For example, if your program reads the number seven, it should print `*******`.

```
// Exercise 2.48 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 7
 8  int main()
 9  {
10     int number;
11
12     cout << "Enter 5 numbers between 1 and 30: ";
13
14     for ( int i = 1; i <= 5; ++i ) {
15        cin >> number;
16
17        for ( int j = 1; j <= number; ++j )
18           cout << '*';
19
20        cout << '\n';
21     }
22
23     cout << endl;
24
25     return 0;
26  }
```

```
Enter 5 numbers between 1 and 30: 16 12 8 27 9
****************
************
********
**************************
*********
```

2.49 A mail order house sells five different products whose retail prices are product 1 — $2.98, product 2—$4.50, product 3—$9.98, product 4—$4.49 and product 5—$6.87. Write a program that reads a series of pairs of numbers as follows:

a) Product number
b) Quantity sold for one day

Your program should use a **switch** statement to help determine the retail price for each product. Your program should calculate and display the total retail value of all products sold last week.

```
 1  // Exercise 2.49 Solution
 2  #include <iostream>
 3
 4  using std::cout;
 5  using std::endl;
 6  using std::cin;
 7  using std::ios;
 8
 9  #include <iomanip>
10
11  using std::setprecision;
12  using std::setiosflags;
13
14  int main()
15  {
16     int product, quantity;
17     double total = 0.0;
18
19     cout << "Enter pairs of item numbers and quantities."
20          << "\nEnter -1 for the item number to end input: ";
21     cin >> product;
22
23     while ( product != -1 ) {
24        cin >> quantity;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
25
26       switch ( product ) {
27          case 1:
28             total += quantity * 2.98;
29             break;
30          case 2:
31             total += quantity * 4.50;
32             break;
33          case 3:
34             total += quantity * 9.98;
35             break;
36          case 4:
37             total += quantity * 4.49;
38             break;
39          case 5:
40             total += quantity * 6.87;
41             break;
42          default:
43             cout << "Invalid product code: " << product
44                  << "\n            Quantity: " << quantity << '\n';
45             break;
46       }
47
48       cout << "Enter pairs of item numbers and quantities.\n"
49            << "Enter -1 for the item number to end input: ";
50       cin >> product;
51    }
52
53    cout << setiosflags( ios::fixed | ios::showpoint )
54         << "The total retail value was: " << setprecision( 2 )
55         << total << endl;
56
57    return 0;
58 }
```

```
Enter pairs of item numbers and quantities.
Enter -1 for the item number to end input: 2 10
Enter pairs of item numbers and quantities.
Enter -1 for the item number to end input: 1 5
Enter pairs of item numbers and quantities.
Enter -1 for the item number to end input: -1
The total retail value was: 59.90
```

2.50 Modify the program of Fig. 2.22 so that it calculates the grade-point average for the class. A grade of 'A' is worth 4 points, 'B' is worth 3 points, etc.

```
1  // Exercise 2.50 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <iomanip>
9
10 using std::setw;
11 using std::setprecision;
12 using std::setiosflags;
13
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
int main()
{
   int grade, gradeTotal = 0, gradeCount, aCount = 0,
       bCount = 0, cCount = 0, dCount = 0, fCount = 0;

   cout << "Enter the letter grades."
        << "\nEnter the EOF character to end input.\n"
        << setiosflags(ios::fixed | ios::showpoint);

   while ( ( grade = cin.get() ) != EOF ) {

      switch ( grade ) {
         case 'A': case 'a':
            gradeTotal += 4;
            ++aCount;
            break;
         case 'B': case 'b':
            gradeTotal += 3;
            ++bCount;
            break;
         case 'C': case 'c':
            gradeTotal += 2;
            ++cCount;
            break;
         case 'D': case 'd':
            ++gradeTotal;
            ++dCount;
            break;
         case 'F': case 'f':
            ++fCount;
            break;
         case ' ': case '\n':
            break;
         default:
            cout << "Incorrect letter grade entered."
                 << " Enter a new grade.\n";
            break;
      }
   }

   gradeCount = aCount + bCount + cCount + dCount + fCount;

   if ( gradeCount != 0 )
      cout << "\nThe class average is: " << setprecision( 1 )
           << static_cast< double > ( gradeTotal ) / gradeCount
           << endl;

   return 0;
}
```

```
Enter the letter grades.
Enter the EOF character to end input.
aABcccBbDf
E
Incorrect letter grade entered. Enter a new grade.
F
The class average is: 2.2
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

2.51 Modify the program in Fig. 2.21 so it uses only integers to calculate the compound interest. (Hint: Treat all monetary amounts as integral numbers of pennies. Then "break" the result into its dollar portion and cents portion by using the division and modulus operations. Insert a period.)

```
// Exercise 2.51 Solution
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>
using std::setw;

#include <cmath>

int main()
{
   int amount, principal = 1000, dollars, cents;
   double rate = .05;

   cout << "Year" << setw( 24 ) << "Amount on deposit\n";

   for ( int year = 1; year <= 10; ++year ) {
      amount = principal * pow( 1.0 + rate, year );
      cents = amount % 100;
      dollars = amount;  // assignment truncates decimal places
      cout << setw( 4 ) << year << setw( 21 ) << dollars << '.';

      if ( cents < 10 )
         cout << '0' << cents << endl;
      else
         cout << cents << endl;
   }

   return 0;
}
```

```
Year      Amount on deposit
   1                 1050.50
   2                 1102.02
   3                 1157.57
   4                 1215.15
   5                 1276.76
   6                 1340.40
   7                 1407.07
   8                 1477.77
   9                 1551.51
  10                 1628.28
```

2.52 Assume **i = 1**, **j = 2**, **k = 3** and **m = 2**. What does each of the following statements print? Are the parentheses necessary in each case?

a) **cout << (i == 1) << endl;**
ANS: 1, no.
b) **cout << (j == 3) << endl;**
ANS: 1, no.
c) **cout << (i >= 1 && j < 4) << endl;**
ANS: 1, no.
d) **cout << (m <= 99 && k < m) << endl;**
ANS: 0, no.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

e) `cout << ( j >= i || k == m ) << endl;`
ANS: 1, no.
f) `cout << ( k + m < j || 3 - j >= k ) << endl;`
ANS: 0, no.
g) `cout << ( !m ) << endl;`
ANS: 0, no.
h) `cout << ( !( j - m ) ) << endl;`
ANS: 1, yes. The inner pair of parentheses are required.
i) `cout << ( !( k > m ) ) << endl;`
ANS: 0, yes. The inner pair of parentheses are required.

2.53 Write a program that prints a table of the binary, octal and hexadecimal equivalents of the decimal numbers in the range 1 through 256. If you are not familiar with these number systems, read Appendix C first.

```
// Exercise 2.53 Solution
// The oct, hex, and dec identifiers are stream manipulators
// like endl that are defined in Chapter 11. The manipulator
// oct causes integers to be output in octal, the manipulator
// hex causes integers to be output in hexadecimal, and the manipulator
// dec causes integers to be output in decimal.
#include <iostream>

using std::cout;
using std::endl;
using std::oct;
using std::hex;
using std::dec;

int main()
{
   cout << "Decimal\t\tBinary\t\t\tOctal\tHexadecimal\n";

   for ( int loop = 1; loop <= 256; ++loop ) {
      cout << dec << loop << "\t\t";

      // Output binary number
      int number = loop;
      cout << ( number == 256 ? '1' : '0' );
      int factor = 256;

      do {
         cout << ( number < factor && number >= ( factor / 2 ) ? '1' : '0' );
         factor /= 2;
         number %= factor;
      } while ( factor > 2 );

      // Output octal and hexadecimal numbers
      cout << '\t' << oct << loop << '\t' << hex << loop << endl;
   }

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Decimal         Binary          Octal   Hexadecimal
1               00000000        1       1
2               00000001        2       2
...
245             01111010        365     f5
246             01111011        366     f6
247             01111011        367     f7
248             01111100        370     f8
249             01111100        371     f9
250             01111101        372     fa
251             01111101        373     fb
252             01111110        374     fc
253             01111110        375     fd
254             01111111        376     fe
255             01111111        377     ff
256             10000000        400     100
```

2.54 Calculate the value of π from the infinite series

$$\pi = 4 - \frac{4}{3} + \frac{4}{5} - \frac{4}{7} + \frac{4}{9} - \frac{4}{11} + \cdots$$

Print a table that shows the value of π approximated by 1 term of this series, by two terms, by three terms, etc. How many terms of this series do you have to use before you first get 3.14? 3.141? 3.1415? 3.14159?

```
1  // Exercise 2.54 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::ios;
7
8  #include <iomanip>
9
10 using std::setprecision;
11 using std::setiosflags;
12
13 int main()
14 {
15    long double pi = 0.0, num = 4.0, denom = 1.0;
16    long accuracy = 4;    // set decimal accuracy
17
18    cout << setiosflags( ios::fixed | ios::showpoint )
19         << "Accuracy set at: " << accuracy
20         << "\nterm\t\t  pi\n";
21
22    for ( long loop = 1; loop <= accuracy; ++loop ) {
23
24       if ( loop % 2 != 0 )
25          pi += num / denom;
26       else
27          pi -= num / denom;
28
29       cout << loop << "\t\t" << setprecision( 8 ) << pi << '\n';
30       denom += 2.0;
31    }
32
33    cout << endl;
34
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
35     return 0;
36  }
```

```
Accuracy set at: 400000
term              pi
1              4.00000000
2              2.66666667
3              3.46666667
4              2.89523810
...
236138         3.14158999
236139         3.14159531
236140         3.14159000
...
```

2.55 *(Pythagorean Triples)* A right triangle can have sides that are all integers. The set of three integer values for the sides of a right triangle is called a Pythagorean triple. These three sides must satisfy the relationship that the sum of the squares of two of the sides is equal to the square of the hypotenuse. Find all Pythagorean triples for **side1**, **side2** and **hypotenuse** all no larger than 500. Use a triple-nested **for**-loop that tries all possibilities. This is an example of "brute force" computing. You will learn in more advanced computer science courses that there are many interesting problems for which there is no known algorithmic approach other than using sheer brute force.

```
1  // Exercise 2.55 Solution
2  #include<iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     int count = 0;
10    long int hyptSquared, sidesSquared;
11
12    for ( long side1 = 1; side1 <= 500; ++side1 ) {
13
14       for ( long side2 = 1; side2 <= 500; ++side2 ) {
15
16          for ( long hypt = 1; hypt <= 500; ++hypt ) {
17             hyptSquared = hypt * hypt;
18             sidesSquared = side1 * side1 + side2 * side2;
19
20             if ( hyptSquared == sidesSquared ) {
21                cout << side1 << '\t' << side2 << '\t'
22                     << hypt << '\n';
23                ++count;
24             }
25          }
26       }
27    }
28
29    cout << "A total of " << count << " triples were found." << endl;
30
31    return 0;
32 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
...
476     93      485
480     31      481
480     88      488
480     108     492
480     140     500
483     44      485
A total of 772 triples were found.
```

2.56 A company pays its employees as managers (who receive a fixed weekly salary), hourly workers (who receive a fixed hourly wage for up to the first 40 hours they work and "time-and-a-half," i.e., 1.5 times their hourly wage, for overtime hours worked), commission workers (who receive $250 plus 5.7% of their gross weekly sales), or pieceworkers (who receive a fixed amount of money per item for each of the items they produce—each pieceworker in this company works on only one type of item). Write a program to compute the weekly pay for each employee. You do not know the number of employees in advance. Each type of employee has its own pay code: Managers have paycode 1, hourly workers have code 2, commission workers have code 3 and pieceworkers have code 4. Use a **switch** to compute each employee's pay based on that employee's paycode. Within the **switch**, prompt the user (i.e., the payroll clerk) to enter the appropriate facts your program needs to calculate each employee's pay based on that employee's paycode.

```
1  // Exercise 2.56 Solution
2  #include<iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include<iomanip>
10
11 using std::setprecision;
12 using std::setiosflags;
13
14 int main()
15 {
16    int payCode, managers = 0, hWorkers = 0, cWorkers = 0;
17    int pWorkers = 0, pieces;
18    double mSalary, hSalary, cSalary, pSalary, hours;
19    double pay;
20
21    cout << "Enter paycode (-1 to end): "
22         << setiosflags( ios::fixed | ios::showpoint );
23    cin >> payCode;
24
25    while ( payCode != -1 ) {
26       switch ( payCode ) {
27          case 1:
28             cout << "Manager selected."
29                  << "\nEnter weekly salary: ";
30             cin >> mSalary;
31             cout << "The manager's pay is $ "
32                  << setprecision( 2 ) << mSalary;
33             ++managers;
34             break;
35          case 2:
36             cout << "Hourly worker selected.\n"
37                  << "Enter the hourly salary: ";
38             cin >> hSalary;
39             cout << "Enter the total hours worked: ";
40             cin >> hours;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
41
42             pay = hours > 40.0 ? ( hours - 40 ) * 1.5 * hSalary + hSalary * 40.0:
43                                  hSalary * hours;
44
45             cout << "Worker's pay is $ " << setprecision( 2 ) << pay << '\n';
46             ++hWorkers;
47             break;
48          case 3:
49             cout << "Commission worker selected.\n"
50                  << "Enter gross weekly sales: ";
51             cin >> cSalary;
52             pay = 250.0 + 0.057 * cSalary;
53             cout << "Commission Worker's pay is $ " << setprecision( 2 )
54                  << pay << '\n';
55             ++cWorkers;
56             break;
57          case 4:
58             cout << "Piece worker selected.\n"
59                  << "Enter number of pieces: ";
60             cin >> pieces;
61             cout << "Enter wage per piece: ";
62             cin >> pSalary;
63             pay = pieces * pSalary;
64             cout << "Piece Worker's pay is $ " << setprecision( 2 )
65                  << pay << '\n';
66             ++pWorkers;
67             break;
68          default:
69             cout << "Invalid pay code.\n";
70             break;
71       }
72
73       cout << "\nEnter paycode (-1 to end): ";
74       cin >> payCode;
75    }
76
77    cout << "\n\nTotal number of managers paid          : "
78         << managers
79         << "\nTotal number of hourly workers paid    : "
80         << hWorkers
81         << "\nTotal number of commission workers paid: "
82         << cWorkers
83         << "\nTotal number of piece workers paid     : "
84         << pWorkers << endl;
85
86    return 0;
87 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter paycode (-1 to end): 3
Commission worker selected.
Enter gross weekly sales: 4000
Commission Worker's pay is $ 478.00

Enter paycode (-1 to end): 2
Hourly worker selected.
Enter the hourly salary: 4.50
Enter the total hours worked: 20
Worker's pay is $ 90.00

Enter paycode (-1 to end): 4
Piece worker selected.
Enter number of pieces: 50
Enter wage per piece: 3
Piece Worker's pay is $ 150.00

Enter paycode (-1 to end): -1


Total number of managers paid          : 0
Total number of hourly workers paid    : 1
Total number of commission workers paid: 1
Total number of piece workers paid     : 1
```

2.57 *(De Morgan's Laws)* In this chapter, we discussed the logical operators **&&**, **||** and **!**. De Morgan's Laws can sometimes make it more convenient for us to express a logical expression. These laws state that the expression **!(***condition1* **&&** *condition2***)** is logically equivalent to the expression **(!***condition1* **||** **!***condition2***)**. Also, the expression **!(***condition1* **||** *condition2***)** is logically equivalent to the expression **(!***condition1***&& !***condition2***)**. Use De Morgan's Laws to write equivalent expressions for each of the following, then write a program to show that both the original expression and the new expression in each case are equivalent:

a) `!( x < 5 ) && !( y >= 7 )`
b) `!( a == b ) || !( g != 5 )`
c) `!( ( x <= 8 ) && ( y > 4 ) )`
d) `!( ( i > 4 ) || ( j <= 6 ) )`

```
1  // Exercise 2.57 Solution
2  #include<iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     int x = 10, y = 1, a = 3, b = 3,
10        g = 5, Y = 1, i = 2, j = 9;
11
12    cout << "current variable values are:" << endl
13         << "x = " << x << ", y = " << y << ", a = " << a
14         << ", b = " << b << endl << "g = " << g << ", Y = "
15         << Y << ", i = " << i << ", j = " << j << "\n\n";
16
17    if ((!(x < 5) && !(y >= 7)) && (!((x < 5) || (y >= 7))))
18       cout << "!(x < 5) && !(y >= 7) is equivalent to"
19            << " !((x < 5) || (y >= 7))" << endl;
20    else
21       cout << "!(x < 5) && !(y >= 7) is not equivalent to"
22            << " !((x < 5) || (y >= 7))" << endl;
23
24    if ((!(a == b) || !(g != 5)) && (!((a == b) && (g != 5))))
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
25       cout << "!(a == b) || !(g != 5) is equivalent to"
26            << " !((a == b) && (g != 5))" << endl;
27    else
28       cout << "!(a == b) || !(g != 5) is not equivalent to"
29            << " !((a == b) && (g != 5))" << endl;
30
31    if (!((x <= 8) && (Y > 4)) && (!((x <= 8) || (Y > 4))))
32       cout << "!((x <= 8) && (Y > 4)) is equivalent to"
33            << " !((x <= 8) || (Y > 4))" << endl;
34    else
35       cout << "!((x <= 8) && (Y > 4)) is not equivalent to"
36            << " !((x <= 8) || (Y > 4))" << endl;
37
38    if (!((i > 4) || (j <= 6)) && !((i > 4) && (j <= 6)))
39       cout << "!((i > 4) || (j <= 6)) is equivalent to"
40            << " !((i > 4) && (j <= 6))" << endl;
41    else
42       cout << "!((i > 4) || (j <= 6)) is not equivalent to"
43            << " !((i > 4) && (j <= 6))" << endl;
44
45    return 0;
46 }
```

```
current variable values are:
x = 10, y = 1, a = 3, b = 3
g = 5, Y = 1, i = 2, j = 9

!(x < 5) && !(y >= 7) is equivalent to !((x < 5) || (y >= 7))
!(a == b) || !(g != 5) is equivalent to !((a == b) && (g != 5))
!((x <= 8) && (Y > 4)) is equivalent to !((x <= 8) || (Y > 4))
!((i > 4) || (j <= 6)) is equivalent to !((i > 4) && (j <= 6))
```

2.58 Write a program that prints the following diamond shape. You may use output statements that print either a single asterisk (*) or a single blank. Maximize your use of repetition (with nested **for** structures) and minimize the number of output statements.

```
    *
   ***
  *****
 *******
*********
 *******
  *****
   ***
    *
```

```
1  // Exercise 2.58 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     // top half
10    for ( int row = 1; row <= 5; ++row ) {
11
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
12         for ( int space = 1; space <= 5 - row; ++space )
13            cout << ' ';
14
15         for ( int asterisk = 1; asterisk <= 2 * row - 1; ++asterisk )
16            cout << '*';
17
18         cout << '\n';
19      }
20
21      // bottom half
22      for ( row = 4; row >= 1; --row ) {
23
24         for ( int space = 1; space <= 5 - row; ++space )
25            cout << ' ';
26
27         for ( int asterisk = 1; asterisk <= 2 * row - 1; ++asterisk )
28            cout << '*';
29
30         cout << '\n';
31      }
32
33      cout << endl;
34
35      return 0;
36   }
```

```
    *
   ***
  *****
 *******
*********
 *******
  *****
   ***
    *
```

2.59 Modify the program you wrote in Exercise 2.58 to read an odd number in the range 1 to 19 to specify the number of rows in the diamond. Your program should then display a diamond of the appropriate size.

```
1   // Exercise 2.59 Solution
2   #include <iostream>
3
4   using std::cout;
5   using std::endl;
6   using std::cin;
7
8   int main()
9   {
10     int size;
11
12     cout << "Enter an odd number for the diamond size (1-19): \n";
13     cin >> size;
14
15     // top half
16     for ( int rows = 1; rows <= size -  2; rows += 2 ) {
17
18        for ( int space = ( size - rows ) / 2; space > 0; --space )
19           cout << ' ';
20
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
21         for ( int asterisk = 1; asterisk <= rows; ++asterisk )
22            cout << '*';
23
24         cout << '\n';
25      }
26
27      // bottom half
28      for ( rows = size; rows >= 0; rows -= 2 ) {
29
30         for ( int space = ( size - rows ) / 2; space > 0; --space )
31            cout << ' ';
32
33         for ( int asterisk = 1; asterisk <= rows; ++asterisk )
34            cout << '*';
35
36         cout << '\n';
37      }
38
39      cout << endl;
40
41      return 0;
42   }
```

```
Enter an odd number for the diamond size (1-19):
15
       *
      ***
     *****
    *******
   *********
  ***********
 *************
***************
 *************
  ***********
   *********
    *******
     *****
      ***
       *
```

2.60 A criticism of the **break** statement and the **continue** statement is that each is unstructured. Actually **break** statements and **continue** statements can always be replaced by structured statements, although doing so can be awkward. Describe in general how you would remove any **break** statement from a loop in a program and replace that statement with some structured equivalent. (Hint: The **break** statement leaves a loop from within the body of the loop. The other way to leave is by failing the loop-continuation test. Consider using in the loop-continuation test a second test that indicates "early exit because of a 'break' condition.") Use the technique you developed here to remove the break statement from the program of Fig. 2.26.

```
1   // Exercise 2.60 Solution
2   #include <iostream>
3
4   using std::cout;
5   using std::endl;
6
7   int main()
8   {
9      bool breakOut = false;
10     int x;
11
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   for ( x = 1; x <= 10 && !breakOut; ++x ) {

      if ( x == 4 )
         breakOut = true;

      cout << x << ' ';
   }

   cout << "\nBroke out of loop at x = " << x << endl;

   return 0;
}
```

```
1 2 3 4
Broke out of loop at x = 5
```

2.61 What does the following program segment do?

```
for ( i = 1; i <= 5; i++ ) {
   for ( j = 1; j <= 3; j++ ) {
      for ( k = 1; k <= 4; k++ )
         cout << '*';
      cout << endl;
   }
   cout << endl;
}
```

```
****
****
****

****
****
****

****
****
****

****
****
****

****
****
****
```

2.62 Describe in general how you would remove any **`continue`** statement from a loop in a program and replace that statement with some structured equivalent. Use the technique you developed here to remove the **`continue`** statement from the program of Fig. 2.27.

```
// Exercise 2.62 Solution
#include <iostream>

using std::cout;
using std::endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
6
7  int main()
8  {
9     for ( int x = 1; x <= 10; ++x ) {
10
11       if ( x == 5 )
12          ++x;
13
14       cout << x << ' ';
15    }
16
17    cout << "\nUsed ++x to skip printing the value 5" << endl;
18
19    return 0;
20 }
```

```
1 2 3 4 6 7 8 9 10
Used ++x to skip printing the value 5
```

2.63 *("The Twelve Days of Christmas" Song)* Write a program that uses repetition and **switch** structures to print the song "The Twelve Days of Christmas." One **switch** structure should be used to print the day (i.e., "First," "Second," etc.). A separate **switch** structure should be used to print the remainder of each verse.

```
1  // Exercise 2.63 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  int main()
8  {
9     for ( int day = 1; day < 13; day++ ) {
10       cout << "On the ";
11
12       switch ( day ) {       // switch for current day
13          case 1:
14             cout << "first";
15             break;
16          case 2:
17             cout << "second";
18             break;
19          case 3:
20             cout << "third";
21             break;
22          case 4:
23             cout << "fourth";
24             break;
25          case 5:
26             cout << "fifth";
27             break;
28          case 6:
29             cout << "sixth";
30             break;
31          case 7:
32             cout << "seventh";
33             break;
34          case 8:
35             cout << "eighth";
36             break;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
37             case 9:
38                cout << "nineth";
39                break;
40             case 10:
41                cout << "tenth";
42                break;
43             case 11:
44                cout << "eleventh";
45                break;
46             case 12:
47                cout << "twelfth";
48                break;
49          }
50
51          cout << " day of Christmas,\nMy true love sent to me:\n";
52
53          switch ( day ) {     // switch for gifts
54             case 12:
55                cout << "\tTwelve drummers drumming,\n";
56             case 11:
57                cout << "\tEleven pipers piping,\n";
58             case 10:
59                cout << "\tTen lords a-leaping,\n";
60             case 9:
61                cout << "\tNine ladies dancing,\n";
62             case 8:
63                cout << "\tEight maids a-milking,\n";
64             case 7:
65                cout << "\tSeven swans a-swimming,\n";
66             case 6:
67                cout << "\tSix geese a-laying,\n";
68             case 5:
69                cout << "\tFive golden rings,\n";
70             case 4:
71                cout << "\tFour calling birds,\n";
72             case 3:
73                cout << "\tThree French hens,\n";
74             case 2:
75                cout << "\tTwo turtle doves, and\n";
76             case 1:
77                cout << "A partridge in a pear tree.\n\n\n";
78          }
79       }
80
81       cout << endl;
82
83       return 0;
84    }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
...
        Three French hens,
        Two turtle doves, and
A partridge in a pear tree.


On the twelfth day of Christmas,
My true love sent to me:
        Twelve drummers drumming,
        Eleven pipers piping,
        Ten lords a-leaping,
        Nine ladies dancing,
        Eight maids a-milking,
        Seven swans a-swimming,
        Six geese a-laying,
        Five golden rings,
        Four calling birds,
        Three French hens,
        Two turtle doves, and
A partridge in a pear tree.
```

Exercise 2.64 corresponds to Section 2.22, "Thinking About Objects."

2.64 Describe in 200 words or less what an automobile is and does. List the nouns and verbs separately. In the text, we stated that each noun might correspond to an object that will need to be built to implement a system, in this case a car. Pick five of the objects you listed, and, for each, list several attributes and several behaviors. Describe briefly how these objects interact with one another and other objects in your description. You have just performed several of the key steps in a typical object-oriented design.

ANS:

A specific type of vehicle containing 4 wheels, doors, seats, windows, steering wheel, brakes, radio, engine, exhaust system, transmission, axels, windshield, mirrors, etc.

A car can accelerate, decelerate, turn, move forward, move backward, stop, etc.

Wheels:

Attributes: size, type, tread depth.
Behaviors: rotate forward, rotate backward.

Doors:

Attributes: type (passenger, trunk, etc.), open or closed.
Behaviors: open, close, lock, unlock.

Steering Wheel:

Attributes: adjustible.
Behaviors: turn left, turn right, adjust up, adjust down.

Brakes:

Attributes: pressed or not pressed, pressure of press.
Behaviors: press, antilock.

Engine:

Attributes: cylinders, radiator, timing belts, spark plugs, etc.
Behaviors: accelerate, decelerate, turn on, turn off.

Interactions:

Person turns the steering wheel which causes the wheels to turn in the appropriate direction.
Person presses the accelerator pedal which causes the engine revolutions per minute to increase, resulting in a faster rotation of the wheels.
Person opens door. Person closes door.
Person releases accelerator pedal which causes engine RPMs to decrease, resulting in a slower rotation of the wheels.
Person presses brake pedal which causes brakes to be applied to wheels slows the rotation of thewheels.

2.65 *(Peter Minuit Problem)* Legend has it that in 1626 Peter Minuit purchased Manhattan for $24.00 in barter. Did he make a good investment? To answer this question, modify the compound interest program of Fig. 2.21 to begin with a principal of $24.00 and to calculate the amount of interest on deposit if that money had been kept on deposit until this year (374 years through 2000). Run the program with interest rates of 5%, 6%, 7%, 8%, 9% and 10% to observe the wonders of compound interest.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

3

Functions Solutions

Solutions

3.11 Show the value of **x** after each of the following statements is performed:

a) `x = fabs( 7.5 );`
ANS: 7.5

b) `x = floor( 7.5 );`
ANS: 7.0

c) `x = fabs( 0.0 );`
ANS: 0.0

d) `x = ceil( 0.0 );`
ANS: 0.0

e) `x = fabs( -6.4 );`
ANS: 6.4

f) `x = ceil( -6.4 );`
ANS: -6.0

g) `x = ceil( -fabs( -8 + floor( -5.5 ) ) );`
ANS: -14.0

3.12 A parking garage charges a $2.00 minimum fee to park for up to three hours. The garage charges an additional $0.50 per hour for each hour *or part thereof* in excess of three hours. The maximum charge for any given 24-hour period is $10.00. Assume that no car parks for longer than 24 hours at a time. Write a program that will calculate and print the parking charges for each of 3 customers who parked their cars in this garage yesterday. You should enter the hours parked for each customer. Your program should print the results in a neat tabular format and should calculate and print the total of yesterday's receipts. The program should use the function **`calculateCharges`** to determine the charge for each customer. Your outputs should appear in the following format:

```
Car       Hours       Charge
1           1.5         2.00
2           4.0         2.50
3          24.0        10.00
TOTAL      29.5        14.50
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 3.12 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;

#include <cmath>

double calculateCharges( double );

main()
{
   double hour, currentCharge, totalCharges = 0.0, totalHours = 0.0;
   int first = 1;

   cout << "Enter the hours parked for 3 cars: ";

   for ( int i = 1; i <= 3; i++ ) {
      cin >> hour;
      totalHours += hour;

      if ( first ) {
         cout << setw( 5 ) << "Car" << setw( 15 ) << "Hours"
              << setw( 15 ) << "Charge\n";
         first = 0;   // prevents this from printing again
      }

      totalCharges += ( currentCharge = calculateCharges( hour ) );
      cout << setiosflags( ios::fixed | ios::showpoint )
           << setw( 3 ) << i << setw( 17 ) << setprecision( 1 ) << hour
           << setw( 15 ) << setprecision( 2 ) << currentCharge << "\n";
   }

   cout << setw( 7 ) << "TOTAL" << setw( 13 ) << setprecision( 1 )
        << totalHours << setw( 15 ) << setprecision( 2 )
        << totalCharges << endl;


   return 0;
}

double calculateCharges( double hours )
{
   double charge;

   if ( hours < 3.0 )
      charge = 2.0;
   else if ( hours < 19.0 )
      charge = 2.0 + .5 * ceil( hours - 3.0 );
   else
      charge = 10.0;

   return charge;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
62  }
```

```
Enter the hours parked for 3 cars: 1 2 3
 Car          Hours        Charge
 1              1.0           2.00
 2              2.0           2.00
 3              3.0           2.00
 TOTAL          6.0           6.00
```

3.13 An application of function **floor** is rounding a value to the nearest integer. The statement

```
y = floor( x + .5 );
```

will round the number **x** to the nearest integer and assign the result to **y**. Write a program that reads several numbers and uses the preceding statement to round each of these numbers to the nearest integer. For each number processed, print both the original number and the rounded number.

```
1  // Exercise 3.13 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <iomanip>
10
11 using std::setprecision;
12 using std::setiosflags;
13
14 #include <cmath>
15
16 void roundToIntegers( void );
17
18 int main()
19 {
20    roundToIntegers();
21
22    return 0;
23 }
24
25 void roundToIntegers( void )
26 {
27    double x, y;
28
29    cout << setiosflags( ios::fixed | ios::showpoint );
30
31    for ( int loop = 1; loop <= 5; loop++ ) {
32       cout << "Enter a number: ";
33       cin >> x;
34       y = floor( x + .5 );
35       cout << x << " rounded is " << setprecision( 1 ) << y << endl;
36    }
37 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter a number: 8.22
8.220000 rounded is 8.0
Enter a number: 7.98
8.0 rounded is 8.0
Enter a number: 4.52
4.5 rounded is 5.0
Enter a number: 6.9999
7.0 rounded is 7.0
Enter a number: 3.345
3.3 rounded is 3.0
```

3.14 Function **floor** can be used to round a number to a specific decimal place. The statement

```
y = floor( x * 10 + .5 ) / 10;
```

rounds **x** to the tenths position (the first position to the right of the decimal point). The statement

```
y = floor( x * 100 + .5 ) / 100;
```

rounds **x** to the hundredths position (the second position to the right of the decimal point). Write a program that defines four functions to round a number **x** in various ways:

a) **roundToInteger(number)**
b) **roundToTenths(number)**
c) **roundToHundredths(number)**
d) **roundToThousandths(number)**

For each value read, your program should print the original value, the number rounded to the nearest integer, the number rounded to the nearest tenth, the number rounded to the nearest hundredth and the number rounded to the nearest thousandth.

```
1  // Exercise 3.14 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6  using std::ios;
7
8  #include <iomanip>
9
10 using std::setprecision;
11 using std::setiosflags;
12 using std::resetiosflags;
13
14 #include <cmath>
15
16 double roundToInteger( double );
17 double roundToTenths( double );
18 double roundToHundreths( double );
19 double roundToThousandths( double );
20
21 int main()
22 {
23    int count;
24    double number;
25
26    cout << "How many numbers do you want to process? "
27         << setiosflags( ios::fixed );
28    cin >> count;
29
30    for ( int i = 0; i < count; ++i ) {
31       cout << "\nEnter number: ";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cin >> number;
      cout << number << " rounded to the nearest integer is:    "
           << setprecision( 0 ) << roundToInteger( number ) << '\n'
           << setiosflags( ios::showpoint )
           << number << " rounded to the nearest tenth is:      "
           << setprecision( 1 ) << roundToTenths( number ) << '\n'
           << number << " rounded to the nearest hundredth is:  "
           << setprecision( 2 ) << roundToHundreths( number ) << '\n'
           << number << " rounded to the nearest thousandth is: "
           << setprecision( 3 ) << roundToThousandths( number ) << '\n'
           << resetiosflags( ios::showpoint );
   }

   return 0;
}

double roundToInteger( double n )
{
   return floor( n + .5 );
}

double roundToTenths( double n )
{
   return floor( n * 10 + .5 ) / 10;
}

double roundToHundreths( double n )
{
   return floor( n * 100 + .5 ) / 100;
}

double roundToThousandths( double n )
{
   return floor( n * 1000 + .5 ) / 1000.0;
}
```

```
How many numbers do you want to process? 1

Enter number: 2.564
2.564000 rounded to the nearest integer is:    3
3. rounded to the nearest tenth is:      2.6
2.6 rounded to the nearest hundredth is:  2.56
2.56 rounded to the nearest thousandth is: 2.564
```

3.15 Answer each of the following questions.

a) What does it mean to choose numbers "at random?"

ANS: Every number has an equal chance of being chosen at any time.

b) Why is the **rand** function useful for simulating games of chance?

ANS: Because it produces a sequence of pseudo-random numbers that when scaled appear to be random.

c) Why would you randomize a program by using **srand**? Under what circumstances is it desirable not to randomize?

ANS: The sequence of numbers produced by the random number generator differ each time function **srand** is called. Not randomizing is useful for debugging purposes—the programmer knows the sequence of numbers.

d) Why is it often necessary to scale and/or shift the values produced by **rand**?

ANS: To produce random values in a specific range.

e) Why is computerized simulation of real-world situations a useful technique?

ANS: It enables more accurate predictions of random events such as cars arriving at a toll booth, people arriving in lines, birds arriving at a tree, etc. The results of a simulation can help determine how many toll booths to have open or how many cashiers to have open at specified times.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

3.16 Write statements that assign random integers to the variable *n* in the following ranges:

a) $1 \leq n \leq 2$

ANS: `n = 1 + rand() % 2;`

b) $1 \leq n \leq 100$

ANS: `n = 1 + rand() % 100;`

c) $0 \leq n \leq 9$

ANS: `n = rand() % 10;`

d) $1000 \leq n \leq 1112$

ANS: `n = 1000 + rand() % 13;`

e) $-1 \leq n \leq 1$

ANS: `n = rand() % 3 - 1;`

f) $-3 \leq n \leq 11$

ANS: `n = rand() % 15 - 3;`

3.17 For each of the following sets of integers, write a single statement that will print a number at random from the set.

a) 2, 4, 6, 8, 10.

ANS: `cout << 2 * ( 1 + rand() % 5 ) ) << '\n';`

b) 3, 5, 7, 9, 11.

ANS: `cout << 1 + 2 * ( 1 + rand() % 5 ) ) << '\n';`

c) 6, 10, 14, 18, 22.

ANS: `cout << 6 + 4 * ( rand() % 5 ) << '\n';`

3.18 Write a function `integerPower(base, exponent )` that returns the value of

$$base^{exponent}$$

For example, `integerPower( 3, 4 ) = 3 * 3 * 3 * 3`. Assume that `exponent` is a positive, nonzero integer and that `base` is an integer. The function `integerPower` should use `for` or `while` to control the calculation. Do not use any math library functions.

ANS:

```
1  // Exercise 3.18 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int integerPower( int, int );
9
10 int main()
11 {
12    int exp, base;
13
14    cout << "Enter base and exponent: ";
15    cin >> base >> exp;
16    cout << base << " to the power " << exp << " is: "
17         << integerPower( base, exp ) << endl;
18
19    return 0;
20 }
21
22 int integerPower( int b, int e )
23 {
24    int product = 1;
25
26    for ( int i = 1; i <= e; ++i )
27       product *= b;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
28
29       return product;
30    }
```

```
Enter base and exponent: 5 2
5 to the power 2 is: 25
```

3.19 Define a function **hypotenuse** that calculates the length of the hypotenuse of a right triangle when the other two sides are given. Use this function in a program to determine the length of the hypotenuse for each of the following triangles. The function should take two arguments of type **double** and return the hypotenuse as a **double**.

Triangle	Side 1	Side 2
1	3.0	4.0
2	5.0	12.0
3	8.0	15.0

```
1  // Exercise 3.19 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <iomanip>
10
11 using std::setprecision;
12 using std::setiosflags;
13
14 #include <cmath>
15
16 double hypotenuse( double, double );
17
18 int main()
19 {
20    double side1, side2;
21
22    cout << setiosflags( ios::fixed | ios::showpoint );
23
24    for ( int i = 1; i <= 3; ++i ) {
25       cout << "\nEnter 2 sides of right triangle: ";
26       cin >> side1 >> side2;
27       cout << "Hypotenuse:  " << setprecision( 1 )
28            << hypotenuse( side1, side2 ) << endl;
29    }
30
31    return 0;
32 }
33
34 double hypotenuse( double s1, double s2 )
35 {
36    return sqrt( s1 * s1 + s2 * s2 );
37 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter 2 sides of right triangle: 4 5
Hypotenuse:  6.4

Enter 2 sides of right triangle: 3 4
Hypotenuse:  5.0

Enter 2 sides of right triangle: 12 7
Hypotenuse:  13.9
```

3.20 Write a function **multiple** that determines for a pair of integers whether the second integer is a multiple of the first. The function should take two integer arguments and return **true** if the second is a multiple of the first, **false** otherwise. Use this function in a program that inputs a series of pairs of integers.

```
1  // Exercise 3.20 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  bool multiple( int, int );
9
10 int main()
11 {
12    int x, y;
13
14    for ( int i = 1; i <= 3; ++i ) {
15       cout << "Enter two integers: ";
16       cin >> x >> y;
17
18       if ( multiple( x, y ) )
19          cout << y << " is a multiple of " << x << "\n\n";
20       else
21          cout << y << " is not a multiple of " << x << "\n\n";
22    }
23
24    cout << endl;
25
26    return 0;
27 }
28
29 bool multiple( int a, int b )
30 {
31    return !( b % a );
32 }
```

```
Enter two integers: 3 4
4 is not a multiple of 3

Enter two integers: 12 3
3 is not a multiple of 12

Enter two integers: 3 12
12 is a multiple of 3
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

3.21 Write a program that inputs a series of integers and passes them one at a time to function **even**, which uses the modulus operator to determine whether an integer is even. The function should take an integer argument and return **true** if the integer is even and **false** otherwise.

```
// Exercise 3.21 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

bool even( int );

int main()
{
   int x;

   for ( int i = 1; i <= 3; ++i ) {
      cout << "Enter an integer: ";
      cin >> x;

      if ( even( x ) )
         cout << x << " is an even integer\n\n";
      else
         cout << x << " is an odd integer\n\n";
   }

   cout << endl;

   return 0;
}

bool even( int a )
{
   return !( a % 2 );
}
```

```
Enter an integer: 8
8 is an even integer

Enter an integer: 3
3 is an odd integer

Enter an integer: 99
99 is an odd integer
```

3.22 Write a function that displays at the left margin of the screen a solid square of asterisks whose side is specified in integer parameter **side**. For example, if **side** is **4**, the function displays

```
****
****
****
****
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 3.22 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

void square( int );

int main()
{
   int side;

   cout << "Enter side: ";
   cin >> side;
   cout << '\n';

   square( side );

   cout << endl;

   return 0;
}

void square( int s )
{
   for ( int row = 1; row <= s; ++row ) {

      for ( int col = 1; col <= s; ++col )
         cout << '*';

      cout << '\n';
   }
}
```

```
Enter side: 8

********
********
********
********
********
********
********
********
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

3.23 Modify the function created in Exercise 3.22 to form the square out of whatever character is contained in character parameter **fillCharacter**. Thus, if **side** is **5** and **fillCharacter** is "**#**," then this function should print

```
#####
#####
#####
#####
#####
```

```
1  // Exercise 3.23 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  void square( int, char );
9
10 int main()
11 {
12    int s;
13    char c;
14
15    cout << "Enter a character and the side length: ";
16    cin >> c >> s;
17    cout << '\n';
18
19    square( s, c );
20
21    cout << endl;
22
23    return 0;
24 }
25
26 void square( int side, char fillCharacter )
27 {
28    for ( int row = 1; row <= side; ++row ) {
29
30       for ( int col = 1; col <= side; ++col )
31          cout << fillCharacter;
32
33       cout << '\n';
34    }
35 }
```

```
Enter a character and the side length: H 5

HHHHH
HHHHH
HHHHH
HHHHH
HHHHH
```

3.24 Use techniques similar to those developed in Exercises 3.22 and 3.23 to produce a program that graphs a wide range of shapes.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

3.25 Write program segments that accomplish each of the following:

a) Calculate the integer part of the quotient when integer **a** is divided by integer **b**.

b) Calculate the integer remainder when integer **a** is divided by integer **b**.

c) Use the program pieces developed in a) and b) to write a function that inputs an integer between **1** and **32767** and prints it as a series of digits, each pair of which is separated by two spaces. For example, the integer **4562** should be printed as

```
4  5  6  2
```

```
// Exercise 3.25 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <iomanip>

using std::setw;

int quotient( int, int );
int remainder( int, int );

int main()
{
   int number, divisor = 10000;

   cout << "Enter an integer between 1 and 32767: ";
   cin >> number;

   cout << "The digits in the number are:\n";

   while ( number >= 1 ) {

      if ( number >= divisor ) {
         cout << setw( 3 ) << quotient( number, divisor );
         number = remainder( number, divisor );
         divisor = quotient( divisor, 10 );
      }
      else
         divisor = quotient( divisor, 10 );
   }

   cout << endl;

   return 0;
}

// Part A: determine quotient using integer division
int quotient( int a, int b )
{
   return a / b;
}

// Part B: determine remainder using the modulus operator
int remainder( int a, int b )
{
   return a % b;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
50 }
```

```
Enter an integer between 1 and 32767: 6758
The digits in the number are:
  6  7  5  8
```

3.26 Write a function that takes the time as three integer arguments (for hours, minutes and seconds), and returns the number of seconds since the last time the clock "struck 12." Use this function to calculate the amount of time in seconds between two times, both of which are within one 12-hour cycle of the clock.

```
1  // Exercise 3.26 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  unsigned seconds( unsigned, unsigned, unsigned );
9
10 int main()
11 {
12    unsigned hours, minutes, secs, temp;
13
14    cout << "Enter the first time as three integers: ";
15    cin >> hours >> minutes >> secs;
16
17    temp = seconds( hours, minutes, secs );
18
19    cout << "Enter the second time as three integers: ";
20    cin >> hours >> minutes >> secs;
21
22    cout << "The difference between the times is "
23         << seconds( hours, minutes, secs ) - temp
24         << " seconds" << endl;
25
26    return 0;
27 }
28
29 unsigned seconds( unsigned h, unsigned m, unsigned s )
30 {
31    return 3600 * ( h >= 12 ? h - 12 : h ) + 60 * m + s;
32 }
```

```
Enter the first time as three integers: 5 33 45
Enter the second time as three integers: 9 22 8
The difference between the times is 13703 seconds
```

3.27 Implement the following integer functions:

a) Function **`celsius`** returns the Celsius equivalent of a Fahrenheit temperature.

b) Function **`fahrenheit`** returns the Fahrenheit equivalent of a Celsius temperature.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

c) Use these functions to write a program that prints charts showing the Fahrenheit equivalents of all Celsius temperatures from 0 to 100 degrees, and the Celsius equivalents of all Fahrenheit temperatures from 32 to 212 degrees. Print the outputs in a neat tabular format that minimizes the number of lines of output while remaining readable.

```
// Exercise 3.27 Solution
#include <iostream>

using std::cout;
using std::endl;

int celcius( int );
int fahrenheit( int );

int main()
{
   cout << "Fahrenheit equivalents of Celcius temperatures:\n"
        << "Celcius\t\tFahrenheit\n";

   for ( int i = 0; i <= 100; ++i )
      cout << i << "\t\t" << fahrenheit( i ) << '\n';

   cout << "\nCelcius equivalents of Fahrenheit temperatures:"
        << "\nFahrenheit\tCelcius\n";

   for ( int j = 32; j <= 212; ++j )
      cout << j << "\t\t" << celcius( j ) << '\n';

   cout << endl;

   return 0;
}

int celcius( int fTemp )
{
   return static_cast< int > ( 5.0 / 9.0 * ( fTemp - 32 ) );
}

int fahrenheit( int cTemp )
{
   return static_cast< int > ( 9.0 / 5.0 * cTemp + 32 );
}
```

```
Fahrenheit equivalents of Celcius temperatures:
Celcius         Fahrenheit
0               32
1               33
2               35
...
Celcius equivalents of Fahrenheit temperatures:
Fahrenheit      Celcius
32              0
33              0
34              1
...
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

3.28 Write a function that returns the smallest of three double-precision, floating-point numbers.

```
// Exercise 3.28 Solution
#include <iostream>
using std::cout;
using std::endl;
using std::cin;

double smallest3( double, double, double );

int main()
{
   double x, y, z;

   cout << "Enter three numbers: ";
   cin >> x >> y >> z;
   cout << "The smallest value is " << smallest3( x, y, z ) << endl;

   return 0;
}

double smallest3( double smallest, double b, double c )
{
   if ( b < smallest && c > smallest )
      return b;
   else if ( c < smallest )
      return c;
   else
      return smallest;
}
```

```
Enter three numbers: 4.3 6.77 9.76
The smallest value is 4.3
```

3.29 An integer number is said to be a *perfect number* if the sum of its factors, including 1 (but not the number itself), is equal to the number. For example, 6 is a perfect number, because 6 = 1 + 2 + 3. Write a function **`perfect`** that determines whether parameter **`number`** is a perfect number. Use this function in a program that determines and prints all the perfect numbers between 1 and 1000. Print the factors of each perfect number to confirm that the number is indeed perfect. Challenge the power of your computer by testing numbers much larger than 1000.

```
// Exercise 3.29 Solution
#include <iostream>

using std::cout;
using std::endl;

bool perfect( int );

int main()
{
   cout << "For the integers from 1 to 1000:\n";

   for ( int j = 2; j <= 1000; ++j )
      if ( perfect( j ) )
         cout << j << " is perfect\n";

   cout << endl;

   return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}

bool perfect( int value )
{
   int factorSum = 1;

   for ( int i = 2; i <= value / 2; ++i )
      if ( value % i == 0 )
         factorSum += i;

   return factorSum == value ? true : false;
}
```

```
For the integers from 1 to 1000:
6 is perfect
28 is perfect
496 is perfect
```

3.30 An integer is said to be *prime* if it is divisible by only 1 and itself. For example, 2, 3, 5 and 7 are prime, but 4, 6, 8 and 9 are not.

a) Write a function that determines whether a number is prime.

b) Use this function in a program that determines and prints all the prime numbers between 1 and 10,000. How many of these 10,000 numbers do you really have to test before being sure that you have found all the primes?

c) Initially, you might think that $n/2$ is the upper limit for which you must test to see whether a number is prime, but you need only go as high as the square root of n. Why? Rewrite the program, and run it both ways. Estimate the performance improvement.

```
// Exercise 3.30 Part A Solution
#include <iostream>
using std::cout;

#include <iomanip>

using std::setw;

bool prime( int );

int main()
{
   int count = 0;

   cout << "The prime numbers from 1 to 10000 are:\n";

   for ( int loop = 2; loop <= 10000; ++loop )
      if ( prime( loop ) ) {
         ++count;
         cout << setw( 6 ) << loop;

         if ( count % 10 == 0 )
            cout << '\n';
      }

   return 0;
}

bool prime( int n )
{
   for ( int loop2 = 2; loop2 <= n / 2; loop2++ )
      if ( n % loop2 == 0 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
33          return false;
34
35       return true;
36    }
```

```
The prime numbers from 1 to 10000 are:
     2     3     5     7    11    13    17    19    23    29
    31    37    41    43    47    53    59    61    67    71
    73    79    83    89    97   101   103   107   109   113
   127   131   137   139   149   151   157   163   167   173
   179   181   191   193   197   199   211   223   227   229
   233   239   241   251   257   263   269   271   277   281
   283   293   307   311   313   317   331   337   347   349
   353   359   367   373   379   383   389   397   401   409
   419   421   431   433   439   443   449   457   461   463
  ...
  9739  9743  9749  9767  9769  9781  9787  9791  9803  9811
  9817  9829  9833  9839  9851  9857  9859  9871  9883  9887
  9901  9907  9923  9929  9931  9941  9949  9967  9973
```

```
1   // Exercise 3.30 Part C Solution
2   #include <iostream>
3
4   using std::cout;
5
6   #include <iomanip>
7   using std::setw;
8
9   #include <cmath>
10
11  bool prime( int n );
12
13  int main()
14  {
15     int count = 0;
16
17     cout << "The prime numbers from 1 to 10000 are:\n";
18
19     for ( int j = 2; j <= 10000; ++j )
20        if ( prime( j ) ) {
21           ++count;
22           cout << setw( 5 ) << j;
23
24           if ( count % 10 == 0 )
25              cout << '\n';
26        }
27
28     return 0;
29  }
30
31  bool prime( int n )
32  {
33     for ( int i = 2; i <= static_cast< int > ( sqrt( n ) ); ++i )
34        if ( n % i == 0 )
35           return false;
36
37     return true;
38  }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
The prime numbers from 1 to 10000 are:
     2     3     5     7    11    13    17    19    23    29
    31    37    41    43    47    53    59    61    67    71
    73    79    83    89    97   101   103   107   109   113
   127   131   137   139   149   151   157   163   167   173
   179   181   191   193   197   199   211   223   227   229
   233   239   241   251   257   263   269   271   277   281
   283   293   307   311   313   317   331   337   347   349
   353   359   367   373   379   383   389   397   401   409
   419   421   431   433   439   443   449   457   461   463
  ...
  9739  9743  9749  9767  9769  9781  9787  9791  9803  9811
  9817  9829  9833  9839  9851  9857  9859  9871  9883  9887
  9901  9907  9923  9929  9931  9941  9949  9967  9973
```

3.31 Write a function that takes an integer value and returns the number with its digits reversed. For example, given the number 7631, the function should return 1367.

```
1  // Exercise 3.31 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <iomanip>
9
10 using std::setw;
11 using std::setfill;
12
13 int reverseDigits( int );
14 int width( int );
15
16 int main()
17 {
18    int number;
19
20    cout << "Enter a number between 1 and 9999: ";
21    cin >> number;
22
23    cout << "The number with its digits reversed is: "
24         << setw( ( width( number ) ) ) << setfill( '0' )
25         << reverseDigits( number )
26         << endl;
27
28    return 0;
29 }
30
31 int reverseDigits( int n )
32 {
33    int reverse = 0, divisor = 1000, multiplier = 1;
34
35    while ( n > 10 ) {
36
37       if ( n >= divisor ) {
38          reverse += n / divisor * multiplier;
39          n %= divisor;
40          divisor /= 10;
41          multiplier *= 10;
42       }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      else
         divisor /= 10;
   }

   reverse += n * multiplier;
   return reverse;
}

int width( int n )
{
    if ( n /= 1000 )
       return 4;
    else if ( n /= 100 )
       return 3;
    else if ( n /= 10 )
       return 2;
    else
       return 1;
}
```

```
Enter a number between 1 and 9999: 8765
The number with its digits reversed is: 5678
```

3.32 The *greatest common divisor (GCD)* of two integers is the largest integer that evenly divides each of the numbers. Write a function **gcd** that returns the greatest common divisor of two integers.

```
// Exercise 3.32 Solution
#include <iostream>

using std::cout;
using std::cin;

int gcd( int, int );

int main()
{
   int a, b;

   for ( int j = 1; j <= 5; ++j ) {
      cout << "Enter two integers: ";
      cin >> a >> b;
      cout << "The greatest common divisor of " << a << " and "
           << b << " is " <<  gcd( a, b ) << "\n\n";
   }

   return 0;
}

int gcd( int x, int y )
{
   int greatest = 1;

   for ( int i = 2; i <= ( ( x < y ) ? x: y ); ++i )
      if ( x % i == 0 && y % i == 0 )
         greatest = i;

   return greatest;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter two integers: 6 8
The greatest common divisor of 6 and 8 is 2

Enter two integers: 789 4
The greatest common divisor of 789 and 4 is 1

Enter two integers: 9999 27
The greatest common divisor of 9999 and 27 is 9

Enter two integers: 73652 8
The greatest common divisor of 73652 and 8 is 4

Enter two integers: 99 11
The greatest common divisor of 99 and 11 is 11
```

3.33 Write a function **qualityPoints** that inputs a student's average and returns 4 if a student's average is 90–100, 3 if the average is 80–89, 2 if the average is 70–79, 1 if the average is 60–69 and 0 if the average is lower than 60.

```
1  // Exercise 3.33 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  int qualityPoints( int );
9
10 int main()
11 {
12    int average;
13
14    for ( int loop = 1; loop <= 5; ++loop ) {
15       cout << "\nEnter the student's average: ";
16       cin >> average;
17       cout << average << " on a 4 point scale is "
18            << qualityPoints( average ) << '\n';
19    }
20
21    cout << endl;
22    return 0;
23 }
24
25 int qualityPoints( int average )
26 {
27    if ( average >= 90 )
28       return 4;
29    else if ( average >= 80 )
30       return 3;
31    else if ( average >= 70 )
32       return 2;
33    else if ( average >= 60 )
34       return 1;
35    else
36       return 0;
37 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter the student's average: 99
99 on a 4 point scale is 4

Enter the student's average: 72
72 on a 4 point scale is 2

Enter the student's average: 88
88 on a 4 point scale is 3

Enter the student's average: 65
65 on a 4 point scale is 1

Enter the student's average: 33
33 on a 4 point scale is 0
```

3.34 Write a program that simulates coin tossing. For each toss of the coin, the program should print **Heads** or **Tails**. Let the program toss the coin 100 times and count the number of times each side of the coin appears. Print the results. The program should call a separate function **flip** that takes no arguments and returns **0** for tails and **1** for heads. *Note:* If the program realistically simulates the coin tossing, then each side of the coin should appear approximately half the time.

```
1  // Exercise 3.34 Solution
2
3  #include <iostream>
4
5  using std::cout;
6  using std::endl;
7
8  #include <cstdlib>
9  #include <ctime>
10
11 int flip( void );
12
13 int main()
14 {
15    int headCount = 0, tailCount = 0;
16
17    srand( time( 0 ) );
18
19    for ( int loop = 1; loop <= 100; loop++ ) {
20
21       if ( flip() == 0 ) {
22          tailCount++;
23          cout << "Tails ";
24       }
25       else {
26          headCount++;
27          cout << "Heads ";
28       }
29
30       if ( loop % 10 == 0 )
31          cout << '\n';
32    }
33
34    cout << "\nThe total number of Heads was "
35         << headCount << "\nThe total number of Tails was "
36         << tailCount << endl;
37
38    return 0;
39 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
40
41  int flip( void )
42  {
43     return rand() % 2;
44  }
```

```
Tails Heads Heads Heads Heads Tails Tails Tails Tails Tails
Tails Heads Heads Tails Tails Heads Tails Tails Heads Tails
Heads Tails Heads Heads Tails Tails Tails Heads Tails Heads
Heads Heads Heads Tails Heads Heads Heads Tails Heads Heads
Heads Heads Heads Heads Heads Heads Tails Heads Tails Heads
Heads Tails Tails Heads Heads Heads Heads Heads Tails Tails
Tails Heads Heads Heads Tails Tails Heads Heads Heads Heads
Heads Tails Tails Heads Tails Heads Tails Tails Heads Heads
Heads Tails Heads Tails Tails Tails Heads Tails Heads Heads
Heads Heads Heads Heads Heads Tails Tails Heads Heads Heads

The total number of Heads was 60
The total number of Tails was 40
```

3.35 Computers are playing an increasing role in education. Write a program that will help an elementary school student learn multiplication. Use **rand** to produce two positive one-digit integers. It should then type a question such as:

```
How much is 6 times 7?
```

The student then types the answer. Your program checks the student's answer. If it is correct, print **"Very good!"**, and then ask another multiplication question. If the answer is wrong, print **"No. Please try again."** and then let the student try the same question again repeatedly until the student finally gets it right.

```
1  // Exercise 3.35 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstdlib>
9  #include <ctime>
10
11 void multiplication( void );
12
13 int main()
14 {
15    srand( time( 0 ) );
16    multiplication();
17    return 0;
18 }
19
20 void multiplication( void )
21 {
22    int x, y, response = 0;
23
24    cout << "Enter -1 to End.\n";
25
26    while ( response != -1 ) {
27       x = rand() % 10;
28       y = rand() % 10;
29
30       cout << "How much is " << x << " times " << y << " (-1 to End)? ";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
31         cin >> response;
32
33         while ( response != -1 && response != x * y ) {
34            cout << "No. Please try again.\n? ";
35            cin >> response;
36         }
37
38         if ( response != -1 )
39            cout << "Very good!\n\n";
40      }
41
42      cout << "That's all for now. Bye." << endl;
43   }
```

```
Enter -1 to End.
How much is 4 times 9 (-1 to End)? 36
Very good!

How much is 7 times 0 (-1 to End)? 0
Very good!

How much is 7 times 8 (-1 to End)? 55
No. Please try again.
? 56
Very good!

How much is 5 times 0 (-1 to End)? -1
That's all for now. Bye.
```

3.36 The use of computers in education is referred to as *computer-assisted instruction* (CAI). One problem that develops in CAI environments is student fatigue. This can be eliminated by varying the computer's dialogue to hold the student's attention. Modify the program of Exercise 3.35 so the various comments are printed for each correct answer and each incorrect answer as follows:

Responses to a correct answer

```
Very good!
Excellent!
Nice work!
Keep up the good work!
```

Responses to an incorrect answer

```
No. Please try again.
Wrong. Try once more.
Don't give up!
No. Keep trying.
```

Use the random number generator to choose a number from 1 to 4 to select an appropriate response to each answer. Use a **`switch`** structure to issue the responses.

```
1  // Exercise 3.36 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstdlib>
9  #include <ctime>
10
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
11 void correctMessage( void );
12 void incorrectMessage( void );
13 void multiplication( void );
14
15 int main()
16 {
17    srand( time( 0 ) );
18    multiplication();
19
20    return 0;
21 }
22
23 void correctMessage( void )
24 {
25    switch ( rand() % 4 ) {
26       case 0:
27          cout << "Very good!";
28          break;
29       case 1:
30          cout << "Excellent!";
31          break;
32       case 2:
33          cout << "Nice work!";
34          break;
35       case 3:
36          cout << "Keep up the good work!";
37          break;
38    }
39
40    cout << "\n\n";
41 }
42
43 void incorrectMessage( void )
44 {
45    switch ( rand() % 4 ) {
46       case 0:
47          cout << "No. Please try again.";
48          break;
49       case 1:
50          cout << "Wrong. Try once more.";
51          break;
52       case 2:
53          cout << "Don't give up!";
54          break;
55       case 3:
56          cout << "No. Keep trying.";
57          break;
58    }
59
60    cout << "\n? ";
61 }
62
63 void multiplication( void )
64 {
65    int x, y, response = 0;
66
67    while ( response != -1 ) {
68       x = rand() % 10;
69       y = rand() % 10;
70
71       cout << "How much is " << x << " times " << y
72            << " (-1 to End)? ";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cin >> response;

      while ( response != -1 && response != x * y ) {
         incorrectMessage();
         cin >> response;
      }

      if ( response != -1 ) {
         correctMessage();
      }
   }

   cout << "That's all for now. Bye." << endl;
}
```

```
Enter -1 to End.
How much is 4 times 9 (-1 to End)? 36
Very good!

How much is 7 times 0 (-1 to End)? 0
Nice Work!

How much is 7 times 8 (-1 to End)? 55
No. Please try again.
? 56
Excellent!

How much is 5 times 0 (-1 to End)? -1
That's all for now. Bye.
```

3.37 More sophisticated computer-aided instruction systems monitor the student's performance over a period of time. The decision to begin a new topic is often based on the student's success with previous topics. Modify the program of Exercise 3.36 to count the number of correct and incorrect responses typed by the student. After the student types 10 answers, your program should calculate the percentage of correct responses. If the percentage is lower than 75 percent, your program should print **"Please ask your instructor for extra help"** and then terminate.

```
// Exercise 3.37 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstdlib>
#include <ctime>

void multiplication( void );
void correctMessage( void );
void incorrectMessage( void );

int main()
{
   srand( time( 0 ) );
   multiplication();

   return 0;
}

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
23  void multiplication( void )
24  {
25     int x, y, response, right = 0, wrong = 0;
26
27     for ( int i = 1; i <= 10; ++i ) {
28        x = rand() % 10;
29        y = rand() % 10;
30
31        cout << "How much is " << x << " times " << y << "? ";
32        cin >> response;
33
34        while ( response != x * y ) {
35           ++wrong;
36           incorrectMessage();
37           cin >> response;
38        }
39
40        ++right;
41        correctMessage();
42     }
43
44     if ( static_cast< double > ( right ) / ( right + wrong ) < .75 )
45        cout << "Please ask your instructor for extra help.\n";
46
47     cout << "That's all for now. Bye." << endl;
48  }
49
50  void correctMessage( void )
51  {
52     switch ( rand() % 4 ) {
53        case 0:
54           cout << "Very good!";
55           break;
56        case 1:
57           cout << "Excellent!";
58           break;
59        case 2:
60           cout << "Nice work!";
61           break;
62        case 3:
63           cout << "Keep up the good work!";
64           break;
65     }
66
67     cout << "\n\n";
68  }
69
70  void incorrectMessage( void )
71  {
72     switch ( rand() % 4 ) {
73        case 0:
74           cout << "No. Please try again.";
75           break;
76        case 1:
77           cout << "Wrong. Try once more.";
78           break;
79        case 2:
80           cout << "Don't give up!";
81           break;
82        case 3:
83           cout << "No. Keep trying.";
84           break;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
85     }
86
87     cout << "\n? ";
88  }
```

```
...

How much is 3 times 7? 21
Nice work!

How much is 5 times 9? 45
Very good!

That's all for now. Bye.
```

3.38 Write a program that plays the game of "guess the number" as follows: Your program chooses the number to be guessed by selecting an integer at random in the range 1 to 1000. The program then types:

```
I have a number between 1 and 1000.
Can you guess my number?
Please type your first guess.
```

The player then types a first guess. The program responds with one of the following:

```
1. Excellent! You guessed the number!
   Would you like to play again (y or n)?
2. Too low. Try again.
3. Too high. Try again.
```

If the player's guess is incorrect, your program should loop until the player finally gets the number right. Your program should keep telling the player **Too high** or **Too low** to help the player "zero in" on the correct answer.

```
1  // Exercise 3.38 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6
7  #include <cstdlib>
8  #include <ctime>
9
10 void guessGame( void );
11 bool isCorrect( int, int );
12
13 int main()
14 {
15    srand( time( 0 ) );
16    guessGame();
17
18    return 0;
19 }
20
21 void guessGame( void )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   int answer, guess;
   char response;

   do {
      answer = 1 + rand() % 1000;
      cout << "\nI have a number between 1 and 1000.\n"
           << "Can you guess my number?\nPlease type your"
           << " first guess.\n? ";
      cin >> guess;

      while ( !isCorrect( guess, answer ) )
         cin >> guess;

      cout << "\nExcellent! You guessed the number!\n"
           << "Would you like to play again?\nPlease type (y/n)? ";
      cin >> response;

   } while ( response == 'y' );
}

bool isCorrect( int g, int a )
{
   if ( g == a )
      return true;

   if ( g < a )
      cout << "Too low. Try again.\n? ";
   else
      cout << "Too high. Try again.\n? ";

   return false;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
I have a number between 1 and 1000.
Can you guess my number?
Please type your first guess.
? 500
Too high. Try again.
? 250
Too low. Try again.
? 375
Too low. Try again.
? 438
Too high. Try again.
? 405
Too high. Try again.
? 380
Too low. Try again.
? 393
Too low. Try again.
? 399
Too high. Try again.
? 396
Too low. Try again.
? 398
Too high. Try again.
? 397

Excellent! You guessed the number!
Would you like to play again?
Please type (y/n)? n
```

3.39 Modify the program of Exercise 3.38 to count the number of guesses the player makes. If the number is 10 or fewer, print **Either you know the secret or you got lucky!** If the player guesses the number in 10 tries, then print **Ahah! You know the secret!** If the player makes more than 10 guesses, then print **You should be able to do better!** Why should it take no more than 10 guesses? Well, with each "good guess" the player should be able to eliminate half of the numbers. Now show why any number from 1 to 1000 can be guessed in 10 or fewer tries.

```
1  // Exercise 3.39 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6
7  #include <cstdlib>
8  #include <ctime>
9
10 void guessGame( void );
11 bool isCorrect( int, int );
12 void display( int );
13
14 int main()
15 {
16    srand( time( 0 ) );
17    guessGame();
18
19    return 0;
20 }
21
22 void guessGame( void )
23 {
24    int answer, guess, total = 1;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
25    char response;
26
27    do {
28       answer = 1 + rand() % 1000;
29       cout << "I have a number between 1 and 1000."
30            << "\nCan you guess my number?\nPlease type"
31            << " your first guess.\n? ";
32       cin >> guess;
33
34       while ( !isCorrect( guess, answer ) ) {
35          cin >> guess;
36          ++total;
37       }
38
39       cout << "\nExcellent! You guessed the number!\n";
40
41       display( total );
42
43       cout << "Would you like to play again?\nPlease type (y/n)? ";
44       cin >> response;
45
46    } while ( response == 'y' );
47 }
48
49 bool isCorrect( int g, int a )
50 {
51    if ( g == a )
52       return true;
53
54    if ( g < a )
55       cout << "Too low. Try again.\n? ";
56    else
57       cout << "Too high. Try again.\n? ";
58
59    return false;
60 }
61
62 void display( int t )
63 {
64    if ( t < 10 )
65       cout << "Either you know the secret or you got lucky!\n";
66    else if ( t == 10 )
67       cout << "Ahah! You know the secret!\n";
68    else
69       cout << "You should be able to do better!\n\n";
70 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
I have a number between 1 and 1000.
Can you guess my number?
Please type your first guess.
? 500
Too high. Try again.
? 250
Too low. Try again.
? 375
Too high. Try again.
? 313
Too low. Try again.
? 344
Too low. Try again.
? 360
Too high. Try again.
? 352
Too high. Try again.
? 348
Too low. Try again.
? 350
Too low. Try again.
? 351

Excellent! You guessed the number!
Ahah! You know the secret!
Would you like to play again?
Please type (y/n)? n
Press any key to continue
```

3.40 Write a recursive function **power(base, exponent)** that, when invoked, returns

$$base^{exponent}$$

For example, **power(3, 4) = 3 * 3 * 3 * 3**. Assume that **exponent** is an integer greater than or equal to 1. *Hint:* The recursion step would use the relationship

$$base^{exponent} = base \cdot base^{exponent - 1}$$

and the terminating condition occurs when **exponent** is equal to **1** because

$$base^{1} = base$$

```
1  // Exercise 3.40 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  long power( long, long );
9
10 int main()
11 {
12    long b, e;
13
14    cout << "Enter a base and an exponent: ";
15    cin >> b >> e;
16    cout << b << " raised to the " << e << " is "
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
17          << power( b, e ) << endl;
18
19       return 0;
20    }
21
22    long power( long base, long exponent )
23    {
24       return exponent == 1 ? base : base * power( base, exponent - 1 );
25    }
```

```
Enter a base and an exponent: 3 4
3 raised to the 4 is 81
```

3.41 The Fibonacci series

0, 1, 1, 2, 3, 5, 8, 13, 21, …

begins with the terms 0 and 1 and has the property that each succeeding term is the sum of the two preceding terms. a) Write a *nonrecursive* function **fibonacci(n)** that calculates the *n*th Fibonacci number. b) Determine the largest Fibonacci number that can be printed on your system. Modify the program of part a) to use **double** instead of **int** to calculate and return Fibonacci numbers, and use this modified program to repeat part b).

```
1   // Exercise 3.41 Part A Solution
2   // NOTE: This exercise was accidently placed in this
3   // chapter. The solution utilizes ARRAYS which are
4   // introduced in the next chapter.
5   #include <iostream>
6
7   using std::cout;
8   using std::endl;
9
10  int MAX = 22;    // the maximum number for which the
11                   // fibonacci value can be calculated
12                   // on 2-byte integer systems
13
14  int fibonacci( int );
15
16  int main()
17  {
18     for ( int loop = 0; loop <= MAX; ++loop )
19        cout << "fibonacci(" << loop << ") = " << fibonacci( loop )
20             << "\n";
21
22     cout << endl;
23     return 0;
24  }
25
26  int fibonacci( int n )
27  {
28     int fib[ 23 ];
29
30     fib[ 0 ] = 0;
31     fib[ 1 ] = 1;
32
33     for ( int j = 2; j <= n; ++j )
34        fib[ j ] = fib[ j - 1 ] + fib[ j - 2 ];
35
36     return fib[ n ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}
```

```
fibonacci(0) = 0
fibonacci(1) = 1
fibonacci(2) = 1
fibonacci(3) = 2
fibonacci(4) = 3
fibonacci(5) = 5
fibonacci(6) = 8
fibonacci(7) = 13
fibonacci(8) = 21
fibonacci(9) = 34
fibonacci(10) = 55
fibonacci(11) = 89
fibonacci(12) = 144
fibonacci(13) = 233
fibonacci(14) = 377
fibonacci(15) = 610
fibonacci(16) = 987
fibonacci(17) = 1597
fibonacci(18) = 2584
fibonacci(19) = 4181
fibonacci(20) = 6765
fibonacci(21) = 10946
fibonacci(22) = 17711
fibonacci(23) = 28658
```

```
// Exercise 3.41 Part B Solution
// NOTE: This exercise was accidently placed in this
// chapter. The solution utiliizes ARRAYS which are
// introduced in the next chapter.
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <iomanip>

using std::setprecision;
using std::setiosflags;

double fibonacci( int );

int main()
{
   cout << setiosflags( ios::fixed | ios::showpoint );

   for ( int loop = 0; loop < 100; ++loop )
      cout << setprecision( 1 ) << "fibonacci(" << loop << ") = "
           << fibonacci( loop ) << endl;

   return 0;
}

double fibonacci( int n )
{
   double fib[ 100 ];

   fib[ 0 ] = 0.0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
34      fib[ 1 ] = 1.0;
35
36      for ( int j = 2; j <= n; j++ )
37         fib[ j ] = fib[ j - 1 ] + fib[ j - 2 ];
38
39      return fib[ n ];
40   }
```

```
fibonacci(0) = 0.0
fibonacci(1) = 1.0
fibonacci(2) = 1.0
fibonacci(3) = 2.0
fibonacci(4) = 3.0
fibonacci(5) = 5.0
fibonacci(6) = 8.0
fibonacci(7) = 13.0
...
fibonacci(96) = 51680708854858326000.0
fibonacci(97) = 83621143489848426000.0
fibonacci(98) = 135301852344706760000.0
fibonacci(99) = 218922995834555200000.0
```

3.42 *(Towers of Hanoi)* Every budding computer scientist must grapple with certain classic problems. The Towers of Hanoi (see Fig.3.28) is one of the most famous of these. Legend has it that in a temple in the Far East, priests are attempting to move a stack of disks from one peg to another. The initial stack had 64 disks threaded onto one peg and arranged from bottom to top by decreasing size. The priests are attempting to move the stack from this peg to a second peg under the constraints that exactly one disk is moved at a time, and at no time may a larger disk be placed above a smaller disk. A third peg is available for temporarily holding disks. Supposedly, the world will end when the priests complete their task, so there is little incentive for us to facilitate their efforts.

Let us assume that the priests are attempting to move the disks from peg 1 to peg 3. We wish to develop an algorithm that will print the precise sequence of peg-to-peg disk transfers.

If we were to approach this problem with conventional methods, we would rapidly find ourselves hopelessly knotted up in managing the disks. Instead, if we attack the problem with recursion in mind, it immediately becomes tractable. Moving *n* disks can be viewed in terms of moving only *n* - 1 disks (hence, the recursion), as follows:



Fig. 3.1 The Towers of Hanoi for the case with four disks.

a) Move *n* - 1 disks from peg 1 to peg 2, using peg 3 as a temporary holding area.
b) Move the last disk (the largest) from peg 1 to peg 3.
c) Move the *n* - 1 disks from peg 2 to peg 3, using peg 1 as a temporary holding area.

The process ends when the last task involves moving *n* = 1 disk, i.e., the base case. This is accomplished by trivially moving the disk without the need for a temporary holding area.

Write a program to solve the Towers of Hanoi problem. Use a recursive function with four parameters:

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

a) The number of disks to be moved
b) The peg on which these disks are initially threaded
c) The peg to which this stack of disks is to be moved
d) The peg to be used as a temporary holding area

Your program should print the precise instructions it will take to move the disks from the starting peg to the destination peg. For example, to move a stack of three disks from peg 1 to peg 3, your program should print the following series of moves:

1 → 3 (This means move one disk from peg 1 to peg 3.)
1 → 2
3 → 2
1 → 3
2 → 1
2→ 3
1→ 3

```
1  // Exercise 3.42 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6
7  void towers( int, int, int, int );
8
9  int main()
10 {
11    int nDisks;
12
13    cout << "Enter the starting number of disks: ";
14    cin >> nDisks;
15    towers( nDisks, 1, 3, 2 );
16
17    return 0;
18 }
19
20 void towers( int disks, int start, int end, int temp )
21 {
22    if ( disks == 1 ) {
23       cout << start << " --> " << end << '\n';
24       return;
25    }
26
27    // move disks - 1 disks from start to temp
28    towers( disks - 1, start, temp, end );
29
30    // move last disk from start to end
31    cout << start << " --> " << end << '\n';
32
33    // move disks - 1 disks from temp to end
34    towers( disks - 1, temp, end, start );
35 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter the starting number of disks: 4
1 --> 2
1 --> 3
2 --> 3
1 --> 2
3 --> 1
3 --> 2
1 --> 2
1 --> 3
2 --> 3
2 --> 1
3 --> 1
2 --> 3
1 --> 2
1 --> 3
2 --> 3
```

3.43 Any program that can be implemented recursively can be implemented iteratively, although sometimes with more difficulty and less clarity. Try writing an iterative version of the Towers of Hanoi. If you succeed, compare your iterative version with the recursive version you developed in Exercise 3.42. Investigate issues of performance, clarity and your ability to demonstrate the correctness of the programs.

3.44 (Visualizing Recursion) It is interesting to watch recursion "in action." Modify the factorial function of Fig. 3.14 to print its local variable and recursive call parameter. For each recursive call, display the outputs on a separate line and add a level of indentation. Do your utmost to make the outputs clear, interesting and meaningful. Your goal here is to design and implement an output format that helps a person understand recursion better. You may want to add such display capabilities to the many other recursion examples and exercises throughout the text.

```
1  // Exercise 3.44 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <iomanip>
8
9  using std::setw;
10
11 long factorial( long );
12 void printRecursion( int );
13
14 int main()
15 {
16    for ( int i = 0; i <= 10; ++i )
17       cout << setw( 3 ) << i << "! = " << factorial( i ) << endl;
18
19    return 0;
20 }
21
22 long factorial( long number )
23 {
24    if ( number <= 1 )
25       return 1;
26    else {
27       printRecursion( number );
28       return ( number * factorial( number - 1 ) );
29    }
30 }
31
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
32  void printRecursion( int n )
33  {
34     cout << "number =" << setw( n ) << n << '\n';
35  }
```

```
   0! = 1
   1! = 1
number = 2
2! = 2
number =  3
number = 2
3! = 6
number =   4
number =  3
number = 2
4! = 24
number =    5
number =   4
number =  3
number = 2
5! = 120
number =     6
number =    5
number =   4
number =  3
number = 2
...
number =         10
number =         9
number =        8
number =       7
number =      6
number =     5
number =    4
number =   3
number = 2
10! = 3628800
```

3.45 The greatest common divisor of integers **x** and **y** is the largest integer that evenly divides both **x** and **y**. Write a recursive function **gcd** that returns the greatest common divisor of **x** and **y**. The **gcd** of **x** and **y** is defined recursively as follows: If **y** is equal to **0**, then **gcd(x, y)** is **x**; otherwise **gcd(x, y)** is **gcd(y, x % y)**, where **%** is the modulus operator.

```
1   // Exercise 3.45 Solution
2   #include <iostream>
3
4   using std::cout;
5   using std::endl;
6   using std::cin;
7
8   unsigned gcd( unsigned int, unsigned int );
9
10  int main()
11  {
12     unsigned x, y, gcDiv;
13
14     cout << "Enter two integers: ";
15     cin >> x >> y;
16
17     gcDiv = gcd( x, y );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   cout << "Greatest common divisor of " << x << " and "
        << y << " is " << gcDiv << endl;

   return 0;
}

unsigned gcd( unsigned xMatch, unsigned yMatch )
{
   return yMatch == 0 ? xMatch : gcd( yMatch, xMatch % yMatch );
}
```

```
Enter two integers: 32727 9
Greatest common divisor of 32727 and 9 is 3
```

3.46 Can **main** be called recursively? Write a program containing a function **main**. Include **static** local variable **count** and initialize it to 1. Postincrement and print the value of **count** each time **main** is called. Compile your program. What happens?

```
// Exercise 3.46 Solution
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   static int count = 1;

   ++count;
   cout << count << endl;
   main();

   return 0;
}
```

```
1
2
3
...
12298
12299
12300
12301
12302
12303
12304
...
```

3.47 Exercises 3.35 through 3.37 developed a computer-assisted instruction program to teach an elementary school student multiplication. This exercise suggests enhancements to that program.

a) Modify the program to allow the user to enter a grade-level capability. A grade level of 1 means to use only single-digit numbers in the problems, a grade level of two means to use numbers as large as two digits, etc.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

b) Modify the program to allow the user to pick the type of arithmetic problems he or she wishes to study. An option of 1 means addition problems only, 2 means subtraction problems only, 3 means multiplication problems only, 4 means division problems only, and 5 means to randomly intermix problems of all these types.

```
// Exercise 3.47 Part A Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstdlib>
#include <ctime>

int randValue( int );
void multiplication( void );
void correctMessage( void );
void incorrectMessage( void );

int main()
{
   srand( time( 0 ) );
   multiplication();

   return 0;
}

int randValue( int level )
{
   switch ( level ) {
      case 1:
         return rand() % 10;
      case 2:
         return rand() % 100;
      case 3:
         return rand() % 1000;
      default:
         return rand() % 10;
   }
}

void multiplication( void )
{
   int x, y, gradeLevel, right = 0, wrong = 0;
   unsigned int response;

   cout << "Enter the grade-level (1 to 3): ";
   cin >> gradeLevel;

   for ( int i = 1; i <= 10; i++ ) {
      x = randValue( gradeLevel );
      y = randValue( gradeLevel );

      cout << "How much is " << x << " times " << y << "? ";
      cin >> response;

      while ( response != x * y ) {
         ++wrong;
         incorrectMessage();
         cin >> response;
      }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
58
59          ++right;
60          correctMessage();
61       }
62
63       if ( static_cast< double > ( right ) / ( right + wrong ) < .75 )
64          cout << "Please ask your instructor for extra help.\n";
65
66       cout << "That's all for now. Bye." << endl;
67    }
68
69    void correctMessage( void )
70    {
71       switch ( rand() % 4 ) {
72          case 0:
73             cout << "Very good!";
74             break;
75          case 1:
76             cout << "Excellent!";
77             break;
78          case 2:
79             cout << "Nice work!";
80             break;
81          case 3:
82             cout << "Keep up the good work!";
83             break;
84       }
85
86       cout << "\n\n";
87    }
88
89    void incorrectMessage( void )
90    {
91       switch ( rand() % 4 ) {
92          case 0:
93             cout << "No. Please try again.";
94             break;
95          case 1:
96             cout << "Wrong. Try once more.";
97             break;
98          case 2:
99             cout << "Don't give up!";
100            break;
101         case 3:
102            cout << "No. Keep trying.";
103            break;
104      }
105
106      cout << "\n? ";
107   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter the grade-level (1 to 3): 3
How much is 643 times 462? 297066
Very good!

How much is 763 times 731? 537753
Don't give up!
? 557753
Keep up the good work!

How much is 382 times 120?
...
```

```
1  // Exercise 3.47 Part B Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstdlib>
9  #include <ctime>
10
11 int menu( void );
12 void arithmetic( void );
13 void correctMessage( void );
14 void incorrectMessage( void );
15
16 int main()
17 {
18    srand( time( 0 ) );
19    arithmetic();
20
21    return 0;
22 }
23
24 int menu( void )
25 {
26    int choice;
27
28    do {
29       cout << "Choose type of problem to study."
30            << "\nEnter: 1 for addition, 2 for subtraction"
31            << "\nEnter: 3 for multiplication, 4 for division"
32            << "\nEnter: 5 for a combination of 1 through 4\n? ";
33       cin >> choice;
34
35    } while ( choice < 1 || choice > 5 );
36
37    return choice;
38 }
39
40 void incorrectMessage( void )
41 {
42    switch ( rand() % 4 ) {
43       case 0:
44          cout << "No. Please try again.";
45          break;
46       case 1:
47          cout << "Wrong. Try once more.";
48          break;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
49          case 2:
50             cout << "Don't give up!";
51             break;
52          case 3:
53             cout << "No. Keep trying.";
54             break;
55       }
56
57       cout << "\n? ";
58    }
59
60    void correctMessage( void )
61    {
62       switch ( rand() % 4 ) {
63          case 0:
64             cout << "Very good!";
65             break;
66          case 1:
67             cout << "Excellent!";
68             break;
69          case 2:
70             cout << "Nice work!";
71             break;
72          case 3:
73             cout << "Keep up the good work!";
74             break;
75       }
76
77       cout << "\n\n";
78    }
79
80    void arithmetic( void )
81    {
82       int x, y, response, answer, selection, right = 0, wrong = 0;
83       int type, problemMix;
84       char op;
85
86       selection = menu();
87       type = selection;
88
89       for ( int i = 1; i <= 10; ++i ) {
90          x = rand() % 10;
91          y = rand() % 10;
92
93          if ( selection == 5 ) {
94             problemMix = 1 + rand() % 4;
95             type = problemMix;
96          }
97
98          switch ( type ) {
99             case 1:
100               op = '+';
101               answer = x + y;
102               break;
103            case 2:                // note negative answers can exist
104               op = '-';
105               answer = x - y;
106               break;
107            case 3:
108               op = '*';
109               answer = x * y;
110               break;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
111          case 4:                // note this is integer division
112             op = '/';
113
114             if ( y == 0 ) {
115                y = 1;           // eliminate divide by zero error
116                answer = x / y;
117             }
118             else {
119                x *= y;          // create "nice" division
120                answer = x / y;
121             }
122
123             break;
124       }
125
126       cout << "How much is " << x << " " << op << " " << y << "? ";
127       cin >> response;
128
129       while ( response != answer ) {
130          ++wrong;
131          incorrectMessage();
132          cin >> response;
133       }
134
135       ++right;
136       correctMessage();
137    }
138
139    if ( static_cast< double > ( right ) / ( right + wrong ) < .75 )
140       cout << "Please ask your instructor for extra help.\n";
141
142    cout << "That's all for now. Bye." << endl;
143 }
```

```
Choose type of problem to study.
Enter: 1 for addition, 2 for subtraction
Enter: 3 for multiplication, 4 for division
Enter: 5 for a combination of 1 through 4
? 5
How much is 7 * 5? 35
Keep up the good work!

How much is 45 / 5? 9
Keep up the good work!

How much is 0 * 7? 0
Excellent!

How much is 1 * 1? 1
Nice work!

How much is 9 * 5? 45
Very good!

How much is 4 + 6?
...
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

3.48 Write function **distance** that calculates the distance between two points *(x1, y1)* and *(x2, y2)*. All numbers and return values should be of type **double**.

```
// Exercise 3.48 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setprecision;
using std::setiosflags;

#include <cmath>

double distance( double, double, double, double );

int main()
{
   double x1, y1, x2, y2, dist;

   cout << "Enter the first point: ";
   cin >> x1 >> y1;

   cout << "Enter the second point: ";
   cin >> x2 >> y2;

   dist = distance( x1, y1, x2, y2 );

   cout << setiosflags( ios::fixed | ios::showpoint )
        << "Distance between (" << setprecision( 1 ) << x1 << ", "
        << y1 << ") and (" << x2 << ", " << y2 << ") is "
        << dist << endl;

   return 0;
}

double distance( double xOne, double yOne, double xTwo, double yTwo )
{
   return sqrt( pow( xOne - xTwo, 2 ) + pow( yOne - yTwo, 2 ) );
}
```

```
Enter the first point: 8 9
Enter the second point: 0 1
Distance between (8.0, 9.0) and (0.0, 1.0) is 11.3
```

3.49 What is wrong with the following program?

```
// ex03_49.cpp
#include <iostream>

using std::cin;
using std::cout;

int main()
{
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   int c;

   if ( ( c = cin.get() ) != EOF ) {
      main();
      cout << c;
   }

   return 0;
}
```

ANS: Standard C++ does not allow recursive calls of **main**, however, on nonstandard compilers, this program would print the characters input in reverse order.

3.50 What does the following program do?

```
// ex03_50.cpp
#include <iostream>

using std::cout;
using std::cin;
using std::endl;

int mystery( int, int );

int main()
{
   int x, y;

   cout << "Enter two integers: ";
   cin >> x >> y;
   cout << "The result is " << mystery( x, y ) << endl;
   return 0;
}

// Parameter b must be a positive
// integer to prevent infinite recursion
int mystery( int a, int b )
{
   if ( b == 1 )
      return a;
   else
      return a + mystery( a, b - 1 );
}
```

```
Enter two integers: 8 2
The result is 16
```

3.51 After you determine what the program of Exercise 3.50 does, modify the program to function properly after removing the restriction that the second argument be nonnegative.

```
// Exercise 3.51 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int mystery( int, int );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 9
10  int main()
11  {
12     int x, y;
13
14     cout << "Enter two integers: ";
15     cin >> x >> y;
16     cout << "The result is " << mystery( x, y ) << endl;
17     return 0;
18  }
19
20  int mystery( int a, int b )
21  {
22     if ( ( a < 0 && b < 0 ) || b < 0 ) {
23        a *= -1;
24        b *= -1;
25     }
26
27     return b == 1 ? a : a + mystery( a, b - 1 );
28  }
```

```
Enter two integers: -8 8
The result is -64
```

3.52 Write a program that tests as many of the math library functions in Fig. 3.2 as you can. Exercise each of these functions by having your program print out tables of return values for a diversity of argument values.

```
 1  // Exercise 3.52 Solution
 2  #include <iostream>
 3
 4  using std::cout;
 5  using std::endl;
 6  using std::ios;
 7
 8  #include <iomanip>
 9
10  using std::setw;
11  using std::setprecision;
12  using std::setiosflags;
13
14  #include <cmath>
15
16  int main()
17  {
18     cout << "function";      // header
19
20     for ( int a = 1; a < 6; ++a )
21        cout << setw( 12 ) << a << ' ';
22
23     cout << setiosflags( ios::fixed | ios::showpoint ) << "\n\nsqrt()  ";
24
25     for ( int b = 1; b < 6; ++b )
26        cout << setw( 12 ) << setprecision( 2 ) << sqrt( b ) << ' ';
27
28     cout << "\nexp()   ";
29
30     for ( int c = 1; c < 6; ++c )
31        cout << setw( 12 ) << setprecision( 2 ) << exp( c ) << ' ';
32
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
33     cout << "\nlog()   ";
34
35     for ( int d = 1; d < 6; ++d )
36        cout << setw( 12 ) << setprecision( 2 ) << log( d ) << ' ';
37
38     cout << "\nlog10() ";
39
40     for ( int e = 1; e < 6; ++e )
41        cout << setw( 12 ) << setprecision( 2 ) << log10( e ) << ' ';
42
43     cout << "\npow(2,x)";
44
45     for ( int f = 1; f < 6; ++f )
46        cout << setw( 12 ) << setprecision( 2 ) << pow( 2, f ) << ' ';
47
48     cout << "\n\n\nfunction";      // header
49
50     for ( double g = -1.5; g < 3.0; g += 1.1 )
51        cout << setw( 12 ) << setprecision( 2 ) << g << ' ';
52
53     cout << "\n\n\nfabs()  ";
54
55     for ( double h = -1.5; h < 3.0; h += 1.1 )
56        cout << setw( 12 ) << setprecision( 2 ) << fabs( h ) << ' ';
57
58     cout << "\nceil()  ";
59
60     for ( double i = -1.5; i < 3.0; i += 1.1 )
61        cout << setw( 12 ) << setprecision( 2 ) << ceil( i ) << ' ';
62
63     cout << "\nfloor() ";
64
65     for ( double j = -1.5; j < 3.0; j += 1.1 )
66        cout << setw( 12 ) << setprecision( 2 ) << floor( j ) << ' ';
67
68     cout << "\nsin()   ";
69
70     for ( double k = -1.5; k < 3.0; k += 1.1 )
71        cout << setw( 12 ) << setprecision( 2 ) << sin( k ) << ' ';
72
73     cout << "\ncos()   ";
74
75     for ( double l = -1.5; l < 3.0; l += 1.1 )
76        cout << setw( 12 ) << setprecision( 2 ) << cos( l ) << ' ';
77
78     cout << "\ntan()   ";
79
80     for ( double m = -1.5; m < 3.0; m += 1.1 )
81        cout << setw( 12 ) << setprecision( 2 ) << tan( m ) << ' ';
82
83     cout << endl;
84     return 0;
85  }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
function          1          2          3          4          5

sqrt()         1.00       1.41       1.73       2.00       2.24
exp()          2.72       7.39      20.09      54.60     148.41
log()          0.00       0.69       1.10       1.39       1.61
log10()        0.00       0.30       0.48       0.60       0.70
pow(2,x)       2.00       4.00       8.00      16.00      32.00


function      -1.50      -0.40       0.70       1.80       2.90


fabs()         1.50       0.40       0.70       1.80       2.90
ceil()        -1.00       0.00       1.00       2.00       3.00
floor()       -2.00      -1.00       0.00       1.00       2.00
sin()         -1.00      -0.39       0.64       0.97       0.24
cos()          0.07       0.92       0.76      -0.23      -0.97
tan()        -14.10      -0.42       0.84      -4.29      -0.25
```

3.53 Find the error in each of the following program segments and explain how to correct it:

a)
```
float cube( float );          // function prototype

double cube( float number )   // function definition
{
   return number * number * number;
}
```
ANS: The function definition defaults to a return type of **int**. Specify a return type of **float** for the definition.

b)
```
register auto int x = 7;
```
ANS: Only one storage class specifier can be used. Either **register** or **auto** must be removed.

c)
```
int randomNumber = srand();
```
ANS: Function **srand** takes an **unsigned** argument and does not return a value. Use **rand** instead of **srand**.

d)
```
float y = 123.45678;
int x;

x = y;
cout << static_cast< float >( x ) << endl;
```
ANS: The assignment of **y** to **x** truncates decimal places.

e)
```
double square( double number )
{
   double number;
   return number * number;
}
```
ANS: Variable **number** is declared twice. Remove the declaration within the **{}**.

f)
```
int sum( int n )
{
   if ( n == 0 )
      return 0;
   else
      return n + sum( n );
}
```
ANS: Infinite recursion. Change operator **+** to operator **-**.

3.54 Modify the craps program of Fig. 3.10 to allow wagering. Package as a function the portion of the program that runs one game of craps. Initialize variable **bankBalance** to 1000 dollars. Prompt the player to enter a **wager**. Use a **while** loop to check that **wager** is less than or equal to **bankBalance** and, if not, prompt the user to reenter **wager** until a valid **wager** is entered. After a correct **wager** is entered, run one game of craps. If the player wins, increase **bankBalance** by **wager** and print the new **bankBalance**. If the player loses, decrease **bankBalance** by **wager**, print the new **bankBalance**, check on whether **bank-**

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Balance has become zero and, if so, print the message **"Sorry. You busted!"** As the game progresses, print various messages to create some "chatter" such as **"Oh, you're going for broke, huh?"** or **"Aw cmon, take a chance!"**, or **"You're up big. Now's the time to cash in your chips!"**.

```
// Exercise 3.54 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstdlib>
#include <ctime>

enum Status { WON, LOST, CONTINUE };

int rollDice( void );
int craps( void );
void chatter( void );

int main()
{
   int result, wager = 0, bankBalance = 1000;
   char playAgain;

   srand( time( 0 ) );

   do {
      cout << "You have $" << bankBalance
           << " in the bank.\nPlace your wager: ";
      cin >> wager;

      while ( wager <= 0 || wager > bankBalance ) {
         cout << "Please bet a valid amount.\n";
         cin >> wager;
      }

      result = craps();

      if ( result == LOST ) {
         bankBalance -= wager;
         cout << "Your new bank balance is $" << bankBalance << "\n";

         if ( bankBalance == 0 ) {
            cout << "Sorry. You Busted! Thank You For Playing.\n";
            break;
         }
      }
      else {
         bankBalance += wager;
         cout << "Your new bank balance is $" << bankBalance << "\n";
      }

      cout << "Would you like to try your luck again (y/n)? ";
      cin >> playAgain;
   } while ( playAgain == 'y' || playAgain == 'Y' );

   cout << endl;

   return 0;
}

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
59  int rollDice( void )
60  {
61     int die1, die2, workSum;
62
63     die1 = 1 + rand() % 6;
64     die2 = 1 + rand() % 6;
65     workSum = die1 + die2;
66     cout << "Player rolled " << die1 << " + " << die2 << " = "
67          << workSum << '\n';
68
69     return workSum;
70  }
71
72  int craps( void )
73  {
74     int gameStatus, sum, myPoint;
75
76     sum = rollDice();
77
78     switch ( sum ) {
79        case 7: case 11:
80           gameStatus = WON;
81           chatter();
82           break;
83        case 2: case 3: case 12:
84           gameStatus = LOST;
85           chatter();
86           break;
87        default:
88           gameStatus = CONTINUE;
89           myPoint = sum;
90           cout << "Point is " << myPoint << '\n';
91           chatter();
92           break;
93     }
94
95     while ( gameStatus == CONTINUE ) {
96        chatter();
97        sum = rollDice();
98
99        if ( sum == myPoint )
100          gameStatus = WON;
101       else if ( sum == 7 )
102          gameStatus = LOST;
103    }
104
105    if ( gameStatus == WON ) {
106       cout << "Player wins\n";
107       return WON;
108    }
109    else {
110       cout << "Player loses\n";
111       return LOST;
112    }
113 }
114
115 void chatter( void )
116 {
117    switch ( 1 + rand() % 9 ) {
118       case 1:
119          cout << "Oh, you're going for broke, huh?";
120          break;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      case 2:
         cout << "Aw cmon, take a chance!";
         break;
      case 3:
         cout << "Hey, I think this guy is going to break the bank!!";
         break;
      case 4:
         cout << "You're up big. Now's the time to cash in your chips!";
         break;
      case 5:
         cout << "Way too lucky! Those dice have to be loaded!";
         break;
      case 6:
         cout << "Bet it all! Bet it all!";
         break;
      case 7:
         cout << "Can I borrow a chip?";
         break;
      case 8:
         cout << "Let's try our luck at another table.";
         break;
      case 9:
         cout << "You're a cheat! It is just a matter of time"
              << "\nbefore I catch you!!!";
         break;
   }

   cout << endl;
}
```

```
You have $1000 in the bank.
Place your wager: 1000
Player rolled 5 + 4 = 9
Point is 9
Way too lucky! Those dice have to be loaded!
You're up big. Now's the time to cash in your chips!
Player rolled 5 + 4 = 9
Player wins
Your new bank balance is $2000
Would you like to try your luck again (y/n)? n
```

3.55 Write a C++ program that uses an **inline** function **circleArea** to prompt the user for the radius of a circle and to calculate and print the area of that circle.

```
// Exercise 3.55 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

double pi = 3.14159;   // global variable

inline double circleArea( double r ) { return pi * r * r; }

int main()
{
   double radius;

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   cout << "Enter the radius of the circle: ";
   cin >> radius;
   cout << "The area of the circle is " << circleArea( radius ) << endl;

   return 0;
}
```

```
Enter the radius of the circle: 10
The area of the circle is 314.159
```

3.56 Write a complete C++ program with the two alternate functions specified below, of which each simply triples the variable **count** defined in **main**. Then compare and contrast the two approaches. These two functions are

a) Function **tripleCallByValue** that passes a copy of **count** call-by-value, triples the copy and returns the new value.

b) Function **tripleByReference** that passes **count** with true call-by-reference via a reference parameter and triples the original copy of **count** through its alias (i.e., the reference parameter).

```
// Exercise 3.56 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int tripleCallByValue( int );
void tripleByReference( int & );

int main()
{
   int value, &valueRef = value;

   cout << "Enter an integer: ";
   cin >> value;

   cout << "\nValue before call to tripleCallByValue() is: "
        << value << "\nValue returned from tripleCallByValue() is: "
        << tripleCallByValue( value )
        << "\nValue (in main) after tripleCallByValue() is: " << value
        << "\n\nValue before call to tripleByReference() is: "
        << value << '\n';

   tripleByReference( valueRef );

   cout << "Value (in main) after call to tripleByReference() is: "
        << value << endl;

   return 0;
}

int tripleCallByValue( int valueCopy )
{
   return valueCopy *= 3;
}

void tripleByReference( int &aliasRef )
{
   aliasRef *= 3;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter an integer: 8

Value before call to tripleCallByValue() is: 8
Value returned from tripleCallByValue() is: 24
Value (in main) after tripleCallByValue() is: 8

Value before call to tripleByReference() is: 8
Value (in main) after call to tripleByReference() is: 24
```

3.57 What is the purpose of the unary scope resolution operator?

ANS: The unary scope resolution operator is used to access a global variable. In particular, the unary scope resolution operator is useful when a global variable needs to be accessed and a local varible has the same name.

3.58 Write a program that uses a function template called **min** to determine the smaller of two arguments. Test the program using integer, character and floating-point number pairs.

```
1  // Exercise 3.58 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  template < class T >
8  void min( T value1, T value2 )   // find the smallest value
9  {
10    if ( value1 > value2 )
11       cout << value2 << " is smaller than " << value1;
12    else
13       cout << value1 << " is smaller than " << value2;
14
15    cout << endl;
16 }
17
18 int main()
19 {
20    min( 7, 54 );      // integers
21    min( 4.35, 8.46 ); // doubles
22    min( 'g', 'T' );   // characters
23
24    return 0;
25 }
```

```
7 is smaller than 54
4.35 is smaller than 8.46
T is smaller than g
```

3.59 Write a program that uses a function template called **max** to determine the largest of three arguments. Test the program using integer, character and floating-point number pairs.

```
1  // Exercise 3.59 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  template < class T >
8  void max( T value1, T value2, T value3 )  // find the largest value
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   if ( value1 > value2 && value1 > value3 )
      cout << value1 << " is greater than " << value2
           << " and " << value3;
   else if ( value2 > value1 && value2 > value3 )
      cout << value2 << " is greater than " << value1
           << " and " << value3;
   else
      cout << value3 << " is greater than " << value1
           << " and " << value2;

   cout << endl;
}


int main()
{
   max( 7, 5, 2 );             // integers
   max( 9.35, 8.461, 94.3 );   // doubles
   max( '!', 'T', '$' );       // characters

   return 0;
}
```

```
7 is greater than 5 and 2
94.3 is greater than 9.35 and 8.461
T is greater than ! and $
```

3.60 Determine whether the following program segments contain errors. For each error, explain how it can be corrected. Note: For a particular program segment, it is possible that no errors are present in the segment.

a)
```
template < class A >
int sum( int num1, int num2, int num3 )
{
   return num1 + num2 + num3;
}
```
ANS: The function return type and parameter types should be **A**.

b)
```
void printResults( int x, int y )
{
   cout << "The sum is " << x + y << '\n';
   return x + y;
}
```
ANS: The function specifies a **void** return type and attempts to return a value. Two possible solutions: (1) change **void** to **int**. or (2) remove the line **return x + y;**.

c)
```
template < A >
A product( A num1, A num2, A num3 )
{
   return num1 * num2 * num3;
}
```
ANS: Keyword **class** is needed in the template declaration **template <class A>**.

d)
```
double cube( int );
int cube( int );
```
ANS: The signatures are not different. Overloaded functions must have different signatures meaning that the name and parameter list must be different. If only the returns types differ, the compiler generates an error message.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Arrays
Solutions

Solutions

4.6 Fill in the blanks in each of the following:

a) C++ stores lists of values in _____.

ANS: arrays.

b) The elements of an array are related by the fact that they _____.

ANS: have the same name and type.

c) When referring to an array element, the position number contained within square brackets is called a _____.

ANS: subscript.

d) The names of the four elements of array **p** are _____, _____, _____ and _____.

ANS: `p[ 0 ]`, `p[ 1 ]`, `p[ 2 ]`, `p[ 3 ]`

e) Naming an array, stating its type and specifying the number of elements in the array is called _____ the array.

ANS: declaring.

f) The process of placing the elements of an array into either ascending or descending order is called _____.

ANS: sorting.

g) In a double-subscripted array, the first subscript (by convention) identifies the _____ of an element, and the second subscript (by convention) identifies the _____ of an element.

ANS: row, column.

h) An *m*-by-*n* array contains _____ rows, _____ columns and _____ elements.

ANS: m, n, m x n.

i) The name of the element in row 3 and column 5 of array **d** is _____.

ANS: `d[ 2 ][ 4 ]`.

4.7 State which of the following are true and which are false; for those that are false, explain why they are false.

a) To refer to a particular location or element within an array, we specify the name of the array and the value of the particular element.

ANS: False. The name of the array and the subscript of the array are specified.

b) An array declaration reserves space for the array.

ANS: True.

c) To indicate that 100 locations should be reserved for integer array **p**, the programmer writes the declaration

```
p[ 100 ];
```

ANS: False. A data type must be specified. An example of a correct definition would be: `unsigned p[ 100 ];`.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

d) A C++ program that initializes the elements of a 15-element array to zero must contain at least one **for** statement.
ANS: False. The array can be initialized in a declaration with a member initializer list.
e) A C++ program that totals the elements of a double-subscripted array must contain nested **for** statements.
ANS: False. The sum of the elements can be obtained without **for** loops, with one **for** loop, three **for** loops, etc.

4.8 Write C++ statements to accomplish each of the following:
a) Display the value of the seventh element of character array **f**.
ANS:
```
cout << f[ 6 ] << '\n';
```
b) Input a value into element 4 of single-subscripted floating-point array **b**.
ANS:
```
cin >> b[ 4 ];
```
c) Initialize each of the 5 elements of single-subscripted integer array **g** to **8**.
ANS:
```
int g[ 5 ] = { 8, 8, 8, 8, 8 };
```
or
```
for ( int j = 0; j < 5; ++j )
   g[ j ] = 8;
```
d) Total and print the elements of floating-point array **c** of 100 elements.
ANS:
```
for ( int k = 0; k < 5; ++k ) {
    total += c[ k ];  // assume total declared and initalized
    cout << c[ k ] << '\n'
}
```
e) Copy array **a** into the first portion of array **b**. Assume **double a[11], b[34];**
ANS:
```
for ( int i = 0; i < 11; ++i )
   b[ i ] = a[ i ];
```
f) Determine and print the smallest and largest values contained in 99-element floating-point array **w**.
ANS:
```
// assume all variables declared and initialized
for ( int j = 0; j < 99; ++j )
   if ( w[ j ] < smallest )
      smallest = w[ j ];
   else if ( w[ j ] > largest )
      largest = w[ j ];
```

4.9 Consider a 2-by-3 integer array **t**.
a) Write a declaration for **t**.
ANS: `int t[ 2 ][ 3 ];`
b) How many rows does **t** have?
ANS: 2
c) How many columns does **t** have?
ANS: 3
d) How many elements does **t** have?
ANS: 6
e) Write the names of all the elements in the second row of **t**.
ANS: `t[ 1 ][ 0 ], t[ 1 ][ 1 ], t[ 1 ][ 2 ]`
f) Write the names of all the elements in the third column of **t**.
ANS: `t[ 0 ][ 2 ], t[ 1 ][ 2 ]`
g) Write a single statement that sets the element of **t** in row 1 and column 2 to zero.
ANS: `t[ 0 ][ 1 ] = 0;`
h) Write a series of statements that initialize each element of **t** to zero. Do not use a repetition structure.
ANS:
```
t[ 0 ][ 0 ] = 0;
t[ 0 ][ 1 ] = 0;
t[ 0 ][ 2 ] = 0;
t[ 1 ][ 0 ] = 0;
t[ 1 ][ 1 ] = 0;
t[ 1 ][ 2 ] = 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

i) Write a nested **for** structure that initializes each element of **t** to zero.

ANS:

```
for ( int i = 0; i < 2; ++i )
   for ( int j = 0; j < 3; ++j )
      t[ i ][ j ] = 0;
```

j) Write a statement that inputs the values for the elements of **t** from the terminal.

ANS:

```
for ( int r = 0; r < 2; ++r )
   for ( int c = 0; c < 3; ++c )
      t[ r ][ c ] = 0;
```

k) Write a series of statements that determine and print the smallest value in array **t**.

ANS:

```
int smallest = t[ 0 ][ 0 ];
for ( int r = 1; r < 2; ++r )
   for ( int c = 1; c < 3; ++c )
      if ( t[ r ][ c ] < smallest )
         smallest = t[ r ][ c ];
cout << smallest;
```

l) Write a statement that displays the elements of the first row of **t**

ANS:

```
cout << t[ 0 ][ 0 ] << ' ' << t[ 0 ][ 1 ] << ' ' << t[ 0 ][ 2 ] << '\n';
```

m) Write a statement that totals the elements of the fourth column of **t**.

ANS: **t** does not contain a fourth column.

n) Write a series of statements that prints the array **t** in neat, tabular format. List the column subscripts as headings across the top and list the row subscripts at the left of each row.

ANS:

```
cout << "  0     1    2\n";
for ( int r = 0; r < 2; ++r ) {
   cout << r << ' ';

   for ( int c = 0; c < 3; ++c )
      cout << t[ r ][ c ] << "   ";

   cout << '\n';
}
```

4.10 Use a single-subscripted array to solve the following problem. A company pays its salespeople on a commission basis. The salespeople receive $200 per week plus 9 percent of their gross sales for that week. For example, a salesperson who grosses $5000 in sales in a week receives $200 plus 9 percent of $5000, or a total of $650. Write a program (using an array of counters) that determines how many of the salespeople earned salaries in each of the following ranges (assume that each salesperson's salary is truncated to an integer amount):

a) $200–$299
b) $300–$399
c) $400–$499
d) $500–$599
e) $600–$699
f) $700–$799
g) $800–$899
h) $900–$999
i) $1000 and over

```
1  // Exercise 4.10 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#include <iomanip>

using std::setprecision;
using std::setiosflags;

void wages( int [] );
void display( const int [] );

int main()
{
   int salaries[ 11 ] = { 0 };

   cout << setiosflags( ios::fixed | ios::showpoint );
   wages( salaries );
   display( salaries );

   return 0;
}

void wages( int money[] )
{
   double sales, i = 0.09;

   cout << "Enter employee gross sales (-1 to end): ";
   cin >> sales;

   while ( sales != -1 ) {
      double salary = 200.0 + sales * i;
      cout << setprecision( 2 ) << "Employee Commission is $"
           << salary << '\n';

      int x = static_cast< int > ( salary ) / 100;
      ++money[ ( x < 10 ? x : 10 ) ];

      cout << "\nEnter employee gross sales (-1 to end): ";
      cin >> sales;
   }
}

void display( const int dollars[] )
{
   cout << "Employees in the range:";
   for ( int i = 2; i < 10; ++i )
      cout << "\n$" << i << "00-$" << i << "99 : " << dollars[ i ];

   cout << "\nOver $1000: " << dollars[ 10 ] << endl;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter employee gross sales (-1 to end): 10000
Employee Commission is $1100.00

Enter employee gross sales (-1 to end): 4235
Employee Commission is $581.15

Enter employee gross sales (-1 to end): 600
Employee Commission is $254.00

Enter employee gross sales (-1 to end): 12500
Employee Commission is $1325.00

Enter employee gross sales (-1 to end): -1
Employees in the range:
$200-$299 : 1
$300-$399 : 0
$400-$499 : 0
$500-$599 : 1
$600-$699 : 0
$700-$799 : 0
$800-$899 : 0
$900-$999 : 0
Over $1000: 2
```

4.11 The bubble sort presented in Fig. 4.16 is inefficient for large arrays. Make the following simple modifications to improve the performance of the bubble sort:

a) After the first pass, the largest number is guaranteed to be in the highest-numbered element of the array; after the second pass, the two highest numbers are "in place," and so on. Instead of making nine comparisons on every pass, modify the bubble sort to make eight comparisons on the second pass, seven on the third pass, and so on.

b) The data in the array may already be in the proper order or near-proper order, so why make nine passes if fewer will suffice? Modify the sort to check at the end of each pass if any swaps have been made. If none have been made, then the data must already be in the proper order, so the program should terminate. If swaps have been made, then at least one more pass is needed.

```
1  // Exercise 4.11 Part A Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <iomanip>
8
9  using std::setw;
10
11 int main()
12 {
13    const int SIZE = 10;
14    int a[ SIZE ] = { 2, 6, 4, 8, 10, 12, 89, 68, 45, 37 };
15    int hold, numberOfComp = 0, comp;
16
17    cout << "Data items in original order\n";
18    for ( int i = 0; i < SIZE; ++i )
19       cout << setw( 4 ) << a[ i ];
20
21    cout << "\n\n";
22
23    for ( int pass = 1; pass < SIZE; ++pass ) {
24       cout << "After pass " << pass - 1 << ": ";
25
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      for ( comp = 0; comp < SIZE - pass; ++comp ) {
         ++numberOfComp;

         if ( a[ comp ] > a[ comp + 1 ] ) {
            hold = a[ comp ];
            a[ comp ] = a[ comp + 1 ];
            a[ comp + 1 ] = hold;
         }

         cout << setw( 3 ) << a[ comp ];
      }

      cout << setw( 3 ) << a[ comp ] << '\n';    // print last array value
   }

   cout << "\nData items in ascending order\n";

   for ( int j = 0; j < SIZE; ++j )
      cout << setw( 4 ) << a[ j ];

   cout << "\nNumber of comparisons = " << numberOfComp << endl;

   return 0;
}
```

```
Data items in original order
   2   6   4   8  10  12  89  68  45  37

After pass 0:   2  4  6  8 10 12 68 45 37 89
After pass 1:   2  4  6  8 10 12 45 37 68
After pass 2:   2  4  6  8 10 12 37 45
After pass 3:   2  4  6  8 10 12 37
After pass 4:   2  4  6  8 10 12
After pass 5:   2  4  6  8 10
After pass 6:   2  4  6  8
After pass 7:   2  4  6
After pass 8:   2  4

Data items in ascending order
   2   4   6   8  10  12  37  45  68  89
Number of comparisons = 45
```

```
// Exercise 4.11 Part B Solution
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>

using std::setw;

int main()
{
   const int SIZE = 10;
   int a[ SIZE ] = { 6, 4, 2, 8, 10, 12, 37, 45, 68, 89 };
   int hold, numberOfComp = 0, comp;
   bool swapCheck = true;

   cout << "Data items in original order\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   for ( int i = 0; i < SIZE; ++i )
      cout << setw( 4 ) << a[ i ];

   cout << "\n\n";

   for ( int pass = 1; pass < SIZE - 1 && swapCheck == true; ++pass ) {
      cout << "After pass " << pass - 1 << ": ";
      swapCheck = false;  // assume no swaps will be made

      for ( comp = 0; comp < SIZE - pass; ++comp ) {
         ++numberOfComp;

         if ( a[ comp ] > a[ comp + 1 ] ) {
            hold = a[ comp ];
            a[ comp ] = a[ comp + 1 ];
            a[ comp + 1 ] = hold;
            swapCheck = true;  // a swap has been made
         }

         cout << setw( 3 ) << a[ comp ];
      }

      cout << setw( 3 ) << a[ comp ] << '\n';   // print last array value
   }

   cout << "\nData items in ascending order\n";

   for ( int q = 0; q < SIZE; ++q )
      cout << setw( 4 ) << a[ q ];

   cout << "\nNumber of comparisons = " << numberOfComp << endl;

   return 0;
}
```

```
Data items in original order
   6   4   2   8  10  12  37  45  68  89

After pass 0:   4  2  6  8 10 12 37 45 68 89
After pass 1:   2  4  6  8 10 12 37 45 68
After pass 2:   2  4  6  8 10 12 37 45

Data items in ascending order
   2   4   6   8  10  12  37  45  68  89
Number of comparisons = 24
```

4.12 Write single statements that perform the following single-subscripted array operations:

a) Initialize the 10 elements of integer array **counts** to zero.

ANS: `int counts[ 10 ] = { 0 };`

b) Add 1 to each of the 15 elements of integer array **bonus**.

ANS:

```
for ( int i = 0; i < 15; ++i )
   ++bonus[ i ];
```

c) Read 12 values for **double** array **monthlyTemperatures** from the keyboard.

ANS:

```
for ( int p = 0; p < 12; ++p )
   cin >> monthlyTemperatures[ p ];
```

d) Print the 5 values of integer array **bestScores** in column format.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS:

```
for ( int u = 0; u < 5; ++u )
   cout << bestScores[ u ] << '\t';
```

4.13 Find the error(s) in each of the following statements:

a) Assume that: `char str[ 5 ];`

```
cin >> str;    // User types hello
```

ANS: Inadequate length. The string input exceeds the valid subscript range.

b) Assume that: `int a[ 3 ];`

```
cout << a[ 1 ] << " " << a[ 2 ] << " " << a[ 3 ] << endl;
```

ANS: `a[ 3 ]` is not a valid location in the array. `a[ 2 ]` is the last valid location.

c) `double f[ 3 ] = { 1.1, 10.01, 100.001, 1000.0001 };`

ANS: Too many initializers in the initializer list. Only 1, 2, or 3 values may be provided in the initializer list.

d) Assume that: `double d[ 2 ][ 10 ];`

```
d[ 1, 9 ] = 2.345;
```

ANS: Incorrect syntax array element access. `d[ 1 ][ 9 ]` is the correct syntax.

4.14 Modify the program of Fig. 4.17 so function **mode** is capable of handling a tie for the mode value. Also modify function **median** so the two middle elements are averaged in an array with an even number of elements.

```
// Exercise 4.14 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;

void mean( int [], int );
void median( int [], int );
void mode( int [], int [], int, int );

int main()
{
   const int SIZE = 100, MAXFREQUENCY = 10;
   int response[ SIZE ] = { 6, 7, 8, 9, 8, 7, 8, 9, 8, 9,
                            7, 8, 9, 5, 9, 8, 7, 8, 7, 1,
                            6, 7, 8, 9, 3, 9, 8, 7, 1, 7,
                            7, 8, 9, 8, 9, 8, 9, 7, 1, 9,
                            6, 7, 8, 7, 8, 7, 9, 8, 9, 2,
                            7, 8, 9, 8, 9, 8, 9, 7, 5, 3,
                            5, 6, 7, 2, 5, 3, 9, 4, 6, 4,
                            7, 8, 9, 6, 8, 7, 8, 9, 7, 1,
                            7, 4, 4, 2, 5, 3, 8, 7, 5, 6,
                            4, 5, 6, 1, 6, 5, 7, 8, 7, 9 };
   int frequency[ MAXFREQUENCY ] = { 0 };

   mean( response, SIZE );
   median( response, SIZE );
   mode( frequency, response, SIZE, MAXFREQUENCY );

   return 0;
}

void mean( int answer[], int size )      // mean
{
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
42     int total = 0;
43
44     cout << "******\nMean\n******\n";
45
46     for ( int j = 0; j < size; ++j )
47        total += answer[ j ];
48
49     cout << setiosflags( ios::fixed | ios::showpoint )
50          << "The mean is the average value of the data items.\n"
51          << "The mean is equal to the total of all the data\n"
52          << "items divided by the number of data items (" << size << ")."
53          << "\nThe mean value for this run is: " << total
54          << " / " << size << " = " << setprecision( 2 )
55          << static_cast< double > ( total ) / size << "\n\n";
56  }
57
58  void median( int answer[], int size )                // median
59  {
60     int hold;
61     bool firstRow = true;
62
63     cout << "\n******\nMedian\n******\n"
64          << "The unsorted array of responses is\n";
65
66     for ( int loop = 0; loop < size; loop++ ) {
67        if ( loop % 20 == 0 && !firstRow )
68           cout << '\n';
69
70        cout << setw( 2 ) << answer[ loop ];
71        firstRow = false;
72     }
73
74     cout << "\n\n";
75
76     for ( int pass = 0; pass <= size - 2; ++pass )
77        for ( int k = 0; k <= size - 2; ++k )
78           if ( answer[ k ] > answer[ k + 1 ] ) {
79              hold = answer[ k ];
80              answer[ k ] = answer[ k + 1 ];
81              answer[ k + 1 ] = hold;
82           }
83
84     cout << "The sorted array is\n";
85
86     firstRow = true;
87     for ( int j = 0; j < size; ++j ) {
88        if ( j % 20 == 0 && !firstRow )
89           cout << '\n';
90
91        cout << setw( 2 ) << answer[ j ];
92        firstRow = false;
93     }
94
95     cout << "\n\n";
96
97     if ( size % 2 == 0 )      // even number of elements
98        cout << "The median is the average of elements " << ( size + 1 ) / 2
99             << " and " << 1 + ( size + 1 ) / 2 << " of the sorted "
100            << size << " element array.\nFor this run the median is "
101            << setprecision( 1 )
102            << static_cast< double >( answer[ ( size + 1 ) / 2 ] +
103                                      answer[ ( size + 1 ) / 2 + 1 ] ) / 2
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
104            << "\n\n";
105      else                    // odd number of elements
106         cout << "The median is element " << ( size + 1 ) / 2  << " of "
107              << "the sorted " << size << " element array.\n"
108              << "For this run the median is " << answer[ ( size + 1 ) / 2 - 1 ]
109              << "\n\n";
110   }
111
112   void mode( int freq[], int answer[], int aSize, int fSize )
113   {
114      const int SIZE2 = 10;
115      int largest = 0, array[ SIZE2 ] = { 0 }, count = 0;
116
117      cout << "\n******\nMode\n******\n";
118
119      for ( int rating = 1; rating < fSize; ++rating )
120         freq[ rating ] = 0;
121
122      for ( int loop = 0; loop < aSize; ++loop )
123         ++freq[ answer[ loop ] ];
124
125      cout << setw( 13 ) << "Response" << setw( 11 ) << "Frequency" << setw( 19 )
126           << "Histogram\n\n" << setw( 55 ) << "1    1    2    2\n"
127           << setw( 56 ) << "5    0    5    0    5\n\n";
128
129      for ( int r = 1; r < fSize; ++r ) {
130         cout << setw( 8 ) << rating << setw( 11 ) << freq[ r ] << "          ";
131
132         if ( freq[ r ] > largest ) {
133            largest = freq[ r ];
134
135            for ( int v = 0; v < SIZE2; ++v )
136               array[ v ] = 0;
137
138            array[ r ] = largest;
139            ++count;
140         }
141         else if ( freq[ r ] == largest ) {
142            array[ r ] = largest;
143            ++count;
144         }
145
146         for ( int b = 1; b <= freq[ r ]; b++ )
147            cout << '*';
148
149         cout << '\n';
150      }
151
152      cout << ( count > 1 ? "\nThe modes are:  " : "\nThe mode is: " );
153
154      for ( int m = 1; m < SIZE2; ++m )
155         if ( array[ m ] != 0 )
156            cout << m << " with a frequency of " << array[ m ] << "\n\t\t";
157
158      cout << endl;
159   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
******
Mean
******
The mean is the average value of the data items.
The mean is equal to the total of all the data
items divided by the number of data items (100).
The mean value for this run is: 662 / 100 = 6.62


******
Median
******
The unsorted array of responses is
 6 7 8 9 8 7 8 9 8 9 7 8 9 5 9 8 7 8 7 1
 6 7 8 9 3 9 8 7 1 7 7 8 9 8 9 8 9 7 1 9
 6 7 8 7 8 7 9 8 9 2 7 8 9 8 9 8 9 7 5 3
 5 6 7 2 5 3 9 4 6 4 7 8 9 6 8 7 8 9 7 1
 7 4 4 2 5 3 8 7 5 6 4 5 6 1 6 5 7 8 7 9

The sorted array is
 1 1 1 1 1 2 2 2 3 3 3 3 4 4 4 4 4 5 5 5
 5 5 5 5 5 6 6 6 6 6 6 6 6 6 7 7 7 7 7 7
 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 8 8 8
 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8
 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9

The median is the average of elements 50 and 51 of the sorted 100 element array.

For this run the median is 7.0


******
Mode
******
     Response  Frequency        Histogram

                                      1    1    2    2
                                 5    0    5    0    5

       10          5          *****
       10          3          ***
       10          4          ****
       10          5          *****
       10          8          ********
       10          9          *********
       10         23          ***********************
       10         23          ***********************
       10         20          ********************

The modes are:  7 with a frequency of 23
                8 with a frequency of 23
```

4.15 Use a single-subscripted array to solve the following problem. Read in 20 numbers, each of which is between 10 and 100, inclusive. As each number is read, print it only if it is not a duplicate of a number already read. Provide for the "worst case" in which all 20 numbers are different. Use the smallest possible array to solve this problem.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 4.15 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <iomanip>

using std::setw;

int main()
{
   const int SIZE = 20;
   int a[ SIZE ] = { 0 }, subscript = 0, duplicate, value;

   cout << "Enter 20 integers between 10 and 100:\n";

   for ( int i = 0; i < SIZE; ++i ) {
      duplicate = 0;
      cin >> value;

      for ( int j = 0; j < subscript; ++j )
         if ( value == a[ j ] ) {
            duplicate = 1;
            break;
         }

      if ( !duplicate )
         a[ subscript++ ] = value;
   }

   cout << "\nThe nonduplicate values are:\n";

   for ( i = 0; a[ i ] != 0; ++i )
      cout << setw( 4 ) << a[ i ];

   cout << endl;

   return 0;
}
```

```
Enter 20 integers between 10 and 100:
22 56 78 94 22 94 38 10 11 12 22 12 13 14 15 16 17 88 88 77

The nonduplicate values are:
  22  56  78  94  38  10  11  12  13  14  15  16  17  88  77
```

4.16 Label the elements of 3-by-5 double-subscripted array **sales** to indicate the order in which they are set to zero by the following program segment:

```
for ( row = 0; row < 3; row++ )
   for ( column = 0; column < 5; column++ )
      sales[ row ][ column ] = 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS:

```
sales[ 0 ][ 0 ], sales[ 0 ][ 1 ], sales[ 0 ][ 2 ], sales[ 0 ][ 3 ],
sales[ 0 ][ 4 ], sales[ 1 ][ 0 ], sales[ 1 ][ 1 ], sales[ 1 ][ 2 ],
sales[ 1 ][ 3 ], sales[ 1 ][ 4 ], sales[ 2 ][ 0 ], sales[ 2 ][ 1 ],
sales[ 2 ][ 2 ], sales[ 2 ][ 3 ], sales[ 2 ][ 4 ]
```

4.17 Write a program that simulates the rolling of two dice. The program should use **rand** to roll the first die and should use **rand** again to roll the second die. The sum of the two values should then be calculated. *Note:* Since each die can show an integer value from 1 to 6, then the sum of the two values will vary from 2 to 12, with 7 being the most frequent sum and 2 and 12 being the least frequent sums. Figure 4.24 shows the 36 possible combinations of the two dice. Your program should roll the two dice 36,000 times. Use a single-subscripted array to tally the numbers of times each possible sum appears. Print the results in a tabular format. Also, determine if the totals are reasonable (i.e., there are six ways to roll a 7, so approximately one sixth of all the rolls should be 7).

	1	2	3	4	5	6
1	2	3	4	5	6	7
2	3	4	5	6	7	8
3	4	5	6	7	8	9
4	5	6	7	8	9	10
5	6	7	8	9	10	11
6	7	8	9	10	11	12

Fig. 4.24 The 36 possible outcomes of rolling two dice.

```
1  // Exercise 4.17 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::ios;
6
7  #include <iomanip>
8
9  using std::setw;
10 using std::setprecision;
11 using std::setiosflags;
12
13 #include <cstdlib>
14 #include <ctime>
15
16 int main()
17 {
18    const long ROLLS = 36000;
19    const int SIZE = 13;
20    // array exepected contains counts for the expected
21    // number of times each sum occurs in 36 rolls of the dice
22    int expected[ SIZE ] = { 0, 0, 1, 2, 3, 4, 5, 6, 5, 4, 3, 2, 1 };
23    int x, y, sum[ SIZE ] = { 0 };
24
25    srand( time( 0 ) );
26
27    for ( long i = 1; i <= ROLLS; ++i ) {
28       x = 1 + rand() % 6;
29       y = 1 + rand() % 6;
30       ++sum[ x + y ];
31    }
32
33    cout << setw( 10 ) << "Sum" << setw( 10 ) << "Total" << setw( 10 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
         << "Expected" << setw( 10 ) << "Actual\n"
         << setiosflags( ios::fixed | ios::showpoint );

   for ( int j = 2; j < SIZE; ++j )
      cout << setw( 10 ) << j << setw( 10 ) << sum[ j ] << setprecision( 3 )
           << setw( 9 ) << 100.0 * expected[ j ] / 36 << "%" << setprecision(3)
           << setw( 9 ) << 100.0 * sum[ j ] / 36000 << "%\n";

   return 0;
}
```

```
 Sum      Total   Expected    Actual
   2        996     2.778%     2.767%
   3       2015     5.556%     5.597%
   4       3005     8.333%     8.347%
   5       3965    11.111%    11.014%
   6       5003    13.889%    13.897%
   7       5985    16.667%    16.625%
   8       5000    13.889%    13.889%
   9       4035    11.111%    11.208%
  10       3042     8.333%     8.450%
  11       1947     5.556%     5.408%
  12       1007     2.778%     2.797%
```

4.18 What does the following program do?

```
// ex04_18.cpp
#include <iostream>

using std::cout;
using std::endl;

int whatIsThis( int [], int );

int main()
{
   const int arraySize = 10;
   int a[ arraySize ] = { 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 };

   int result = whatIsThis( a, arraySize );

   cout << "Result is " << result << endl;
   return 0;
}

int whatIsThis( int b[], int size )
{
   if ( size == 1 )
      return b[ 0 ];
   else
      return b[ size - 1 ] + whatIsThis( b, size - 1 );
}
```

```
Result is 55
```

4.19 Write a program that runs 1000 games of craps and answers the following questions:

a) How many games are won on the 1st roll, 2nd roll, …, 20th roll, and after the 20th roll?

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

b) How many games are lost on the 1st roll, 2nd roll, …, 20th roll, and after the 20th roll?
c) What are the chances of winning at craps? (*Note:* You should discover that craps is one of the fairest casino games. What do you suppose this means?)
d) What is the average length of a game of craps?
e) Do the chances of winning improve with the length of the game?

```
// Exercise 4.19 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;

#include <cstdlib>
#include <ctime>

int rollDice( void );

int main()
{
   enum Outcome { CONTINUE, WIN, LOSE };
   const int SIZE = 22, ROLLS = 1000;
   int gameStatus, sum, myPoint, roll, length = 0, wins[ SIZE ] = { 0 },
       losses[ SIZE ] = { 0 }, winSum = 0, loseSum = 0;

   srand( time( 0 ) );

   for ( int i = 1; i <= ROLLS; ++i ) {
      sum = rollDice();
      roll = 1;

      switch ( sum ) {
         case 7: case 11:
            gameStatus = WIN;
            break;
         case 2: case 3: case 12:
            gameStatus = LOSE;
            break;
         default:
            gameStatus = CONTINUE;
            myPoint = sum;
            break;
      }

      while ( gameStatus == CONTINUE ) {
         sum = rollDice();
         ++roll;

         if ( sum == myPoint )
            gameStatus = WIN;
         else if ( sum == 7 )
            gameStatus = LOSE;
      }

      if ( roll > 21 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
56             roll = 21;
57
58          if ( gameStatus == WIN ) {
59             ++wins[ roll ];
60             ++winSum;
61          }
62          else {
63             ++losses[ roll ];
64             ++loseSum;
65          }
66       }
67
68       cout << "Games won or lost after the 20th roll"
69            << "\nare displayed as the 21st roll.\n\n";
70
71       for ( int z = 1; z <= 21; ++z )
72          cout << setw( 3 ) << wins[ z ] << " games won and " << setw( 3 )
73               << losses[ z ] << " games lost on roll " << z << '\n';
74
75       // calculate chances of winning
76       cout << setiosflags( ios::fixed | ios::showpoint )
77            << "\nThe chances of winning are " << winSum << " / "
78            << winSum + loseSum << " = " << setprecision( 2 )
79            << 100.0 * winSum / ( winSum + loseSum ) << "%\n";
80
81       // calculate average length of game
82       for ( int k = 1; k <= 21; ++k )
83          length += wins[ k ] * k + losses[ k ] * k;
84
85       cout << "The average game length is " << setprecision( 2 )
86            << length / 1000.0 << " rolls." << endl;
87
88       return 0;
89    }
90
91    int rollDice( void )
92    {
93       int die1, die2, workSum;
94
95       die1 = 1 + rand() % 6;
96       die2 = 1 + rand() % 6;
97       workSum = die1 + die2;
98
99       return workSum;
100   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Games won or lost after the 20th roll
are displayed as the 21st roll.

225 games won and 102 games lost on roll 1
 72 games won and 106 games lost on roll 2
 63 games won and  86 games lost on roll 3
 40 games won and  64 games lost on roll 4
 28 games won and  32 games lost on roll 5
 21 games won and  37 games lost on roll 6
 12 games won and  26 games lost on roll 7
 13 games won and  11 games lost on roll 8
  9 games won and   8 games lost on roll 9
  2 games won and  10 games lost on roll 10
  3 games won and   9 games lost on roll 11
  2 games won and   6 games lost on roll 12
  1 games won and   0 games lost on roll 13
  1 games won and   3 games lost on roll 14
  2 games won and   0 games lost on roll 15
  1 games won and   1 games lost on roll 16
  0 games won and   1 games lost on roll 17
  1 games won and   0 games lost on roll 18
  0 games won and   0 games lost on roll 19
  0 games won and   1 games lost on roll 20
  1 games won and   0 games lost on roll 21

The chances of winning are 497 / 1000 = 49.70%
The average game length is 3.36 rolls.
```

4.20 (*Airline Reservations System*) A small airline has just purchased a computer for its new automated reservations system. You have been asked to program the new system. You are to write a program to assign seats on each flight of the airline's only plane (capacity: 10 seats).

Your program should display the following menu of alternatives— **`Please type 1 for "First Class"`** and **`Please type 2 for "Economy"`**. If the person types **`1`**, your program should assign a seat in the first class section (seats 1-5). If the person types **`2`**, your program should assign a seat in the economy section (seats 6-10). Your program should print a boarding pass indicating the person's seat number and whether it is in the first class or economy section of the plane.

Use a single-subscripted array to represent the seating chart of the plane. Initialize all the elements of the array to 0 to indicate that all seats are empty. As each seat is assigned, set the corresponding elements of the array to 1 to indicate that the seat is no longer available.

Your program should, of course, never assign a seat that has already been assigned. When the first class section is full, your program should ask the person if it is acceptable to be placed in the nonsmoking section (and vice versa). If yes, then make the appropriate seat assignment. If no, then print the message **`"Next flight leaves in 3 hours."`**

```
1  // Exercise 4.20 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cctype>
9
10 int main()
11 {
12    const int SEATS = 11;
13    int plane[ SEATS ] = { 0 }, people = 0, economy = 1, firstClass = 6,
14        choice;
15    char response;
16
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
17      while ( people < 10 ) {
18         cout << "\nPlease type 1 for \"firstClass\"\n"
19              << "Please type 2 for \"economy\"\n";
20         cin >> choice;
21
22         if ( choice == 1 ) {
23            if ( !plane[ firstClass ] && firstClass <= 10 ) {
24               cout << "Your seat assignment is " << firstClass << ' ';
25               plane[ firstClass++ ] = 1;
26               ++people;
27            }
28            else if ( firstClass > 10 && economy <= 5 ) {
29               cout << "The firstClass section is full.\n"
30                    << "Would you like to sit in the economy"
31                    << " section (Y or N)? ";
32               cin >> response;
33
34               if ( toupper( response ) == 'Y' ) {
35                  cout << "Your seat assignment is " << economy << ' ';
36                  plane[ economy++ ] = 1;
37                  ++people;
38               }
39               else
40                  cout << "Next flight leaves in 3 hours.\n";
41            }
42            else
43               cout << "Next flight leaves in 3 hours.\n";
44         }
45         else {
46            if ( !plane[ economy ] && economy <= 5 ) {
47               cout << "Your seat assignment is " << economy << '\n';
48               plane[ economy++ ] = 1;
49               ++people;
50            }
51            else if ( economy > 5 && firstClass <= 10 ) {
52               cout << "The economy section is full.\n"
53                    << "Would you like to sit in the firstClass"
54                    << " section (Y or N)? ";
55               cin >> response;
56
57               if ( toupper( response ) == 'Y' ) {
58                  cout << "Your seat assignment is " << firstClass << '\n';
59                  plane[ firstClass++ ] = 1;
60                  ++people;
61               }
62               else
63                  cout << "Next flight leaves in 3 hours.\n";
64            }
65            else
66               cout << "Next flight leaves in 3 hours.\n";
67         }
68      }
69
70      cout << "All seats for this flight are sold." << endl;
71
72      return 0;
73   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Please type 1 for "firstClass"
Please type 2 for "economy"
1
...

Please type 1 for "firstClass"
Please type 2 for "economy"
1
Your seat assignment is 9
Please type 1 for "firstClass"
Please type 2 for "economy"
1
Your seat assignment is 10
Please type 1 for "firstClass"
Please type 2 for "economy"
2
Your seat assignment is 5
All seats for this flight are sold.
```

4.21 What does the following program do?

```
1  // ex04_21.cpp
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  void someFunction( int [], int );
8
9  int main()
10 {
11    const int arraySize = 10;
12    int a[ arraySize ] =
13       32, 27, 64, 18, 95, 14, 90, 70, 60, 37 };
14
15    cout << "The values in the array are:" << endl;
16    someFunction( a, arraySize );
17    cout << endl;
18
19    return 0;
20 }
21
22 void someFunction( int b[], int size )
23 {
24    if ( size > 0 ) {
25       someFunction( &b[ 1 ], size - 1 );
26       cout << b[ 0 ] << "  ";
27    }
28 }
```

```
The values in the array are:
37 60 70 90 14 95 18 64 27 32
```

4.22 Use a double-subscripted array to solve the following problem. A company has four salespeople (1 to 4) who sell five different products (1 to 5). Once a day, each salesperson passes in a slip for each different type of product sold. Each slip contains the following:

a) The salesperson number

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

b) The product number
c) The total dollar value of that product sold that day

Thus, each salesperson passes in between 0 and 5 sales slips per day. Assume that the information from all of the slips for last month is available. Write a program that will read all this information for last month's sales and summarize the total sales by salesperson by product. All totals should be stored in the double-subscripted array **sales**. After processing all the information for last month, print the results in tabular format with each of the columns representing a particular salesperson and each of the rows representing a particular product. Cross total each row to get the total sales of each product for last month; cross total each column to get the total sales by salesperson for last month. Your tabular printout should include these cross totals to the right of the totaled rows and to the bottom of the totaled columns.

```
// Exercise 4.22 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;

int main()
{
   const int PEOPLE = 5, PRODUCTS = 6;
   double sales[ PEOPLE ][ PRODUCTS ] = { 0.0 }, value, totalSales,
          productSales[ PRODUCTS ] = { 0.0 };
   int salesPerson, product;

   cout << "Enter the salesperson (1 - 4), product number (1 - 5), "
        << "and total sales.\nEnter -1 for the salesperson"
        << " to end input.\n";
   cin >> salesPerson;

   while ( salesPerson != -1 ) {
      cin >> product >> value;
      sales[ salesPerson ][ product ] += value;
      cin >> salesPerson;
   }

   cout << "\nThe total sales for each salesperson are displayed"
        << " at the end of each row,\n" << "and the total sales for"
        << " each product are displayed at the bottom of each\n"
        << "column.\n " << setw( 12 ) << 1 << setw( 12 ) << 2
        << setw( 12 ) << 3 << setw( 12 ) << 4 << setw( 12 ) << 5 << setw( 13 )
        << "Total\n" << setiosflags( ios::fixed | ios::showpoint );

   for ( int i = 1; i < PEOPLE; ++i ) {
      totalSales = 0.0;
      cout << i;

      for ( int j = 1; j < PRODUCTS; ++j ) {
         totalSales += sales[ i ][ j ];
         cout << setw( 12 ) << setprecision( 2 ) << sales[ i ][ j ];
         productSales[ j ] += sales[ i ][ j ];
      }

      cout << setw( 12 ) << setprecision( 2 ) << totalSales << '\n';
   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
52
53     cout << "\nTotal" << setw( 8 ) << setprecision( 2 ) << productSales[ 1 ];
54
55     for ( int j = 2; j < PRODUCTS; ++j )
56        cout << setw( 12 ) << setprecision( 2 ) << productSales[ j ];
57
58     cout << endl;
59
60     return 0;
61  }
```

```
Enter the salesperson (1 - 4), product number (1 - 5), and total sales.
Enter -1 for the salesperson to end input.
1 1 9.99
3 3 5.99
2 2 4.99
-1

The total sales for each salesperson are displayed at the end of each row,
and the total sales for each product are displayed at the bottom of each
column.
            1           2           3           4           5       Total
1        9.99        0.00        0.00        0.00        0.00        9.99
2        0.00        4.99        0.00        0.00        0.00        4.99
3        0.00        0.00        5.99        0.00        0.00        5.99
4        0.00        0.00        0.00        0.00        0.00        0.00

Total    9.99        4.99        5.99        0.00        0.00
```

4.23 (*Turtle Graphics*) The Logo language, which is particularly popular among personal computer users, made the concept of *turtle graphics* famous. Imagine a mechanical turtle that walks around the room under the control of a C++ program. The turtle holds a pen in one of two positions, up or down. While the pen is down, the turtle traces out shapes as it moves; while the pen is up, the turtle moves about freely without writing anything. In this problem, you will simulate the operation of the turtle and create a computerized sketchpad as well.

Use a 20-by-20 array **floor** that is initialized to zeros. Read commands from an array that contains them. Keep track of the current position of the turtle at all times and whether the pen is currently up or down. Assume that the turtle always starts at position 0,0 of the floor with its pen up. The set of turtle commands your program must process are as follows:

Command	Meaning
1	Pen up
2	Pen down
3	Turn right
4	Turn left
5,10	Move forward 10 spaces (or a number other than 10)
6	Print the 20-by-20 array
9	End of data (sentinel)

Suppose that the turtle is somewhere near the center of the floor. The following "program" would draw and print a 12-by-12 square and end with the pen in the up position:

```
2
5,12
3
5,12
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
3
5,12
3
5,12
1
6
9
```

As the turtle moves with the pen down, set the appropriate elements of array **floor** to **1**'s. When the **6** command (print) is given, wherever there is a **1** in the array, display an asterisk or some other character you choose. Wherever there is a zero, display a blank. Write a program to implement the turtle graphics capabilities discussed here. Write several turtle graphics programs to draw interesting shapes. Add other commands to increase the power of your turtle graphics language.

```
1  // Exercise 4.23 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  const int MAXCOMMANDS = 100, SIZE = 20;
9
10 int turnRight( int );
11 int turnLeft( int );
12 void getCommands( int [][ 2 ] );
13 void movePen( int, int [][ SIZE ], int, int );
14 void printArray( const int [][ SIZE ] );
15
16 int main()
17 {
18    int floor[ SIZE ][ SIZE ] = { 0 }, command, direction = 0,
19        commandArray[ MAXCOMMANDS ][ 2 ] = { 0 }, distance, count = 0;
20    bool penDown = false;
21
22    getCommands( commandArray );
23    command = commandArray[ count ][ 0 ];
24
25    while ( command != 9 ) {
26       switch ( command ) {
27          case 1:
28             penDown = false;
29             break;
30          case 2:
31             penDown = true;
32             break;
33          case 3:
34             direction = turnRight( direction );
35             break;
36          case 4:
37             direction = turnLeft( direction );
38             break;
39          case 5:
40             distance = commandArray[ count ][ 1 ];
41             movePen( penDown, floor, direction, distance );
42             break;
43          case 6:
44             cout << "\nThe drawing is:\n\n";
45             printArray( floor );
46             break;
47       }
48
49       command = commandArray[ ++count ][ 0 ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
50    }
51
52    return 0;
53 }
54
55 void getCommands( int commands[][ 2 ] )
56 {
57    int tempCommand;
58
59    cout << "Enter command (9 to end input): ";
60    cin >> tempCommand;
61
62    for ( int i = 0; tempCommand != 9 && i < MAXCOMMANDS; ++i ) {
63       commands[ i ][ 0 ] = tempCommand;
64
65       if ( tempCommand == 5 ) {
66          cin.ignore();   // skip comma
67          cin >> commands[ i ][ 1 ];
68       }
69
70       cout << "Enter command (9 to end input): ";
71       cin >> tempCommand;
72    }
73
74    commands[ i ][ 0 ] = 9;  // last command
75 }
76
77 int turnRight( int d )
78 {
79    return ++d > 3 ? 0 : d;
80 }
81
82 int turnLeft( int d )
83 {
84    return --d < 0 ? 3 : d;
85 }
86
87 void movePen( int down, int a[][ SIZE ], int dir, int dist )
88 {
89    static int xPos = 0, yPos = 0;
90    int j;  // looping variable
91
92    switch ( dir ) {
93       case 0:   // move to the right
94          for ( j = 1; j <= dist && yPos + j < SIZE; ++j )
95             if ( down )
96                a[ xPos ][ yPos + j ] = 1;
97
98          yPos += j - 1;
99          break;
100      case 1:   // move down
101         for ( j = 1; j <= dist && xPos + j < SIZE; ++j )
102            if ( down )
103               a[ xPos + j ][ yPos ] = 1;
104
105         xPos += j - 1;
106         break;
107      case 2:   // move to the left
108         for ( j = 1; j <= dist && yPos - j >= 0; ++j )
109            if ( down )
110               a[ xPos ][ yPos - j ] = 1;
111
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
112          yPos -= j - 1;
113          break;
114       case 3:   // move up
115          for ( j = 1; j <= dist && xPos - j >= 0; ++j )
116             if ( down )
117                a[ xPos - j ][ yPos ] = 1;
118
119          xPos -= j - 1;
120          break;
121    }
122 }
123
124 void printArray( const int a[][ SIZE ] )
125 {
126    for ( int i = 0; i < SIZE; ++i ) {
127       for ( int j = 0; j < SIZE; ++j )
128          cout << ( a[ i ][ j ] ? '*' : ' ' );
129
130       cout << endl;
131    }
132 }
```

```
Enter command (9 to end input): 2
Enter command (9 to end input): 5,6
Enter command (9 to end input): 3
Enter command (9 to end input): 5,12
Enter command (9 to end input): 3
Enter command (9 to end input): 5,12
Enter command (9 to end input): 3
Enter command (9 to end input): 5,12
Enter command (9 to end input): 1
Enter command (9 to end input): 6
Enter command (9 to end input): 9

The drawing is:

*******
*     *
*     *
*     *
*     *
*     *
*     *
*     *
*     *
*     *
*     *
*     *
*******
```

4.24 (*Knight's Tour*) One of the more interesting puzzlers for chess buffs is the Knight's Tour problem, originally proposed by the mathematician Euler. The question is this: Can the chess piece called the knight move around an empty chessboard and touch each of the 64 squares once and only once? We study this intriguing problem in depth here.

The knight makes L-shaped moves (over two in one direction and then over one in a perpendicular direction). Thus, from a square in the middle of an empty chessboard, the knight can make eight different moves (numbered 0 through 7) as shown in Fig. 4.25.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net



Fig. 4.25 The eight possible moves of the knight.

a) Draw an 8-by-8 chessboard on a sheet of paper and attempt a Knight's Tour by hand. Put a **1** in the first square you move to, a **2** in the second square, a **3** in the third, etc. Before starting the tour, estimate how far you think you will get, remembering that a full tour consists of 64 moves. How far did you get? Was this close to your estimate?

b) Now let us develop a program that will move the knight around a chessboard. The board is represented by an 8-by-8 double-subscripted array **board**. Each of the squares is initialized to zero. We describe each of the eight possible moves in terms of both their horizontal and vertical components. For example, a move of type 0, as shown in Fig. 4.25, consists of moving two squares horizontally to the right and one square vertically upward. Move 2 consists of moving one square horizontally to the left and two squares vertically upward. Horizontal moves to the left and vertical moves upward are indicated with negative numbers. The eight moves may be described by two single-subscripted arrays, **horizontal** and **vertical**, as follows:

```
horizontal[ 0 ] = 2
horizontal[ 1 ] = 1
horizontal[ 2 ] = -1
horizontal[ 3 ] = -2
horizontal[ 4 ] = -2
horizontal[ 5 ] = -1
horizontal[ 6 ] = 1
horizontal[ 7 ] = 2

vertical[ 0 ] = -1
vertical[ 1 ] = -2
vertical[ 2 ] = -2
vertical[ 3 ] = -1
vertical[ 4 ] = 1
vertical[ 5 ] = 2
vertical[ 6 ] = 2
vertical[ 7 ] = 1
```

Let the variables **currentRow** and **currentColumn** indicate the row and column of the knight's current position. To make a move of type **moveNumber**, where **moveNumber** is between 0 and 7, your program uses the statements

```
currentRow += vertical[ moveNumber ];
currentColumn += horizontal[ moveNumber ];
```

Keep a counter that varies from **1** to **64**. Record the latest count in each square the knight moves to. Remember to test each potential move to see if the knight has already visited that square, and, of course, test every potential move to

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

make sure that the knight does not land off the chessboard. Now write a program to move the knight around the chessboard. Run the program. How many moves did the knight make?

c) After attempting to write and run a Knight's Tour program, you have probably developed some valuable insights. We will use these to develop a *heuristic* (or strategy) for moving the knight. Heuristics do not guarantee success, but a carefully developed heuristic greatly improves the chance of success. You may have observed that the outer squares are more troublesome than the squares nearer the center of the board. In fact, the most troublesome, or inaccessible, squares are the four corners.

Intuition may suggest that you should attempt to move the knight to the most troublesome squares first and leave open those that are easiest to get to, so when the board gets congested near the end of the tour, there will be a greater chance of success.

We may develop an "accessibility heuristic" by classifying each of the squares according to how accessible they are and then always moving the knight to the square (within the knight's L-shaped moves, of course) that is most inaccessible. We label a double-subscripted array **`accessibility`** with numbers indicating from how many squares each particular square is accessible. On a blank chessboard, each center square is rated as **`8`**, each corner square is rated as **`2`** and the other squares have accessibility numbers of **`3`**, **`4`** or **`6`** as follows:

```
2  3  4  4  4  4  3  2
3  4  6  6  6  6  4  3
4  6  8  8  8  8  6  4
4  6  8  8  8  8  6  4
4  6  8  8  8  8  6  4
4  6  8  8  8  8  6  4
3  4  6  6  6  6  4  3
2  3  4  4  4  4  3  2
```

Now write a version of the Knight's Tour program using the accessibility heuristic. At any time, the knight should move to the square with the lowest accessibility number. In case of a tie, the knight may move to any of the tied squares. Therefore, the tour may begin in any of the four corners. (*Note:* As the knight moves around the chessboard, your program should reduce the accessibility numbers as more and more squares become occupied. In this way, at any given time during the tour, each available square's accessibility number will remain equal to precisely the number of squares from which that square may be reached.) Run this version of your program. Did you get a full tour? Now modify the program to run 64 tours, one starting from each square of the chessboard. How many full tours did you get?

d) Write a version of the Knight's Tour program which, when encountering a tie between two or more squares, decides what square to choose by looking ahead to those squares reachable from the "tied" squares. Your program should move to the square for which the next move would arrive at a square with the lowest accessibility number.

```
1  // Exercise 4.24 Part C Solution
2  // Knight's Tour - access version
3  // runs one tour
4  #include <iostream>
5
6  using std::cout;
7  using std::endl;
8
9  #include <iomanip>
10
11 using std::setw;
12
13 #include <cstdlib>
14 #include <ctime>
15
16 const int SIZE = 8;
17
18 void clearBoard( int [][ SIZE ] );
19 void printBoard( const int [][ SIZE ] );
20 bool validMove( int, int, const int [][ SIZE ] );
21
22 int main()
23 {
24    int board[ SIZE ][ SIZE ], currentRow, currentColumn, moveNumber = 0,
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
25          access[ SIZE ][ SIZE ] = { 2, 3, 4, 4, 4, 4, 3, 2,
26                                     3, 4, 6, 6, 6, 6, 4, 3,
27                                     4, 6, 8, 8, 8, 8, 6, 4,
28                                     4, 6, 8, 8, 8, 8, 6, 4,
29                                     4, 6, 8, 8, 8, 8, 6, 4,
30                                     4, 6, 8, 8, 8, 8, 6, 4,
31                                     3, 4, 6, 6, 6, 6, 4, 3,
32                                     2, 3, 4, 4, 4, 4, 3, 2 },
33
34          testRow, testColumn, minRow, minColumn,
35          minAccess = 9, accessNumber,
36          horizontal[ SIZE ] = { 2, 1, -1, -2, -2, -1, 1, 2 },
37          vertical[ SIZE ] = { -1, -2, -2, -1, 1, 2, 2, 1 };
38       bool done;
39
40       srand( time( 0 ) );
41
42       clearBoard( board );   // initialize array board
43       currentRow = rand() % 8;
44       currentColumn = rand() % 8;
45       board[ currentRow ][ currentColumn ] = ++moveNumber;
46       done = false;
47
48       while ( !done ) {
49          accessNumber = minAccess;
50
51          for ( int moveType = 0; moveType < SIZE; ++moveType ) {
52             testRow = currentRow + vertical[ moveType ];
53             testColumn = currentColumn + horizontal[ moveType ];
54
55             if ( validMove( testRow, testColumn, board ) ) {
56
57                if ( access[ testRow ][ testColumn ] < accessNumber ) {
58                   accessNumber = access[ testRow ][ testColumn ];
59                   minRow = testRow;
60                   minColumn = testColumn;
61                }
62
63                --access[ testRow ][ testColumn ];
64             }
65          }
66
67          if ( accessNumber == minAccess )
68             done = true;
69          else {
70             currentRow = minRow;
71             currentColumn = minColumn;
72             board[ currentRow ][ currentColumn ] = ++moveNumber;
73          }
74       }
75
76       cout << "The tour ended with " << moveNumber << " moves.\n";
77
78       if ( moveNumber == 64 )
79          cout << "This was a full tour!\n\n";
80       else
81          cout << "This was not a full tour.\n\n";
82
83       cout << "The board for this test is:\n\n";
84       printBoard( board );
85
86       return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}

void clearBoard( int workBoard[][ SIZE ] )
{
   for ( int row = 0; row < SIZE; ++row )
      for ( int col = 0; col < SIZE; ++col )
         workBoard[ row ][ col ] = 0;
}

void printBoard( const int workBoard[][ SIZE ] )
{
   cout << "   0  1  2  3  4  5  6  7\n";

   for ( int row = 0; row < SIZE; ++row ) {
      cout << row;

      for ( int col = 0; col < SIZE; ++col )
         cout << setw( 3 ) << workBoard[ row ][ col ];

      cout << '\n';
   }

   cout << endl;
}

bool validMove( int row, int column, const int workBoard[][ SIZE ] )
{
   // NOTE: This test stops as soon as it becomes false
   return ( row >= 0 && row < SIZE && column >= 0 && column < SIZE
            && workBoard[ row ][ column ] == 0 );
}
```

```
The tour ended with 64 moves.
This was a full tour!

The board for this test is:

   0  1  2  3  4  5  6  7
0  7 36  5 44  9 34 29 56
1  4 45  8 35 30 55 10 33
2 37  6 43 50 47 32 57 28
3 42  3 46 31 58 49 54 11
4 21 38 51 48 53 60 27 62
5  2 41 20 59 24 63 12 15
6 19 22 39 52 17 14 61 26
7 40  1 18 23 64 25 16 13
```

4.25 (*Knight's Tour: Brute-Force Approaches*) In Exercise 4.24, we developed a solution to the Knight's Tour problem. The approach used, called the "accessibility heuristic," generates many solutions and executes efficiently.

As computers continue increasing in power, we will be able to solve more problems with sheer computer power and relatively unsophisticated algorithms. Let us call this approach "brute force" problem solving.

a) Use random-number generation to enable the knight to walk around the chessboard (in its legitimate L-shaped moves, of course) at random. Your program should run one tour and print the final chessboard. How far did the knight get?

b) Most likely, the preceding program produced a relatively short tour. Now modify your program to attempt 1000 tours. Use a single-subscripted array to keep track of the number of tours of each length. When your program finishes attempting the 1000 tours, it should print this information in neat tabular format. What was the best result?

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

c) Most likely, the preceding program gave you some "respectable" tours, but no full tours. Now "pull all the stops out" and simply let your program run until it produces a full tour. (*Caution:* This version of the program could run for hours on a powerful computer.) Once again, keep a table of the number of tours of each length, and print this table when the first full tour is found. How many tours did your program attempt before producing a full tour? How much time did it take?

d) Compare the brute-force version of the Knight's Tour with the accessibility-heuristic version. Which required a more careful study of the problem? Which algorithm was more difficult to develop? Which required more computer power? Could we be certain (in advance) of obtaining a full tour with the accessibility heuristic approach? Could we be certain (in advance) of obtaining a full tour with the brute-force approach? Argue the pros and cons of brute-force problem solving in general.

```
// Exercise 4.25 Part A Solution
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>

using std::setw;

#include <cstdlib>
#include <ctime>

const int SIZE = 8;

bool validMove( int, int, const int [][ SIZE ] );
void printBoard( const int [][ SIZE ] );

int main()
{
   int currentRow, currentColumn, moveType, moveNumber = 0,
       testRow, testColumn, board[ SIZE ][ SIZE ] = { 0 },
       horizontal[ SIZE ] = { 2, 1, -1, -2, -2, -1, 1, 2 },
       vertical[ SIZE ] = { -1, -2, -2, -1, 1, 2, 2, 1 };
   bool done, goodMove;

   srand( time( 0 ) );

   currentRow = rand() % SIZE;
   currentColumn = rand() % SIZE;
   board[ currentRow ][ currentColumn ] = ++moveNumber;
   done = false;

   while ( !done ) {
      moveType = rand() % SIZE;
      testRow = currentRow + vertical[ moveType ];
      testColumn = currentColumn + horizontal[ moveType ];
      goodMove = validMove( testRow, testColumn, board );

      if ( goodMove ) {
         currentRow = testRow;
         currentColumn = testColumn;
         board[ currentRow ][ currentColumn ] = ++moveNumber;
      }
      else {

         for ( int count = 0; count < SIZE - 1 && !goodMove; ++count ) {
            moveType = ++moveType % SIZE;
            testRow = currentRow + vertical[ moveType ];
            testColumn = currentColumn + horizontal[ moveType ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
51             goodMove = validMove( testRow, testColumn, board );
52
53             if ( goodMove ) {
54                currentRow = testRow;
55                currentColumn = testColumn;
56                board[ currentRow ][ currentColumn ] = ++moveNumber;
57             }
58          }
59
60          if ( !goodMove )
61             done = true;
62       }
63
64       if ( moveNumber == 64 )
65          done = true;
66    }
67
68    cout << "The tour has ended with " << moveNumber << " moves.\n";
69
70    if ( moveNumber == 64 )
71       cout << "This was a full tour!\n";
72    else
73       cout << "This was not a full tour.\n";
74
75    cout << "The board for this random test was:\n\n";
76    printBoard( board );
77    return 0;
78 }
79
80 bool validMove( int row, int column, const int workBoard[][ SIZE ] )
81 {
82    // NOTE: This test stops as soon as it becomes false
83    return ( row >= 0 && row < SIZE && column >= 0 && column < SIZE
84             && workBoard[ row ][ column ] == 0 );
85 }
86
87 void printBoard( const int board[][ SIZE ] )
88 {
89    cout << "   0  1  2  3  4  5  6  7\n";
90
91    for ( int row = 0; row < SIZE; ++row ) {
92       cout << row;
93
94       for ( int col = 0; col < SIZE; ++col )
95          cout << setw( 3 ) << board[ row ][ col ];
96
97       cout << '\n';
98    }
99
100   cout << endl;
101 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
The tour has ended with 30 moves.
This was not a full tour.
The board for this random test was:

   0  1  2  3  4  5  6  7
0 30 27  0 17  0  0 14  0
1  0 18 25 28 15  0  0  0
2 26 29 16 21  0  0  0 13
3  0 24 19  0 11 22  0  0
4  0  1  0 23 20  9 12  7
5  0  0  0 10  0  6  0  0
6  2  0  0  0  4  0  8  0
7  0  0  3  0  0  0  5  0
```

```
1  // Exercise 4.25 Part B Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  #include <iomanip>
7
8  using std::setw;
9
10 #include <cstdlib>
11 #include <ctime>
12
13 const int SIZE = 8, TOURS = 1000, MAXMOVES = 65;
14
15 bool validMove( int, int, int, const int [][ SIZE ] );
16
17 int main()
18 {
19    int currentRow, currentColumn, moveType, moveNumber, testRow, testColumn,
20        moveTotal[ MAXMOVES ] = { 0 }, goodMove, board[ SIZE ][ SIZE ],
21        horizontal[ SIZE ] = { 2, 1, -1, -2, -2, -1, 1, 2 },
22        vertical[ SIZE ] = { -1, -2, -2, -1, 1, 2, 2, 1 };
23    bool done;
24
25    srand( time( 0 ) );
26
27    for ( int i = 0; i < TOURS; ++i ) {
28       for ( int row = 0; row < SIZE; ++row )
29          for ( int col = 0; col < SIZE; ++col )
30             board[ row ][ col ] = 0;
31
32       moveNumber = 0;
33
34       currentRow = rand() % SIZE;
35       currentColumn = rand() % SIZE;
36       board[ currentRow ][ currentColumn ] = ++moveNumber;
37       done = false;
38
39       while ( !done ) {
40          moveType = rand() % SIZE;
41          testRow = currentRow + vertical[ moveType ];
42          testColumn = currentColumn + horizontal[ moveType ];
43          goodMove = validMove( testRow, testColumn, moveType, board );
44
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
45          if ( goodMove ) {
46             currentRow = testRow;
47             currentColumn = testColumn;
48             board[ currentRow ][ currentColumn ] = ++moveNumber;
49          }
50          else {
51
52             for ( int count = 0; count < SIZE - 1 && !goodMove; ++count ) {
53                moveType = ++moveType % SIZE;
54                testRow = currentRow + vertical[ moveType ];
55                testColumn = currentColumn + horizontal[ moveType ];
56                goodMove = validMove( testRow, testColumn, moveType, board );
57
58                if ( goodMove ) {
59                   currentRow = testRow;
60                   currentColumn = testColumn;
61                   board[ currentRow ][ currentColumn ] = ++moveNumber;
62                }
63
64             }
65
66             if ( !goodMove )
67                done = true;
68          }
69
70          if ( moveNumber == 64 )
71             done = true;
72       }
73
74       ++moveTotal[ moveNumber ];
75    }
76
77    for ( int j = 1; j < MAXMOVES; ++j )
78       if ( moveTotal[ j ] )
79          cout << "There were " << moveTotal[ j ] << " tours of " << j
80               << " moves." << endl;
81
82    return 0;
83 }
84
85 bool validMove( int testRow, int testColumn, int moveType,
86                 const int board[][ SIZE ] )
87 {
88    if ( testRow >= 0 && testRow < SIZE && testColumn >= 0 &&
89         testColumn < SIZE )
90       return board[ testRow ][ testColumn ] != 0 ? false : true;
91    else
92       return false;
93 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
There were 1 tours of 5 moves.
There were 3 tours of 6 moves.
There were 3 tours of 8 moves.
There were 2 tours of 10 moves.
There were 6 tours of 11 moves.
There were 4 tours of 12 moves.
There were 6 tours of 13 moves.
There were 5 tours of 14 moves.
There were 11 tours of 15 moves.
There were 7 tours of 16 moves.
There were 5 tours of 17 moves.
There were 15 tours of 18 moves.
There were 6 tours of 19 moves.
There were 11 tours of 20 moves.
There were 6 tours of 21 moves.
There were 10 tours of 22 moves.
There were 19 tours of 23 moves.
There were 20 tours of 24 moves.
There were 12 tours of 25 moves.
There were 25 tours of 26 moves.
There were 21 tours of 27 moves.
There were 29 tours of 28 moves.
There were 24 tours of 29 moves.
There were 23 tours of 30 moves.
There were 23 tours of 31 moves.
There were 25 tours of 32 moves.
There were 26 tours of 33 moves.
There were 34 tours of 34 moves.
There were 32 tours of 35 moves.
There were 30 tours of 36 moves.
There were 24 tours of 37 moves.
There were 42 tours of 38 moves.
There were 21 tours of 39 moves.
There were 42 tours of 40 moves.
There were 31 tours of 41 moves.
There were 49 tours of 42 moves.
There were 46 tours of 43 moves.
There were 42 tours of 44 moves.
There were 28 tours of 45 moves.
There were 33 tours of 46 moves.
There were 31 tours of 47 moves.
There were 28 tours of 48 moves.
There were 22 tours of 49 moves.
There were 24 tours of 50 moves.
There were 17 tours of 51 moves.
There were 22 tours of 52 moves.
There were 12 tours of 53 moves.
There were 13 tours of 54 moves.
There were 13 tours of 55 moves.
There were 6 tours of 56 moves.
There were 4 tours of 57 moves.
There were 4 tours of 58 moves.
There were 2 tours of 59 moves.
```

4.26 (*Eight Queens*) Another puzzler for chess buffs is the Eight Queens problem. Simply stated: Is it possible to place eight queens on an empty chessboard so that no queen is "attacking" any other, i.e., no two queens are in the same row, the same column, or along the same diagonal? Use the thinking developed in Exercise 4.24 to formulate a heuristic for solving the Eight Queens problem. Run your program. (*Hint:* It is possible to assign a value to each square of the chessboard indicating how many squares of an empty chessboard are "eliminated" if a queen is placed in that square. Each of the corners would be assigned the value 22, as in Fig.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

4.26.) Once these "elimination numbers" are placed in all 64 squares, an appropriate heuristic might be: Place the next queen in the square with the smallest elimination number. Why is this strategy intuitively appealing?

```
* * * * * * * *
* *
*   *
*     *
*       *
*         *
*           *
*             *
```

Fig. 4.26 The 22 squares eliminated by placing a queen in the upper-left corner.

4.27 (*Eight Queens: Brute-Force Approaches*) In this exercise, you will develop several brute-force approaches to solving the Eight Queens problem introduced in Exercise 4.26.

a) Solve the Eight Queens exercise, using the random brute-force technique developed in Exercise 4.25.
b) Use an exhaustive technique, i.e., try all possible combinations of eight queens on the chessboard.
c) Why do you suppose the exhaustive brute-force approach may not be appropriate for solving the Knight's Tour problem?
d) Compare and contrast the random brute-force and exhaustive brute-force approaches in general.

```
1  // Exercise 4.27 Part A Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <iomanip>
8
9  using std::setw;
10
11 #include <ctime>
12 #include <cstdlib>
13
14 bool queenCheck( const char [][ 8 ], int, int );
15 void placeQueens( char [][ 8 ] );
16 void printBoard( const char [][ 8 ] );
17 void xConflictSquares( char [][ 8 ], int, int );
18 void xDiagonals( char [][ 8 ], int, int );
19 bool availableSquare( const char [][ 8 ] );
20 inline int validMove( const char board[][ 8 ], int row, int col )
21    { return ( row >= 0 && row < 8 && col >= 0 && col < 8 ); }
22
23 int main()
24 {
25    char board [ 8 ][ 8 ] = { '\0' };
26
27    srand( time( 0 ) );
28
29    placeQueens( board );
30    printBoard( board );
31
32    return 0;
33 }
34
35 bool availableSquare( const char board[][ 8 ] )
36 {
37    for ( int row = 0; row < 8; ++row )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
38          for ( int col = 0; col < 8; ++col )
39             if ( board[ row ][ col ] == '\0' )
40                return false;  // at least one open square is available
41
42       return true;  // no available squares
43    }
44
45    void placeQueens( char board[][ 8 ] )
46    {
47       const char QUEEN = 'Q';
48       int rowMove, colMove, queens = 0;
49       bool done = false;
50
51       while ( queens < 8 && !done ) {
52          rowMove = rand() % 8;
53          colMove = rand() % 8;
54
55          if ( queenCheck( board, rowMove, colMove ) ) {
56             board[ rowMove ][ colMove ] = QUEEN;
57             xConflictSquares( board, rowMove, colMove );
58             ++queens;
59          }
60
61          done = availableSquare( board );
62       }
63    }
64
65    void xConflictSquares( char board[][ 8 ], int row, int col )
66    {
67        for ( int loop = 0; loop < 8; ++loop ) {
68           // place an '*' in the row occupied by the queen
69           if ( board[ row ][ loop ] == '\0' )
70              board[ row ][ loop ] = '*';
71
72           // place an '*' in the col occupied by the queen
73           if ( board[ loop ][ col ] == '\0' )
74              board[ loop ][ col ] = '*';
75        }
76
77        // place an '*' in the diagonals occupied by the queen
78        xDiagonals( board, row, col );
79    }
80
81    bool queenCheck( const char board[][ 8 ], int row, int col )
82    {
83       int r = row, c = col;
84
85       // check row and column for a queen
86       for ( int d = 0; d < 8; ++d )
87          if ( board[ row ][ d ] == 'Q' || board[ d ][ col ] == 'Q' )
88             return false;
89
90       // check upper left diagonal for a queen
91       for ( int e = 0; e < 8 && validMove( board, --r, --c ); ++e )
92          if ( board[ r ][ c ] == 'Q' )
93             return false;
94
95       r = row;
96       c = col;
97       // check upper right diagonal for a queen
98       for ( int f = 0; f < 8 && validMove( board, --r, ++c ); ++f )
99          if ( board[ r ][ c ] == 'Q' )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
100          return false;
101
102    r = row;
103    c = col;
104    // check lower left diagonal for a queen
105    for ( int g = 0; g < 8 && validMove( board, ++r, --c ); ++g )
106       if (board[ r ][ c ] == 'Q' )
107          return false;
108
109    r = row;
110    c = col;
111    // check lower right diagonal for a queen
112    for ( int h = 0; h < 8 && validMove( board, ++r, ++c ); ++h )
113       if ( board[ r ][ c ] == 'Q' )
114          return false;
115
116    return true;  // no queen in conflict
117 }
118
119 void xDiagonals( char board[][ 8 ], int row, int col )
120 {
121    int r = row, c = col;
122
123    // upper left diagonal
124    for ( int a = 0; a < 8 && validMove( board, --r, --c ); ++a )
125       board[ r ][ c ] = '*';
126
127    r = row;
128    c = col;
129    // upper right diagonal
130    for ( int b = 0; b < 8 && validMove( board, --r, ++c ); ++b )
131       board[ r ][ c ] = '*';
132
133    r = row;
134    c = col;
135    // lower left diagonal
136    for ( int d = 0; d < 8 && validMove( board, ++r, --c ); ++d )
137       board[ r ][ c ] = '*';
138
139    r = row;
140    c = col;
141    // lower right diagonal
142    for ( int e = 0; e < 8 && validMove( board, ++r, ++c ); ++e )
143       board[ r ][ c ] = '*';
144 }
145
146 void printBoard( const char board[][ 8 ] )
147 {
148    int queens = 0;
149
150    // header for columns
151    cout << "   0 1 2 3 4 5 6 7\n";
152
153    for ( int r = 0; r < 8; ++r ) {
154       cout << setw( 2 ) << r << ' ';
155
156       for ( int c = 0; c < 8; ++c ) {
157          cout << board[ r ][ c ] << ' ';
158
159          if ( board[ r ][ c ] == 'Q' )
160             ++queens;
161       }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
162
163       cout << '\n';
164    }
165
166    if ( queens == 8 )
167       cout << "\nEight Queens were placed on the board!" << endl;
168    else
169       cout << '\n' << queens << " Queens were placed on the board." << endl;
170 }
```

```
   0 1 2 3 4 5 6 7
 0 * * * * Q * * *
 1 * Q * * * * * *
 2 * * * * * Q * *
 3 * * Q * * * * *
 4 * * * * * * * *
 5 * * * * * * * Q
 6 Q * * * * * * *
 7 * * * Q * * * *

7 Queens were placed on the board.
```

4.28 (*Knight's Tour: Closed-Tour Test*) In the Knight's Tour, a full tour occurs when the knight makes 64 moves touching each square of the chess board once and only once. A closed tour occurs when the 64th move is one move away from the location in which the knight started the tour. Modify the Knight's Tour program you wrote in Exercise 4.24 to test for a closed tour if a full tour has occurred.

```
1  // Exercise 4.28 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <iomanip>
8
9  using std::setw;
10
11 #include <cstdlib>
12 #include <ctime>
13
14 const int SIZE = 8;
15
16 void clearBoard( int [][ SIZE ] );
17 void printBoard( const int [][ SIZE ] );
18 bool validMove( int, int, const int [][ SIZE ] );
19
20 int main()
21 {
22    int board[ SIZE ][ SIZE ], firstMoveRow, firstMoveCol,
23        access[ SIZE ][ SIZE ] = { 2, 3, 4, 4, 4, 4, 3, 2,
24                                   3, 4, 6, 6, 6, 6, 4, 3,
25                                   4, 6, 8, 8, 8, 8, 6, 4,
26                                   4, 6, 8, 8, 8, 8, 6, 4,
27                                   4, 6, 8, 8, 8, 8, 6, 4,
28                                   4, 6, 8, 8, 8, 8, 6, 4,
29                                   3, 4, 6, 6, 6, 6, 4, 3,
30                                   2, 3, 4, 4, 4, 4, 3, 2 },
31        currentRow, currentColumn, moveNumber = 0, testRow, testColumn,
32        minRow, minColumn, minAccess = 9, accessNumber,
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
33          horizontal[ SIZE ] = { 2, 1, -1, -2, -2, -1, 1, 2 },
34          vertical[ SIZE ] = { -1, -2, -2, -1, 1, 2, 2, 1 };
35       bool done, closedTour = false;
36
37       srand( time( 0 ) );
38
39       clearBoard( board );   // initialize array board
40       currentRow = rand() % SIZE;
41       currentColumn = rand() % SIZE;
42       firstMoveRow = currentRow;      // store first moves row
43       firstMoveCol = currentColumn;   // store first moves col
44
45       board[ currentRow ][ currentColumn ] = ++moveNumber;
46       done = false;
47
48       while ( !done ) {
49          accessNumber = minAccess;
50
51          for ( int moveType = 0; moveType < SIZE; ++moveType ) {
52             testRow = currentRow + vertical[ moveType ];
53             testColumn = currentColumn + horizontal[ moveType ];
54
55             if ( validMove( testRow, testColumn, board ) ) {
56                if ( access[ testRow ][ testColumn ] < accessNumber ) {
57                   accessNumber = access[ testRow ][ testColumn ];
58                   minRow = testRow;
59                   minColumn = testColumn;
60                }
61
62                --access[ testRow ][ testColumn ];
63             }
64          }
65
66          if ( accessNumber == minAccess )
67             done = true;
68          else {
69             currentRow = minRow;
70             currentColumn = minColumn;
71             board[ currentRow ][ currentColumn ] = ++moveNumber;
72
73             // check for closed tour
74             if ( moveNumber == 64 )
75                for ( int m = 0; m < SIZE; ++m ) {
76                   testRow = currentRow + vertical[ m ];
77                   testColumn = currentColumn + horizontal[ m ];
78
79                   if ( testRow == firstMoveRow && testColumn == firstMoveCol )
80                      closedTour = true;
81                }
82          }
83       }
84
85       cout << "The tour ended with " << moveNumber << " moves.\n";
86
87       if ( moveNumber == 64 && closedTour == true )
88          cout << "This was a CLOSED tour!\n\n";
89       else if ( moveNumber == 64 )
90          cout << "This was a full tour!\n\n";
91       else
92          cout << "This was not a full tour.\n\n";
93
94       cout << "The board for this test is:\n\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
95     printBoard( board );
96
97     return 0;
98  }
99
100 void clearBoard( int workBoard[][ SIZE ] )
101 {
102    for ( int row = 0; row < SIZE; ++row )
103       for ( int col = 0; col < SIZE; ++col )
104          workBoard[ row ][ col ] = 0;
105 }
106
107 void printBoard( const int workBoard[][ SIZE ] )
108 {
109    cout << "   0  1  2  3  4  5  6  7\n";
110
111    for ( int row = 0; row < SIZE; ++row ) {
112       cout << row;
113
114       for ( int col = 0; col < SIZE; ++col )
115          cout << setw( 3 ) << workBoard[ row ][ col ];
116
117       cout << '\n';
118    }
119
120    cout << endl;
121 }
122
123 bool validMove( int row, int column, const int workBoard[][ SIZE ] )
124 {
125    // NOTE: This test stops as soon as it becomes false
126    return ( row >= 0 && row < SIZE && column >= 0 && column < SIZE
127             && workBoard[ row ][ column ] == 0 );
128 }
```

```
The tour ended with 64 moves.
This was a full tour!

The board for this test is:

   0  1  2  3  4  5  6  7
0 42 25 50  7 40 23 52  5
1 49  8 41 24 51  6 39 22
2 26 43 48 55 46 59  4 53
3  9 56 45 60 63 54 21 38
4 44 27 64 47 58 37 62  3
5 13 10 57 36 61 18 31 20
6 28 35 12 15 30 33  2 17
7 11 14 29 34  1 16 19 32
```

4.29 (*The Sieve of Eratosthenes*) A prime integer is any integer that is evenly divisible only by itself and 1. The Sieve of Eratosthenes is a method of finding prime numbers. It operates as follows:

a) Create an array with all elements initialized to 1 (true). Array elements with prime subscripts will remain 1. All other array elements will eventually be set to zero.

b) Starting with array subscript 2 (subscript 1 must be prime), every time an array element is found whose value is 1, loop through the remainder of the array and set to zero every element whose subscript is a multiple of the subscript for the element with value 1. For array subscript 2, all elements beyond 2 in the array that are multiples of 2 will be set to zero (subscripts 4, 6, 8, 10, etc.); for array subscript 3, all elements beyond 3 in the array that are multiples of 3 will be set to zero (subscripts 6, 9, 12, 15, etc.); and so on.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

When this process is complete, the array elements that are still set to one indicate that the subscript is a prime number. These subscripts can then be printed. Write a program that uses an array of 1000 elements to determine and print the prime numbers between 1 and 999. Ignore element 0 of the array.

```
// Exercise 4.29 Solution
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>

using std::setw;

int main()
{
   const int SIZE = 1000;
   int array[ SIZE ], count = 0;

   for ( int k = 0; k < SIZE; ++k )
      array[ k ] = 1;

   for ( int i = 1; i < SIZE; ++i )
      if ( array[ i ] == 1 && i != 1 )
         for ( int j = i; j <= SIZE; ++j )
            if ( j % i == 0 && j != i )
               array[ j ] = 0;

   // range 2 - 197
   for ( int q = 2; q < SIZE; ++q )
      if ( array[ q ] == 1 ) {
         cout << setw( 3 ) << q << " is a prime number.\n";
         ++count;
      }

   cout << "A total of " << count << " prime numbers were found." << endl;

   return 0;
}
```

```
  3 is a prime number.
  5 is a prime number.
  7 is a prime number.
 11 is a prime number.
 ...
983 is a prime number.
991 is a prime number.
997 is a prime number.
A total of 168 prime numbers were found.
```

4.30 (*Bucket Sort*) A bucket sort begins with a single-subscripted array of positive integers to be sorted and a double-subscripted array of integers with rows subscripted from 0 to 9 and columns subscripted from 0 to *n* - 1, where *n* is the number of values in the array to be sorted. Each row of the double-subscripted array is referred to as a bucket. Write a function **`bucketSort`** that takes an integer array and the array size as arguments and performs as follows:

a) Place each value of the single-subscripted array into a row of the bucket array based on the value's ones digit. For example, 97 is placed in row 7, 3 is placed in row 3 and 100 is placed in row 0. This is called a "distribution pass."

b) Loop through the bucket array row by row, and copy the values back to the original array. This is called a "gathering pass." The new order of the preceding values in the single-subscripted array is 100, 3 and 97.

c) Repeat this process for each subsequent digit position (tens, hundreds, thousands, etc.).

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

On the second pass, 100 is placed in row 0, 3 is placed in row 0 (because 3 has no tens digit) and 97 is placed in row 9. After the gathering pass, the order of the values in the single-subscripted array is 100, 3 and 97. On the third pass, 100 is placed in row 1, 3 is placed in row zero and 97 is placed in row zero (after the 3). After the last gathering pass, the original array is now in sorted order.

Note that the double-subscripted array of buckets is 10 times the size of the integer array being sorted. This sorting technique provides better performance than a bubble sort, but requires much more memory. The bubble sort requires space for only one additional element of data. This is an example of the space–time trade-off: The bucket sort uses more memory than the bubble sort, b ut performs better. This version of the bucket sort requires copying all the data back to the original array on each pass. Another possibility is to create a second double-subscripted bucket array and repeatedly swap the data between the two bucket arrays.

```
1  // Exercise 4.30 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <iomanip>
8
9  using std::setw;
10
11 // constant size must be defined as the array size for bucketSort to work
12 const int SIZE = 12;
13
14 void bucketSort( int [] );
15 void distributeElements( int [], int [][ SIZE ], int );
16 void collectElements( int [], int [][ SIZE ] );
17 int numberOfDigits( int [], int );
18 void zeroBucket( int [][ SIZE ] );
19
20 int main()
21 {
22    int array[ SIZE ] = { 19, 13, 5, 27, 1, 26, 31, 16, 2, 9, 11, 21 };
23
24    cout << "Array elements in original order:\n";
25
26    for ( int i = 0; i < SIZE; ++i )
27       cout << setw( 3 ) << array[ i ];
28
29    cout << '\n';
30    bucketSort( array );
31
32    cout << "\nArray elements in sorted order:\n";
33
34    for ( int j = 0; j < SIZE; ++j )
35       cout << setw( 3 ) << array[ j ];
36
37    cout << endl;
38
39    return 0;
40 }
41
42 // Perform the bucket sort algorithm
43 void bucketSort( int a[] )
44 {
45    int totalDigits, bucket[ 10 ][ SIZE ] = { 0 };
46
47    totalDigits = numberOfDigits( a, SIZE );
48
49    for ( int i = 1; i <= totalDigits; ++i ) {
50       distributeElements( a, bucket, i );
51       collectElements( a, bucket );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
52
53       if ( i != totalDigits )
54          zeroBucket( bucket );  // set all bucket contents to zero
55    }
56 }
57
58 // Determine the number of digits in the largest number
59 int numberOfDigits( int b[], int arraySize )
60 {
61    int largest = b[ 0 ], digits = 0;
62
63    for ( int i = 1; i < arraySize; ++i )
64       if ( b[ i ] > largest )
65          largest = b[ i ];
66
67    while ( largest != 0 ) {
68       ++digits;
69       largest /= 10;
70    }
71
72    return digits;
73 }
74
75 // Distribute elements into buckets based on specified digit
76 void distributeElements( int a[], int buckets[][ SIZE ], int digit )
77 {
78    int divisor = 10, bucketNumber, elementNumber;
79
80    for ( int i = 1; i < digit; ++i )   // determine the divisor
81       divisor *= 10;                  // used to get specific digit
82
83    for ( int k = 0; k < SIZE; ++k ) {
84       // bucketNumber example for hundreds digit:
85       // (1234 % 1000 - 1234 % 100) / 100 --> 2
86       bucketNumber = ( a[ k ] % divisor - a[ k ] %
87                      ( divisor / 10 ) ) / ( divisor / 10 );
88
89       // retrieve value in buckets[bucketNumber][0] to determine
90       // which element of the row to store a[i] in.
91       elementNumber = ++buckets[ bucketNumber ][ 0 ];
92       buckets[ bucketNumber ][ elementNumber ] = a[ k ];
93    }
94 }
95
96 // Return elements to original array
97 void collectElements( int a[], int buckets[][ SIZE ])
98 {
99    int subscript = 0;
100
101   for ( int i = 0; i < 10; ++i )
102      for ( int j = 1; j <= buckets[ i ][ 0 ]; ++j )
103         a[ subscript++ ] = buckets[ i ][ j ];
104 }
105
106 // Set all buckets to zero
107 void zeroBucket( int buckets[][ SIZE ] )
108 {
109    for ( int i = 0; i < 10; ++i )
110       for ( int j = 0; j < SIZE; ++j )
111          buckets[ i ][ j ] = 0;
112 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Array elements in original order:
 19 13  5 27  1 26 31 16  2  9 11 21

Array elements in sorted order:
  1  2  5  9 11 13 16 19 21 26 27 31
```

RECURSION EXERCISES

4.31 (*Selection Sort*) A selection sort searches an array looking for the smallest element in the array. Then, the smallest element is swapped with the first element of the array. The process is repeated for the subarray beginning with the second element of the array. Each pass of the array results in one element being placed in its proper location. This sort performs comparably to the bubble sort—for an array of *n* elements, *n* - 1 passes must be made, and for each subarray, *n* - 1 comparisons must be made to find the smallest value. When the subarray being processed contains one element, the array is sorted. Write recursive function **selectionSort** to perform this algorithm.

```
1  // Exercise 4.31 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <cstdlib>
8  #include <ctime>
9
10 void selectionSort( int [], int );
11
12 int main()
13 {
14    const int SIZE = 10, MAXRANGE = 1000;
15    int sortThisArray[ SIZE ] = { 0 };
16
17    srand( time( 0 ) );
18
19    for ( int i = 0; i < SIZE; ++i )
20       sortThisArray[ i ] = 1 + rand() % MAXRANGE;
21
22    cout << "\nUnsorted array is:\n";
23    for ( int j = 0; j < SIZE; ++j )
24       cout << ' ' << sortThisArray[ j ] << ' ';
25
26    selectionSort( sortThisArray, SIZE );
27
28    cout << "\n\nSorted array is:\n";
29    for ( int k = 0; k < SIZE; ++k )
30       cout << ' ' << sortThisArray[ k ] << ' ';
31
32    cout << '\n' << endl;
33
34    return 0;
35 }
36
37 void selectionSort( int array[], int size )
38 {
39    int temp;
40
41    if ( size >= 1 ) {
42
43       for ( int loop = 0; loop < size; ++loop )
44          if ( array[ loop ] < array[ 0 ] ) {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
            temp = array[ loop ];
            array[ loop ] = array[ 0 ];
            array[ 0 ] = temp;
         }

      selectionSort( &array[ 1 ], size - 1 );
   }
}
```

```
Unsorted array is:
 957  848  727  597  384  617  228  424  878  10

Sorted array is:
 10  228  384  424  597  617  727  848  878  957
```

4.32 (*Palindromes*) A palindrome is a string that is spelled the same way forwards and backwards. Some examples of palindromes are "radar," "able was i ere i saw elba" and (if blanks are ignored) "a man a plan a canal panama." Write a recursive function **testPalindrome** that returns **true** if the string stored in the array is a palindrome, and **false** otherwise. The function should ignore spaces and punctuation in the string.

```
// Exercise 4.32 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

bool testPalindrome( const char [], int, int );

int main()
{
   const int SIZE = 80;
   char c, string[ SIZE ], copy[ SIZE ];
   int count = 0, copyCount, i;

   cout << "Enter a sentence:\n";

   while ( ( c = cin.get() ) != '\n' && count < SIZE )
      string[ count++ ] = c;

   string[ count ] = '\0';    // terminate cstring

   // make a copy of cstring without spaces
   for ( copyCount = 0, i = 0; string[ i ] != '\0'; ++i )
      if ( string[ i ] != ' ' )
         copy[ copyCount++ ] = string[ i ];

   if ( testPalindrome( copy, 0, copyCount - 1 ) )
      cout << '\"' << string << "\" is a palindrome" << endl;
   else
      cout << '\"' << string << "\" is not a palindrome" << endl;

   return 0;
}

bool testPalindrome( const char array[], int left, int right )
{
   if ( left == right || left > right )
      return true;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   else if ( array[ left ] != array[ right ] )
      return false;
   else
      return testPalindrome( array, left + 1, right - 1 );
}
```

```
Enter a sentence:
alucard e dracula
"alucard e dracula" is a palindrome
```

4.33 (*Linear Search*) Modify the program in Fig. 4.19 to use recursive function **linearSearch** to perform a linear search of the array. The function should receive an integer array and the size of the array as arguments. If the search key is found, return the array subscript; otherwise, return –1.

```
// Exercise 4.33 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int linearSearch( const int [], int, int, int );

int main()
{
   const int SIZE = 100;
   int array[ SIZE ], searchKey, element;

   for ( int loop = 0; loop < SIZE; ++loop )
      array[ loop ] = 2 * loop;

   cout << "Enter the integer search key: ";
   cin >> searchKey;

   element = linearSearch( array, searchKey, 0, SIZE - 1 );

   if ( element != -1 )
      cout << "Found value in element " << element << endl;
   else
      cout << "Value not found" << endl;

   return 0;
}

int linearSearch( const int array[], int key, int low, int high )
{
   if ( array[low] == key )
      return low;
   else if ( low == high )
      return -1;
   else
      return linearSearch( array, key, low + 1, high );
}
```

```
Enter the integer search key: 22
Found value in element 11
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

4.34 (*Binary Search*) Modify the program of Fig. 4.20 to use a recursive function **binarySearch** to perform the binary search of the array. The function should receive an integer array and the starting subscript and ending subscript as arguments. If the search key is found, return the array subscript; otherwise, return –1.

```
// Exercise 4.34 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <iomanip>

using std::setw;

const int SIZE = 15;

int binarySearch( const int [], int, int, int );
void printRow( const int [], int, int, int );
void printHeader( void );

int main()
{
   int a[ SIZE ], key, result;

   for ( int i = 0; i < SIZE; ++i )
      a[ i ] = 2 * i;

   cout << "Enter a number between 0 and 28: ";
   cin >> key;

   printHeader();
   result = binarySearch( a, key, 0, SIZE - 1 );

   if ( result != -1 )
      cout << '\n' << key << " found in array element " << result << endl;
   else
      cout << '\n' << key << " not found" << endl;

   return 0;
}

int binarySearch( const int b[], int searchKey, int low, int high )
{
   int middle;

   if ( low <= high ) {
      middle = ( low + high ) / 2;
      printRow( b, low, middle, high );

      if ( searchKey == b[ middle ] )
         return middle;
      else if ( searchKey < b[ middle ] )
         return binarySearch( b, searchKey, low, middle - 1 );
      else
         return binarySearch( b, searchKey, middle + 1, high );
   }

   return -1;   // searchKey not found
}

// Print a header for the output
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
void printHeader( void )
{
   cout << "Subscripts:\n";

   for ( int i = 0; i < SIZE; ++i )
      cout << setw( 3 ) << i << ' ';

   cout << '\n';

   for ( int k = 1; k <= 4 * SIZE; ++k )
      cout << '-';

   cout << '\n';
}

// print one row of output showing the current
// part of the array being processed.
void printRow( const int b[], int low, int mid, int high )
{
   for ( int i = 0; i < SIZE; ++i )
      if ( i < low || i > high )
         cout << "    ";
      else if ( i == mid )
         cout << setw( 3 ) << b[ i ] << '*';    // mark middle value
      else
         cout << setw( 3 ) << b[ i ] << ' ';

   cout << '\n';
}
```

```
Enter a number between 0 and 28: 17
Subscripts:
  0   1   2   3   4   5   6   7   8   9  10  11  12  13  14
-------------------------------------------------------------
  0   2   4   6   8  10  12  14* 16  18  20  22  24  26  28
                                 16  18  20  22* 24  26  28
                                 16  18* 20
                                 16*

17 not found
```

4.35 (*Eight Queens*) Modify the Eight Queens program you created in Exercise 4.26 to solve the problem recursively.

4.36 (*Print an array*) Write a recursive function **printArray** that takes an array and the size of the array as arguments and returns nothing. The function should stop processing and return when it receives an array of size zero.

```
// Exercise 4.36 Solution
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>

using std::setw;

#include <cstdlib>
#include <ctime>

void printArray( const int [], int, int );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
15
16 int main()
17 {
18    const int SIZE = 10, MAXNUMBER = 500;
19    int array[ SIZE ];
20
21    srand( time( 0 ) );
22
23    for ( int loop = 0; loop < SIZE; ++loop )
24       array[ loop ] = 1 + rand() % MAXNUMBER;
25
26    cout << "Array values printed in main:\n";
27
28    for ( int j = 0; j < SIZE; ++j )
29       cout << setw( 5 ) << array[ j ];
30
31    cout << "\n\nArray values printed in printArray:\n";
32    printArray( array, 0, SIZE - 1 );
33    cout << endl;
34
35    return 0;
36 }
37
38 void printArray( const int array[], int low, int high )
39 {
40    cout << setw( 5 ) << array[ low ];
41
42    if ( low == high )
43       return;
44    else
45       printArray( array, low + 1, high );
46 }
```

```
Array values printed in main:
  432   14   59  484   45  388  355  384  425  448

Array values printed in printArray:
  432   14   59  484   45  388  355  384  425  448
```

4.37 (*Print a string backwards*) Write a recursive function **stringReverse** that takes a character array containing a string as an argument, prints the string backwards and returns nothing. The function should stop processing and return when the terminating null character is encountered.

```
1  // Exercise 4.37 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  void stringReverse( const char [] );
8
9  int main()
10 {
11    const int SIZE = 30;
12    char strArray[ SIZE ] = "Print this string backwards.";
13
14    for ( int loop = 0; loop < SIZE; ++loop )
15       cout << strArray[ loop ];
16
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   cout << '\n';
   stringReverse( strArray );
   cout << endl;

   return 0;
}

void stringReverse( const char strArray[] )
{
   if ( strArray[ 0 ] == '\0' )
      return;

   stringReverse( &strArray[ 1 ] );
   cout << strArray[ 0 ];
}
```

```
Print this string backwards.
.sdrawkcab gnirts siht tnirP
```

4.38 (*Find the minimum value in an array*) Write a recursive function **recursiveMinimum** that takes an integer array and the array size as arguments and returns the smallest element of the array. The function should stop processing and return when it receives an array of 1 element.

```
// Exercise 4.38 Solution
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>

using std::setw;

#include <cstdlib>
#include <ctime>

const int MAXRANGE = 1000;
int recursiveMinimum( const int [], int, int );

int main()
{
   const int SIZE = 10;
   int array[ SIZE ], smallest;

   srand( time( 0 ) );

   for ( int loop = 0; loop < SIZE; ++loop )
      array[ loop ] = 1 + rand() % MAXRANGE;

   cout << "Array members are:\n";
   for ( int k = 0; k < SIZE; ++k )
      cout << setw( 5 ) << array[ k ];

   cout << '\n';
   smallest = recursiveMinimum( array, 0, SIZE - 1 );
   cout << "\nSmallest element is: " << smallest << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
37
38 int recursiveMinimum( const int array[], int low, int high )
39 {
40    static int smallest = MAXRANGE;
41
42    if ( array[ low ] < smallest )
43       smallest = array[ low ];
44
45    return low == high ? smallest : recursiveMinimum( array, low + 1, high );
46 }
```

```
Array members are:
    7   84  951  884  404  167  905   93  744  115
Smallest element is: 7
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Pointers and Strings Solutions

Solutions

5.8 State whether the following are *true* or *false*. If *false*, explain why.

a) Two pointers that point to different arrays cannot be compared meaningfully.

ANS: True.

b) Because the name of an array is a pointer to the first element of the array, array names may be manipulated in precisely the same manner as pointers.

ANS: False. An array name cannot be used to refer to another location in memory.

5.9 Answer each of the following. Assume that unsigned integers are stored in 2 bytes and that the starting address of the array is at location 1002500 in memory.

a) Declare an array of type **`unsigned int`** called **`values`** with 5 elements, and initialize the elements to the even integers from 2 to 10. Assume that the symbolic constant **`SIZE`** has been defined as **`5`**.

ANS: `unsigned values[ SIZE ] = { 2, 4, 6, 8, 10 };`

b) Declare a pointer **`vPtr`** that points to an object of type **`unsigned int`**.

ANS: `unsigned *vPtr;`

c) Print the elements of array **`values`** using array subscript notation. Use a **`for`** structure and assume integer control variable **`i`** has been declared.

ANS:

```
for ( i = 0; i < SIZE; ++i )
   cout << setw( 4 ) << values[ i ];
```

d) Give two separate statements that assign the starting address of array **`values`** to pointer variable **`vPtr`**.

ANS: `vPtr = values;` and `vPtr = &values[ 0 ];`

e) Print the elements of array **`values`** using pointer/offset notation.

ANS:

```
for ( i = 0; i < SIZE; ++i )
   cout << setw( 4 ) << *( vPtr + i );
```

f) Print the elements of array **`values`** using pointer/offset notation with the array name as the pointer.

ANS:

```
for ( i = 0; i < SIZE; ++i )
   cout << setw( 4 ) << *( values + i );
```

g) Print the elements of array **`values`** by subscripting the pointer to the array.

ANS:

```
for ( i = 0; i < SIZE; ++i )
   cout << setw( 4 ) << vPtr[ i ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

h) Refer to the fifth element of **values** using array subscript notation pointer/offset notation with the array name as the pointer, pointer subscript notation, and pointer/offset notation.

ANS: `values[ 4 ]`, `*( values + 4 )`, `vPtr[ 4 ]`, `*( vPtr + 4 )`

i) What address is referenced by `vPtr + 3`? What value is stored at that location?

ANS: The address of the location pertaining to `values[ 3 ]` (i.e., 1002506). 8.

j) Assuming `vPtr` points to `values[ 4 ]`, what address is referenced by `vPtr -= 4`? What value is stored at that location?

ANS: The address of where `values` begins in memory (i.e., 1002500). 2.

5.10 For each of the following, write a single statement that performs the indicated task. Assume that long integer variables `value1` and `value2` have been declared and that `value1` has been initialized to `200000`.

a) Declare the variable `lPtr` to be a pointer to an object of type `long`.

ANS:
```
long *lPtr;
```

b) Assign the address of variable `value1` to pointer variable `lPtr`.

ANS:
```
lPtr = &value1;
```

c) Print the value of the object pointed to by `lPtr`.

ANS:
```
cout << *lPtr << '\n';
```

d) Assign the value of the object pointed to by `lPtr` to variable `value2`.

ANS:
```
value2 = *lPtr;
```

e) Print the value of `value2`.

ANS:
```
cout << value2 << '\n';
```

f) Print the address of `value1`.

ANS:
```
cout << &value1 << '\n';
```

g) Print the address stored in `lPtr`. Is the value printed the same as the address of `value1`?

ANS:
```
cout << lPtr << '\n';
```
yes.

5.11 Do each of the following.

a) Write the function header for function `zero` that takes a long integer array parameter `bigIntegers` and does not return a value.

ANS:
```
void zero( long bigIntegers[] )
```
or
```
void zero( long *bigIntegers )
```

b) Write the function prototype for the function in part **(a)**.

ANS: `void zero( long [] );` or `void zero( long * );`

c) Write the function header for function `add1AndSum` that takes an integer array parameter `oneTooSmall` and returns an integer.

ANS:
```
int add1Andsum( int oneTooSmall[] )
```
or
```
int add1Andsum( int *oneTooSmall )
```

d) Write the function prototype for the function described in part **(c).**

ANS: `int add1Andsum( int [] );` or `int add1Andsum( int * );`

Note: Exercises 5.12 through 5.15 are reasonably challenging. Once you have done these problems, you ought to be able to implement most popular card games easily.

5.12 Modify the program in Fig. 5.24 so that the card dealing function deals a five-card poker hand. Then write functions to accomplish each of the following:

a) Determine if the hand contains a pair.
b) Determine if the hand contains two pairs.
c) Determine if the hand contains three of a kind (e.g., three jacks).
d) Determine if the hand contains four of a kind (e.g., four aces).
e) Determine if the hand contains a flush (i.e., all five cards of the same suit).
f) Determine if the hand contains a straight (i.e., five cards of consecutive face values).

```
1  // Exercise 5.12 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::ios;
6
7  #include <iomanip>
8
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
using std::setw;
using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

#include <cstdlib>
#include <ctime>

void shuffle( int [][ 13 ] );
void deal( const int [][ 13 ], const char *[], const char *[], int [][ 2 ] );
void pair( const int [][ 13 ], const int [][ 2 ], const char *[] );
void threeOfKind( const int [][ 13 ], const int [][ 2 ], const char *[] );
void fourOfKind( const int [][ 13 ], const int [][ 2 ], const char *[] );
void flushHand( const int [][ 13 ], const int [][ 2 ], const char *[] );
void straightHand( const int [][ 13 ], const int [][ 2 ], const char *[],
                   const char *[] );

int main()
{
   const char *suit[] = { "Hearts", "Diamonds", "Clubs", "Spades" },
              *face[] = { "Ace", "Deuce", "Three", "Four", "Five", "Six",
                          "Seven", "Eight", "Nine", "Ten", "Jack", "Queen",
                          "King" };
   int deck[ 4 ][ 13 ] = { 0 }, hand[ 5 ][ 2 ] = { 0 };

   srand( time( 0 ) );

   shuffle( deck );
   deal( deck, face, suit, hand );
   pair( deck, hand, face );
   threeOfKind( deck, hand, face );
   fourOfKind( deck, hand, face );
   flushHand( deck, hand, suit );
   straightHand( deck, hand, suit, face );

   return 0;
}

void shuffle( int wDeck[][ 13 ] )
{
   int row, column;

   for ( int card = 1; card <= 52; ++card ) {
      do {
        row = rand() % 4;
        column = rand() % 13;
      } while ( wDeck[ row ][ column ] != 0 );

      wDeck[ row ][ column ] = card;
   }
}

// deal a five card poker hand
void deal( const int wDeck[][ 13 ], const char *wFace[],
           const char *wSuit[], int wHand[][ 2 ] )
{
   int r = 0;

   cout << "The hand is:\n";

   for ( int card = 1; card < 6; ++card )
      for ( int row = 0; row <= 3; ++row )
         for ( int column = 0; column <= 12; ++column )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
            if ( wDeck[ row ][ column ] == card ) {
               wHand[ r ][ 0 ] = row;
               wHand[ r ][ 1 ] = column;
               cout << setw( 5 ) << wFace[ column ]
                    << " of " << setw( 8 ) << setiosflags( ios::left )
                    << wSuit[ row ] << ( card % 2 == 0 ? '\n' : '\t' )
                    << resetiosflags( ios::left );
               ++r;
            }

   cout << '\n';
}

// pair determines if the hand contains one or two pair
void pair( const int wDeck[][ 13 ], const int wHand[][ 2 ],
           const char *wFace[] )
{
   int counter[ 13 ] = { 0 };

   for ( int r = 0; r < 5; ++r )
      ++counter[ wHand[ r ][ 1 ] ];

   cout << '\n';

   for ( int p = 0; p < 13; ++p )
      if ( counter[ p ] == 2 )
        cout << "The hand contains a pair of " << wFace[ p ] << "'s.\n";
}

void threeOfKind( const int wDeck[][ 13 ], const int wHand[][ 2 ],
                  const char *wFace[] )
{
   int counter[ 13 ] = { 0 };

   for ( int r = 0; r < 5; ++r )
      ++counter[ wHand[ r ][ 1 ] ];

   for ( int t = 0; t < 13; t++ )
      if ( counter[ t ] == 3 )
         cout << "The hand contains three " << wFace[ t ] << "'s.\n";
}

void fourOfKind( const int wDeck[][ 13 ], const int wHand[][ 2 ],
                 const char *wFace[] )
{
   int counter[ 13 ] = { 0 };

   for ( int r = 0; r < 5; ++r )
      ++counter[ wHand[ r ][ 1 ] ];

   for ( int k = 0; k < 13; ++k )
      if ( counter[ k ] == 4 )
         cout << "The hand contains four " << wFace[ k ] << "'s.\n";
}

void flushHand( const int wDeck[][ 13 ], const int wHand[][ 2 ],
                const char *wSuit[] )
{
   int count[ 4 ] = { 0 };

   for ( int r = 0; r < 5; ++r )
      ++count[ wHand[ r ][ 0 ] ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
134
135    for ( int f = 0; f < 4; ++f )
136       if ( count[ f ] == 5 )
137          cout << "The hand contains a flush of " << wSuit[ f ] << "'s.\n";
138 }
139
140 void straightHand( const int wDeck[][ 13 ], const int wHand[][ 2 ],
141                    const char *wSuit[], const char *wFace[] )
142 {
143    int s[ 5 ] = { 0 }, temp;
144
145    // copy column locations to sort
146    for ( int r = 0; r < 5; ++r )
147       s[ r ] = wHand[ r ][ 1 ];
148
149    // bubble sort column locations
150    for ( int pass = 1; pass < 5; ++pass )
151       for ( int comp = 0; comp < 4; ++comp )
152          if ( s[ comp ] > s[ comp + 1 ] ) {
153             temp = s[ comp ];
154             s[ comp ] = s[ comp + 1 ];
155             s[ comp + 1 ] = temp;
156          }
157
158    // check if sorted columns are a straight
159    if ( s[ 4 ] - 1 == s[ 3 ] && s[ 3 ] - 1 == s[ 2 ]
160         && s[ 2 ] - 1 == s[ 1 ] && s[ 1 ] - 1 == s[ 0 ] ) {
161       cout << "The hand contains a straight consisting of\n";
162
163       for ( int j = 0; j < 5; ++j )
164          cout << wFace[ wHand[ j ][ 1 ] ] << " of " << wSuit[ wHand[ j ][ 0 ] ]
165               << '\n';
166    }
167 }
```

```
The hand is:
  Ace of Diamonds        Jack of Clubs
  Ten of Clubs          Queen of Clubs
Deuce of Hearts
```

5.13 Use the functions developed in Exercise 5.12 to write a program that deals two five-card poker hands, evaluates each hand, and determines which is the better hand.

5.14 Modify the program developed in Exercise 5.13 so that it can simulate the dealer. The dealer's five-card hand is dealt "face down" so the player cannot see it. The program should then evaluate the dealer's hand, and, based on the quality of the hand, the dealer should draw one, two or three more cards to replace the corresponding number of unneeded cards in the original hand. The program should then reevaluate the dealer's hand. (*Caution:* This is a difficult problem!)

5.15 Modify the program developed in Exercise 5.14 so that it can handle the dealer's hand automatically, but the player is allowed to decide which cards of the player's hand to replace. The program should then evaluate both hands and determine who wins. Now use this new program to play 20 games against the computer. Who wins more games: you or the computer? Have one of your friends play 20 games against the computer. Who wins more games? Based on the results of these games, make appropriate modifications to refine your poker-playing program. (This, too, is a difficult problem.) Play 20 more games. Does your modified program play a better game?

5.16 In the card-shuffling and dealing program of Fig. 5.24, we intentionally used an inefficient shuffling algorithm that introduced the possibility of indefinite postponement. In this problem, you will create a high-performance shuffling algorithm that a voids indefinite postponement.

Modify Fig. 5.24 as follows. Initialize the **deck** array as shown in Fig. 5.35. Modify the **shuffle** function to loop row by row and column by column through the array touching every element once. Each element should be swapped with a randomly

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

selected element of the array. Print the resulting array to determine if the deck is satisfactorily shuffled (as in Fig. 5.36, for example). You may want your program to call the **shuffle** function several times to ensure a satisfactory shuffle.

Note that although the approach in this problem improves the shuffling algorithm, the dealing algorithm still requires searching the **deck** array for card 1, then card 2, then card 3, and so on. Worse yet, even after the dealing algorithm locates and deals the card, the algorithm continues searching through the remainder of the deck. Modify the program of Fig. 5.24 so that once a card is dealt, no further attempts are made to match that card number, and the program immediately proceeds with dealing the next card.

Unshuffled deck array

	0	1	2	3	4	5	6	7	8	9	10	11	12
0	1	2	3	4	5	6	7	8	9	10	11	12	13
1	14	15	16	17	18	19	20	21	22	23	24	25	26
2	27	28	29	30	31	32	33	34	35	36	37	38	39
3	40	41	42	43	44	45	46	47	48	49	50	51	52

Fig. 5.35 Unshuffled **deck** array.

Sample shuffled deck array

	0	1	2	3	4	5	6	7	8	9	10	11	12
0	19	40	27	25	36	46	10	34	35	41	18	2	44
1	13	28	14	16	21	30	8	11	31	17	24	7	1
2	12	33	15	42	43	23	45	3	29	32	4	47	26
3	50	38	52	39	48	51	9	5	37	49	22	6	20

Fig. 5.36 Sample shuffled **deck** array.

```
1  // Exercise 5.16 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::ios;
6
7
8  #include <iomanip>
9  using std::setw;
10 using std::setprecision;
11 using std::setiosflags;
12 using std::resetiosflags;
13
14 #include <cstdlib>
15 #include <ctime>
16
17 void shuffle( int [][ 13 ] );
18 void deal( const int [][ 13 ], const char *[], const char *[] );
19
20 int main()
21 {
22    int card = 1, deck[ 4 ][ 13 ] = { 0 };
23    const char *suit[ 4 ] = { "Hearts", "Diamonds", "Clubs", "Spades" };
24    const char *face[ 13 ] = { "Ace", "Deuce", "Three", "Four", "Five", "Six",
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
                                "Seven", "Eight", "Nine", "Ten", "Jack", "Queen",
                                "King" };

   srand( time( 0 ) );

   // initialize deck
   for ( int row = 0; row <= 3; ++row )
      for ( int column = 0; column <= 12; ++column )
         deck[ row ][ column ] = card++;

   shuffle( deck );
   deal( deck, face, suit );

   return 0;
}

void shuffle( int workDeck[][ 13 ] )
{
   int temp, randRow, randColumn;

   for ( int row = 0; row <= 3; ++row )
      for ( int column = 0; column <= 12; ++column ) {
         randRow = rand() % 4;
         randColumn = rand() % 13;
         temp = workDeck[ row ][ column ];
         workDeck[ row][ column ] = workDeck[ randRow ][ randColumn ];
         workDeck[ randRow ][ randColumn ] = temp;
      }
}

void deal( const int workDeck2[][ 13 ], const char *workFace[],
           const char *workSuit[] )
{
   for ( int card = 1; card <= 52; ++card )
      for ( int row = 0; row <= 3; ++row )
         for ( int column = 0; column <= 12; ++column )
            if ( workDeck2[ row ][ column ] == card ) {
               cout << setw( 8 ) << workFace[ column ] << " of "
                    << setiosflags( ios::left ) << setw( 8 )
                    << workSuit[ row ]
                    << ( card % 2 == 0 ? '\n' : '\t' )
                    << resetiosflags( ios::left );
               break;
            }
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 King of Hearts          King of Diamonds
Eight of Spades          Four of Clubs
 Five of Clubs          Queen of Hearts
Eight of Hearts          Nine of Diamonds
  Ace of Clubs          Deuce of Clubs
  Six of Diamonds        Five of Hearts
Seven of Hearts          Nine of Hearts
  Six of Spades          Jack of Diamonds
 Five of Spades         Queen of Diamonds
 King of Clubs           King of Spades
 Five of Diamonds       Seven of Diamonds
Eight of Diamonds        Four of Hearts
 Four of Spades           Ten of Hearts
Three of Spades         Three of Diamonds
  Ten of Spades          Four of Diamonds
  Ten of Diamonds       Deuce of Hearts
  Ace of Diamonds         Six of Hearts
 Nine of Clubs           Nine of Spades
Deuce of Spades         Eight of Clubs
Queen of Spades           Six of Clubs
Seven of Clubs           Jack of Clubs
  Ace of Hearts         Three of Clubs
Deuce of Diamonds       Queen of Clubs
Seven of Spades           Ace of Spades
 Jack of Hearts          Jack of Spades
  Ten of Clubs          Three of Hearts
```

5.17 (*Simulation: The Tortoise and the Hare*) In this problem you will re-create the classic race of the tortoise and the hare. You will use random-number generation to develop a simulation of this memorable event.

Our contenders begin the race at "square 1" of 70 squares. Each square represents a possible position along the race course. The finish line is at square 70. The first contender to reach or pass square 70 is rewarded with a pail of fresh carrots and lettuce. The course weaves its way up the side of a slippery mountain, so occasionally the contenders lose ground.

There is a clock that ticks once per second. With each tick of the clock, your program should adjust the position of the animals according to the following rules:

Animal	Move type	Percentage of the time	Actual move
Tortoise	Fast plod	50%	3 squares to the right
	Slip	20%	6 squares to the left
	Slow plod	30%	1 square to the right
Hare	Sleep	20%	No move at all
	Big hop	20%	9 squares to the right
	Big slip	10%	12 squares to the left
	Small hop	30%	1 square to the right
	Small slip	20%	2 squares to the left

Use variables to keep track of the positions of the animals (i.e., position numbers are 1–70). Start each animal at position 1 (i.e., the "starting gate"). If an animal slips left before square 1, move the animal back to square 1.

Generate the percentages in the preceding table by producing a random integer i in the range $1 \le i \le 10$. For the tortoise, perform a "fast plod" when $1 \le i \le 5$, a "slip" when $6 \le i \le 7$ or a "slow plod" when $8 \le i \le 10$. Use a similar technique to move the hare.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Begin the race by printing

```
BANG !!!!!
AND THEY'RE OFF !!!!!
```

For each tick of the clock (i.e., each repetition of a loop), print a 70-position line showing the letter **T** in the tortoise's position and the letter **H** in the hare's position. Occasionally, the contenders land on the same square. In this case, the tortoise bites the hare, and your program should print **OUCH!!!** beginning at that position. All print positions other than the **T**, the **H** or the **OUCH!!!** (in case of a tie) should be blank.

After printing each line, test if either animal has reached or passed square 70. If so, print the winner and terminate the simulation. If the tortoise wins, print **TORTOISE WINS!!! YAY!!!** If the hare wins, print **Hare wins. Yuch.** If both animals win on the same clock tick, you may want to favor the turtle (the "underdog"), or you may want to print **It's a tie**. If neither animal wins, perform the loop again to simulate the next tick of the clock. When you are ready to run your program, assemble a group of fans to watch the race. You'll be amazed how involved the audience gets!

```
1  // Exercise 5.17 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <cstdlib>
8  #include <ctime>
9
10 #include <iomanip>
11
12 using std::setw;
13
14 const int RACE_END = 70;
15
16 void moveTortoise( int * const );
17 void moveHare( int * const );
18 void printCurrentPositions( const int * const, const int * const );
19
20 int main()
21 {
22    int tortoise = 1, hare = 1, timer = 0;
23
24    srand( time( 0 ) );
25
26    cout << "ON YOUR MARK, GET SET\nBANG               !!!!"
27         << "\nAND THEY'RE OFF    !!!!\n";
28
29    while ( tortoise != RACE_END && hare != RACE_END ) {
30       moveTortoise( &tortoise );
31       moveHare( &hare );
32       printCurrentPositions( &tortoise, &hare );
33       ++timer;
34    }
35
36    if ( tortoise >= hare )
37       cout << "\nTORTOISE WINS!!! YAY!!!\n";
38    else
39       cout << "Hare wins. Yuch.\n";
40
41    cout << "TIME ELAPSED = " << timer << " seconds" << endl;
42
43    return 0;
44 }
45
46 void moveTortoise( int * const turtlePtr )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   int x = 1 + rand() % 10;

   if ( x >= 1 && x <= 5 )        // fast plod
      *turtlePtr += 3;
   else if ( x == 6 || x == 7 )   // slip
      *turtlePtr -= 6;
   else                           // slow plod
      ++( *turtlePtr );

   if ( *turtlePtr < 1 )
      *turtlePtr = 1;
   else if ( *turtlePtr > RACE_END )
      *turtlePtr = RACE_END;
}

void moveHare( int * const rabbitPtr )
{
   int y = 1 + rand() % 10;

   if ( y == 3 || y == 4 )        // big hop
      *rabbitPtr += 9;
   else if ( y == 5 )             // big slip
      *rabbitPtr -= 12;
   else if ( y >= 6 && y <= 8 )   // small hop
      ++( *rabbitPtr );
   else if ( y > 8 )            // small slip
      *rabbitPtr -= 2;

   if ( *rabbitPtr < 1 )
      *rabbitPtr = 1;
   else if ( *rabbitPtr > RACE_END )
      *rabbitPtr = RACE_END;
}

void printCurrentPositions( const int * const snapperPtr,
                            const int * const bunnyPtr )
{
   if ( *bunnyPtr == *snapperPtr )
      cout << setw( *bunnyPtr ) << "OUCH!!!";
   else if ( *bunnyPtr < *snapperPtr )
      cout << setw( *bunnyPtr ) << 'H'
           << setw( *snapperPtr - *bunnyPtr ) << 'T';
   else
      cout << setw( *snapperPtr ) << 'T'
           << setw( *bunnyPtr - *snapperPtr ) << 'H';

   cout << '\n';
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net



http://librosysolucionarios.net

SPECIAL SECTION: BUILDING YOUR OWN COMPUTER

In the next several problems, we take a temporary diversion away from the world of high-level-language programming. We "peel open" a computer and look at its internal structure. We introduce machine-language programming and write several machine-language programs. To make this an especially valuable experience, we then build a computer (through the technique of software-based *simulation)* on which you can execute your machine-language programs!

5.18 (*Machine-Language Programming*) Let us create a computer we will call the Simpletron. As its name implies, it is a simple machine, but, as we will soon see, a powerful one as well. The Simpletron runs programs written in the only language it directly understands; that is, Simpletron Machine Language, or SML for short.

The Simpletron contains an *accumulator*—a "special register" in which information is put before the Simpletron uses that information in calculations or examines it in various ways. All information in the Simpletron is handled in terms of *words*. A word is a signed four-digit decimal number, such as **+3364**, **-1293**, **+0007**, **-0001**, etc. The Simpletron is equipped with a 100-word memory, and these words are referenced by their location numbers **00**, **01**, ..., **99**.

Before running an SML program, we must *load,* or place, the program into memory. The first instruction (or statement) of every SML program is always placed in location **00**. The simulator will start executing at this location.

Each instruction written in SML occupies one word of the Simpletron's memory. (Thus, instructions are signed four-digit decimal numbers.) We shall assume that the sign of an SML instruction is always plus, but the sign of a data word may be either plus or minus. Each location in the Simpletron's memory may contain an instruction, a data value used by a program or an unused (and hence undefined) area of memory. The first two digits of each SML instruction are the *operation code* that specifies the operation to be performed. SML operation codes are shown in Fig. 5.37.

Operation code	Meaning
Input/output operations:	
`const int READ = 10`	Read a word from the keyboard into a specific location in memory.
`const int WRITE = 11;`	Write a word from a specific location in memory to the screen.
Load and store operations:	
`const int LOAD = 20;`	Load a word from a specific location in memory into the accumulator.
`const int STORE = 21;`	Store a word from the accumulator into a specific location in memory.
Arithmetic operations:	
`const int ADD = 30;`	Add a word from a specific location in memory to the word in the accumulator (leave result in accumulator).
`const int SUBTRACT = 31;`	Subtract a word from a specific location in memory from the word in the accumulator (leave result in accumulator).
`const int DIVIDE = 32;`	Divide a word from a specific location in memory into the word in the accumulator (leave result in accumulator).
`const int MULTIPLY = 33;`	Multiply a word from a specific location in memory by the word in the accumulator (leave result in accumulator).
Transfer of control operations:	
`const int BRANCH = 40;`	Branch to a specific location in memory.

Fig. 5.37 Simpletron Machine Language (SML) operation codes (part 1 of 2).

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Operation code	Meaning
`const int BRANCHNEG = 41;`	Branch to a specific location in memory if the accumulator is negative.
`const int BRANCHZERO = 42;`	Branch to a specific location in memory if the accumulator is zero.
`const int HALT = 43;`	Halt—the program has completed its task.

Fig. 5.37 Simpletron Machine Language (SML) operation codes (part 2 of 2).

The last two digits of an SML instruction are the *operand*—the address of the memory location containing the word to which the operation applies.

Now let us consider several simple SML programs. The first SML program (Example 1) reads two numbers from the keyboard and computes and prints their sum. The instruction **+1007** reads the first number from the keyboard and places it into location **07** (which has been initialized to zero). Then instruction **+1008** reads the next number into location **08**. The *load* instruction, **+2007**, puts (copies) the first number into the accumulator, and the *add* instruction, **+3008**, adds the second number to the number in the accumulator. *All SML arithmetic instructions leave their results in the accumulator.* The *store* instruction, **+2109**, places (copies) the result back into memory location **09** from which the *write* instruction, **+1109**, takes the number and prints it (as a signed four-digit decimal number). The *halt* instruction, **+4300**, terminates execution.

Example 1 Location	Number	Instruction
00	+1007	(Read A)
01	+1008	(Read B)
02	+2007	(Load A)
03	+3008	(Add B)
04	+2109	(Store C)
05	+1109	(Write C)
06	+4300	(Halt)
07	+0000	(Variable A)
08	+0000	(Variable B)
09	+0000	(Result C)

The SML program in Example 2 reads two numbers from the keyboard and determines and prints the larger value. Note the use of the instruction **+4107** as a conditional transfer of control, much the same as C++'s **if** statement.

Example 2 Location	Number	Instruction
00	+1009	(Read A)
01	+1010	(Read B)
02	+2009	(Load A)
03	+3110	(Subtract B)
04	+4107	(Branch negative to 07)
05	+1109	(Write A)
06	+4300	(Halt)
07	+1110	(Write B)

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Example 2 Location	Number	Instruction
08	+4300	(Halt)
09	+0000	(Variable A)
10	+0000	(Variable B)

Now write SML programs to accomplish each of the following tasks.

a) Use a sentinel-controlled loop to read positive numbers and compute and print their sum. Terminate input when a negative number is entered.

b) Use a counter-controlled loop to read seven numbers, some positive and some negative, and compute and print their average.

c) Read a series of numbers and determine and print the largest number. The first number read indicates how many numbers should be processed.

5.19 (*A Computer Simulator*) It may at first seem outrageous, but in this problem, you are going to build your own computer. No, you will not be soldering components together. Rather, you will use the powerful technique of *software-based simulation* to create a *software model* of the Simpletron. You will not be disappointed. Your Simpletron simulator will turn the computer you are using into a Simpletron, and you will actually be able to run, test and debug the SML programs you wrote in Exercise 5.18.

When you run your Simpletron simulator, it should begin by printing

```
*** Welcome to Simpletron! ***

*** Please enter your program one instruction ***
*** (or data word) at a time. I will type the ***
*** location number and a question mark (?).  ***
*** You then type the word for that location. ***
*** Type the sentinel -99999 to stop entering ***
*** your program. ***
```

Simulate the memory of the Simpletron with a single-subscripted array **memory** that has 100 elements. Now assume that the simulator is running, and let us examine the dialog as we enter the program of Example 2 of Exercise 5.18:

```
00 ? +1009
01 ? +1010
02 ? +2009
03 ? +3110
04 ? +4107
05 ? +1109
06 ? +4300
07 ? +1110
08 ? +4300
09 ? +0000
10 ? +0000
11 ? -99999

*** Program loading completed ***
*** Program execution begins  ***
```

The SML program has now been placed (or loaded) in array **memory**. Now the Simpletron executes your SML program. Execution begins with the instruction in location **00** and, like C++, continues sequentially, unless directed to some other part of the program by a transfer of control.

Use the variable **accumulator** to represent the accumulator register. Use the variable **counter** to keep track of the location in memory that contains the instruction being performed. Use variable **operationCode** to indicate the operation currently being performed (i.e., the left two digits of the instruction word). Use variable **operand** to indicate the memory location on which the current instruction operates. Thus, **operand** is the rightmost two digits of the instruction currently being performed. Do not execute instructions directly from memory. Rather, transfer the next instruction to be performed from memory to a variable called **instructionRegister**. Then "pick off" the left two digits and place them in **operationCode**, and "pick off" the right two digits and place them in **operand**. When Simpletron begins execution, the special registers are all initialized to zero.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Now let us "walk through" the execution of the first SML instruction, **+1009** in memory location **00**. This is called an *instruction execution cycle.*

The **counter** tells us the location of the next instruction to be performed. We *fetch* the contents of that location from **memory** by using the C++ statement

```
instructionRegister = memory[ counter ];
```

The operation code and operand are extracted from the instruction register by the statements

```
operationCode = instructionRegister / 100;
operand = instructionRegister % 100;
```

Now the Simpletron must determine that the operation code is actually a *read* (versus a *write*, a *load*, etc.). A **switch** differentiates among the twelve operations of SML.

In the **switch** structure, the behavior of various SML instructions is simulated as follows (we leave the others to the reader):

read: `cin >> memory[ operand ];`

load: `accumulator = memory[ operand ];`

add: `accumulator += memory[ operand ];`

branch: We will discuss the branch instructions shortly.

halt: This instruction prints the message
`*** Simpletron execution terminated ***`

It then prints the name and contents of each register, as well as the complete contents of memory. Such a printout is often called a *computer dump* (and, no, a computer dump is not a place where old computers go). To help you program your dump function, a sample dump format is shown in Fig. 5.38. Note that a dump after executing a Simpletron program would show the actual values of instructions and data values at the moment execution terminated.

Let us proceed with the execution of our program's first instruction—**+1009** in location **00**. As we have indicated, the **switch** statement simulates this by performing the C++ statement

```
cin >> memory[ operand ];
```

A question mark (**?**) should be displayed on the screen before the **cin** is executed to prompt the user for input. The Simpletron waits for the user to type a value and then press the *Return key*. The value is then read into location **09**.

At this point, simulation of the first instruction is completed. All that remains is to prepare the Simpletron to execute the next instruction. Since the instruction just performed was not a transfer of control, we need merely increment the instruction counter register as follows:

```
++counter;
```

This completes the simulated execution of the first instruction. The entire process (i.e., the instruction execution cycle) begins anew with the fetch of the next instruction to be executed.

Now let us consider how the branching instructions—the transfers of control—are simulated. All we need to do is adjust the value in the instruction counter appropriately. Therefore, the unconditional branch instruction (**40**) is simulated within the **switch** as

```
counter = operand;
```

The conditional "branch if accumulator is zero" instruction is simulated as

```
if ( accumulator == 0 )
   counter = operand;
```

At this point you should implement your Simpletron simulator and run each of the SML programs you wrote in Exercise 5.18. You may embellish SML with additional features and provide for these in your simulator.

Your simulator should check for various types of errors. During the program loading phase, for example, each number the

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

user types into the Simpletron's **memory** must be in the range **-9999** to **+9999**. Your simulator should use a **while** loop to test that each number entered is in this range and, if not, keep prompting the user to reenter the number until the user enters a correct number.

```
REGISTERS:
accumulator          +0000
counter                 00
instructionRegister  +0000
operationCode           00
operand                 00

MEMORY:
       0     1     2     3     4     5     6     7     8     9
 0 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
10 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
20 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
30 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
40 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
50 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
60 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
70 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
80 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
90 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
```

Fig. 5.38 A sample dump.

During the execution phase, your simulator should check for various serious errors, such as attempts to divide by zero, attempts to execute invalid operation codes, accumulator overflows (i.e., arithmetic operations resulting in values larger than **+9999** or smaller than **-9999**) and the like. Such serious errors are called *fatal errors.* When a fatal error is detected, your simulator should print an error message such as

```
*** Attempt to divide by zero ***
*** Simpletron execution abnormally terminated ***
```

and should print a full computer dump in the format we have discussed previously. This will help the user locate the error in the program.

```
1  // Exercise 5.19 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <iomanip>
10
11 using std::setfill;
12 using std::setw;
13 using std::setiosflags;
14 using std::resetiosflags;
15
16 const int SIZE = 100, MAX_WORD = 9999, MIN_WORD = -9999;
17 const long SENTINEL = -99999;
18 enum Commands { READ = 10, WRITE, LOAD = 20, STORE, ADD = 30, SUBTRACT,
19                 DIVIDE, MULTIPLY, BRANCH = 40, BRANCHNEG, BRANCHZERO, HALT };
20
21 void load( int * const );
22 void execute( int * const, int * const, int * const, int * const,
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
23                int * const, int * const);
24 void dump( const int * const, int, int, int, int, int );
25 bool validWord( int );
26
27 int main()
28 {
29    int memory[ SIZE ] = { 0 }, accumulator = 0, instructionCounter = 0,
30        opCode = 0, operand = 0, instructionRegister = 0;
31
32    load( memory );
33    execute( memory, &accumulator, &instructionCounter, &instructionRegister,
34             &opCode, &operand );
35    dump( memory, accumulator, instructionCounter, instructionRegister,
36          opCode, operand );
37
38    return 0;
39 }
40
41 void load( int * const loadMemory )
42 {
43    long instruction;
44    int i = 0;
45
46    cout << "***           Welcome to Simpletron           ***\n"
47         << "*** Please enter your program one instruction ***\n"
48         << "*** (or data word) at a time. I will type the ***\n"
49         << "*** location number and a question mark (?).  ***\n"
50         << "*** You then type the word for that location. ***\n"
51         << "*** Type the sentinel -99999 to stop entering ***\n"
52         << "*** your program.                             ***\n" << "00 ? ";
53    cin >> instruction;
54
55    while ( instruction != SENTINEL ) {
56
57       if ( !validWord( instruction ) )
58          cout << "Number out of range. Please enter again.\n";
59       else
60          loadMemory[ i++ ] = instruction;
61
62       // function setfill sets the padding character for unused
63       // field widths.
64       cout << setw( 2 ) << setfill( '0' ) << i << " ? ";
65       cin >> instruction;
66    }
67 }
68
69 void execute( int * const memory, int * const acPtr, int * const icPtr,
70               int * const irPtr, int * const opCodePtr, int * const opPtr )
71 {
72    bool fatal = false;
73    int temp;
74    const char *messages[] = { "Accumulator overflow          ***",
75                               "Attempt to divide by zero     ***",
76                               "Invalid opcode detected       ***" },
77          *termString = "\n*** Simpletron execution abnormally terminated ***",
78          *fatalString = "*** FATAL ERROR: ";
79
80    cout << "\n***********START SIMPLETRON EXECUTION***********\n\n";
81
82    do {
83       *irPtr = memory[ *icPtr ];
84       *opCodePtr = *irPtr / 100;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
85          *opPtr = *irPtr % 100;
86
87          switch ( *opCodePtr ) {
88             case READ:
89                cout << "Enter an integer: ";
90                cin >> temp;
91
92                while ( !validWord( temp ) ) {
93                   cout << "Number out of range. Please enter again: ";
94                   cin >> temp;
95                }
96
97                memory[ *opPtr ] = temp;
98                ++( *icPtr );
99                break;
100            case WRITE:
101               cout << "Contents of " << setw( 2 ) << setfill( '0' ) << *opPtr
102                    << ": " << memory[ *opPtr ] << '\n';
103               ++( *icPtr );
104               break;
105            case LOAD:
106               *acPtr = memory[ *opPtr ];
107               ++( *icPtr );
108               break;
109            case STORE:
110               memory[ *opPtr ] = *acPtr;
111               ++( *icPtr );
112               break;
113            case ADD:
114               temp = *acPtr + memory[ *opPtr ];
115
116               if ( !validWord( temp ) ) {
117                  cout << fatalString << messages[ 0 ] << termString << '\n';
118                  fatal = true;
119               }
120               else {
121                  *acPtr = temp;
122                  ++( *icPtr );
123               }
124
125               break;
126            case SUBTRACT:
127               temp = *acPtr - memory[ *opPtr ];
128
129               if ( !validWord( temp ) ) {
130                  cout << fatalString << messages[ 0 ] << termString << '\n';
131                  fatal = true;
132               }
133               else {
134                  *acPtr = temp;
135                  ++( *icPtr );
136               }
137
138               break;
139            case DIVIDE:
140               if ( memory[ *opPtr ] == 0 ) {
141                  cout << fatalString << messages[ 1 ] << termString << '\n';
142                  fatal = true;
143               }
144               else {
145                  *acPtr /= memory[ *opPtr ];
146                  ++( *icPtr );
147               }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
148
149            break;
150         case MULTIPLY:
151            temp = *acPtr * memory[ *opPtr ];
152
153            if ( !validWord( temp ) ) {
154               cout << fatalString << messages[ 0 ] << termString << '\n';
155               fatal = true;
156            }
157            else {
158               *acPtr = temp;
159               ++( *icPtr );
160            }
161            break;
162         case BRANCH:
163            *icPtr = *opPtr;
164            break;
165         case BRANCHNEG:
166            *acPtr < 0 ? *icPtr = *opPtr : ++( *icPtr );
167            break;
168         case BRANCHZERO:
169            *acPtr == 0 ? *icPtr = *opPtr : ++( *icPtr );
170            break;
171         case HALT:
172            cout << "*** Simpletron execution terminated ***\n";
173            break;
174         default:
175            cout << fatalString << messages[ 2 ] << termString << '\n';
176            fatal = true;
177            break;
178      }
179   } while ( *opCodePtr != HALT && !fatal );
180
181   cout << "\n*************END SIMPLETRON EXECUTION************\n";
182}
183
184void dump( const int * const memory, int accumulator, int instructionCounter,
185           int instructionRegister, int operationCode, int operand )
186{
187   void output( const char * const, int, int, bool );   // prototype
188
189   cout << "\nREGISTERS:\n";
190   output( "accumulator", 5, accumulator, true );
191   output( "instructionCounter", 2, instructionCounter, false );
192   output( "instructionRegister", 5, instructionRegister, true );
193   output( "operationCode", 2, operationCode, false );
194   output( "operand", 2, operand, false );
195   cout << "\n\nMEMORY:\n";
196
197   int i = 0;
198   cout << setfill( ' ' ) << setw( 3 ) << ' ';
199
200   // print header
201   for ( ; i <= 9; ++i )
202      cout << setw( 5 ) << i << ' ';
203
204   for ( i = 0; i < SIZE; ++i ) {
205      if ( i % 10 == 0 )
206         cout << '\n' << setw( 2 ) << i << ' ';
207
208      cout << setiosflags( ios::internal | ios::showpos )
209           << setw( 5 ) << setfill( '0' ) << memory[ i ] << ' '
210           << resetiosflags( ios::internal | ios::showpos );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
211    }
212
213    cout << endl;
214 }
215
216 bool validWord( int word )
217 {
218    return word >= MIN_WORD && word <= MAX_WORD;
219 }
220
221 void output( const char * const sPtr, int width, int value, bool sign )
222 {
223    // format of "accumulator", etc.
224    cout << setfill( ' ' ) << setiosflags( ios::left ) << setw( 20 )
225         << sPtr << ' ';
226
227    // is a +/- sign needed?
228    if ( sign )
229       cout << setiosflags( ios::showpos | ios::internal );
230
231    // setup for displaying accumulator value, etc.
232    cout << resetiosflags( ios::left ) << setfill( '0' );
233
234    // determine the field widths and display value
235    if ( width == 5 )
236       cout << setw( width ) << value << '\n';
237    else  // width is 2
238       cout << setfill( ' ' ) << setw( 3 ) << ' ' << setw( width )
239            << setfill( '0' ) << value << '\n';
240
241    // disable sign if it was set
242    if ( sign )
243       cout << resetiosflags( ios::showpos | ios::internal );
244 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
***           Welcome to Simpletron           ***
*** Please enter your program one instruction ***
*** (or data word) at a time. I will type the ***
*** location number and a question mark (?).  ***
*** You then type the word for that location. ***
*** Type the sentinel -99999 to stop entering ***
*** your program.                             ***
00 ? 1099
01 ? 1098
02 ? 2099
03 ? 3398
04 ? 2150
05 ? 1150
06 ? 1199
07 ? 1198
08 ? 4300
09 ? -99999

************START SIMPLETRON EXECUTION************

Enter an integer: 4
Enter an integer: 9
Contents of 50: 36
Contents of 99: 4
Contents of 98: 9
*** Simpletron execution terminated ***

*************END SIMPLETRON EXECUTION*************

REGISTERS:
accumulator          +0036
instructionCounter      08
instructionRegister  +4300
operationCode           43
operand                 00


MEMORY:
       0     1     2     3     4     5     6     7     8     9
 0 +1099 +1098 +2099 +3398 +2150 +1150 +1199 +1198 +4300 +0000
10 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
20 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
30 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
40 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
50 +0036 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
60 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
70 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
80 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000
90 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0000 +0009 +0004
```

MORE POINTER EXERCISES

5.20 Modify the card-shuffling and dealing program of Fig. 5.24 so the shuffling and dealing operations are performed by the same function (**shuffleAndDeal**). The function should contain one nested looping structure that is similar to function **shuffle** in Fig. 5.24.

```
1  // Exercise 5.20 Solution
2  #include <iostream>
3
4  using std::cout;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
using std::ios;

#include <iomanip>

using std::setw;
using std::setiosflags;
using std::resetiosflags;

#include <cstdlib>
#include <ctime>

void shuffleAndDeal( int [][ 13 ], const char *[], const char *[] );

int main()
{
   const char *suit[ 4 ] = { "Hearts", "Diamonds", "Clubs", "Spades" };
   const char *face[ 13 ] = { "Ace", "Deuce", "Three", "Four", "Five",
                              "Six", "Seven", "Eight", "Nine", "Ten",
                              "Jack", "Queen", "King" };
   int deck[ 4 ][ 13 ] = { 0 };

   srand( time( 0 ) );
   shuffleAndDeal( deck, face, suit );

   return 0;
}

void shuffleAndDeal( int workDeck[][ 13 ], const char *workFace[],
                     const char *workSuit[] )
{
   int row, column;

   for ( int card = 1; card <= 52; ++card ) {

      do {
         row = rand() % 4;
         column = rand() % 13;
      } while ( workDeck[ row ][ column ] != 0 );

      workDeck[ row ][ column ] = card;
      cout << setw( 8 ) << workFace[ column ] << " of "
           << setiosflags( ios::left ) << setw( 8 )
           << workSuit[ row ] << resetiosflags( ios::left )
           << ( card % 2 == 0 ? '\n' : '\t' );
   }
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Six of Hearts           Ten of Diamonds
Deuce of Spades          Five of Hearts
  Ace of Spades          Nine of Spades
Seven of Diamonds        King of Spades
 Nine of Diamonds       Eight of Spades
 Five of Clubs          Seven of Spades
Deuce of Clubs           Four of Clubs
  Ten of Hearts          Jack of Diamonds
 Nine of Clubs           Four of Diamonds
  Ace of Hearts          Five of Spades
 Jack of Hearts         Deuce of Diamonds
  Ten of Spades         Queen of Hearts
Queen of Spades         Queen of Diamonds
 King of Clubs            Six of Spades
Deuce of Hearts         Three of Spades
 King of Diamonds       Three of Hearts
 Four of Hearts          Jack of Spades
 Jack of Clubs          Three of Clubs
 Four of Spades         Three of Diamonds
  Ace of Diamonds        Nine of Hearts
Seven of Clubs          Eight of Diamonds
Eight of Clubs          Seven of Hearts
Eight of Hearts         Queen of Clubs
  Six of Clubs            Ace of Clubs
 Five of Diamonds        King of Hearts
  Ten of Clubs            Six of Diamonds
```

5.21 What does this program do?

```
1  // ex05_21.cpp
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6  using std::endl;
7
8  void mystery1( char *, const char * );
9
10 int main()
11 {
12    char string1[ 80 ], string2[ 80 ];
13
14    cout << "Enter two strings: ";
15    cin >> string1 >> string2;
16    mystery1( string1, string2 );
17    cout << string1 << endl;
18
19    return 0;
20 }
21
22 void mystery1( char *s1, const char *s2 )
23 {
24    while ( *s1 != '\0' )
25       ++s1;
26
27    for ( ; *s1 = *s2; s1++, s2++ )
28       ;   // empty statement
29 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter two strings: string1 string2
string1string2
```

5.22 What does this program do?

```
1  // ex05_22.cpp
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6  using std::endl;
7
8  int mystery2( const char * );
9
10 int main()
11 {
12    char string[ 80 ];
13
14    cout << "Enter a string: ";
15    cin >> string;
16    cout << mystery2( string ) << endl;
17
18    return 0;
19 }
20
21 int mystery2( const char *s )
22 {
23    int x;
24
25    for ( x = 0; *s != '\0'; s++ )
26       ++x;
27
28    return x;
29 }
```

```
Enter a string: length
6
```

5.23 Find the error in each of the following program segments. If the error can be corrected, explain how.

a)
```
int *number;
cout << number << endl;
```
ANS: Pointer **number** does not "point" to a valid address. Assigning **number** to an address would correct the problem.

b)
```
double *realPtr;
long *integerPtr;
integerPtr = realPtr;
```
ANS: A pointer of type **float** cannot be directly assigned to a pointer of type **long**.

c)
```
int * x, y;
x = y;
```
ANS: Variable **y** is not a pointer, and therefore cannot be assigned to **x**. Change the assignment statement to **x = &y;**.

d)
```
char s[] = "this is a character array";
for ( ; *s != '\0'; s++)
   cout << *s << ' ';
```
ANS: **s** is not a modifiable value. Attempting to use operator **++** is a syntax error. Changing to **[]** notation corrects the problem as in:
```
for ( int t = 0; s[ t ] != '\0'; ++t )
   cout << s[ t ] << ' ';
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

e)
```
short *numPtr, result;
void *genericPtr = numPtr;
result = *genericPtr + 7;
```
ANS: A **void *** pointer cannot be dereferenced.

f)
```
double x = 19.34;
double xPtr = &x;
cout << xPtr << endl;
```
ANS: **xPtr** is not a pointer and therefore cannot be assigned an address. Place a ***** before **xPtr** (in the declaration) to correct the problem. The **cout** statement display's the address to which **xPtr** points (once the previous correction is made)—this is not an error.

g)
```
char *s;
cout << s << endl;
```
ANS: **s** does not "point" to anything. **s** should be provided with an address.

5.24 (*Quicksort*) In the examples and exercises of Chapter 4, we discussed the sorting techniques of the bubble sort, bucket sort, and selection sort. We now present the recursive sorting technique called Quicksort. The basic algorithm for a single-subscripted array of values is as follows:

a) *Partitioning Step:* Take the first element of the unsorted array and determine its final location in the sorted array (i.e., all values to the left of the element in the array are less than the element, and all values to the right of the element in the array are greater than the element). We now have one element in its proper location and two unsorted subarrays.

b) *Recursive Step:* Perform step 1 on each unsorted subarray.

Each time step 1 is performed on a subarray, another element is placed in its final location of the sorted array, and two unsorted subarrays are created. When a subarray consists of one element, it must be sorted, therefore that element is in its final location.

The basic algorithm seems simple enough, but how do we determine the final position of the first element of each subarray. As an example, consider the following set of values (the element in bold is the partitioning element—it will be placed in its final location in the sorted array):

37 2 6 4 89 8 10 12 68 45

a) Starting from the rightmost element of the array, compare each element with **37** until an element less than **37** is found. Then swap **37** and that element. The first element less than **37** is 12, so **37** and 12 are swapped. The new array is

12 2 6 4 89 8 10 **37** 68 45

Element 12 is in italic to indicate that it was just swapped with **37**.

b) Starting from the left of the array, but beginning with the element after 12, compare each element with **37** until an element greater than **37** is found. Then swap **37** and that element. The first element greater than **37** is 89, so **37** and 89 are swapped. The new array is

12 2 6 4 **37** 8 10 *89* 68 45

c) Starting from the right, but beginning with the element before 89, compare each element with **37** until an element less than **37** is found. Then swap **37** and that element. The first element less than **37** is 10, so **37** and 10 are swapped. The new array is

12 2 6 4 *10* 8 **37** 89 68 45

d) Starting from the left, but beginning with the element after 10, compare each element with **37** until an element greater than **37** is found. Then swap **37** and that element. There are no more elements greater than **37**, so when we compare **37** with itself, we know that **37** has been placed in its final location of the sorted array.

Once the partition has been applied on the array, there are two unsorted subarrays. The subarray with values less than 37 contains 12, 2, 6, 4, 10 and 8. The subarray with values greater than 37 contains 89, 68 and 45. The sort continues with both subarrays being partitioned in the same manner as the original array.

Based on the preceding discussion, write recursive function **quickSort** to sort a single-subscripted integer array. The function should receive as arguments an integer array, a starting subscript and an ending subscript. Function **partition** should be called by **quickSort** to perform the partitioning step.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 5.24 Solution
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>

using std::setw;

#include <cstdlib>
#include <ctime>

const int SIZE = 10, MAX_NUMBER = 1000;

void quicksort( int * const, int, int );
void swap( int * const, int * const );

int main()
{
   int arrayToBeSorted[ SIZE ] = { 0 };
   int loop;

   srand( time( 0 ) );

   for ( loop = 0; loop < SIZE; ++loop )
      arrayToBeSorted[ loop ] = rand() % MAX_NUMBER;

   cout << "Initial array values are:\n";

   for ( loop = 0; loop < SIZE; ++loop )
       cout << setw( 4 ) << arrayToBeSorted[ loop ];

   cout << "\n\n";

   if ( SIZE == 1 )
      cout << "Array is sorted: " << arrayToBeSorted[ 0 ] << '\n';
   else {
      quicksort( arrayToBeSorted, 0, SIZE - 1 );
      cout << "The sorted array values are:\n";

      for ( loop = 0; loop < SIZE; ++loop )
         cout << setw( 4 ) << arrayToBeSorted[ loop ];

      cout << endl;
   }

   return 0;
}

void quicksort( int * const array, int first, int last )
{
   int partition( int * const, int, int );
   int currentLocation;

   if ( first >= last )
      return;

   currentLocation = partition( array, first, last );  // place an element
   quicksort( array, first, currentLocation - 1 );     // sort left side
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
61    quicksort( array, currentLocation + 1, last );      // sort right side
62 }
63
64 int partition( int * const array, int left, int right )
65 {
66    int position = left;
67
68    while ( true ) {
69       while ( array[ position ] <= array[ right ] && position != right )
70          --right;
71
72       if ( position == right )
73          return position;
74
75       if ( array[ position ] > array[ right ]) {
76          swap( &array[ position ], &array[ right ] );
77          position = right;
78       }
79
80       while ( array[ left ] <= array[ position ] && left != position )
81          ++left;
82
83       if ( position == left )
84          return position;
85
86       if ( array[ left ] > array[ position ] ) {
87          swap( &array[ position ], &array[ left ] );
88          position = left;
89       }
90    }
91 }
92
93 void swap( int * const ptr1, int * const ptr2 )
94 {
95    int temp;
96
97    temp = *ptr1;
98    *ptr1 = *ptr2;
99    *ptr2 = temp;
100 }
```

```
Initial array values are:
 407 766 451 328  17  50 551 620 192  35

The sorted array values are:
  17  35  50 192 328 407 451 551 620 766
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

5.25 (*Maze Traversal*) The following grid of hashes (**#**) and dots (**.**) is a double-subscripted array representation of a maze:

```
# # # # # # # # # # # #
# . . . # . . . . . . #
. . # . # . # # # # . #
# # # . # . . . . # . #
# . . . . # # # . # . .
# # # # . # . # . # . #
# . . # . # . # . # . #
# # . # . # . # . # . #
# . . . . . . . . # . #
# # # # # # . # # # . #
# . . . . . . # . . . #
# # # # # # # # # # # #
```

In the preceding double-subscripted array, the hashes (**#**), represent the walls of the maze and the dots represent squares in the possible paths through the maze. Moves can only be made to a location in the array that contains a dot.

There is a simple algorithm for walking through a maze that guarantees finding the exit (assuming that there is an exit). If there is not an exit, you will arrive at the starting location again. Place your right hand on the wall to your right and begin walking forward. Never remove your hand from the wall. If the maze turns to the right, you follow the wall to the right. As long as you do not remove your hand from the wall, eventually you will arrive at the exit of the maze. There may be a shorter path than the one you have taken, but you are guaranteed to get out of the maze if you follow the algorithm.

Write recursive function **mazeTraverse** to walk through the maze. The function should receive as arguments a 12-by-12 character array representing the maze and the starting location of the maze. As **mazeTraverse** attempts to locate the exit from the maze, it should place the character **X** in each square in the path. The function should display the maze after each move so the user can watch as the maze is solved.

```
1  // Exercise 5.25 Solution
2  // This solution assumes that there is only one
3  // entrance and one exit for a given maze, and
4  // these are the only two zeroes on the borders.
5  #include <iostream>
6
7  using std::cout;
8  using std::cin;
9
10 #include <cstdlib>
11
12 enum Direction { DOWN, RIGHT, UP, LEFT };
13 const int X_START = 2, Y_START = 0;   // starting coordinate for maze
14
15 void mazeTraversal( char [][ 12 ], int, int, int );
16 void printMaze( const char[][ 12 ] );
17 bool validMove( const char [][ 12 ], int, int );
18 bool coordsAreEdge( int, int );
19
20 int main()
21 {
22    char maze[ 12 ][ 12 ] =
23           { {'#', '#', '#', '#', '#', '#', '#', '#', '#', '#', '#', '#'},
24             {'#', '.', '.', '.', '#', '.', '.', '.', '.', '.', '.', '#'},
25             {'.', '.', '#', '.', '#', '.', '#', '#', '#', '#', '.', '#'},
26             {'#', '#', '#', '.', '#', '.', '.', '.', '.', '#', '.', '#'},
27             {'#', '.', '.', '.', '.', '#', '#', '#', '.', '#', '.', '.'},
28             {'#', '#', '#', '#', '.', '#', '.', '#', '.', '#', '.', '#'},
29             {'#', '.', '.', '#', '.', '#', '.', '#', '.', '#', '.', '#'},
30             {'#', '#', '.', '#', '.', '#', '.', '#', '.', '#', '.', '#'},
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
            {'#', '.', '.', '.', '.', '.', '.', '.', '.', '#', '.', '#'},
            {'#', '#', '#', '#', '#', '#', '.', '#', '#', '#', '.', '#'},
            {'#', '.', '.', '.', '.', '.', '.', '#', '.', '.', '.', '#'},
            {'#', '#', '#', '#', '#', '#', '#', '#', '#', '#', '#', '#'} };

   mazeTraversal( maze, X_START, Y_START, RIGHT );

   return 0;
}

// Assume that there is exactly 1 entrance and exactly 1 exit to the maze.
void mazeTraversal( char maze[][ 12 ], int xCoord, int yCoord, int direction )
{
   static bool flag = false;

   maze[ xCoord ][ yCoord ] = 'x';
   printMaze( maze );

   if ( coordsAreEdge(xCoord, yCoord) && xCoord != X_START &&
        yCoord != Y_START ) {
      cout << "\nMaze successfully exited!\n\n";
      return;   // maze is complete
   }
   else if ( xCoord == X_START && yCoord == X_START && flag ) {
      cout << "\nArrived back at the starting location.\n\n";
      return;
   }
   else {
      flag = true;

      for ( int move = direction, count = 0; count < 4; ++count,
            ++move, move %= 4 )
         switch( move ) {
            case DOWN:
               if ( validMove( maze, xCoord + 1, yCoord ) ) { // move down
                  mazeTraversal( maze, xCoord + 1, yCoord, LEFT );
                  return;
               }
               break;
            case RIGHT:
               if ( validMove( maze, xCoord, yCoord + 1 ) ) { // move right
                  mazeTraversal( maze, xCoord, yCoord + 1, DOWN );
                  return;
               }
               break;
            case UP:
               if ( validMove( maze, xCoord - 1, yCoord ) ) { // move up
                  mazeTraversal( maze, xCoord - 1, yCoord, RIGHT );
                  return;
               }
               break;
            case LEFT:
               if ( validMove( maze, xCoord, yCoord - 1 ) ) { // move left
                  mazeTraversal( maze, xCoord, yCoord - 1, UP );
                  return;
               }
               break;
         }
   }
}

bool validMove( const char maze[][ 12 ], int r, int c )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
93  {
94     return ( r >= 0 && r <= 11 && c >= 0 && c <= 11 && maze[ r ][ c ] != '#' );
95  }
96
97  bool coordsAreEdge( int x, int y )
98  {
99     if ( ( x == 0 || x == 11 ) && ( y >= 0 && y <= 11 ) )
100       return true;
101    else if ( ( y == 0 || y == 11 ) && ( x >= 0 && x <= 11 ) )
102       return true;
103    else
104       return false;
105 }
106
107 void printMaze( const char maze[][ 12 ] )
108 {
109    for ( int x = 0; x < 12; ++x ) {
110
111       for ( int y = 0; y < 12; ++y )
112          cout << maze[ x ][ y ] << ' ';
113
114       cout << '\n';
115    }
116
117    cout << "\nHit return to see next move\n";
118    cin.get();
119 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
...
# # # # # # # # # # #
# x x x # x x x x x x #
x x # x # x # # # # x #
# # # x # x x x x # x #
# x x x x # # # x # x .
# # # # x # . # x # x #
# x x # x # . # x # x #
# # x # x # . # x # x #
# x x x x x x x x # x #
# # # # # # x # # # x #
# x x x x x x # x x x #
# # # # # # # # # # # #

Hit return to see next move

# # # # # # # # # # #
# x x x # x x x x x x #
x x # x # x # # # # x #
# # # x # x x x x # x #
# x x x x # # # x # x x
# # # # x # . # x # x #
# x x # x # . # x # x #
# # x # x # . # x # x #
# x x x x x x x x # x #
# # # # # # x # # # x #
# x x x x x x # x x x #
# # # # # # # # # # # #

Hit return to see next move


Maze successfully exited!
```

5.26 (*Generating Mazes Randomly*) Write a function **mazeGenerator** that takes as an argument a double-subscripted 12-by-12 character array and randomly produces a maze. The function should also provide the starting and ending locations of the maze. Try your function **mazeTraverse** from Exercise 5.25 using several randomly generated mazes.

```
1  // Exercise 5.26 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6
7  #include <cstdlib>
8  #include <ctime>
9
10 enum Direction { DOWN, RIGHT, UP, LEFT };
11 const int MAX_DOTS = 100;  // maximum possible dots for maze
12
13 void mazeTraversal( char [][ 12 ], const int, const int, int, int, int );
14 void mazeGenerator( char [][ 12 ], int *, int * );
15 void printMaze( const char[][ 12 ] );
16 bool validMove( const char [][ 12 ], int, int );
17 bool coordsAreEdge( int, int );
18
19 int main()
20 {
21    char maze[ 12 ][ 12 ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
22    int xStart, yStart, x, y;
23
24    srand( time( 0 ) );
25
26    for ( int loop = 0; loop < 12; ++loop )
27       for ( int loop2 = 0; loop2 < 12; ++loop2 )
28          maze[ loop ][ loop2 ] = '#';
29
30    mazeGenerator( maze, &xStart, &yStart );
31
32    x = xStart;  // starting row
33    y = yStart;  // starting col
34
35    mazeTraversal( maze, xStart, yStart, x, y, RIGHT );
36
37    return 0;
38 }
39
40 // Assume that there is exactly 1 entrance and exactly 1 exit to the maze.
41 void mazeTraversal( char maze[][ 12 ], const int xCoord, const int yCoord,
42                     int row, int col, int direction )
43 {
44    static bool flag = false;   // starting position flag
45
46    maze[ row ][ col ] = 'x';  // insert X at current location
47    printMaze( maze );
48
49    if ( coordsAreEdge( row, col ) && row != xCoord && col != yCoord ) {
50       cout << "Maze successfully exited!\n\n";
51       return;   // maze is complete
52    }
53    else if ( row == xCoord && col == yCoord && flag ) {
54       cout << "Arrived back at the starting location.\n\n";
55       return;
56    }
57    else {
58       flag = true;
59
60       for ( int move = direction, count = 0; count < 4;
61             ++count, ++move, move %= 4 )
62
63          switch( move ) {
64             case DOWN:
65                if ( validMove( maze, row + 1, col ) ) { // move down
66                   mazeTraversal( maze, xCoord, yCoord, row + 1, col, LEFT );
67                   return;
68                }
69                break;
70             case RIGHT:
71                if ( validMove( maze, row, col + 1 ) ) { // move right
72                   mazeTraversal( maze, xCoord, yCoord, row, col + 1, DOWN );
73                   return;
74                }
75                break;
76             case UP:
77                if ( validMove( maze, row - 1, col ) ) { // move up
78                   mazeTraversal( maze, xCoord, yCoord, row - 1, col, RIGHT );
79                   return;
80                }
81                break;
82             case LEFT:
83                if ( validMove( maze, row, col - 1 ) ) { // move left
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
84                   mazeTraversal( maze, xCoord, yCoord, row, col - 1, UP );
85                   return;
86                }
87                break;
88             }
89          }
90       }
91
92       bool validMove( const char maze[][ 12 ], int r, int c )
93       {
94          return ( r >= 0 && r <= 11 && c >= 0 && c <= 11 && maze[ r ][ c ] != '#' );
95       }
96
97       bool coordsAreEdge( int x, int y )
98       {
99          if ( ( x == 0 || x == 11 ) && ( y >= 0 && y <= 11 ) )
100            return true;
101         else if ( ( y == 0 || y == 11 ) && ( x >= 0 && x <= 11 ) )
102            return true;
103         else
104            return false;
105      }
106
107      void printMaze( const char maze[][ 12 ] )
108      {
109         for ( int x = 0; x < 12; ++x ) {
110
111            for ( int y = 0; y < 12; ++y )
112               cout << maze[ x ][ y ] << ' ';
113
114            cout << '\n';
115         }
116
117         cout << "Hit return to see next move";
118         cin.get();
119      }
120
121      void mazeGenerator(char maze[][ 12 ], int *xPtr, int *yPtr )
122      {
123         int a, x, y, entry, exit;
124
125         do {
126            entry = rand() % 4;
127            exit = rand() % 4;
128         } while ( entry == exit );
129
130         // Determine entry position
131
132         if ( entry == 0 ) {
133            *xPtr = 1 + rand() % 10;    // avoid corners
134            *yPtr = 0;
135            maze[ *xPtr ][ 0 ] = '.';
136         }
137         else if ( entry == 1 ) {
138            *xPtr = 0;
139            *yPtr = 1 + rand() % 10;
140            maze[ 0 ][ *yPtr ] = '.';
141         }
142         else if ( entry == 2 ) {
143            *xPtr = 1 + rand() % 10;
144            *yPtr = 11;
145            maze[ *xPtr ][ 11 ] = '.';
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
146     }
147     else {
148        *xPtr = 11;
149        *yPtr = 1 + rand() % 10;
150        maze[ 11 ][ *yPtr ] = '.';
151     }
152
153     // Determine exit location
154
155     if ( exit == 0 ) {
156        a = 1 + rand() % 10;
157        maze[ a ][ 0 ] = '.';
158     }
159     else if ( exit == 1 ) {
160        a = 1 + rand() % 10;
161        maze[ 0 ][ a ] = '.';
162     }
163     else if ( exit == 2 ) {
164        a = 1 + rand() % 10;
165        maze[ a ][ 11 ] = '.';
166     }
167     else {
168        a = 1 + rand() % 10;
169        maze[ 11 ][ a ] = '.';
170     }
171
172     for ( int loop = 1; loop < MAX_DOTS; ++loop ) {   // add dots randomly
173        x = 1 + rand() % 10;
174        y = 1 + rand() % 10;
175        maze[ x ][ y ] = '.';
176     }
177  }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 ...
# # # # # # # # # # #
# # . # # # x # # # #
# # . . . # x x x # x #
# . # # # x x x x x #
# . . # # # # x . x x #
# # . # x x x x # x # .
# # . # x x x # # x x #
# # # x x # x . . . x #
# # x x x # x x x x x #
# # # # # x # x x # x #
# . # x x x x x # # # #
# # # # # # # x # # # #
Hit return to see next move
# # # # # # # # # # #
# # . # # # x # # # #
# # . . . # x x x # x #
# . # # # x x x x x #
# . . # # # # x . x x #
# # . # x x x x # x # .
# # . # x x x # # x x #
# # # x x # x . . . x #
# # x x x # x x x x x #
# # # # # x # x x # x #
# . # x x x x x # # # #
# # # # # # # x # # # #
Hit return to see next move
Arrived back at the starting location.
```

5.27 (*Mazes of Any Size*) Generalize functions **mazeTraverse** and **mazeGenerator** of Exercises 5.25 and 5.26 to process mazes of any width and height.

```
1  // Exercise 5.27 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstdlib>
9  #include <ctime>
10
11 enum Direction { DOWN, RIGHT, UP, LEFT };
12 const int ROWS = 15, COLS = 30;
13
14 void mazeTraversal( char [][ COLS ], const int, const int, int, int, int );
15 void mazeGenerator( char [][ COLS ], int *, int * );
16 void printMaze( const char[][ COLS ] );
17 bool validMove( const char [][ COLS ], int, int );
18 bool coordsAreEdge( int, int );
19
20 int main()
21 {
22    char maze[ ROWS ][ COLS ];
23    int xStart, yStart, x, y;
24
25    srand( time( 0 ) );
26
27    for ( int loop = 0; loop < ROWS; ++loop )
28       for ( int loop2 = 0; loop2 < COLS; ++loop2 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
29          maze[ loop ][ loop2 ] = '#';
30
31    mazeGenerator( maze, &xStart, &yStart );
32
33    x = xStart;  // starting row
34    y = yStart;  // starting col
35
36    mazeTraversal( maze, xStart, yStart, x, y, RIGHT );
37
38    return 0;
39 }
40
41 // Assume that there is exactly 1 entrance and exactly 1 exit to the maze.
42 void mazeTraversal( char maze[][ COLS ], const int xCoord, const int yCoord,
43                     int row, int col, int direction )
44 {
45    static bool flag = false;   // starting position flag
46
47    maze[ row ][ col ] = 'x';  // insert x at current location
48    printMaze( maze );
49
50    if ( coordsAreEdge( row, col ) && row != xCoord && col != yCoord ) {
51       cout << endl << "Maze successfully exited!\n\n";
52       return;   // maze is complete
53    }
54    else if ( row == xCoord && col == yCoord && flag ) {
55       cout << "\nArrived back at the starting location.\n\n";
56       return;
57    }
58    else {
59       flag = true;
60
61       for ( int move = direction, count = 0; count < 4;
62             ++count, ++move, move %= 4 )
63          switch( move ) {
64             case DOWN:
65                if ( validMove( maze, row + 1, col ) ) { // move down
66                   mazeTraversal( maze, xCoord, yCoord, row + 1, col, LEFT );
67                   return;
68                }
69                break;
70             case RIGHT:
71                if ( validMove( maze, row, col + 1 ) ) { // move right
72                   mazeTraversal( maze, xCoord, yCoord, row, col + 1, DOWN );
73                   return;
74                }
75                break;
76             case UP:
77                if ( validMove( maze, row - 1, col ) ) { // move up
78                   mazeTraversal( maze, xCoord, yCoord, row - 1, col, RIGHT );
79                   return;
80                }
81                break;
82             case LEFT:
83                if ( validMove( maze, row, col - 1 ) ) { // move left
84                   mazeTraversal( maze, xCoord, yCoord, row, col - 1, UP );
85                   return;
86                }
87                break;
88          }
89    }
90 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
91
92  bool validMove( const char maze[][ COLS ], int r, int c )
93  {
94     return ( r >= 0 && r <= ROWS - 1 && c >= 0 && c <= COLS - 1 &&
95              maze[ r ][ c ] != '#' );  // a valid move
96  }
97
98  bool coordsAreEdge( int x, int y )
99  {
100    if ( ( x == 0 || x == ROWS - 1 ) && ( y >= 0 && y <= COLS - 1 ) )
101       return true;
102    else if ( ( y == 0 || y == COLS - 1 ) && ( x >= 0 && x <= ROWS - 1 ) )
103       return true;
104    else
105       return false;
106 }
107
108 void printMaze( const char maze[][ COLS ] )
109 {
110    for ( int x = 0; x < ROWS; ++x ) {
111
112       for ( int y = 0; y < COLS; ++y )
113          cout << maze[ x ][ y ] << ' ';
114
115       cout << '\n';
116    }
117
118    cout << "\nHit return to see next move";
119    cin.get();
120 }
121
122 void mazeGenerator( char maze[][ COLS ], int *xPtr, int *yPtr )
123 {
124    int a, x, y, entry, exit;
125
126    do {
127       entry = rand() % 4;
128       exit = rand() % 4;
129    } while ( entry == exit );
130
131    // Determine entry position
132    if ( entry == 0 ) {
133       *xPtr = 1 + rand() % ( ROWS - 2 );    // avoid corners
134       *yPtr = 0;
135       maze[ *xPtr ][ *yPtr ] = '.';
136    }
137    else if ( entry == 1 ) {
138       *xPtr = 0;
139       *yPtr = 1 + rand() % ( COLS - 2 );
140       maze[ *xPtr ][ *yPtr ] = '.';
141    }
142    else if ( entry == 2 ) {
143       *xPtr = 1 + rand() % ( ROWS - 2 );
144       *yPtr = COLS - 1;
145       maze[ *xPtr ][ *yPtr ] = '.';
146    }
147    else {
148       *xPtr = ROWS - 1;
149       *yPtr = 1 + rand() % ( COLS - 2 );
150       maze[ *xPtr ][ *yPtr ] = '.';
151    }
152
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
153    // Determine exit location
154    if ( exit == 0 ) {
155       a = 1 + rand() % ( ROWS - 2 );
156       maze[ a ][ 0 ] = '.';
157    }
158    else if ( exit == 1 ) {
159       a = 1 + rand() % ( COLS - 2 );
160       maze[ 0 ][ a ] = '.';
161    }
162    else if ( exit == 2 ) {
163       a = 1 + rand() % ( ROWS - 2 );
164       maze[ a ][ COLS - 1 ] = '.';
165    }
166    else {
167       a = 1 + rand() % ( COLS - 2 );
168       maze[ ROWS - 1 ][ a ] = '.';
169    }
170
171    for ( int loop = 1; loop < ( ROWS - 2 ) * ( COLS - 2 ); ++loop ) {
172       x = 1 + rand() % ( ROWS - 2 );    // add dots to maze
173       y = 1 + rand() % ( COLS - 2 );
174       maze[ x ][ y ] = '.';
175    }
176 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
...
Hit return to see next move
# # # # # # # # # # # # # . # # # # # # # # # # # # # # #
# . . # . . . . . . # . . # x x x # x x x x x x # . # . # #
# . . . . # # . # # # # # . . . x x x # # x x x x # . . # #
# . # . # . # # . # # . # # . . # . # . # x # # # . . # # #
# . # # . . . # # . . # # . . . . # . . x x x x x # . # # #
# . # # # . . . # . # . # # . . . . # . x # # x x x # . # #
# # # . # . . . . . # . # # . . # # # . x # . # x # . . # #
# . x x x x x x . # # . . . . . # . # . x x # x # . # . # #
# x x # # x # x . . . . # # . . # # . # # x x x x # . . . #
# x # # x x # x x . . . . . . . . # . . # . # # x # . . . #
x x # x x x x # x x x . . x x x x x x x x . x x x x x # # . #
# # x x x # # x # # # x . # x # x x # # x x x # x # x # # # #
# # x x # . # x # x x x x x x # x # # # # # x x x # # . . #
# . # x # . # x x x x # x # # # x x x # # x x # x # . . . #
# # # # # # # # # # # # # # # # # # # # # # # # # # # # # #

Hit return to see next move
# # # # # # # # # # # # # # x # # # # # # # # # # # # # # #
# . . # . . . . . . # . . # x x x # x x x x x x # . # . # #
# . . . . # # . # # # # # . . . x x x # # x x x x # . . # #
# . # . # . # # . # # . # # . . # . # . # x # # # . . # # #
# . # # . . . # # . . # # . . . . # . . x x x x x # . # # #
# . # # # . . . # . # . # # . . . . # . x # # x x x # . # #
# # # . # . . . . . # . # # . . # # # . x # . # x # . . # #
# . x x x x x x . # # . . . . . # . # . x x # x # . # . # #
# x x # # x # x . . . . # # . . # # . # # x x x x # . . . #
# x # # x x # x x . . . . . . . . # . . # . # # x # . . . #
x x # x x x x # x x x . . x x x x x x x x . x x x x x # # . #
# # x x x # # x # # # x . # x # x x # # x x x # x # x # # # #
# # x x # . # x # x x x x x x # x # # # # # x x x # # . . #
# . # x # . # x x x x # x # # # x x x # # x x # x # . . . #
# # # # # # # # # # # # # # # # # # # # # # # # # # # # # #

Hit return to see next move

Maze successfully exited!
```

5.28 (*Arrays of Pointers to Functions*) Rewrite the program of Fig. 4.23 to use a menu-driven interface. The program should offer the user five options as follows (these should be displayed on the screen):

```
Enter a choice:
  0  Print the array of grades
  1  Find the minimum grade
  2  Find the maximum grade
  3  Print the average on all tests for each student
  4  End program
```

One restriction on using arrays of pointers to functions is that all the pointers must have the same type. The pointers must be to functions of the same return type that receive arguments of the same type. For this reason, the functions in Fig. 4.23 must be modified so they each return the same type and take the same parameters. Modify functions **minimum** and **maximum** to print the minimum or maximum value and return nothing. For option 3, modify function **average** of Fig. 4.23 to output the average for each student (not a specific student). Function **average** should return nothing and take the same parameters as **printArray**, **minimum** and **maximum**. Store the pointers to the four functions in array **processGrades**, and use the choice made by the user as

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

the subscript into the array for calling each function.

```
// Exercise 5.28 Solution
#include <iostream>

using std::cout;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

const int STUDENTS = 3, EXAMS = 4;

void minimum( const int [][ EXAMS ], int, int );
void maximum( const int [][ EXAMS ], int, int );
void average( const int [][ EXAMS ], int, int );
void printArray( const int [][ EXAMS ], int, int );
void printMenu( void );
int test( bool ( * )( int, int ), int, int, int, const int [][ EXAMS ] );

int main()
{
   void ( *processGrades[ 4 ] )( const int [][ EXAMS ], int, int )
                      = { printArray, minimum, maximum, average };

   int choice = 0,
       studentGrades[ STUDENTS ][ EXAMS ] = { { 77, 68, 86, 73 },
                                              { 96, 87, 89, 78 },
                                              { 70, 90, 86, 81 } };

   while ( choice != 4 ) {

      do {
         printMenu();
         cin >> choice;
      } while ( choice < 0 || choice > 4 );

      if ( choice != 4 )
         ( *processGrades[ choice ] )( studentGrades, STUDENTS, EXAMS );
      else
         cout << "Program Ended.\n";
   }

   return 0;
}

void minimum( const int grades[][ EXAMS ], int pupils, int tests )
{
   bool smaller( int, int );

   cout << "\n\tThe lowest grade is "
        << test( smaller, pupils, tests, 100, grades ) << '\n';
}

void maximum( const int grades[][ EXAMS ], int pupils, int tests )
{
   bool greater( int, int );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
61
62    cout << "\n\tThe highest grade is "
63         << test( greater, pupils, tests, 0, grades ) << '\n';
64 }
65
66 int test( bool ( *ptr )( int, int ), int p, int t, int value,
67           const int g[][ EXAMS ] )
68 {
69     for ( int i = 0; i < p; ++i )
70       for ( int j = 0; j < t; ++j )
71          if ( ( *ptr )( g[ i ][ j ], value ) )
72             value = g[ i ][ j ];
73
74     return value;   // return max/min value
75 }
76
77 void average( const int grades[][ EXAMS ], int pupils, int tests )
78 {
79    int total;
80
81    cout << setiosflags( ios::fixed | ios::showpoint ) << '\n';
82
83    for ( int i = 0; i < pupils; ++i ) {
84       total = 0;  // reset total
85
86       for ( int j = 0; j < tests; ++j )
87          total += grades[ i ][ j ];
88
89       cout << "\tThe average for student " << pupils + 1 << " is "
90            << setprecision( 1 )
91            << static_cast< double > ( total ) / tests << '\n';
92    }
93
94    cout << resetiosflags( ios::fixed | ios::showpoint );
95 }
96
97 void printArray( const int grades[][ EXAMS ], int pupils, int tests )
98 {
99    cout << "\n                  [0]  [1]  [2]  [3]";
100
101   for ( int i = 0; i < pupils; ++i ) {
102      cout << "\nstudentGrades[" << i << ']';
103
104      for ( int j = 0; j < tests; ++j )
105         cout << setw( 5 ) << grades[ i ][ j ];
106   }
107
108   cout << '\n';
109 }
110
111 void printMenu( void )
112 {
113    cout << "\nEnter a choice:\n"
114         << "  0  Print the array of grades\n"
115         << "  1  Find the minimum grade\n"
116         << "  2  Find the maximum grade\n"
117         << "  3  Print the average on all tests for each student\n"
118         << "  4  End program\n? ";
119 }
120
121 bool greater( int a, int b )
122 {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
123    return a > b;
124 }
125
126 bool smaller( int a, int b )
127 {
128    return a < b;
129 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter a choice:
  0  Print the array of grades
  1  Find the minimum grade
  2  Find the maximum grade
  3  Print the average on all tests for each student
  4  End program
? 0

                  [0]   [1]   [2]   [3]
studentGrades[0]   77    68    86    73
studentGrades[1]   96    87    89    78
studentGrades[2]   70    90    86    81

Enter a choice:
  0  Print the array of grades
  1  Find the minimum grade
  2  Find the maximum grade
  3  Print the average on all tests for each student
  4  End program
? 1

        The lowest grade is 68

Enter a choice:
  0  Print the array of grades
  1  Find the minimum grade
  2  Find the maximum grade
  3  Print the average on all tests for each student
  4  End program
? 2

        The highest grade is 96

Enter a choice:
  0  Print the array of grades
  1  Find the minimum grade
  2  Find the maximum grade
  3  Print the average on all tests for each student
  4  End program
? 3

        The average for student 4 is 76.0
        The average for student 4 is 87.5
        The average for student 4 is 81.8

Enter a choice:
  0  Print the array of grades
  1  Find the minimum grade
  2  Find the maximum grade
  3  Print the average on all tests for each student
  4  End program
? 4
Program Ended.
```

5.29 (*Modifications to the Simpletron Simulator*) In Exercise 5.19, you wrote a software simulation of a computer that executes programs written in Simpletron Machine Language (SML). In this exercise, we propose several modifications and enhancements to the Simpletron Simulator. In Exercises 15.26 and 15.27, we propose building a compiler that converts programs written in a high-level programming language (a variation of BASIC) to SML. Some of the following modifications and enhancements may be required to execute the programs produced by the compiler. (*Note:* Some modifications may conflict with others and therefore must be done separately.)

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

a) Extend the Simpletron Simulator's memory to contain 1000 memory locations to enable the Simpletron to handle larger programs.
b) Allow the simulator to perform modulus calculations. This requires an additional Simpletron Machine Language instruction.
c) Allow the simulator to perform exponentiation calculations. This requires an additional Simpletron Machine Language instruction.
d) Modify the simulator to use hexadecimal values rather than integer values to represent Simpletron Machine Language instructions.
e) Modify the simulator to allow output of a newline. This requires an additional Simpletron Machine Language instruction.
f) Modify the simulator to process floating-point values in addition to integer values.
g) Modify the simulator to handle string input. [*Hint:* Each Simpletron word can be divided into two groups, each holding a two-digit integer. Each two-digit integer represents the ASCII decimal equivalent of a character. Add a machine-language instruction that will input a string and store the string beginning at a specific Simpletron memory location. The first half of the word at that location will be a count of the number of characters in the string (i.e., the length of the string). Each succeeding half-word contains one ASCII character expressed as two decimal digits. The machine-language instruction converts each character into its ASCII equivalent and assigns it to a half-word.]
h) Modify the simulator to handle output of strings stored in the format of part (g). [*Hint:* Add a machine language instruction that will print a string beginning at a certain Simpletron memory location. The first half of the word at that location is a count of the number of characters in the string (i.e., the length of the string). Each succeeding half-word contains one ASCII character expressed as two decimal digits. The machine-language instruction checks the length and prints the string by translating each two-digit number into its equivalent character.]
i) Modify the simulator to include instruction **SML_DEBUG** that prints a memory dump after each instruction is executed. Give **SML_DEBUG** an operation code of **44**. The word **+4401** turns on debug mode and **+4400** turns off debug mode.

5.30 What does this program do?

```
// ex05_30.cpp
#include <iostream>

using std::cout;
using std::cin;
using std::endl;

bool mystery3( const char *, const char * );

int main()
{
   char string1[ 80 ], string2[ 80 ];

   cout << "Enter two strings: ";
   cin >> string1 >> string2;
   cout << "The result is "
        << mystery3( string1, string2 ) << endl;

   return 0;
}

bool mystery3( const char *s1, const char *s2 )
{
   for ( ; *s1 != '\0' && *s2 != '\0'; s1++, s2++ )

      if ( *s1 != *s2 )
         return false;

   return true;
}
```

ANS: Function **mystery3** compares two strings for equality.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

STRING MANIPULATION EXERCISES

5.31 Write a program that uses function **strcmp** to compare two strings input by the user. The program should state whether the first string is less than, equal to or greater than the second string.

```
// Exercise 5.31 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstring>

const int SIZE = 20;

int main()
{
   char string1[ SIZE ], string2[ SIZE ];
   int result;

   cout << "Enter two strings: ";
   cin >> string1 >> string2;

   result = strcmp( string1, string2 );

   if ( result > 0 )
      cout << '\"' << string1 << '\"' << " is greater than \""
           << string2 << '\"' << endl;
   else if ( result == 0 )
      cout << '\"' << string1 << '\"' << " is equal to \"" << string2
           << '\"' << endl;
   else
      cout << '\"' << string1 << '\"' << " is less than \"" << string2
           << '\"' << endl;

   return 0;
}
```

```
Enter two strings: green leaf
"green" is less than "leaf"
```

5.32 Write a program that uses function **strncmp** to compare two strings input by the user. The program should input the number of characters to be compared. The program should state whether the first string is less than, equal to or greater than the second string.

```
// Exercise 5.32 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstring>

const int SIZE = 20;

int main()
{
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   char string1[ SIZE ], string2[ SIZE ];
   int result, compareCount;

   cout << "Enter two strings: ";
   cin >> string1 >> string2;
   cout << "How many characters should be compared: ";
   cin >> compareCount;

   result = strncmp( string1, string2, compareCount );

   if ( result > 0 )
      cout << '\"' << string1 << "\" is greater than \"" << string2
           << "\" up to " << compareCount << " characters\n";
   else if ( result == 0 )
      cout << '\"' << string1 << "\" is equal to \"" << string2
           << "\" up to " << compareCount << " characters\n";
   else
      cout << '\"' << string1 << "\" is less than \"" << string2
           << "\" up to " << compareCount << " characters\n";

   cout << endl;

   return 0;
}
```

```
Enter two strings: sand sandpaper
How many characters should be compared: 4
"sand" is equal to "sandpaper" up to 4 characters
```

5.33 Write a program that uses random-number generation to create sentences. The program should use four arrays of pointers to **char** called **article**, **noun**, **verb** and **preposition**. The program should create a sentence by selecting a word at random from each array in the following order: **article**, **noun**, **verb**, **preposition**, **article** and **noun**. As each word is picked, it should be concatenated to the previous words in an array that is large enough to hold the entire sentence. The words should be separated by spaces. When the final sentence is output, it should start with a capital letter and end with a period. The program should generate 20 such sentences.

The arrays should be filled as follows: the **article** array should contain the articles **"the"**, **"a"**, **"one"**, **"some"** and **"any"**; the **noun** array should contain the nouns **"boy"**, **"girl"**, **"dog"**, **"town"** and **"car"**; the **verb** array should contain the verbs **"drove"**, **"jumped"**, **"ran"**, **"walked"** and **"skipped"**; the **preposition** array should contain the prepositions **"to"**, **"from"**, **"over"**, **"under"** and **"on"**.

After the preceding program is written and working, modify the program to produce a short story consisting of several of these sentences. (How about the possibility of a random term paper writer!)

```
// Exercise 5.33 Solution
#include <iostream>

using std::cout;
using std::endl;

#include <cstdlib>
#include <ctime>

#include <cstring>
#include <cctype>

const int SIZE = 100;

int main()
{
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   const char *article[] = { "the", "a", "one", "some", "any" },
        *noun[] = { "boy", "girl", "dog", "town", "car" },
        *verb[] = { "drove", "jumped", "ran", "walked", "skipped" },
        *preposition[] = { "to", "from", "over", "under", "on" };
   char sentence[ SIZE ] = "";

   for ( int i = 1; i <= 20; ++i ) {
      strcat( sentence, article[ rand() % 5 ] );
      strcat( sentence, " " );
      strcat( sentence, noun[ rand() % 5 ] );
      strcat( sentence, " " );
      strcat( sentence, verb[ rand() % 5 ] );
      strcat( sentence, " " );
      strcat( sentence, preposition[ rand() % 5 ] );
      strcat( sentence, " " );
      strcat( sentence, article[ rand() % 5 ] );
      strcat( sentence, " " );
      strcat( sentence, noun[ rand() % 5 ] );
      cout << static_cast< char > ( toupper( sentence[ 0 ] ) )
           << &sentence[ 1 ] << ".\n";
      sentence[ 0 ] = '\0';
   }

   cout << endl;

   return 0;
}
```

```
A dog skipped to any car.
Some town ran on the boy.
A dog jumped from the dog.
One girl jumped on one town.
One dog jumped from some boy.
One girl jumped under any dog.
One car drove on some girl.
One town walked on a girl.
Some town ran on one dog.
One car walked from any town.
A boy drove over some girl.
The dog skipped under a boy.
The car drove to a girl.
Some town skipped under any car.
A boy jumped from a town.
Any car jumped under one town.
Some dog skipped from some boy.
Any town skipped to one girl.
Some girl jumped to any dog.
The car ran under one dog.
```

5.34 *(Limericks)* A limerick is a humorous five-line verse in which the first and second lines rhyme with the fifth, and the third line rhymes with the fourth. Using techniques similar to those developed in Exercise 5.33, write a C++ program that produces random limericks. Polishing this program to produce good limericks is a challenging problem, but the result will be worth the effort!

5.35 Write a program that encodes English language phrases into pig Latin. Pig Latin is a form of coded language often used for amusement. Many variations exist in the methods used to form pig Latin phrases. For simplicity, use the following algorithm:

To form a pig-Latin phrase from an English-language phrase, tokenize the phrase into words with function **strtok**. To translate each English word into a pig-Latin word, place the first letter of the English word at the end of the English word, and add the letters "**ay**." Thus the word "**jump**" becomes "**umpjay**," the word "**the**" becomes "**hetay**" and the word "**computer**" becomes "**omputercay**." Blanks between words remain as blanks. Assume that the: the English phrase consists of words separated by blanks, there are no punctuation marks and all words have two or more letters. Function **printLatinWord** should dis-

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

play each word. (*Hint:* Each time a token is found in a call to **strtok**, pass the token pointer to function **printLatinWord**, and print the pig Latin word.)

```
// Exercise 5.35 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstring>

const int SIZE = 80;

void printLatinWord( char const * const );

int main()
{
   char sentence[ SIZE ], *tokenPtr;

   cout << "Enter a sentence:\n";
   cin.getline( sentence, SIZE );

   cout << "\nThe sentence in Pig Latin is:\n";
   tokenPtr = strtok( sentence, " .,;" );

   while ( tokenPtr ) {
      printLatinWord( tokenPtr );
      tokenPtr = strtok( 0, " .,;" );

      if ( tokenPtr )
         cout << ' ';
   }

   cout << '.' << endl;

   return 0;
}

void printLatinWord( char const * const wordPtr )
{
   int len = strlen( wordPtr );
   for (int i = 1; i < len; ++i )
      cout << *( wordPtr + i );

   cout << *wordPtr << "ay";
}
```

```
Enter a sentence:
mirror mirror on the wall

The sentence in Pig Latin is:
irrormay irrormay noay hetay allway.
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

5.36 Write a program that inputs a telephone number as a string in the form **(555) 555-5555**. The program should use function **strtok** to extract the area code as a token, the first three digits of the phone number as a token, and the last four digits of the phone number as a token. The seven digits of the phone number should be concatenated into one string. The program should convert the area code string to **int** and convert the phone number string to **long**. Both the area code and the phone number should be printed.

```
// Exercise 5.36 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstring>
#include <cstdlib>

int main()
{
   const int SIZE1 = 20, SIZE2 = 10;
   char p[ SIZE1 ],
        phoneNumber[ SIZE2 ] = { '\0' }, *tokenPtr;
   int  areaCode;
   long phone;

   cout << "Enter a phone number in the form (555) 555-5555:\n";
   cin.getline( p, SIZE1 );

   areaCode = atoi( strtok( p, "()" ) );

   tokenPtr = strtok( 0, "-" );
   strcpy( phoneNumber, tokenPtr );
   tokenPtr = strtok( 0, "" );
   strcat( phoneNumber, tokenPtr );
   phone = atol( phoneNumber );

   cout << "\nThe integer area code is " << areaCode
        << "\nThe long integer phone number is " << phone << endl;

   return 0;
}
```

```
Enter a phone number in the form (555) 555-5555:
(555) 492-4195

The integer area code is 555
The long integer phone number is 4924195
```

5.37 Write a program that inputs a line of text, tokenizes the line with function **strtok** and outputs the tokens in reverse order.

```
// Exercise 5.37 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstring>

void reverseTokens( char * const );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
11
12 int main()
13 {
14    const int SIZE = 80;
15    char text[ SIZE ];
16
17    cout << "Enter a line of text:\n";
18    cin.getline( text, SIZE );
19    reverseTokens( text );
20    cout << endl;
21
22    return 0;
23 }
24
25 void reverseTokens( char * const sentence )
26 {
27    char *pointers[ 50 ], *temp;
28    int count = 0;
29
30    temp = strtok( sentence, " " );
31
32    while ( temp ) {
33       pointers[ count++ ] = temp;
34       temp = strtok( 0, " " );
35    }
36
37    cout << "\nThe tokens in reverse order are:\n";
38
39    for ( int i = count - 1; i >= 0; --i )
40       cout << pointers[ i ] << ' ';
41 }
```

```
Enter a line of text:
twinkle twinkle little star

The tokens in reverse order are:
star little twinkle twinkle
```

5.38 Use the string comparison functions discussed in Section 5.12.2 and the techniques for sorting arrays developed in Chapter 4 to write a program that alphabetizes a list of strings. Use the names of 10 or 15 towns in your area as data for your program.

```
1  // Exercise 5.38 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstring>
9
10 const int SIZE = 50;
11 void bubbleSort( char [][ SIZE ] );
12
13 int main()
14 {
15    char array[ 10 ][ SIZE ];
16    int i;
17
18    for ( i = 0; i < 10; ++i ) {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cout << "Enter a string: ";
      cin >> &array[ i ][ 0 ];
   }

   bubbleSort( array );
   cout << "\nThe strings in sorted order are:\n";

   for ( i = 0; i < 10; ++i )
      cout << &array[ i ][ 0 ] << endl;

   return 0;
}

void bubbleSort( char a[][ SIZE ] )
{
   char temp[ SIZE ];

   for ( int i = 0; i <= 8; ++i )
      for ( int j = 0; j <= 8; ++j )
         if ( strcmp( &a[ j ][ 0 ], &a[ j + 1 ][ 0 ] ) > 0 ) {
            strcpy( temp, &a[ j ][ 0 ] );
            strcpy( &a[ j ][ 0 ], &a[ j + 1 ][ 0 ] );
            strcpy(&a[ j + 1 ][ 0 ], temp );
         }
}
```

```
Enter a string: Windsor
Enter a string: Pittsford
Enter a string: Warren
Enter a string: Killington
Enter a string: Marlboro
Enter a string: Grafton
Enter a string: Middlebury
Enter a string: Barre
Enter a string: Montpelier
Enter a string: Wolcott

The strings in sorted order are:
Barre
Grafton
Killington
Marlboro
Middlebury
Montpelier
Pittsford
Warren
Windsor
Wolcott
```

5.39 Write two versions of each of the string copy and string concatenation functions in Fig. 5.29. The first version should use array subscripting, and the second version should use pointers and pointer arithmetic.

```
// Exercise 5.39 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 8  char *stringCopy1( char *, const char * );
 9  char *stringCopy2( char *, const char * );
10  char *stringNCopy1( char *, const char *, unsigned );
11  char *stringNCopy2( char *, const char *, unsigned );
12  char *stringCat1( char *, const char * );
13  char *stringCat2( char *, const char * );
14  char *stringNCat1( char *, const char *, unsigned );
15  char *stringNCat2( char *, const char *, unsigned );
16
17  int main()
18  {
19     int n = 4;
20     char string1[ 100 ], string2[ 100 ];
21
22     cout << "Enter a string: ";
23     cin >> string2;
24
25     cout << "Copied string returned from stringCopy1 is "
26          << stringCopy1( string1, string2 )
27          << "\nCopied string returned from stringCopy2 is "
28          << stringCopy2( string1, string2 );
29     cout << "\nCopied " << n << " elements returned from stringNCopy1 is "
30          << stringNCopy1( string1, string2, n );
31     cout << "\nCopied " << n << " elements returned from stringNCopy2 is "
32          << stringNCopy2(string1, string2, n);
33     cout << "\nConcatenated string returned from stringCat1 is "
34          << stringCat1( string1, string2 );
35     cout << "\nConcatenated string returned from stringCat2 is "
36          << stringCat2( string1, string2 );
37     cout << "\nConcatenated string returned from stringNCat1 is "
38          << stringNCat1( string1, string2, n );
39     cout << "\nConcatenated string returned from stringNCat2 is "
40          << stringNCat2( string1, string2, n ) << endl;
41
42     return 0;
43  }
44
45  char *stringCopy1( char *s1, const char *s2 )
46  {
47     for ( int sub = 0; s1[ sub ] = s2[ sub ]; ++sub )
48        ; // empty body
49
50     return s1;
51  }
52
53  char *stringCopy2( char *s1, const char *s2 )
54  {
55     char *ptr = s1;
56
57     for ( ; *s1 = *s2; ++s1, ++s2 )
58        ; // empty body
59
60     return ptr;
61  }
62
63  char *stringNCopy1( char *s1, const char *s2, unsigned n )
64  {
65     unsigned c;
66
67     for ( c = 0; c < n && ( s1[ c ] = s2[ c ] ); ++c )
68        ; // empty body
69
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   s1[ c ] = '\0';
   return s1;
}

char *stringNCopy2( char *s1, const char *s2, unsigned n )
{
   char *ptr = s1;

   for ( unsigned c = 0; c < n; ++c, ++s1, ++s2 )
      *s1 = *s2;

   *s1 = '\0';
   return ptr;
}

char *stringCat1( char *s1, const char *s2 )
{
   int x;

   for ( x = 0; s1[ x ] != '\0'; ++x )
      ; // empty body

   for ( int y = 0; s1[ x ] = s2[ y ]; ++x, ++y )
      ; // empty body

   return s1;
}

char *stringCat2( char *s1, const char *s2 )
{
   char *ptr = s1;

   for ( ; *s1 != '\0'; ++s1 )
      ; // empty body

   for ( ; *s1 = *s2; ++s1, ++s2 )
      ; // empty body

   return ptr;
}

char *stringNCat1( char *s1, const char *s2, unsigned n )
{
   int x;

   for ( x = 0; s1[ x ] != '\0'; ++x )
      ; // empty body

   for ( unsigned y = 0; y < n && ( s1[ x ] = s2[ y ] ); ++x, ++y )
      ; // empty body

   s1[ x ] = '\0';
   return s1;
}

char *stringNCat2( char *s1, const char *s2, unsigned n )
{
   char *ptr = s1;

   for ( ; *s1 != '\0'; ++s1 )
      ; // empty body

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   for ( unsigned c = 0 ; c < n && ( *s1 = *s2 ); ++s1, ++s2 )
      ; // empty body

   *s1 = '\0';
   return ptr;
}
```

```
Enter a string: coo
Copied string returned from stringCopy1 is coo
Copied string returned from stringCopy2 is coo
Copied 4 elements returned from stringNCopy1 is coo
Copied 4 elements returned from stringNCopy2 is coo
Concatenated string returned from stringCat1 is coocoo
Concatenated string returned from stringCat2 is coocoocoo
Concatenated string returned from stringNCat1 is coocoocoocoo
Concatenated string returned from stringNCat2 is coocoocoocoocoo
```

5.40 Write two versions of each string comparison function in Fig. 5.29. The first version should use array subscripting, and the second version should use pointers and pointer arithmetic.

```
// Exercise 5.40 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int stringCompare1( const char *, const char * );
int stringCompare2( const char *, const char * );
int stringNCompare1( const char *, const char *, unsigned );
int stringNCompare2( const char *, const char *, unsigned );

int main()
{
   char string1[ 100 ], string2[ 100 ];
   unsigned n = 3;  // number of characters to be compared

   cout << "Enter two strings: ";
   cin >> string1 >> string2;

   cout << "The value returned from stringCompare1(\"" << string1
        << "\", \"" << string2 << "\") is "
        << stringCompare1(string1, string2)
        << "\nThe value returned from stringCompare2(\"" << string1
        << "\", \"" << string2 << "\") is "
        << stringCompare2(string1, string2) << '\n';

   cout << "\nThe value returned from stringNCompare1(\"" << string1
        << "\", \"" << string2 << "\", " << n << ") is "
        << stringNCompare1(string1, string2, n)
        << "\nThe value returned from stringNCompare2(\"" << string1
        << "\", \"" << string2 << "\", " << n << ") is "
        << stringNCompare2( string1, string2, n ) << endl;

   return 0;
}

int stringCompare1( const char *s1, const char *s2 )
{
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
40    int sub;
41
42    // array subscript notation
43    for ( sub = 0; s1[ sub ] == s2[ sub ]; ++sub )
44       ; // empty statement
45
46    --sub;
47
48    if ( s1[ sub ] == '\0' && s2[ sub ] == '\0')
49       return 0;
50    else if ( s1[ sub] < s2[ sub ] )
51       return -1;
52    else
53       return 1;
54 }
55
56 int stringCompare2( const char *s1, const char *s2 )
57 {
58    // pointer notation
59    for ( ; *s1 == *s2; s1++, s2++ )
60       ; // empty statement
61
62    --s1;
63    --s2;
64
65    if ( *s1 == '\0' && *s2 == '\0' )
66       return 0;
67    else if ( *s1 < *s2 )
68       return -1;
69    else
70       return 1;
71 }
72
73 int stringNCompare1( const char *s1, const char *s2, unsigned n )
74 {
75    unsigned sub;
76
77    // array subscript notation
78    for ( sub = 0; sub < n && ( s1[ sub ] == s2[ sub ] ); sub++ )
79       ; // empty body
80
81    --sub;
82
83    if ( s1[ sub ] == s2[ sub ] )
84       return 0;
85    else if ( s1[ sub ] < s2[ sub ] )
86       return -1;
87    else
88       return 1;
89 }
90
91 int stringNCompare2( const char *s1, const char *s2, unsigned n )
92 {
93    // pointer notation
94    for ( unsigned c = 0; c < n && (*s1 == *s2); c++, s1++, s2++ )
95       ; // empty statement
96
97    --s1;
98    --s2;
99
100   if ( *s1 == *s2 )
101      return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   else if ( *s1 < *s2 )
      return -1;
   else
      return 1;
}
```

```
Enter two strings: tommy tomato
The value returned from stringCompare1("tommy", "tomato") is 1
The value returned from stringCompare2("tommy", "tomato") is 1

The value returned from stringNCompare1("tommy", "tomato", 3) is 0
The value returned from stringNCompare2("tommy", "tomato", 3) is 0
```

5.41 Write two versions of function **strlen** in Fig. 5.29. The first version should use array subscripting, and the second version should use pointers and pointer arithmetic.

```
// Exercise 5.41 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

unsigned long stringLength1( const char * );
unsigned long stringLength2( const char * );

int main()
{
   char string[ 100 ];

   cout << "Enter a string: ";
   cin >> string;

   cout << "\nAccording to stringLength1 the string length is: "
           << stringLength1( string )
           << "\nAccording to stringLength2 the string length is: "
           << stringLength2( string ) << endl;

   return 0;
}

unsigned long stringLength1( const char *sPtr )
{
   // array subscript notation
   for ( int length = 0; sPtr[ length ] != '\0'; ++length )
      ; // empty body

   return length;
}

unsigned long stringLength2( const char *sPtr )
{
   // pointer notation
   for ( int length = 0; *sPtr != '\0'; ++sPtr, ++length )
      ; // empty body

   return length;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter a string: howLongCanThisNameWithoutQuestionPossiblyBe?

According to stringLength1 the string length is: 44
According to stringLength2 the string length is: 44
```

SPECIAL SECTION: ADVANCED STRING MANIPULATION EXERCISES

The preceding exercises are keyed to the text and designed to test the reader's understanding of fundamental string manipulation concepts. This section includes a collection of intermediate and advanced string manipulation exercises. The reader should find these problems challenging, yet enjoyable. The problems vary considerably in difficulty. Some require an hour or two of program writing and implementation. Others are useful for lab assignments that might require two or three weeks of study and implementation. Some are challenging term projects.

5.42 *(Text Analysis)* The availability of computers with string manipulation capabilities has resulted in some rather interesting approaches to analyzing the writings of great authors. Much attention has been focused on whether William Shakespeare ever lived. Some scholars believe there is substantial evidence indicating that Christopher Marlowe or other authors actually penned the masterpieces attributed to Shakespeare. Researchers have used computers to find similarities in the writings of these two authors. This exercise examines three methods for analyzing texts with a computer.

a) Write a program that reads several lines of text from the keyboard and prints a table indicating the number of occurrences of each letter of the alphabet in the text. For example, the phrase

```
To be, or not to be: that is the question:
```

contains one “a,” two “b’s,” no “c’s,” etc.

b) Write a program that reads several lines of text and prints a table indicating the number of one-letter words, two-letter words, three-letter words, etc., appearing in the text. For example, the phrase

```
Whether 'tis nobler in the mind to suffer
```

contains

Word length	Occurrences
1	0
2	2
3	1
4	2 (including 'tis)
5	0
6	2
7	1

c) Write a program that reads several lines of text and prints a table indicating the number of occurrences of each different word in the text. The first version of your program should include the words in the table in the same order in which they appear in the text. For example, the lines

```
To be, or not to be: that is the question:
Whether 'tis nobler in the mind to suffer
```

contain the words “to” three times, the word “be” two times, the word “or” once, etc. A more interesting (and useful) printout should then be attempted in which the words are sorted alphabetically.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 5.42 Part A Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <iomanip>

using std::setw;

#include <cctype>

const int SIZE = 80;

int main()
{
   char letters[ 26 ] = { 0 }, text[ 3 ][ SIZE ], i;

   cout << "Enter three lines of text:\n";

   for ( i = 0; i <= 2; ++i )
      cin.getline( &text[ i ][ 0 ], SIZE );

   for ( i = 0; i <= 2; ++i )
      for ( int j = 0; text[ i ][ j ] != '\0'; ++j )
         if ( isalpha( text[ i ][ j ] ) )
            ++letters[ tolower( text[ i ][ j ] ) - 'a' ];

   cout << "\nTotal letter counts:\n";

   for ( i = 0; i <= 25; ++i )
      cout << setw( 3 ) << static_cast< char > ( 'a' + i ) << ':' << setw( 3 )
           << static_cast< int > ( letters[ i ] ) << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter three lines of text:
when the cats are away the mice will play
still waters run deep
out of sight out of mind

Total letter counts:
  a:  6
  b:  0
  c:  2
  d:  2
  e:  8
  f:  2
  g:  1
  h:  4
  i:  5
  j:  0
  k:  0
  l:  5
  m:  2
  n:  3
  o:  4
  p:  2
  q:  0
  r:  3
  s:  4
  t:  8
  u:  3
  v:  0
  w:  4
  x:  0
  y:  2
  z:  0
```

```
1  // Exercise 5.42 Part B Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstring>
9
10 int main()
11 {
12    const int SIZE = 80;
13    char text[ 3 ][ SIZE ], *temp;
14    int lengths[ 20 ] = { 0 }, i;
15
16    cout << "Enter three lines of text:\n";
17
18    for ( i = 0; i <= 2; ++i )
19       cin.getline( &text[ i ][ 0 ], SIZE );
20
21    for ( i = 0; i <= 2; ++i ) {
22       temp = strtok( &text[ i ][ 0 ], ". \n" );
23
24       while ( temp ) {
25          ++lengths[ strlen( temp ) ];
26          temp = strtok( 0, ". \n" );
27       }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
28     }
29
30     cout << '\n';
31
32     for ( i = 1; i <= 19; ++i )
33        if ( lengths[ i ] )
34           cout << lengths[ i ] << " word(s) of length " << i << endl;
35
36     return 0;
37  }
```

```
Enter three lines of text:
the five time super bowl champion dallas cowboys
americas team the dallas cowboys
the once and future champion dallas cowboys

4 word(s) of length 3
5 word(s) of length 4
1 word(s) of length 5
4 word(s) of length 6
3 word(s) of length 7
3 word(s) of length 8
```

```
1  // Exercise 5.42 Part C Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstring>
9
10 const int SIZE = 80;
11
12 int main()
13 {
14    char text[ 3 ][ SIZE ], *temp, words[ 100 ][ 20 ] = { "" };
15    int count[ 100 ] = { 0 }, i;
16
17    cout << "Enter three lines of text:\n";
18
19    for ( i = 0; i <= 2; ++i )
20       cin.getline( &text[ i ][ 0 ], SIZE );
21
22    for ( i = 0; i <= 2; ++i ) {
23       temp = strtok( &text[ i ][ 0 ], ". \n" );
24
25       while ( temp ) {
26          int j;
27
28          for ( j = 0; words[ j ][ 0 ] &&
29                      strcmp( temp, &words[ j ][ 0 ] ) != 0; ++j )
30             ;  // empty body
31
32          ++count[ j ];
33
34          if ( !words[ j ][ 0 ] )
35             strcpy( &words[ j ][ 0 ], temp );
36
37          temp = strtok( 0, ". \n" );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      }
   }

   cout << '\n';

   for ( int k = 0; words[ k ][ 0 ] != '\0' && k <= 99; ++k )
      cout << "\"" << &words[ k ][ 0 ] << "\" appeared " << count[ k ]
           << " time(s)\n";

   cout << endl;

   return 0;
}
```

```
Enter three lines of text:
lovebirds make great pets
the dallas cowboys are a great organization
peach faced lovebirds are small birds

"lovebirds" appeared 2 time(s)
"make" appeared 1 time(s)
"great" appeared 2 time(s)
"pets" appeared 1 time(s)
"the" appeared 1 time(s)
"dallas" appeared 1 time(s)
"cowboys" appeared 1 time(s)
"are" appeared 2 time(s)
"a" appeared 1 time(s)
"organization" appeared 1 time(s)
"peach" appeared 1 time(s)
"faced" appeared 1 time(s)
"small" appeared 1 time(s)
"birds" appeared 1 time(s)
```

5.43 *(Word Processing)* One important function in word-processing systems is *type justification*—the alignment of words to both the left and right margins of a page. This generates a professional-looking document that gives the appearance of being set in type rather than prepared on a typewriter. Type justification can be accomplished on computer systems by inserting blank characters between each of the words in a line so that the rightmost word aligns with the right margin.

Write a program that reads several lines of text and prints this text in type-justified format. Assume that the text is to be printed on 8-1/2-inch-wide paper, and that one-inch margins are to be allowed on both the left and right sides of the printed page. Assume that the computer prints 10 characters to the horizontal inch. Therefore, your program should print 6 1/2 inches of text, or 65 characters per line.

5.44 *(Printing Dates in Various Formats)* Dates are commonly printed in several different formats in business correspondence. Two of the more common formats are

07/21/1955 and **July 21, 1955**

Write a program that reads a date in the first format and prints that date in the second format.

```
// Exercise 5.44 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
10     const char *months[ 13 ] = { "", "January", "February", "March", "April",
11                                  "May", "June", "July", "August", "September",
12                                  "October", "November", "December" };
13     int m, d, y;
14
15     cout << "Enter a date in the form mm/dd/yy: \n";
16     cin >> m;
17     cin.ignore();
18     cin >> d;
19     cin.ignore();
20     cin >> y;
21
22     cout << "The date is: " << months[ m ] << ' ' << d << ' '
23          << ( ( y < 50 ) ? y + 2000 : y + 1900 ) << endl;
24
25     return 0;
26  }
```

```
Enter a date in the form mm/dd/yy:
6/7/00
The date is: June 7 2000
```

5.45 *(Check Protection)* Computers are frequently employed in check-writing systems such as payroll and accounts payable applications. Many strange stories circulate regarding weekly paychecks being printed (by mistake) for amounts in excess of $1 million. Weird amounts are printed by computerized check-writing systems, because of human error or machine failure. Systems designers build controls into their systems to prevent such erroneous checks from being issued.

Another serious problem is the intentional alteration of a check amount by someone who intends to cash a check fraudulently. To prevent a dollar amount from being altered, most computerized check-writing systems employ a technique called *check protection.*

Checks designed for imprinting by computer contain a fixed number of spaces in which the computer may print an amount. Suppose a paycheck contains eight blank spaces in which the computer is supposed to print the amount of a weekly paycheck. If the amount is large, then all eight of those spaces will be filled, for example,

```
1,230.60    (check amount)
--------
12345678    (position numbers)
```

On the other hand, if the amount is less than $1000, then several of the spaces would ordinarily be left blank. For example,

```
   99.87
--------
12345678
```

contains three blank spaces. If a check is printed with blank spaces, it is easier for someone to alter the amount of the check. To prevent a check from being altered, many check-writing systems insert *leading asterisks* to protect the amount as follows:

```
***99.87
--------
12345678
```

Write a program that inputs a dollar amount to be printed on a check and then prints the amount in check-protected format with leading asterisks if necessary. Assume that nine spaces are available for printing an amount.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 5.45 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setfill;
using std::setw;
using std::setprecision;
using std::setiosflags;

int main()
{
   double amount, base = 100000.0;
   int i;

   cout << "Enter check amount: ";
   cin >> amount;
   cout << "The protected amount is $";

   for ( i = 0; amount < base; ++i )
      base /= 10;

   for ( int j = 1; j <= i; ++j )
      cout << '*';

   cout << setiosflags( ios::fixed | ios::showpoint )
        << setw( 9 - i ) << setfill( '*' )
        << setprecision( 2 ) << amount << endl;

   return 0;
}
```

```
Enter check amount: 22.88
The protected amount is $****22.88
```

5.46 *(Writing the Word Equivalent of a Check Amount)* Continuing the discussion of the previous example, we reiterate the importance of designing check-writing systems to prevent alteration of check amounts. One common security method requires that the check amount be written both in numbers, and "spelled out" in words as well. Even if someone is able to alter the numerical amount of the check, it is extremely difficult to change the amount in words.

Many computerized check-writing systems do not print the amount of the check in words. Perhaps the main reason for this omission is the fact that most high-level languages used in commercial applications do not contain adequate string manipulation features. Another reason is that the logic for writing word equivalents of check amounts is somewhat involved.

Write a program that inputs a numeric check amount and writes the word equivalent of the amount. For example, the amount 112.43 should be written as

```
ONE HUNDRED TWELVE and 43/100
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 5.46 Solution
// NOTE: THIS PROGRAM ONLY HANDLES VALUES UP TO $99.99
// The program is easily modified to process larger values
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

int main()
{
   const char *digits[ 10 ] = { "", "ONE", "TWO", "THREE", "FOUR", "FIVE",
                                "SIX", "SEVEN", "EIGHT", "NINE" };
   const char *teens[ 10 ] = { "TEN", "ELEVEN", "TWELVE", "THIRTEEN",
                               "FOURTEEN", "FIFTEEN", "SIXTEEN",
                               "SEVENTEEN", "EIGHTEEN", "NINETEEN"};
   const char *tens[ 10 ] = { "", "TEN", "TWENTY", "THIRTY", "FORTY", "FIFTY",
                              "SIXTY", "SEVENTY", "EIGHTY", "NINETY" };
   int dollars, cents, digit1, digit2;

   cout << "Enter the check amount (0.00 to 99.99): ";
   cin >> dollars;
   cin.ignore();
   cin >> cents;
   cout << "The check amount in words is:\n";

   if ( dollars < 10 )
      cout << digits[ dollars ] << ' ';
   else if ( dollars < 20 )
      cout << teens[ dollars - 10 ] << ' ';
   else {
      digit1 = dollars / 10;
      digit2 = dollars % 10;

      if ( !digit2 )
         cout << tens[ digit1 ] << ' ';
      else
         cout << tens[ digit1 ] << "-" << digits[ digit2 ] << ' ';
   }

   cout << "Dollars and " << cents << "/100" << endl;

   return 0;
}
```

```
Enter the check amount (0.00 to 99.99): 72.68
The check amount in words is:
SEVENTY-TWO Dollars and 68/100
```

5.47 *(Morse Code)* Perhaps the most famous of all coding schemes is the Morse code, developed by Samuel Morse in 1832 for use with the telegraph system. The Morse code assigns a series of dots and dashes to each letter of the alphabet, each digit and a few special characters (such as period, comma, colon and semicolon). In sound-oriented systems, the dot represents a short sound, and the dash represents a long sound. Other representations of dots and dashes are used with light-oriented systems and signal-flag systems.

Separation between words is indicated by a space, or, quite simply, the absence of a dot or dash. In a sound-oriented system, a space is indicated by a short period of time during which no sound is transmitted. The international version of the Morse code appears in Fig. 5.39.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Write a program that reads an English-language phrase and encodes the phrase into Morse code. Also write a program that reads a phrase in Morse code and converts the phrase into the English-language equivalent. Use one blank between each Morse-coded letter and three blanks between each Morse-coded word.

Character	Code	Character	Code
A	.-	T	-
B	-...	U	..-
C	-.-.	V	...-
D	-..	W	.--
E	.	X	-..-
F	..-.	Y	-.--
G	--.	Z	--..
H	....		
I	..	Digits	
J	.---	1	.----
K	-.-	2	..---
L	.-..	3	...--
M	--	4	....-
N	-.	5	.....
O	---	6	-....
P	.--.	7	--...
Q	--.-	8	---..
R	.-.	9	----.
S	...	0	-----

Fig. 5.39 The letters of the alphabet as expressed in international Morse code.

5.48 *(A Metric Conversion Program)* Write a program that will assist the user with metric conversions. Your program should allow the user to specify the names of the units as strings (i.e., centimeters, liters, grams, etc. for the metric system and inches, quarts, pounds, etc., for the English system) and should respond to simple questions such as

```
"How many inches are in 2 meters?"
"How many liters are in 10 quarts?"
```

Your program should recognize invalid conversions. For example, the question

```
"How many feet in 5 kilograms?"
```

is not meaningful, because `"feet"` are units of length, while `"kilograms"` are units of weight.

A CHALLENGING STRING MANIPULATION PROJECT

5.49 *(A Crossword Puzzle Generator)* Most people have worked a crossword puzzle, but few have ever attempted to generate one. Generating a crossword puzzle is a difficult problem. It is suggested here as a string manipulation project requiring substantial sophistication and effort. There are many issues the programmer must resolve to get even the simplest crossword puzzle generator program working. For example, how does one represent the grid of a crossword puzzle inside the computer? Should one use a series of strings, or should double-subscripted arrays be used? The programmer needs a source of words (i.e., a computerized dictionary) that can be directly referenced by the program. In what form should these words be stored to facilitate the complex manipulations required by the program? The really ambitious reader will want to generate the "clues" portion of the puzzle in which the brief hints for each "across" word and each "down" word are printed for the puzzle worker. Merely printing a version of the blank puzzle itself is not a simple problem.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

6

Classes and Data Abstraction Solutions

Solutions

6.3 What is the purpose of the scope resolution operator?

ANS: The scope resolution operator is used to specify the class to which a function belongs. It also resolves the ambiguity caused by multiple classes having member functions of the same name.

6.4 Compare and contrast the notions of **`struct`** and **`class`** in C++.

ANS: In C++, the keywords **`struct`** and **`class`** are used to define types containing data members (and member functions for **`class`**es). The differences occur in the default access privileges for each. The default access for **`class`** members is **`private`** and the default access for **`struct`** members is **`public`**. The access privileges for **`class`** and **`struct`** can be specified explicitly.

6.5 Provide a constructor that is capable of using the current time from the **`time()`** function—declared in the C Standard Library header **`ctime`**—to initialize an object of the **`Time`** class.

```
// P6_05.H
#ifndef p6_05_H
#define p6_05_H
#include <iostream>

class Time {
public:
   Time();
   void setHour( int h ) { hour = ( h >= 0 && h < 24 ) ? h : 0; }
   void setMinute( int m ) { minute = ( m >= 0 && m < 60 ) ? m : 0; }
   void setSecond( int s ) { second = ( s >= 0 && s < 60 ) ? s : 0; }
   int getHour( void ) { return hour; }
   int getMinute( void ) { return minute; }
   int getSecond( void ) { return second; }
   void printStandard( void );
private:
   int hour;
   int minute;
   int second;
};

#endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// P6_5M.cpp
// member function definitions for p6_05.cpp
#include <iostream>

using std::cout;

#include <ctime>

#include "p6_05.h"

Time::Time()
{
   long int totalTime;            // time in seconds since 1970
   int currentYear = 1998 - 1970; // current year
   double totalYear;              // current time in years
   double totalDay;               // days since beginning of year
   double day;                    // current time in days
   double divisor;                // conversion divisor
   int timeShift = 7;             // time returned by time() is
                                  // given as the number of seconds
                                  // elapsed since 1/1/70 GMT.
                                  // Depending on the time zone
                                  // you are in, you must shift
                                  // the time by a certain
                                  // number of hours. For this
                                  // problem, 7 hours is the
                                  // current shift for EST.
   double tempMinute;             // Used in conversion to seconds.
   double tempSecond;             // Used to set seconds.

   totalTime = time( 0 );
   divisor = ( 60.0 * 60.0 * 24.0 * 365.0 );
   totalYear = totalTime / divisor - currentYear;
   totalDay = 365 * totalYear;    // leap years ignored
   day = totalDay - static_cast< int >( totalDay );
   tempMinute = totalDay * 24 * 60;
   setHour( day * 24 + timeShift );
   setMinute( ( day * 24 - static_cast< int >( day * 24 ) ) * 60 );
   tempMinute -= static_cast< int > ( tempMinute ) * 60;
   tempSecond = tempMinute;
   setSecond( tempSecond );
}

void Time::printStandard()
{
   cout << ( ( hour % 12 == 0 ) ? 12 : hour % 12 ) << ':'
        << ( minute < 10 ? "0" : "" ) << minute << ':'
        << ( second < 10 ? "0" : "" ) << second << '\n';
}
```

```
// driver for p6_05.cpp
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;
#include "p6_05.h"

int main()
{
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   Time t;

   t.printStandard();

   return 0;
}
```

```
11:26:00
```

6.6 Create a class called **Complex** for performing arithmetic with complex numbers. Write a driver program to test your class. Complex numbers have the form

```
realPart + imaginaryPart * i
```

where ***i*** is

$\sqrt{-1}$

Use **double** variables to represent the **private** data of the class. Provide a constructor function that enables an object of this class to be initialized when it is declared. The constructor should contain default values in case no initializers are provided. Provide **public** member functions for each of the following:

a) Addition of two **Complex** numbers: The real parts are added together and the imaginary parts are added together.
b) Subtraction of two **Complex** numbers: The real part of the right operand is subtracted from the real part of the left operand and the imaginary part of the right operand is subtracted from the imaginary part of the left operand.
c) Printing **Complex** numbers in the form **(a, b)** where **a** is the real part and **b** is the imaginary part.

```
// P6_06.H
#ifndef p6_06_H
#define p6_06_H

class Complex {
public:
   Complex( double = 0.0, double = 0.0 ); // default constructor
   void addition( const Complex & );
   void subtraction( const Complex & );
   void printComplex( void );
   void setComplexNumber( double, double );
private:
   double realPart;
   double imaginaryPart;
};

#endif
```

```
// p6_06M.cpp
// member function definitions for p6_06.cpp
#include <iostream>

using std::cout;

#include "p6_06.h"

Complex::Complex( double real, double imaginary )
  { setComplexNumber( real, imaginary ); }

void Complex::addition( const Complex &a )
{
   realPart += a.realPart;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   imaginaryPart += a.imaginaryPart;
}

void Complex::subtraction( const Complex &s )
{
   realPart -= s.realPart;
   imaginaryPart -= s.imaginaryPart;
}

void Complex::printComplex( void )
  { cout << '(' << realPart << ", " << imaginaryPart << ')'; }

void Complex::setComplexNumber( double rp, double ip )
{
   realPart = rp;
   imaginaryPart = ip;
}
```

```
// driver for p6_06.cpp
#include <iostream>

using std::cout;
using std::endl;

#include "p6_06.h"

int main()
{
   Complex b( 1, 7 ), c( 9, 2 );

   b.printComplex();
   cout << " + ";
   c.printComplex();
   cout << " = ";
   b.addition( c );
   b.printComplex();

   cout << '\n';
   b.setComplexNumber( 10, 1 ); // reset realPart and imaginaryPart
   c.setComplexNumber( 11, 5 );
   b.printComplex();
   cout << " - ";
   c.printComplex();
   cout << " = ";
   b.subtraction( c );
   b.printComplex();
   cout << endl;

   return 0;
}
```

```
(1, 7) + (9, 2) = (10, 9)
(10, 1) - (11, 5) = (-1, -4)
```

6.7 Create a class called **Rational** for performing arithmetic with fractions. Write a driver program to test your class.

Use integer variables to represent the **private** data of the class—the numerator and the denominator. Provide a constructor function that enables an object of this class to be initialized when it is declared. The constructor should contain default values in case no initializers are provided and should store the fraction in reduced form (i.e., the fraction

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

$$\frac{2}{4}$$

would be stored in the object as 1 in the numerator and 2 in the denominator). Provide **public** member functions for each of the following:

a) Addition of two **Rational** numbers. The result should be stored in reduced form.
b) Subtraction of two **Rational** numbers. The result should be stored in reduced form.
c) Multiplication of two **Rational** numbers. The result should be stored in reduced form.
d) Division of two **Rational** numbers. The result should be stored in reduced form.
e) Printing **Rational** numbers in the form **a/b** where **a** is the numerator and **b** is the denominator.
f) Printing **Rational** numbers in double floating-point format.

```
// P6_07.H
#ifndef P6_07_H
#define P6_07_H

class Rational {
public:
   Rational( int = 0, int = 1 );  // default constructor
   Rational addition( const Rational & );
   Rational subtraction( const Rational & );
   Rational multiplication( const Rational & );
   Rational division( Rational & );
   void printRational( void );
   void printRationalAsDouble( void );
private:
   int numerator;
   int denominator;
   void reduction( void );   // utility function
};

#endif
```

```
// P6_07M.cpp
// member function definitions for p6_07.cpp
#include <iostream>

using std::cout;

#include "p6_07.h"

Rational::Rational( int n, int d )
{
   numerator = n;
   denominator = d;
}

Rational Rational::addition( const Rational &a )
{
   Rational t;

   t.numerator = a.numerator * denominator;
   t.numerator += a.denominator * numerator;
   t.denominator = a.denominator * denominator;
   t.reduction();

   return t;
}

Rational Rational::subtraction( const Rational &s )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
48  {
49     Rational t;
50
51     t.numerator = s.denominator * numerator;
52     t.numerator -= denominator * s.numerator;
53     t.denominator = s.denominator * denominator;
54     t.reduction();
55
56     return t;
57  }
58
59  Rational Rational::multiplication( const Rational &m )
60  {
61     Rational t;
62
63     t.numerator = m.numerator * numerator;
64     t.denominator = m.denominator * denominator;
65     t.reduction();
66
67     return t;
68  }
69
70  Rational Rational::division( Rational &v )
71  {
72     Rational t;
73
74     t.numerator = v.denominator * numerator;
75     t.denominator = denominator * v.numerator;
76     t.reduction();
77
78     return t;
79  }
80
81  void Rational::printRational( void )
82  {
83     if ( denominator == 0 )
84        cout << "\nDIVIDE BY ZERO ERROR!!!" << '\n';
85     else if ( numerator == 0 )
86        cout << 0;
87     else
88        cout << numerator << '/' << denominator;
89  }
90
91  void Rational::printRationalAsDouble( void )
92     {  cout << static_cast< double >( numerator ) / denominator; }
93
94  void Rational::reduction( void )
95  {
96     int largest;
97     largest = numerator > denominator ? numerator : denominator;
98
99     int gcd = 0;  // greatest common divisor
100
101    for ( int loop = 2; loop <= largest; ++loop )
102       if ( numerator % loop == 0 && denominator % loop == 0 )
103          gcd = loop;
104
105    if (gcd != 0) {
106       numerator /= gcd;
107       denominator /= gcd;
108    }
109 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// driver for P6_07.cpp
#include <iostream>

using std::cout;
using std::endl;

#include "p6_07.h"

int main()
{
   Rational c( 1, 3 ), d( 7, 8 ), x;

   c.printRational();
   cout << " + ";
   d.printRational();
   x = c.addition( d );
   cout << " = ";
   x.printRational();
   cout << '\n';
   x.printRational();
   cout << " = ";
   x.printRationalAsDouble();
   cout << "\n\n";

   c.printRational();
   cout << " - ";
   d.printRational();
   x = c.subtraction( d );
   cout << " = ";
   x.printRational();
   cout << '\n';
   x.printRational();
   cout << " = ";
   x.printRationalAsDouble();
   cout << "\n\n";

   c.printRational();
   cout << " x ";
   d.printRational();
   x = c.multiplication( d );
   cout << " = ";
   x.printRational();
   cout << '\n';
   x.printRational();
   cout << " = ";
   x.printRationalAsDouble();
   cout << "\n\n";

   c.printRational();
   cout << " / ";
   d.printRational();
   x = c.division( d );
   cout << " = ";
   x.printRational();
   cout << '\n';
   x.printRational();
   cout << " = ";
   x.printRationalAsDouble();
   cout << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
1/3 + 7/8 = 29/24
29/24 = 1.20833

1/3 - 7/8 = -13/24
-13/24 = -0.541667

1/3 x 7/8 = 7/24
7/24 = 0.291667

1/3 / 7/8 = 8/21
8/21 = 0.380952
```

6.8 Modify the **Time** class of Fig. 6.10 to include a **tick** member function that increments the time stored in a **Time** object by one second. The **Time** object should always remain in a consistent state. Write a driver program that tests the **tick** member function in a loop that prints the time in standard format during each iteration of the loop to illustrate that the **tick** member function works correctly. Be sure to test the following cases:

a) Incrementing into the next minute.
b) Incrementing into the next hour.
c) Incrementing into the next day (i.e., 11:59:59 PM to 12:00:00 AM).

```
1  // P6_08.H
2  #ifndef p6_08_H
3  #define p6_08_H
4
5  class Time {
6  public:
7     Time( int = 0, int = 0, int = 0 );
8     void setTime( int, int, int );
9     void setHour( int );
10    void setMinute( int );
11    void setSecond( int );
12    int getHour( void );
13    int getMinute( void );
14    int getSecond( void );
15    void printStandard( void );
16    void tick( void );
17 private:
18    int hour;
19    int minute;
20    int second;
21 };
22
23 #endif
```

```
24 // P6_08M.cpp
25 // member function definitions for p6_08.cpp
26 #include <iostream>
27
28 using std::cout;
29
30 #include "p6_08.h"
31
32 Time::Time( int hr, int min, int sec ) { setTime( hr, min, sec ); }
33
34 void Time::setTime( int h, int m, int s )
35 {
36    setHour( h );
37    setMinute( m );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
38    setSecond( s );
39 }
40
41 void Time::setHour( int h ) { hour = ( h >= 0 && h < 24 ) ? h : 0; }
42
43 void Time::setMinute( int m )
44 {
45    minute = ( m >= 0 && m < 60 ) ? m : 0;
46 }
47
48 void Time::setSecond( int s )
49 {
50    second = ( s >= 0 && s < 60 ) ? s : 0;
51 }
52
53 int Time::getHour( void ) { return hour; }
54
55 int Time::getMinute( void ) { return minute; }
56
57 int Time::getSecond( void ) { return second; }
58
59 void Time::printStandard( void )
60 {
61    cout << ( ( hour % 12 == 0 ) ? 12 : hour % 12 ) << ':'
62         << ( minute < 10 ? "0" : "" ) << minute << ':'
63         << ( second < 10 ? "0" : "" ) << second
64         << ( hour < 12 ? " AM" : " PM" );
65 }
66
67 void Time::tick( void )
68 {
69    setSecond( getSecond() + 1 );
70
71    if ( getSecond() == 0 ) {
72       setMinute( getMinute() + 1 );
73
74       if ( getMinute() == 0 )
75          setHour( getHour() + 1 );
76    }
77 }
```

```
78 // driver for p6_08.cpp
79 #include <iostream>
80
81 using std::cout;
82 using std::endl;
83
84 #include "p6_08.h"
85
86 const int MAX_TICKS = 3000;
87
88 main()
89 {
90    Time t;
91
92    t.setTime( 23, 59, 57 );
93
94    for ( int ticks = 1; ticks < MAX_TICKS; ++ticks ) {
95       t.printStandard();
96       cout << endl;
97       t.tick();
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
98     }
99
100    return 0;
101 }
```

```
11:59:57 PM
.
.
.
.
12:49:50 AM
12:49:51 AM
12:49:52 AM
12:49:53 AM
12:49:54 AM
12:49:55 AM
```

6.9 Modify the **Date** class of Fig. 6.12 to perform error checking on the initializer values for data members **month**, **day** and **year**. Also, provide a member function **nextDay** to increment the day by one. The **Date** object should always remain in a consistent state. Write a driver program that tests the **nextDay** function in a loop that prints the date during each iteration of the loop to illustrate that the **nextDay** function works correctly. Be sure to test the following cases:

a) Incrementing into the next month.
b) Incrementing into the next year.

```
1  // P6_09.H
2  #ifndef p6_09_H
3  #define p6_09_H
4
5  class Date {
6  public:
7     Date( int = 1, int = 1, int = 1900 );  // default constructor
8     void print( void );
9     void setDate( int, int, int );
10    void setMonth( int );
11    void setDay( int );
12    void setYear( int );
13    int getMonth( void );
14    int getDay( void );
15    int getYear( void );
16    bool leapYear( void );
17    int monthDays( void );
18    void nextDay( void );
19 private:
20    int month;
21    int day;
22    int year;
23 };
24
25 #endif
```

```
26 // p6_09M.cpp
27 // member function definitions for p6_09.cpp
28 #include <iostream>
29
30 using std::cout;
31
32 #include "p6_09.h"
33
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
34 Date::Date( int m, int d, int y ) { setDate( m, d, y ); }
35
36 int Date::getDay() { return day; }
37
38 int Date::getMonth() { return month; }
39
40 int Date::getYear() { return year; }
41
42 void Date::setDay( int d )
43 {
44    if ( month == 2 && leapYear() )
45       day = ( d <= 29 && d >= 1 ) ? d : 1;
46    else
47       day = ( d <= monthDays() && d >= 1 ) ? d : 1;
48 }
49
50 void Date::setMonth( int m ) { month = m <= 12 && m >= 1 ? m : 1; }
51
52 void Date::setYear( int y )
53 {
54    year = y <= 2000 && y >= 1900 ? y : 1900;
55 }
56
57 void Date::setDate( int mo, int dy, int yr )
58 {
59    setMonth( mo );
60    setDay( dy );
61    setYear( yr );
62 }
63
64 void Date::print()
65    { cout << month << '-' << day << '-' << year << '\n'; }
66
67 void Date::nextDay()
68 {
69    setDay( day + 1 );
70
71    if ( day == 1 ) {
72       setMonth( month + 1 );
73
74       if ( month == 1 )
75          setYear( year + 1 );
76    }
77 }
78
79 bool Date::leapYear( void )
80 {
81    if ( year % 400 == 0 || ( year % 4 == 0 && year % 100 != 0 ) )
82          return true;
83       else
84          return false;    // not a leap year
85 }
86
87 int Date::monthDays( void )
88 {
89    const int days[ 12 ] = { 31, 28, 31, 30, 31, 30,
90                             31, 31, 30, 31, 30, 31 };
91
92    return month == 2 && leapYear() ? 29 : days[ month - 1 ];
93 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// driver for p6_09.cpp
#include <iostream>

using std::cout;
using std::endl;

#include "p6_09.h"

int main()
{
   const int MAXDAYS = 160;
   Date d( 9, 2, 1998 );

   for ( int loop = 1; loop <= MAXDAYS; ++loop ) {
      d.print();
      d.nextDay();
   }

   cout << endl;

   return 0;
}
```

```
9-2-1998
9-3-1998
.
.
.
2-5-1999
2-6-1999
2-7-1999
2-8-1999
```

6.10 Combine the modified **Time** class of Exercise 6.8 and the modified **Date** class of Exercise 6.9 into one class called **DateAndTime** (in Chapter 9 we will discuss inheritance, which will enable us to accomplish this task quickly without modifying the existing class definitions). Modify the **tick**s function to call the **nextDay** function if the time is incremented into the next day. Modify function **printStandard** and **printMilitary** to output the date in addition to the time. Write a driver program to test the new class **DateAndTime**. Specifically, test incrementing the time into the next day.

```
// P6_10.H
#ifndef p6_10_H
#define p6_10_H

class DateAndTime {
public:
   DateAndTime( int = 1, int = 1, int = 1900,
                int = 0, int = 0, int = 0 );
   void setDate( int, int, int );
   void setMonth( int );
   void setDay( int );
   void setYear( int );
   int getMonth( void );
   int getDay( void );
   int getYear( void );
   void nextDay( void );
   void setTime( int, int, int );
   void setHour( int );
   void setMinute( int );
   void setSecond( int );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
21    int getHour( void );
22    int getMinute( void );
23    int getSecond( void );
24    void printStandard( void );
25    void printMilitary( void );
26    int monthDays( void );
27    void tick( void );
28    bool leapYear( void );
29 private:
30    int month;
31    int day;
32    int year;
33    int hour;
34    int minute;
35    int second;
36 };
37
38 #endif
```

```
39 // P6_10M.cpp
40 // member function definitions for p6_10.cpp
41 #include <iostream>
42
43 using std::cout;
44 using std::endl;
45
46 #include "p6_10.h"
47
48 DateAndTime::DateAndTime( int m, int d, int y, int hr,
49                           int min, int sec )
50 {
51    setDate( m, d, y );
52    setTime( hr, min, sec );
53 }
54
55 void DateAndTime::setDate( int mo, int dy, int yr )
56 {
57    setMonth( mo );
58    setDay( dy );
59    setYear( yr );
60 }
61
62 int DateAndTime::getDay( void ) { return day; }
63
64 int DateAndTime::getMonth( void ) { return month; }
65
66 int DateAndTime::getYear( void ) { return year; }
67
68 void DateAndTime::setDay( int d )
69 {
70    if ( month == 2 && leapYear() )
71       day = ( d <= 29 && d >= 1 ) ? d : 1;
72    else
73       day = ( d <= monthDays() && d >= 1 ) ? d : 1;
74 }
75
76 void DateAndTime::setMonth( int m )
77    { month = m <= 12 && m >= 1 ? m : 1; }
78
79 void DateAndTime::setYear( int y )
80    { year = y <= 2000 && y >= 1900 ? y : 1900; }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
81
82 void DateAndTime::nextDay( void )
83 {
84    setDay( day + 1 );
85
86    if ( day == 1 ) {
87       setMonth( month + 1 );
88
89       if ( month == 1 )
90          setYear( year + 1 );
91    }
92 }
93
94 void DateAndTime::setTime( int hr, int min, int sec )
95 {
96    setHour( hr );
97    setMinute( min );
98    setSecond( sec );
99 }
100
101 void DateAndTime::setHour( int h )
102 {
103    hour = ( h >= 0 && h < 24 ) ? h : 0;
104 }
105
106 void DateAndTime::setMinute( int m )
107 {
108    minute = ( m >= 0 && m < 60 ) ? m : 0;
109 }
110
111 void DateAndTime::setSecond( int s )
112 {
113    second = ( s >= 0 && s < 60 ) ? s : 0;
114 }
115
116 int DateAndTime::getHour( void ) { return hour; }
117
118 int DateAndTime::getMinute( void ) { return minute; }
119
120 int DateAndTime::getSecond( void ) { return second; }
121
122 void DateAndTime::printStandard( void )
123 {
124    cout << ( ( hour % 12 == 0 ) ? 12 : hour % 12 ) << ':'
125         << ( minute < 10 ? "0" : "" ) << minute << ':'
126         << ( second < 10 ? "0" : "" ) << second
127         << ( hour < 12 ? " AM " : " PM " )
128         << month << '-' << day << '-' << year << endl;
129 }
130
131 void DateAndTime::printMilitary( void )
132 {
133    cout << ( hour < 10 ? "0" : "" ) << hour << ':'
134         << ( minute < 10 ? "0" : "" ) << minute << ':'
135         << ( second < 10 ? "0" : "" ) << second << "    "
136         << month << '-' << day << '-' << year << endl;
137 }
138
139 void DateAndTime::tick( void )
140 {
141    setSecond( second + 1 );
142
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
143    if ( second == 0 ) {
144       setMinute( minute + 1 );
145
146       if ( minute == 0 ) {
147          setHour( hour + 1 );
148
149          if ( hour == 0 )
150             nextDay();
151       }
152    }
153 }
154
155 bool DateAndTime::leapYear( void )
156 {
157    if ( year % 400 == 0 || ( year % 4 == 0 && year % 100 != 0 ) )
158          return true;
159       else
160          return false;    // not a leap year
161 }
162
163 int DateAndTime::monthDays( void )
164 {
165    const int days[ 12 ] = { 31, 28, 31, 30, 31, 30,
166                             31, 31, 30, 31, 30, 31 };
167
168    return ( month == 2 && leapYear() ) ? 29 : days[ ( month - 1 ) ];
169 }
```

```
170 // driver for p6_10.cpp
171 #include <iostream>
172
173 using std::cout;
174 using std::endl;
175
176 #include "p6_10.h"
177
178 int main()
179 {
180    const int MAXTICKS = 3000;
181
182    DateAndTime d( 3, 2, 1998, 23, 50, 0 );
183
184    for ( int ticks = 1; ticks <= MAXTICKS; ++ticks ) {
185       cout << "Military time: ";
186       d.printMilitary();
187       cout << "Standard time: ";
188       d.printStandard();
189       d.tick();
190    }
191
192    cout << endl;
193
194    return 0;
195 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Military time: 23:50:00    3-2-1998
Standard time: 11:50:00 PM 3-2-1998
.
.
.
Standard time: 12:39:56 AM 3-3-1998
Military time: 00:39:57    3-3-1998
Standard time: 12:39:57 AM 3-3-1998
Military time: 00:39:58    3-3-1998
Standard time: 12:39:58 AM 3-3-1998
Military time: 00:39:59    3-3-1998
Standard time: 12:39:59 AM 3-3-1998
```

6.11 Modify the *set* functions in the program of Fig. 6.10 to return appropriate error values if an attempt is made to *set* a data member of an object of class **Time** to an invalid value.

```
// P6_11.H
#ifndef P6_11_H
#define P6_11_H

class Time {
public:
   Time( int = 0, int = 0, int = 0 );
   void setTime( int, int, int );
   void setHour( int );
   void setMinute( int );
   void setSecond( int );
   void setInvalidTime( int t ) { invalidTime = t; }
   int getHour( void ) { return hour; }
   int getMinute( void ) { return minute; }
   int getSecond( void ) { return second; }
   int getInvalidTime( void ) { return invalidTime; }
   void printMilitary( void );
   void printStandard( void );
private:
   int hour;
   int minute;
   int second;
   int invalidTime;   // set if an invalid time is attempted
};

#endif
```

```
// P6_11M.cpp
// member function defintions for p6_11.cpp
#include <iostream>

using std::cout;

#include "p6_11.h"

Time::Time( int hr, int min, int sec )
   { setTime( hr, min, sec ); }

void Time::setTime( int h, int m, int s )
{
   setHour( h );
   setMinute( m );
   setSecond( s );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
43  }
44
45  void Time::setHour( int hr )
46  {
47     if ( hr >= 0 && hr < 24 ) {
48        hour = hr;
49        setInvalidTime( 1 );  // hour is valid
50     }
51     else {
52        hour = 0;
53        setInvalidTime( 0 );  // hour is invalid
54     }
55  }
56
57  void Time::setMinute( int min )
58  {
59     if ( min >= 0 && min < 60 ) {
60        minute = min;
61        setInvalidTime( 1 );  // minute is valid
62     }
63     else {
64        minute = 0;
65        setInvalidTime( 0 );  // minute is invalid
66     }
67  }
68
69  void Time::setSecond( int sec )
70  {
71     if ( sec >= 0 && sec < 60 ) {
72        second = sec;
73        setInvalidTime( 1 );  // second is valid
74     }
75     else {
76        second = 0;
77        setInvalidTime( 0 );  // second is invalid
78     }
79  }
80
81  void Time::printMilitary( void )
82  {
83     cout << ( hour < 10 ? "0" : "" ) << hour << ':'
84          << ( minute < 10 ? "0" : "" ) << minute << ':'
85          << ( second < 10 ? "0" : "" ) << second;
86  }
87
88  void Time::printStandard( void )
89  {
90     cout << ( ( hour % 12 == 0 ) ? 12 : hour % 12 ) << ':'
91          << ( minute < 10 ? "0": "" ) << minute << ':'
92          << ( second < 10 ? "0": "" ) << second
93          << ( hour < 12 ? " AM" : " PM" );
94  }
```

```
95  // driver for p6_11.cpp
96  #include <iostream>
97
98  using std::cout;
99  using std::endl;
100
101 #include "p6_11.h"
102
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
int main()
{
   Time t1( 17, 34, 25 ), t2( 99, 345, -897 );

   // all t1 object's times are valid
   if ( !t1.getInvalidTime() )
      cout << "Error: invalid time setting(s) attempted." << '\n'
           << "Invalid setting(s) changed to zero." << '\n';

   t1.printStandard();

   // object t2 has invalid time settings
   if ( !t2.getInvalidTime() )
      cout << "\nError: invalid time setting(s) attempted.\n"
           << "Invalid setting(s) changed to zero.\n";

   t2.printMilitary();
   cout << endl;

   return 0;
}
```

```
5:34:25 PM
Error: invalid time setting(s) attempted.
Invalid setting(s) changed to zero.
00:00:00
```

6.12 Create a class **Rectangle**. The class has attributes **length** and **width**, each of which defaults to 1. It has member functions that calculate the **perimeter** and the **area** of the rectangle. It has *set* and *get* functions for both **length** and **width**. The *set* functions should verify that **length** and **width** are each floating-point numbers larger than 0.0 and less than 20.0.

```
// P6_12.H
#ifndef P6_12_H
#define P6_12_H

class Rectangle {
public:
   Rectangle( double = 1.0, double = 1.0 );
   double perimeter( void );
   double area( void );
   void setWidth( double w );
   void setLength( double l );
   double getWidth( void );
   double getLength( void );
private:
   double length;
   double width;
};

#endif
```

```
// P6_12M.cpp
// member function definitions for p6_12.cpp
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
27  using std::ios;
28
29
30  #include "p6_12.h"
31
32  Rectangle::Rectangle( double w, double l )
33  {
34     setWidth(w);
35     setLength(l);
36  }
37
38  double Rectangle::perimeter( void )
39  {
40     return 2 * ( width + length );
41  }
42
43  double Rectangle::area( void )
44  {
45     return width * length;
46  }
47
48  void Rectangle::setWidth( double w )
49  {
50     width = w > 0 && w < 20.0 ? w : 1.0;
51  }
52
53  void Rectangle::setLength( double l )
54  {
55     length = l > 0 && l < 20.0 ? l : 1.0;
56  }
57
58  double Rectangle::getWidth( void ) { return width; }
59
60  double Rectangle::getLength( void ) { return length; }
```

```
61  // driver for p6_12.cpp
62
63  #include "p6_12.h"
64
65  int main()
66  {
67     Rectangle a, b( 4.0, 5.0 ), c( 67.0, 888.0 );
68
69     cout << setiosflags( ios::fixed | ios::showpoint );
70     cout << setprecision( 1 );
71
72     // output Rectangle a
73     cout << "a: length = " << a.getLength()
74             << "; width = " << a.getWidth()
75             << "; perimeter = " << a.perimeter() << "; area = "
76             << a.area() << '\n';
77
78     // output Rectangle b
79     cout << "b: length = " << b.getLength()
80             << "; width = " << b.getWidth()
81             << "; perimeter = " << b.perimeter() << "; area = "
82             << b.area() << '\n';
83
84     // output Rectangle c; bad values attempted
85     cout << "c: length = " << c.getLength()
86             << "; width = " << c.getWidth()
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
            << "; perimeter = " << c.perimeter() << "; area = "
            << c.area() << endl;

   return 0;
}
```

```
a: length = 1.0; width = 1.0; perimeter = 4.0; area = 1.0
b: length = 5.0; width = 4.0; perimeter = 18.0; area = 20.0
c: length = 1.0; width = 1.0; perimeter = 4.0; area = 1.0
```

6.13 Create a more sophisticated **Rectangle** class than the one you created in Exercise 6.12. This class stores only the Cartesian coordinates of the four corners of the rectangle. The constructor calls a *set* function that accepts four sets of coordinates and verifies that each of these is in the first quadrant with no single *x* or *y* coordinate larger than 20.0. The *set* function also verifies that the supplied coordinates do, in fact, specify a rectangle. Member functions calculate the **length**, **width**, **perimeter** and **area**. The length is the larger of the two dimensions. Include a predicate function **square** that determines if the rectangle is a square.

```
// P6_13.H
#ifndef P6_13_H
#define P6_13_H

class Rectangle {
public:
   Rectangle( double *, double *, double *, double * );
   void setCoord( double *, double *, double *, double * );
   void perimeter( void );
   void area( void );
   void square( void );
private:
   double point1[ 2 ];
   double point2[ 2 ];
   double point3[ 2 ];
   double point4[ 2 ];
};

#endif
```

```
// P6_13M.cpp
// member function definitions for p6_13.cpp
#include <iostream>

using std::cout;
using std::ios;

#include <iomanip>

using std::setprecision;
using std::setiosflags;

#include <cmath>

#include "p6_13.h"

Rectangle::Rectangle( double *a, double *b,
                      double *c, double *d )
   { setCoord( a, b, c, d ); }

void Rectangle::setCoord( double *p1, double *p2,
                          double *p3, double *p4 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   // Arrangement of points
   // p4.........p3
   //  .         .
   //  .         .
   // p1.........p2

   const int x = 0, y = 1;  // added for clarity

   // validate all points
   point1[ x ] = ( p1[ x ] > 20.0 || p1[ x ] < 0.0 )? 0.0 : p1[ x ];
   point1[ y ] = ( p1[ y ] > 20.0 || p1[ y ] < 0.0 )? 0.0 : p1[ y ];
   point2[ x ] = ( p2[ x ] > 20.0 || p2[ x ] < 0.0 )? 0.0 : p2[ x ];
   point2[ y ] = ( p2[ y ] > 20.0 || p2[ y ] < 0.0 )? 0.0 : p2[ y ];
   point3[ x ] = ( p3[ x ] > 20.0 || p3[ x ] < 0.0 )? 0.0 : p3[ x ];
   point3[ y ] = ( p3[ y ] > 20.0 || p3[ y ] < 0.0 )? 0.0 : p3[ y ];
   point4[ x ] = ( p4[ x ] > 20.0 || p4[ x ] < 0.0 )? 0.0 : p4[ x ];
   point4[ y ] = ( p4[ y ] > 20.0 || p4[ y ] < 0.0 )? 0.0 : p4[ y ];

   // verify that points form a rectangle
   if ( p1[ y ] == p2[ y ] && p1[ x ] ==
        p4[ x ] && p2[ x ] == p3[ x ] && p3[ y ] == p4[ y ] )
   {

      perimeter();
      area();
      square();
   }
   else
      cout << "Coordinates do not form a rectangle!\n";
}

void Rectangle::perimeter( void )
{
   double l = fabs( point4[ 1 ] - point1[ 1 ] ),
          w = fabs( point2[ 0 ] - point1[ 0 ] );

   cout << setiosflags( ios::fixed | ios::showpoint )
           << "length = " << setprecision( 1 ) << ( l > w ? l : w )
           << '\t' << "width = " << ( l > w ? w : l )
           << "\nThe perimeter is: " << 2 * ( w + l ) << '\n'
           << resetiosflags( ios::fixed | ios::showpoint );
}

void Rectangle::area( void )
{
   double l = fabs( point4[ 1 ] - point1[ 1 ] ),
          w = fabs( point2[ 0 ] - point1[ 0 ] );

   cout << setiosflags( ios::fixed | ios::showpoint )
           << "The area is: " << setprecision( 1 ) << w * l
           << resetiosflags( ios::fixed | ios::showpoint )
           << "\n\n" ;
}

void Rectangle::square( void )
{
   const int x = 0, y = 1;   // added for clarity

   if ( fabs( point4[ y ] - point1[ y ] ) ==
        fabs( point2[ x ] - point1[ x ] ) )
      cout << "The rectangle is a square.\n\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}
```

```
// driver for p6_13.cpp

#include "p6_13.h"

int main()
{
   double w[ 2 ] = { 1.0, 1.0 }, x[ 2 ] = { 5.0, 1.0 },
          y[ 2 ] = { 5.0, 3.0 }, z[ 2 ] = { 1.0, 3.0 },
          j[ 2 ] = { 0.0, 0.0 }, k[ 2 ] = { 1.0, 0.0 },
          m[ 2 ] = { 1.0, 1.0 }, n[ 2 ] = { 0.0, 1.0 },
          v[ 2 ] = { 99.0, -2.3 };
   Rectangle a( z, y, x, w ), b( j, k, m, n ),
             c( w, x, m, n ), d( v, x, y, z );

   return 0;
}
```

```
length = 4.0    width = 2.0
The perimeter is: 12.0
The area is: 8.0

length = 1.0    width = 1.0
The perimeter is: 4.0
The area is: 1.0

The rectangle is a square.

Coordinates do not form a rectangle!
Coordinates do not form a rectangle!
```

6.14 Modify the **Rectangle** class of Exercise 6.13 to include a **draw** function that displays the rectangle inside a 25-by-25 box enclosing the portion of the first quadrant in which the rectangle resides. Include a **setFillCharacter** function to specify the character out of which the body of the rectangle will be drawn. Include a **setPerimeterCharacter** function to specify the character that will be used to draw the border of the rectangle. If you feel ambitious, you might include functions to scale the size of the rectangle, rotate it, and move it around within the designated portion of the first quadrant.

```
// P6_14.H
#ifndef P6_14_H
#define P6_14_H

class Rectangle {
public:
   Rectangle( double *, double *, double *, double *, char, char );
   void setCoord( double *, double *, double *, double * );
   void perimeter( void );
   void area( void );
   void draw( void );
   void square( void );
   void setFillCharacter( char c ) { fillChar = c; }
   void setPerimeterCharacter( char c ) { periChar = c;}
   bool isValid( void ) { return valid; }
   void setValid( bool v ) { valid = v; }
private:
   double point1[ 2 ];
   double point2[ 2 ];
   double point3[ 2 ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
21     double point4[ 2 ];
22     char fillChar;
23     char periChar;
24     bool valid;
25  };
26
27  #endif
```

```
28  // P6_14M.cpp
29  // member function definitions for p6_14.cpp
30  #include <iostream>
31
32  using std::cout;
33  using std::ios;
34
35  #include <iomanip>
36
37  using std::setprecision;
38  using std::setiosflags;
39  using std::resetiosflags;
40
41  #include <cmath>
42
43  #include "p6_14.h"
44
45  Rectangle::Rectangle( double *a, double *b, double *c, double *d,
46                        char x, char y )
47  {
48     setCoord( a, b, c, d );
49     setFillCharacter( x );
50     setPerimeterCharacter( y );
51  }
52
53  void Rectangle::setCoord( double *p1, double *p2,
54                            double *p3, double *p4 )
55  {
56     // Arrangement of points
57     // p4.........p3
58     //  .         .
59     //  .         .
60     // p1.........p2
61
62     const int x = 0, y = 1;  // added for clarity
63
64     // validate all points
65     point1[ x ] = ( p1[ x ] > 20.0 || p1[ x ] < 0.0 )? 0.0 : p1[ x ];
66     point1[ y ] = ( p1[ y ] > 20.0 || p1[ y ] < 0.0 )? 0.0 : p1[ y ];
67     point2[ x ] = ( p2[ x ] > 20.0 || p2[ x ] < 0.0 )? 0.0 : p2[ x ];
68     point2[ y ] = ( p2[ y ] > 20.0 || p2[ y ] < 0.0 )? 0.0 : p2[ y ];
69     point3[ x ] = ( p3[ x ] > 20.0 || p3[ x ] < 0.0 )? 0.0 : p3[ x ];
70     point3[ y ] = ( p3[ y ] > 20.0 || p3[ y ] < 0.0 )? 0.0 : p3[ y ];
71     point4[ x ] = ( p4[ x ] > 20.0 || p4[ x ] < 0.0 )? 0.0 : p4[ x ];
72     point4[ y ] = ( p4[ y ] > 20.0 || p4[ y ] < 0.0 )? 0.0 : p4[ y ];
73
74     // verify that points form a rectangle
75     if (point1[ y ] == point2[ y ] && point1[ x ] == point4[ x ] &&
76         point2[ x ] == point3[ x ] && point3[ y ] == point4[ y ]) {
77
78        perimeter();
79        area();
80        square();
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
81          setValid( true );   // valid set of points
82       }
83       else {
84          cout << "Coordinates do not form a rectangle!\n";
85          setValid( false );   // invalid set of points
86       }
87    }
88
89    void Rectangle::perimeter( void )
90    {
91       double l = fabs( point4[ 1 ] - point1[ 1 ] ),
92              w = fabs( point2[ 0 ] - point1[ 0 ] );
93
94       cout << setiosflags( ios::fixed | ios::showpoint )
95            << "length = " << setprecision( 1 ) << ( l > w ? l : w )
96            << "\twidth = " << ( l > w ? w : l )
97            << "\nThe perimeter is: " << 2 * ( w + l ) << '\n'
98            << resetiosflags( ios::fixed | ios::showpoint );
99    }
100   void Rectangle::area( void )
101   {
102      double l = fabs( point4[ 1 ] - point1[ 1 ] ),
103             w = fabs( point2[ 0 ] - point1[ 0 ] );
104
105      cout << setiosflags( ios::fixed | ios::showpoint )
106           << "The area is: " << setprecision( 1 ) << w * l
107           << resetiosflags( ios::fixed | ios::showpoint )
108           << "\n\n";
109   }
110
111   void Rectangle::square( void )
112   {
113      const int x = 0, y = 1;   // added for clarity
114
115      if ( fabs( point4[ y ] - point1[ y ] ) == fabs( point2[ x ] - point1[ x ] ) )
116         cout << "The rectangle is a square.\n\n";
117   }
118
119   void Rectangle::draw( void )
120   {
121      for ( double y = 25.0; y >= 0.0; --y ) {
122         for ( double x = 0.0; x <= 25.0; ++x ) {
123            if ( ( point1[ 0 ] == x && point1[ 1 ] == y ) ||
124                 ( point4[ 0 ] == x && point4[ 1 ] == y ) ) {
125
126               // print horizontal perimeter of rectangle
127               while ( x <= point2[ 0 ] ) {
128                  cout << periChar;
129                  ++x;
130               }
131
132               // print remainder of quadrant
133               cout << '.';
134            }
135            // prints vertical perimeter of rectangle
136            else if ( ( ( x <= point4[ 0 ] && x >= point1[ 0 ] ) ) &&
137                        point4[ 1 ] >= y && point1[ 1 ] <= y ) {
138               cout << periChar;
139
140               // fill inside of rectangle
141               for ( x++; x < point2[ 0 ]; ) {
142                  cout << fillChar;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
143                ++x;
144             }
145
146             cout << periChar;
147          }
148          else
149             cout << '.';  // print quadrant background
150       }
151
152       cout << '\n';
153    }
154 }
```

```
155 // driver for p6_14.cpp
156
157 #include "p6_14.h"
158
159 int main()
160 {
161    double xy1[ 2 ] = { 12.0, 12.0 }, xy2[ 2 ] = { 18.0, 12.0 },
162           xy3[ 2 ] = { 18.0, 20.0 }, xy4[ 2 ] = { 12.0, 20.0 };
163    Rectangle a( xy1, xy2, xy3, xy4, '?', '*' );
164
165    if ( a.isValid() )
166       a.draw();
167
168    return 0;
169 }
```

```
length = 8.0   width = 6.0
The perimeter is:  28.0
The area is: 48.0



.........................
.........................
.........................
...........******........
...........*??????*......
...........*??????*......
...........*??????*......
...........*??????*......
...........*??????*......
...........*??????*......
...........*??????*......
...........******........
.........................
.........................
.........................
.........................
.........................
.........................
.........................
.........................
.........................
.........................
.........................
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

6.15 Create a class **HugeInteger** that uses a 40-element array of digits to store integers as large as 40-digits each. Provide member functions **inputHugeInteger**, **outputHugeInteger**, **addHugeIntegers** and **substractHugeIntegers**. For comparing **HugeInteger** objects, provide functions **isEqualTo**, **isNotEqualTo**, **isGreaterThan**, **isLessThan**, **IsGreaterThanOrEqualTo** and **isLessThanOrEqualTo**—each of these is a "predicate" function that simply returns **true** if the relationship holds between the two huge integers and returns **false** if the relationship does not hold. Provide a predicate function **isZero**. If you feel ambitious, also provide member functions **multiplyHugeIntegers**, **divideHugeIntegers** and **modulusHugeIntegers.**

6.16 Create a class **TicTacToe** that will enable you to write a complete program to play the game of tic-tac-toe. The class contains as **private** data a 3-by-3 double array of integers. The constructor should initialize the empty board to all zeros. Allow two human players. Wherever the first player moves, place a 1 in the specified square; place a 2 wherever the second player moves. Each move must be to an empty square. After each move, determine if the game has been won or if the game is a draw. If you feel ambitious, modify your program so that the computer makes the moves for one of the players automatically. Also, allow the player t o specify whether he or she wants to go first or second. If you feel exceptionally ambitious, develop a program that will play three-dimensional tic-tac-toe on a 4-by-4-by-4 board (Caution: This is an extremely challenging project that could take many weeks of effort!).

```
1  // p6.16_H
2  #ifndef P6_16_H
3  #define P6_16_H
4
5  class TicTacToe {
6  private:
7     enum Status { WIN, DRAW, CONTINUE };
8     int board[ 3 ][ 3 ];
9  public:
10    TicTacToe();
11    void makeMove( void );
12    void printBoard( void );
13    bool validMove( int, int );
14    bool xoMove( int );
15    Status gameStatus( void );
16 };
17
18 #endif
```

```
19 // P6_16M.cpp
20 // member function definitions for p6_16.cpp
21 #include <iostream>
22
23 using std::cout;
24 using std::cin;
25
26 #include <iomanip>
27
28 using std::setw;
29
30 #include "p6_16.h"
31
32 TicTacToe::TicTacToe()
33 {
34    for ( int j = 0; j < 3; ++j )    // initialize board
35       for ( int k = 0; k < 3; ++k )
36          board[ j ][ k ] = ' ';
37 }
38
39 bool TicTacToe::validMove( int r, int c )
40 {
41    return r >= 0 && r < 3 && c >= 0 && c < 3 && board[ r ][ c ] == ' ';
42 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
43
44 // must specify that type Status is part of the TicTacToe class.
45 // See Chapter 21 for a discussion of namespaces.
46 TicTacToe::Status TicTacToe::gameStatus( void )
47 {
48    int a;
49
50    // check for a win on diagonals
51    if ( board[ 0 ][ 0 ] != ' ' && board[ 0 ][ 0 ] == board[ 1 ][ 1 ] &&
52         board[ 0 ][ 0 ] == board[ 2 ][ 2 ] )
53       return WIN;
54    else if ( board[ 2 ][ 0 ] != ' ' && board[ 2 ][ 0 ] ==
55    board[ 1 ][ 1 ] && board[ 2 ][ 0 ] == board[ 0 ][ 2 ] )
56       return WIN;
57
58    // check for win in rows
59    for ( a = 0; a < 3; ++a )
60       if ( board[ a ][ 0 ] != ' ' && board[ a ][ 0 ] ==
61       board[ a ][ 1 ] && board[ a ][ 0 ] == board[ a ][ 2 ] )
62          return WIN;
63
64    // check for win in columns
65    for ( a = 0; a < 3; ++a )
66       if ( board[ 0 ][ a ] != ' ' && board[ 0 ][ a ] ==
67       board[ 1 ][ a ] && board[ 0 ][ a ] == board[ 2 ][ a ] )
68          return WIN;
69
70    // check for a completed game
71    for ( int r = 0; r < 3; ++r )
72       for ( int c = 0; c < 3; ++c )
73          if ( board[ r ][ c ] == ' ' )
74             return CONTINUE; // game is not finished
75
76    return DRAW; // game is a draw
77 }
78
79 void TicTacToe::printBoard( void )
80 {
81    cout << "   0    1    2\n\n";
82
83    for ( int r = 0; r < 3; ++r ) {
84       cout << r;
85
86       for ( int c = 0; c < 3; ++c ) {
87          cout << setw( 3 ) << static_cast< char > ( board[ r ][ c ] );
88
89          if ( c != 2 )
90             cout << " |";
91       }
92
93       if ( r != 2 )
94          cout << "\n ____|____|____"
95               << "\n     |    |    \n";
96    }
97
98    cout << "\n\n";
99 }
100
101 void TicTacToe::makeMove( void )
102 {
103    printBoard();
104
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   while ( true ) {
      if ( xoMove( 'X' ) )
         break;
      else if ( xoMove( 'O' ) )
         break;
   }
}

bool TicTacToe::xoMove( int symbol )
{
   int x, y;

   do {
      cout << "Player " << static_cast< char >( symbol )
               << " enter move: ";
      cin >> x >> y;
      cout << '\n';
   } while ( !validMove( x, y ) );

   board[ x ][ y ] = symbol;
   printBoard();
   Status xoStatus = gameStatus();

   if ( xoStatus == WIN ) {
      cout << "Player " << static_cast< char >( symbol )
           << " wins!\n";
      return true;
   }
   else if ( xoStatus == DRAW ) {
      cout << "Game is a draw.\n";
      return true;
   }
   else // CONTINUE
      return false;
}
```

```
// driver for p6_16.cpp
#include "p6_16.h"

int main()
{
   TicTacToe g;
   g.makeMove();

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   0    1    2

0     |     |
  ____|____|____
      |     |
1     |     |
  ____|____|____
      |     |
2     |     |

Player X enter move: 2 0

   0    1    2

0     |     |
  ____|____|____
      |     |
1     |     |
  ____|____|____
      |     |
2  X  |     |

Player O enter move: 2 2

   0    1    2

0     |     |
  ____|____|____
      |     |
1     |     |
  ____|____|____
      |     |
2  X  |     |  O

Player X enter move: 1 1
...
Player X enter move: 0 2

   0    1    2

0     |     |  X
  ____|____|____
      |     |
1     |  X  |  O
  ____|____|____
      |     |
2  X  |     |  O

Player X wins!Player X wins!
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

7

Classes: Part II Solutions

Solutions

7.3 Compare and contrast dynamic memory allocation using the C++ operators **new** and **delete**, with dynamic memory allocation using the C Standard Library functions **malloc** and **free**.

ANS: In C, dynamic memory allocation requires function calls to **malloc** and **free**. Also, **malloc** must be told the exact number of bytes to allocate (normally this is accomplished with the **sizeof** operator), then it returns a **void** pointer. C++ uses operators **new** and **delete**. The **new** operator automatically determines the number of bytes to allocate and returns a pointer to the appropriate type. The **delete** operator guarantees a call to the destructor for the object(s) being deleted.

7.4 Explain the notion of friendship in C++. Explain the negative aspects of friendship as described in the text.

ANS: Functions that are declared as **friend**s of a class have access to that class's **private** and **protected** members. Some people in the object-oriented programming community prefer not to use **friend** functions because they break the encapsulation of a class—i.e., they allow direct access to a class's impementation details that are supposed to be hidden.

7.5 Can a correct **Time** class definition include both of the following constructors? If not, explain why not.

```
Time( int h = 0, int m = 0, int s = 0 );
Time();
```

ANS: No, because there is ambiguity between the two constructors. When a call is made to the default constructor, the compiler cannot determine which one to use because they can both be called with no arguments.

7.6 What happens when a return type, even **void**, is specified for a constructor or destructor?

ANS: A compiler syntax error occurs. No return types can be specified for constructors.

7.7 Create a **Date** class with the following capabilities:

a) Output the date in multiple formats such as

```
DDD YYYY
MM/DD/YY
June 14, 1992
```

b) Use overloaded constructors to create **Date** objects initialized with dates of the formats in part (a).

c) Create a **Date** constructor that reads the system date using the standard library functions of the **ctime** header and sets the **Date** members.

In Chapter 8, we will be able to create operators for testing the equality of two dates and for comparing dates to determine if one date is prior to, or after, another.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// P7_07.H
#ifndef p7_07_H
#define p7_07_H

#include <ctime>
#include <cstring>

class Date {
public:
   Date();
   Date( int, int );
   Date( int, int, int );
   Date( char *, int, int );
   void setMonth( int );
   void setDay( int );
   void setYear( int );
   void printDateSlash( void ) const;
   void printDateMonth( void ) const;
   void printDateDay( void ) const;
   const char *monthName( void ) const;
   bool leapYear( void ) const;
   int daysOfMonth( void ) const;
   void convert1( int );
   int convert2( void ) const;
   void convert3( const char * const );
   const char *monthList( int ) const;
   int days( int ) const;
private:
   int day;
   int month;
   int year;
};

#endif
```

```
// P7_07M.cpp
// member function definitions for p7_07.cpp
#include <iostream>

using std::cout;

#include <cstring>
#include <ctime>

#include "p7_07.h"

// Date constructor that uses functions from ctime
Date::Date()
{
   struct tm *ptr;              // pointer of type struct tm
                                // which holds calendar time components
   time_t t = time( 0 );        // determine the current calendar time
                                // which is assigned to timePtr
   ptr = localtime( &t );       // convert the current calendar time
                                // pointed to by timePtr into
                                // broken down time and assign it to ptr
   day = ptr->tm_mday;          // broken down day of month
   month = 1 + ptr->tm_mon;     // broken down month since January
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
58    year = ptr->tm_year + 1900; // broken down year since 1900
59 }
60
61 // Date constructor that uses day of year and year
62 Date::Date( int ddd, int yyyy )
63 {
64    setYear( yyyy );
65    convert1( ddd );  // convert to month and day
66 }
67
68 // Date constructor that uses month, day and year
69 Date::Date( int mm, int dd, int yy )
70 {
71    setYear( yy + 1900 );
72    setMonth( mm );
73    setDay( dd );
74 }
75
76 // Date constructor that uses month name, day and year
77 Date::Date( char *mPtr, int dd, int yyyy )
78 {
79    setYear( yyyy );
80    convert3( mPtr );
81    setDay( dd );
82 }
83
84 // Set the day
85 void Date::setDay( int d )
86    { day = d >= 1 && d <= daysOfMonth() ? d : 1; }
87
88 // Set the month
89 void Date::setMonth( int m ) { month = m >= 1 && m <= 12 ? m : 1; }
90
91 // Set the year
92 void Date::setYear( int y ) { year = y >= 1900 && y <= 1999 ? y : 1900; }
93
94 // Print Date in the form: mm/dd/yyyy
95 void Date::printDateSlash( void ) const
96    { cout << month << '/' << day << '/' << year << '\n'; }
97
98 // Print Date in the form: monthname dd, yyyy
99 void Date::printDateMonth( void ) const
100   { cout << monthName() << ' ' << day << ", " << year << '\n'; }
101
102 // Print Date in the form: ddd yyyy
103 void Date::printDateDay( void ) const
104   { cout << convert2() << ' ' << year << '\n'; }
105
106 // Return the month name
107 const char *Date::monthName( void ) const { return monthList( month - 1 ); }
108
109 // Return the number of days in the month
110 int Date::daysOfMonth( void ) const
111   { return leapYear() && month == 2 ? 29 : days( month ); }
112
113 // Test for a leap year
114 bool Date::leapYear( void ) const
115 {
116    if ( year % 400 == 0 || ( year % 4 == 0 && year % 100 != 0 ) )
117       return true;
118    else
119       return false;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
120 }
121
122 // Convert ddd to mm and dd
123 void Date::convert1( int ddd )  // convert to mm / dd / yyyy
124 {
125    int dayTotal = 0;
126
127    if ( ddd < 1 || ddd > 366 )  // check for invalid day
128       ddd = 1;
129
130    setMonth( 1 );
131
132    for ( int m = 1; m < 13 && ( dayTotal + daysOfMonth() ) < ddd; ++m ) {
133       dayTotal += daysOfMonth();
134       setMonth( m + 1 );
135    }
136
137    setDay( ddd - dayTotal );
138    setMonth( m );
139 }
140
141 // Convert mm and dd to ddd
142 int Date::convert2( void ) const   // convert to a ddd yyyy format
143 {
144    int ddd = 0;
145
146    for ( int m = 1; m < month; ++m )
147       ddd += days( m );
148
149    ddd += day;
150    return ddd;
151 }
152
153 // Convert from month name to month number
154 void Date::convert3( const char * const mPtr )   // convert to mm / dd / yyyy
155 {
156    bool flag = false;
157
158    for ( int subscript = 0; subscript < 12; ++subscript )
159       if ( !strcmp( mPtr, monthList( subscript ) ) ) {
160          setMonth( subscript + 1 );
161          flag = true; // set flag
162          break;    // stop checking for month
163       }
164
165    if ( !flag )
166       setMonth( 1 ); // invalid month default is january
167 }
168
169 // Return the name of the month
170 const char *Date::monthList( int mm ) const
171 {
172    char *months[] = { "January", "February", "March", "April", "May",
173                       "June", "July", "August", "September", "October",
174                       "November", "December" };
175
176    return months[ mm ];
177 }
178
179 // Return the days in the month
180 int Date::days( int m ) const
181 {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   const int monthDays[] = { 31, 28, 31, 30, 31, 30, 31, 31, 30, 31, 30, 31 };

   return monthDays[ m - 1 ];
}
```

```
// driver for p7_07.cpp
#include <iostream>

using std::cout;
using std::endl;

#include "p7_07.h"

int main()
{
   Date d1( 7, 4, 98 ), d2( 86, 1999 ),
        d3, d4( "September", 1, 1998 );

   d1.printDateSlash();   // format m / dd / yy
   d2.printDateSlash();
   d3.printDateSlash();
   d4.printDateSlash();
   cout << '\n';

   d1.printDateDay();     // format ddd yyyy
   d2.printDateDay();
   d3.printDateDay();
   d4.printDateDay();
   cout << '\n';

   d1.printDateMonth();   // format "month" d, yyyy
   d2.printDateMonth();
   d3.printDateMonth();
   d4.printDateMonth();
   cout << endl;

   return 0;
}
```

```
7/4/1998
3/27/1999
6/16/2000
9/1/1998

185 1998
86 1999
167 2000
244 1998

July 4, 1998
March 27, 1999
June 16, 2000
September 1, 1998
```

7.8 Create a **SavingsAccount** class. Use a **static** data member to contain the **annualInterestRate** for each of the savers. Each member of the class contains a **private** data member **savingsBalance** indicating the amount the saver currently has on deposit. Provide a **calculateMonthlyInterest** member function that calculates the monthly interest by multiplying the **balance** by **annualInterestRate** divided by 12; this interest should be added to **savingsBalance**. Provide a **stat-**

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ic member function **modifyInterestRate** that sets the **static annualInterestRate** to a new value. Write a driver program to test class **SavingsAccount**. Instantiate two different **savingsAccount** objects, **saver1** and **saver2**, with balances of $2000.00 and $3000.00, respectively. Set **annualInterestRate** to 3%, then calculate the monthly interest and print the new balances for each of the savers. Then set the **annualInterestRate** to 4% and calculate the next month's interest and print the new balances for each of the savers.

```
// P7_08.H
#ifndef P7_08_H
#define P7_08_H

class SavingsAccount {
public:
   SavingsAccount( double b ) { savingsBalance = b >= 0 ? b : 0; }
   void calculateMonthlyInterest( void );
   static void modifyInterestRate( double );
   void printBalance( void ) const;
private:
   double savingsBalance;
   static double annualInterestRate;
};

#endif
```

```
// P7.08M.cpp
// Member function defintions for p7_08.cpp
#include "p7_08.h"
#include <iostream>

using std::cout;
using std::ios;

#include <iomanip>

using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

// initialize static data member
double SavingsAccount::annualInterestRate = 0.0;

void SavingsAccount::calculateMonthlyInterest( void )
   { savingsBalance += savingsBalance * ( annualInterestRate / 12.0 ); }

void SavingsAccount::modifyInterestRate( double i )
   { annualInterestRate = ( i >= 0 && i <= 1.0 ) ? i : 0.03; }

void SavingsAccount::printBalance( void ) const
{
   cout << setiosflags( ios::fixed | ios::showpoint )
        << '$' << setprecision( 2 ) << savingsBalance
        << resetiosflags( ios::fixed | ios::showpoint );
}
```

```
// driver for p7_08.cpp
#include <iostream>

using std::cout;
using std::endl;

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#include <iomanip>

using std::setw;

#include "p7_08.h"

int main()
{
   SavingsAccount saver1( 2000.0 ), saver2( 3000.0 );

   SavingsAccount::modifyInterestRate( .03 );

   cout << "\nOutput monthly balances for one year at .03"
        << "\nBalances: Saver 1 ";
   saver1.printBalance();
   cout << "\tSaver 2 ";
   saver2.printBalance();

   for ( int month = 1; month <= 12; ++month ) {
      saver1.calculateMonthlyInterest();
      saver2.calculateMonthlyInterest();

      cout << "\nMonth" << setw( 3 ) << month << ": Saver 1 ";
      saver1.printBalance();
      cout << "\tSaver 2 ";
      saver2.printBalance();
   }

   SavingsAccount::modifyInterestRate( .04 );
   saver1.calculateMonthlyInterest();
   saver2.calculateMonthlyInterest();
   cout << "\nAfter setting interest rate to .04"
        << "\nBalances: Saver 1 ";
   saver1.printBalance();
   cout << "\tSaver 2 ";
   saver2.printBalance();
   cout << endl;

   return 0;
}
```

```
 Output monthly balances for one year at .03
Balances: Saver 1 $2000.00      Saver 2 $3000.00
Month  1: Saver 1 $2005.00      Saver 2 $3007.50
Month  2: Saver 1 $2010.01      Saver 2 $3015.02
Month  3: Saver 1 $2015.04      Saver 2 $3022.56
Month  4: Saver 1 $2020.08      Saver 2 $3030.11
Month  5: Saver 1 $2025.13      Saver 2 $3037.69
Month  6: Saver 1 $2030.19      Saver 2 $3045.28
Month  7: Saver 1 $2035.26      Saver 2 $3052.90
Month  8: Saver 1 $2040.35      Saver 2 $3060.53
Month  9: Saver 1 $2045.45      Saver 2 $3068.18
Month 10: Saver 1 $2050.57      Saver 2 $3075.85
Month 11: Saver 1 $2055.69      Saver 2 $3083.54
Month 12: Saver 1 $2060.83      Saver 2 $3091.25
After setting interest rate to .04
Balances: Saver 1 $2067.70      Saver 2 $3101.55
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

7.9 Create a class called **IntegerSet**. Each object of class **IntegerSet** can hold integers in the range 0 through 100. A set is represented internally as an array of ones and zeros. Array element **a[i]** is 1 if integer *i* is in the set. Array element **a[j]** is 0 if integer *j* is not in the set. The default constructor initializes a set to the so-called "empty set," i.e., a set whose array representation contains all zeros.

Provide member functions for the common set operations. For example, provide a **unionOfIntegerSets** member function that creates a third set which is the set-theoretic union of two existing sets (i.e., an element of the third set's array is set to 1 if that element is 1 in either or both of the existing sets, and an element of the third set's array is set to 0 if that element is 0 in each of the existing sets).

Provide an **intersectionOfIntegerSets** member function that creates a third set which is the set-theoretic intersection of two existing sets (i.e., an element of the third set's array is set to 0 if that element is 0 in either or both of the existing sets, and an element of the third set's array is set to 1 if that element is 1 in each of the existing sets).

Provide an **insertElement** member function that inserts a new integer *k* into a set (by setting **a[k]** to 1). Provide a **deleteElement** member function that deletes integer *m* (by setting **a[m]** to 0).

Provide a **setPrint** member function that prints a set as a list of numbers separated by spaces. Print only those elements that are present in the set (i.e., their position in the array has a value of 1). Print **---** for an empty set.

Provide an **isEqualTo** member function that determines if two sets are equal.

Provide an additional constructor to take five integer arguments which can be used to initialize a set object. If you want to provide fewer than five elements in the set, use default arguments of
-1 for the others.

Now write a driver program to test your **IntegerSet** class. Instantiate several **IntegerSet** objects. Test that all your member functions work properly.

```
1  P7_09.H
2  #ifndef P7_09_H
3  #define P7_09_H
4
5  class IntegerSet {
6  public:
7     IntegerSet() { emptySet(); }
8     IntegerSet( int, int = -1, int = -1, int = -1, int = -1 );
9     IntegerSet unionOfIntegerSets( const IntegerSet& );
10    IntegerSet intersectionOfIntegerSets( const IntegerSet& );
11    void emptySet( void );
12    void inputSet( void );
13    void insertElement( int );
14    void deleteElement( int );
15    void setPrint( void ) const;
16    bool isEqualTo( const IntegerSet& ) const;
17 private:
18    int set[ 101 ];  // range of 0 - 100
19    int validEntry( int x ) const { return x >= 0 && x <= 100; }
20 };
21
22 #endif
```

```
23 //P7_09M.cpp
24 //Member function definitions for p7_09.cpp
25 #include <iostream>
26
27 using std::cout;
28 using std::cin;
29 using std::cerr;
30
31 #include <iomanip>
32
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
33  using std::setw;
34
35  #include "p7_09.h"
36
37  IntegerSet::IntegerSet( int a, int b, int c, int d, int e )
38  {
39     emptySet();
40
41     if ( validEntry( a ) )
42        insertElement( a );
43
44     if ( validEntry( b ) )
45        insertElement( b );
46
47     if ( validEntry( c ) )
48        insertElement( c );
49
50     if ( validEntry( d ) )
51        insertElement( d );
52
53     if ( validEntry( e ) )
54        insertElement( e );
55  }
56
57  void IntegerSet::emptySet( void )
58  {
59     for ( int y = 0; y < 101; ++y )
60        set[ y ] = 0;
61  }
62
63  void IntegerSet::inputSet( void )
64  {
65     int number;
66
67     do {
68        cout << "Enter an element (-1 to end): ";
69        cin >> number;
70
71        if ( validEntry( number ) )
72           set[ number ] = 1;
73        else if ( number != -1 )
74           cerr << "Invalid Element\n";
75     } while ( number != -1 );
76
77     cout << "Entry complete\n";
78  }
79
80  void IntegerSet::setPrint( void ) const
81  {
82     int x;
83     bool empty = true;  // assume set is empty
84
85     cout << '{';
86
87     for (int u = 0; u < 101; ++u )
88        if ( set[ u ] ) {
89           cout << setw( 4 ) << u << ( x % 10 == 0 ? "\n" : "" );
90           empty = false; // set is not empty
91           ++x;
92        }
93
94     if ( empty )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
95          cout << setw( 4 ) << "---";  // display an empty set
96
97       cout << setw( 4 ) << "}" << '\n';
98    }
99
100   IntegerSet IntegerSet::unionOfIntegerSets( const IntegerSet &r )
101   {
102      IntegerSet temp;
103
104      for ( int n = 0; n < 101; ++n )
105         if ( set[ n ] == 1 || r.set[ n ] == 1 )
106            temp.set[ n ] = 1;
107
108      return temp;
109   }
110
111   IntegerSet IntegerSet::intersectionOfIntegerSets( const IntegerSet &r )
112   {
113      IntegerSet temp;
114
115      for ( int w = 0; w < 101; ++w )
116         if ( set[ w ] == 1 && r.set[ w ] == 1 )
117            temp.set[ w ] = 1;
118
119      return temp;
120   }
121
122   void IntegerSet::insertElement( int k )
123   {
124      if ( validEntry( k ) )
125         set[ k ] = 1;
126      else
127         cerr << "Invalid insert attempted!\n";
128   }
129
130   void IntegerSet::deleteElement( int m )
131   {
132      if ( validEntry( m ) )
133         set[ m ] = 0;
134      else
135         cerr << "Invalid delete attempted!\n";
136   }
137
138   bool IntegerSet::isEqualTo( const IntegerSet &r ) const
139   {
140      for ( int v = 0; v < 101; ++v )
141         if ( set[ v ] != r.set[ v ] )
142            return false;   // sets are not-equal
143
144      return true;   // sets are equal
145   }
```

```
146   // driver for p7_09.cpp
147   #include <iostream>
148
149   using std::cout;
150   using std::endl;
151
152   #include "p7_09.h"
153
154   int main()
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{

   IntegerSet a, b, c, d, e( 8, 5, 7 );

   cout << "Enter set A:\n";
   a.inputSet();
   cout << "\nEnter set B:\n";
   b.inputSet();
   c = a.unionOfIntegerSets( b );
   d = a.intersectionOfIntegerSets( b );
   cout << "\nUnion of A and B is:\n";
   c.setPrint();
   cout << "Intersection of A and B is:\n";
   d.setPrint();

   if ( a.isEqualTo( b ) )
      cout << "Set A is equal to set B\n";
   else
      cout << "Set A is not equal to set B\n";

   cout << "\nInserting 77 into set A...\n";
   a.insertElement( 77 );
   cout << "Set A is now:\n";
   a.setPrint();

   cout << "\nDeleting 77 from set A...\n";
   a.deleteElement( 77 );
   cout << "Set A is now:\n";
   a.setPrint();

   cout << "\nSet e is:\n";
   e.setPrint();

   cout << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter set A:
Enter an element (-1 to end): 1
Enter an element (-1 to end): 2
Enter an element (-1 to end): 3
Enter an element (-1 to end): 4
Enter an element (-1 to end): -1
Entry complete

Enter set B:
Enter an element (-1 to end): 3
Enter an element (-1 to end): 4
Enter an element (-1 to end): 5
Enter an element (-1 to end): 9
Enter an element (-1 to end): 22
Enter an element (-1 to end): -1
Entry complete

Union of A and B is:
{   1   2   3   4   5   9  22   }
Intersection of A and B is:
{   3   4   }
Set A is not equal to set B

Inserting 77 into set A...
Set A is now:
{   1   2   3   4  77   }

Deleting 77 from set A...
Set A is now:
{   1   2   3   4   }

Set e is:
{   5   7   8   }
```

7.10 It would be perfectly reasonable for the **`Time`** class of Fig. 7.8 to represent the time internally as the number of seconds since midnight rather than the three integer values **`hour`**, **`minute`** and **`second`**. Clients could use the same **`public`** methods and get the same results. Modify the **`Time`** class of Fig. 7.8 to implement the **`Time`** as the number of seconds since midnight and show that there is no visible change in functionality to the clients of the class.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Operator Overloading Solutions

Solutions

8.6 Give as many examples as you can of operator overloading implicit in C++. Give a reasonable example of a situation in which you might want to overload an operator explicitly in C++.

ANS: In C, the operators **+**, **-**, *****, and **&** are overloaded. The context of these operators determines how they are used. It can be argued that the arithmetic operators are all overloaded, because they can be used to perform operations on more than one type of data. In C++, the same operators as in C are overloaded, as well as **<<** and **>>**.

8.7 The C++ operators that cannot be overloaded are _____, _____, _____, _____ and _____.

ANS: **sizeof**, **.**, **?:**, **.***, and **::**.

8.8 String concatenation requires two operands—the two strings that are to be concatenated. In the text we showed how to implement an overloaded concatenation operator that concatenates the second **String** object to the right of the first **String** object, thus modifying the first **String** object. In some applications, it is desirable to produce a concatenated **String** object without modifying the **String** arguments. Implement **operator+** to allow operations such as

```
string1 = string2 + string3;
```

```
1  // P8_08.H
2  #ifndef p8_08_H
3  #define p8_08_H
4
5  #include <cstring>
6  #include <cassert>
7
8  class String {
9     friend ostream &operator<<( ostream &output, const String &s );
10 public:
11    String( const char * const = "" ); // conversion constructor
12    String( const String & );    // copy constructor
13    ~String();                   // destructor
14    const String &operator=( const String & );
15    String operator+( const String & );
16 private:
17    char *sPtr;
18    int length;
19 };
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
20
21 #endif
```

```
22 // P8_08M.cpp
23 // member function definitions for p8_08.cpp
24 // class String
25 #include <iostream>
26
27 using std::cout;
28 using std::ostream;
29
30
31 #include <cstring>
32 #include "p8_08.h"
33
34 // Conversion constructor: Convert a char * to String
35 String::String( const char * const zPtr )
36 {
37    length = strlen( zPtr );          // compute length
38    sPtr = new char[ length + 1 ]; // allocate storage
39    assert( sPtr != 0 );  // terminate if memory not allocated
40    strcpy( sPtr, zPtr );             // copy literal to object
41 }
42
43 // Copy constructor
44 String::String( const String &copy )
45 {
46    length = copy.length;         // copy length
47    sPtr = new char[ length + 1 ]; // allocate storage
48    assert( sPtr != 0 );           // ensure memory allocated
49    strcpy( sPtr, copy.sPtr );     // copy string
50 }
51
52 // Destructor
53 String::~String() { delete [] sPtr; }  // reclaim string
54
55 // Overloaded = operator; avoids self assignment
56 const String &String::operator=( const String &right )
57 {
58    if ( &right != this ) {           // avoid self assignment
59       delete [] sPtr;               // prevents memory leak
60       length = right.length;        // new String length
61       sPtr = new char[ length + 1 ]; // allocate memory
62       assert( sPtr != 0 );           // ensure memory allocated
63       strcpy( sPtr, right.sPtr );    // copy string
64    }
65    else
66       cout << "Attempted assignment of a String to itself\n";
67
68    return *this;   // enables concatenated assignments
69 }
70
71
72 // Concatenate right operand and this object and
73 // store in temp object.
74 String String::operator+( const String &right )
75 {
76    String temp;
77
78    temp.length = length + right.length;
79    temp.sPtr = new char[ temp.length + 1 ]; // create space
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   assert( sPtr != 0 );   // terminate if memory not allocated
   strcpy( temp.sPtr, sPtr );       // left part of new String
   strcat( temp.sPtr, right.sPtr ); // right part of new String
   return temp;                     // enables concatenated calls
}
ostream & operator<<( ostream &output, const String &s )
{
   output << s.sPtr;
   return output;   // enables concatenation
}
```

```
// driver for p8_08.cpp
#include <iostream>

using std::cout;
using std::endl;
using std::ostream;

// Overloaded output operator


#include "p8_08.h"

int main()
{
   String string1, string2( "The date is" );
   String string3( " August 1, 1993" );

   cout << "string1 = string2 + string3\n";
   string1 = string2 + string3;
   cout << string1 << " = " << string2 << " + "
        << string3 << endl;

   return 0;
}
```

```
string1 = string2 + string3
The date is August 1, 1993 = The date is +  August 1, 1993
```

8.9 *(Ultimate operator overloading exercise)* To appreciate the care that should go into selecting operators for overloading, list each of C++'s overloadable operators, and for each, list a possible meaning (or several, if appropriate) for each of several classes you have studied in this course. We suggest you try:

a) Array
b) Stack
c) String

After doing this, comment on which operators seem to have meaning for a wide variety of classes. Which operators seem to be of little value for overloading? Which operators seem ambiguous?

8.10 Now work the process described in the previous problem in reverse. List each of C++'s overloadable operators. For each, list what you feel is perhaps the "ultimate operation" the operator should be used to represent. If there are several excellent operations, list them all.

8.11 *(Project)* C++ is an evolving language, and new languages are always being developed. What additional operators would you recommend adding to C++ or to a future language like C++ that would support both procedural programming and object-oriented programming? Write a careful justification. You might consider sending your suggestions to the ANSI C++ Committee or the newsgroup **comp.std.c++**.

8.12 One nice example of overloading the function call operator **()** is to allow the more common form of double-array subscripting. Instead of saying

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
chessBoard[ row ][ column ]
```

for an array of objects, overload the function call operator to allow the alternate form

```
chessBoard( row, column )
```

```
// P8_12.H
#ifndef P8_12_H
#define P8_12_H

class CallOperator {
public:
   CallOperator();
   int operator()( int, int ); // overloaded function call operator
private:
   int chessBoard[ 8 ][ 8 ];
};

#endif
```

```
// P8_12M.CPP
// member function definitions for p8_12.cpp
#include "p8_12.h"

CallOperator::CallOperator()
{
   for ( int loop = 0; loop < 8; ++loop )
      for ( int loop2 = 0; loop2 < 8; ++loop2 )
         chessBoard[ loop ][ loop2 ] = loop2;
}

int CallOperator::operator()( int r, int c ) { return chessBoard[ r ][ c ]; }
```

```
// driver for p8_12.cpp
#include <iostream>

using std::cout;
using std::endl;

#include "p8_12.h"

int main()
{
   CallOperator board;

   cout << "board[2][5] is " << board( 2, 5 ) << endl;

   return 0;
}
```

```
board[2][5] is 5
```

8.13 Create a class **DoubleSubscriptedArray** that has similar features to class **Array** in Fig. 8.4. At construction time, the class should be able to create an array of any number of rows and any number of columns. The class should supply **operator()** to perform double-subscripting operations. For example, in a 3-by-5 **DoubleSubscriptedArray** called **a**, the user could write **a(1, 3)** to access the element at row **1** and column **3**. Remember that **operator()** can receive any number of arguments (see class **String** in Fig. 18.5 for an example of **operator()**). The underlying representation of the double-sub-

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

scripted array should be a single-subscripted array of integers with *rows * columns* number of elements. Function **operator()** should perform the proper pointer arithmetic to access each element of the array. There should be two versions of **operator()**—one that returns **int &** so an element of a **DoubleSubscriptedArray** can be used as an *lvalue* and one that returns **const int &** so an element of a **const DoubleSubscriptedArray** can be used as an *rvalue*. The class should also provide the following operators: **==**, **!=**, **=**, **<<** (for outputting the array in row and column format) and **>>** (for inputting the entire array contents).

8.14 Overload the subscript operator to return the largest element of a collection, the second largest, the third largest, etc.

8.15 Consider class **Complex** shown in Fig. 8.7. The class enables operations on so-called *complex numbers*. These are numbers of the form **realPart + imaginaryPart *** *i* where *i* has the value:

$$\sqrt{-1}$$

a) Modify the class to enable input and output of complex numbers through the overloaded **>>** and **<<** operators, respectively (you should remove the **print** function from the class).
b) Overload the multiplication operator to enable multiplication of two complex numbers as in algebra.
c) Overload the **==** and **!=** operators to allow comparisons of complex numbers

```
1  // Fig. 8.7: complex1.h
2  // Definition of class Complex
3  #ifndef COMPLEX1_H
4  #define COMPLEX1_H
5
6  class Complex {
7  public:
8     Complex( double = 0.0, double = 0.0 );       // constructor
9     Complex operator+( const Complex & ) const;  // addition
10    Complex operator-( const Complex & ) const;  // subtraction
11    const Complex &operator=( const Complex & ); // assignment
12    void print() const;                          // output
13 private:
14    double real;       // real part
15    double imaginary;  // imaginary part
16 };
17
18 #endif
```

```
19 // Fig. 8.7: complex1.cpp
20 // Member function definitions for class Complex
21 #include <iostream>
22
23 using std::cout;
24
25 #include "complex1.h"
26
27 // Constructor
28 Complex::Complex( double r, double i )
29    : real( r ), imaginary( i ) { }
30
31 // Overloaded addition operator
32 Complex Complex::operator+( const Complex &operand2 ) const
33 {
34    return Complex( real + operand2.real,
35                    imaginary + operand2.imaginary );
36 }
37
38 // Overloaded subtraction operator
39 Complex Complex::operator-( const Complex &operand2 ) const
40 {
41    return Complex( real - operand2.real,
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
                    imaginary - operand2.imaginary );
}

// Overloaded = operator
const Complex& Complex::operator=( const Complex &right )
{
   real = right.real;
   imaginary = right.imaginary;
   return *this;   // enables cascading
}

// Display a Complex object in the form: (a, b)
void Complex::print() const
   { cout << '(' << real << ", " << imaginary << ')'; }
```

```
// Fig. 8.7: fig08_07.cpp
// Driver for class Complex
#include <iostream>

using std::cout;
using std::endl;

#include "complex1.h"

int main()
{
   Complex x, y( 4.3, 8.2 ), z( 3.3, 1.1 );

   cout << "x: ";
   x.print();
   cout << "\ny: ";
   y.print();
   cout << "\nz: ";
   z.print();

   x = y + z;
   cout << "\n\nx = y + z:\n";
   x.print();
   cout << " = ";
   y.print();
   cout << " + ";
   z.print();

   x = y - z;
   cout << "\n\nx = y - z:\n";
   x.print();
   cout << " = ";
   y.print();
   cout << " - ";
   z.print();
   cout << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Solution:

```
// P8_15.H
#ifndef P8_15_H
#define P8_15_H
#include <iostream>

using std::ostream;
using std::istream;

class Complex {
   friend ostream &operator<<( ostream &, const Complex & );
   friend istream &operator>>( istream &, Complex & );
public:
   Complex( double = 0.0, double = 0.0 );     // constructor
   Complex operator+( const Complex& ) const; // addition
   Complex operator-( const Complex& ) const; // subtraction
   Complex operator*( const Complex& ) const; // multiplication
   Complex& operator=( const Complex& );      // assignment
   bool operator==( const Complex& ) const;
   bool operator!=( const Complex& ) const;
private:
   double real;       // real part
   double imaginary;  // imaginary part
};

#endif
```

```
// P8_15M.cpp
// member function definitions for p8_15.cpp
#include "p8_15.h"
#include <iostream>

using std::ostream;
using std::istream;

// Constructor
Complex::Complex( double r, double i )
{
   real = r;
   imaginary = i;
}

// Overloaded addition operator
Complex Complex::operator+( const Complex &operand2 ) const
{
   Complex sum;

   sum.real = real + operand2.real;
   sum.imaginary = imaginary + operand2.imaginary;
   return sum;
}

// Overloaded subtraction operator
Complex Complex::operator-( const Complex &operand2 ) const
{
   Complex diff;

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   diff.real = real - operand2.real;
   diff.imaginary = imaginary - operand2.imaginary;
   return diff;
}

// Overloaded multiplication operator
Complex Complex::operator*( const Complex &operand2 ) const
{
   Complex times;

   times.real = real * operand2.real + imaginary * operand2.imaginary;
   times.imaginary = real * operand2.imaginary + imaginary * operand2.real;
   return times;
}

// Overloaded = operator
Complex& Complex::operator=( const Complex &right )
{
   real = right.real;
   imaginary = right.imaginary;
   return *this;   // enables concatenation
}

bool Complex::operator==( const Complex &right ) const
   { return right.real == real && right.imaginary == imaginary ? true : false; }

bool Complex::operator!=( const Complex &right ) const
   { return !( *this == right ); }

ostream& operator<<( ostream &output, const Complex &complex )
{
   output << complex.real << " + " << complex.imaginary << 'i';
   return output;
}

istream& operator>>( istream &input, Complex &complex )
{
   input >> complex.real;
   input.ignore( 3 );       // skip spaces and +
   input >> complex.imaginary;
   input.ignore( 2 );

   return input;
}
```

```
// driver for p8_15.cpp
#include <iostream>

using std::cout;
using std::cin;

#include "p8_15.h"

int main()
{
   Complex x, y( 4.3, 8.2 ), z( 3.3, 1.1 ), k;

   cout << "Enter a complex number in the form: a + bi\n? ";
   cin >> k;

   cout << "x: " << x << "\ny: " << y << "\nz: " << z << "\nk: "
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
116          << k << '\n';
117
118    x = y + z;
119    cout << "\nx = y + z:\n" << x << " = " << y << " + " << z << '\n';
120
121    x = y - z;
122    cout << "\nx = y - z:\n" << x << " = " << y << " - " << z << '\n';
123
124    x = y * z;
125    cout << "\nx = y * z:\n" << x << " = " << y << " * " << z << "\n\n";
126
127    if ( x != k )
128       cout << x << " != " << k << '\n';
129
130    cout << '\n';
131
132    x = k;
133
134    if ( x == k )
135       cout << x << " == " << k << '\n';
136
137    return 0;
138 }
```

```
Enter a complex number in the form: a + bi
? 0 + 0i
x: 0 + 0i
y: 4.3 + 8.2i
z: 3.3 + 1.1i
k: 0 + 0i

x = y + z:
7.6 + 9.3i = 4.3 + 8.2i + 3.3 + 1.1i

x = y - z:
1 + 7.1i = 4.3 + 8.2i - 3.3 + 1.1i

x = y * z:
23.21 + 31.79i = 4.3 + 8.2i * 3.3 + 1.1i

23.21 + 31.79i != 0 + 0i

0 + 0i == 0 + 0i
```

8.16 A machine with 32-bit integers can represent integers in the range of approximately –2 billion to +2 billion. This fixed-size restriction is rarely troublesome. But there are applications in which we would like to be able to use a much wider range of integers. This is what C++ was built to do, namely create powerful new data types. Consider class **`HugeInt`** of Fig. 8.8. Study the class carefully, then

a) Describe precisely how it operates.
b) What restrictions does the class have?
c) Overload the **`*`** multiplication operator.
d) Overload the **`/`** division operator.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

e) Overload all the relational and equality operators.

```
// Fig. 8.8: hugeint1.h
// Definition for class HugeInt
#ifndef HUGEINT1_H
#define HUGEINT1_H

#include <iostream>

using std::ostream;

class HugeInt {
   friend ostream &operator<<( ostream &, const HugeInt & );
public:
   HugeInt( long = 0 );       // conversion/default constructor
   HugeInt( const char * );           // conversion constructor
   HugeInt operator+( const HugeInt & ); // add another HugeInt
   HugeInt operator+( int );          // add an int
   HugeInt operator+( const char * ); // add an int in a char *
private:
   short integer[ 30 ];
};

#endif
```

```
// Fig. 8.8: hugeint1.cpp
// Member and friend function definitions for class HugeInt
#include <cstring>
#include "hugeint1.h"

// Conversion constructor
HugeInt::HugeInt( long val )
{
   int i;

   for ( i = 0; i <= 29; i++ )
      integer[ i ] = 0;   // initialize array to zero

   for ( i = 29; val != 0 && i >= 0; i-- ) {
      integer[ i ] = val % 10;
      val /= 10;
   }
}

HugeInt::HugeInt( const char *string )
{
   int i, j;

   for ( i = 0; i <= 29; i++ )
      integer[ i ] = 0;

   for ( i = 30 - strlen( string ), j = 0; i <= 29; i++, j++ )
      if ( isdigit( string[ j ] ) )
         integer[ i ] = string[ j ] - '0';
}

// Addition
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
55  HugeInt HugeInt::operator+( const HugeInt &op2 )
56  {
57     HugeInt temp;
58     int carry = 0;
59
60     for ( int i = 29; i >= 0; i-- ) {
61        temp.integer[ i ] = integer[ i ] +
62                            op2.integer[ i ] + carry;
63
64        if ( temp.integer[ i ] > 9 ) {
65           temp.integer[ i ] %= 10;
66           carry = 1;
67        }
68        else
69           carry = 0;
70     }
71
72     return temp;
73  }
74
75  // Addition
76  HugeInt HugeInt::operator+( int op2 )
77     { return *this + HugeInt( op2 ); }
78
79  // Addition
80  HugeInt HugeInt::operator+( const char *op2 )
81     { return *this + HugeInt( op2 ); }
82
83  ostream& operator<<( ostream &output, const HugeInt &num )
84  {
85     int i;
86
87     for ( i = 0; ( num.integer[ i ] == 0 ) && ( i <= 29 ); i++ )
88        ; // skip leading zeros
89
90     if ( i == 30 )
91        output << 0;
92     else
93        for ( ; i <= 29; i++ )
94           output << num.integer[ i ];
95
96     return output;
97  }
```

```
98  // Fig. 8.8: fig08_08.cpp
99  // Test driver for HugeInt class
100 #include <iostream>
101
102 using std::cout;
103 using std::endl;
104
105 #include "hugeint1.h"
106
107 int main()
108 {
109    HugeInt n1( 7654321 ), n2( 7891234 ),
110            n3( "99999999999999999999999999999" ),
111            n4( "1" ), n5;
112
113    cout << "n1 is " << n1 << "\nn2 is " << n2
114         << "\nn3 is " << n3 << "\nn4 is " << n4
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
         << "\nn5 is " << n5 << "\n\n";

   n5 = n1 + n2;
   cout << n1 << " + " << n2 << " = " << n5 << "\n\n";

   cout << n3 << " + " << n4 << "\n= " << ( n3 + n4 )
        << "\n\n";

   n5 = n1 + 9;
   cout << n1 << " + " << 9 << " = " << n5 << "\n\n";

   n5 = n2 + "10000";
   cout << n2 << " + " << "10000" << " = " << n5 << endl;

   return 0;
}
```

```
n1 is 7654321
n2 is 7891234
n3 is 99999999999999999999999999999
n4 is 1
n5 is 0

7654321 + 7891234 = 15545555

99999999999999999999999999999 + 1
= 100000000000000000000000000000

7654321 + 9 = 7654330

7891234 + 10000 = 7901234
```

8.17 Create a class **RationalNumber** (fractions) with the following capabilities:

a) Create a constructor that prevents a 0 denominator in a fraction, reduces or simplifies fractions that are not in reduced form and avoids negative denominators.

b) Overload the addition, subtraction, multiplication and division operators for this class.

c) Overload the relational and equality operators for this class.

```
// P8_17.H
#ifndef P8_17_H
#define P8_17_H

class RationalNumber {
public:
   RationalNumber( int = 0, int = 1 ); // default constructor
   RationalNumber operator+( const RationalNumber& );
   RationalNumber operator-( const RationalNumber& );
   RationalNumber operator*( const RationalNumber& );
   RationalNumber operator/( RationalNumber& );
   bool operator>( const RationalNumber& ) const;
   bool operator<( const RationalNumber& ) const;
   bool operator>=( const RationalNumber& ) const;
   bool operator<=( const RationalNumber& ) const;
   bool operator==( const RationalNumber& ) const;
   bool operator!=( const RationalNumber& ) const;
   void printRational( void ) const;
private:
   int numerator;
   int denominator;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
22    void reduction( void );
23 };
24
25 #endif
```

```
26 // P8_17M.cpp
27 // member function definitions for p8_17.cpp
28 #include <cstdlib>
29
30 #include <iostream>
31
32 using std::cout;
33 using std::endl;
34
35 #include "p8_17.h"
36
37 RationalNumber::RationalNumber( int n, int d )
38 {
39    numerator = n;
40    denominator = d;
41    reduction();
42 }
43
44 RationalNumber RationalNumber::operator+( const RationalNumber &a )
45 {
46    RationalNumber sum;
47
48    sum.numerator = numerator * a.denominator + denominator * a.numerator;
49    sum.denominator = denominator * a.denominator;
50    sum.reduction();
51    return sum;
52 }
53
54 RationalNumber RationalNumber::operator-( const RationalNumber &s )
55 {
56    RationalNumber sub;
57
58    sub.numerator = numerator * s.denominator - denominator * s.numerator;
59    sub.denominator = denominator * s.denominator;
60    sub.reduction();
61    return sub;
62 }
63
64 RationalNumber RationalNumber::operator*( const RationalNumber &m )
65 {
66    RationalNumber multiply;
67
68    multiply.numerator = numerator * m.numerator;
69    multiply.denominator = denominator * m.denominator;
70    multiply.reduction();
71    return multiply;
72 }
73
74 RationalNumber RationalNumber::operator/( RationalNumber &d )
75 {
76    RationalNumber divide;
77
78    if ( d.numerator != 0 ) {   // check for a zero in numerator
79       divide.numerator = numerator * d.denominator;
80       divide.denominator = denominator * d.numerator;
81       divide.reduction();
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
82     }
83     else {
84        cout << "Divide by zero error: terminating program" << endl;
85        exit( 1 );   // stdlib function
86     }
87
88     return divide;
89  }
90
91  bool RationalNumber::operator>( const RationalNumber &gr ) const
92  {
93     if ( static_cast<double>( numerator ) / denominator >
94          static_cast<double>( gr.numerator ) / gr.denominator )
95        return true;
96     else
97        return false;
98  }
99
100 bool RationalNumber::operator<(const RationalNumber &lr) const
101 {
102    if ( static_cast<double>( numerator ) / denominator <
103         static_cast<double>( lr.numerator ) / lr.denominator )
104       return true;
105    else
106       return false;
107 }
108
109 bool RationalNumber::operator>=( const RationalNumber &ger ) const
110    { return *this == ger || *this > ger; }
111
112 bool RationalNumber::operator<=( const RationalNumber &ler ) const
113    { return *this == ler || *this < ler; }
114
115 bool RationalNumber::operator==( const RationalNumber &er ) const
116 {
117    if ( numerator == er.numerator && denominator == er.denominator )
118       return true;
119    else
120       return false;
121 }
122
123 bool RationalNumber::operator!=( const RationalNumber &ner ) const
124    { return !( *this == ner ); }
125
126 void RationalNumber::printRational( void ) const
127 {
128    if ( numerator == 0 )         // print fraction as zero
129       cout << numerator;
130    else if ( denominator == 1 )  // print fraction as integer
131       cout << numerator;
132    else
133       cout << numerator << '/' << denominator;
134 }
135
136 void RationalNumber::reduction( void )
137 {
138    int largest, gcd = 1;  // greatest common divisor;
139
140    largest = ( numerator > denominator ) ? numerator: denominator;
141
142    for ( int loop = 2; loop <= largest; ++loop )
143       if ( numerator % loop == 0 && denominator % loop == 0 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
144            gcd = loop;
145
146      numerator /= gcd;
147      denominator /= gcd;
148   }
```

```
149   // driver for p8_17.cpp
150   #include "p8_17.h"
151   #include <iostream>
152
153   using std::cout;
154   using std::endl;
155
156   int main()
157   {
158      RationalNumber c( 7, 3 ), d( 3, 9 ), x;
159
160      c.printRational();
161      cout << " + " ;
162      d.printRational();
163      cout << " = ";
164      x = c + d;
165      x.printRational();
166
167      cout << '\n';
168      c.printRational();
169      cout << " - " ;
170      d.printRational();
171      cout << " = ";
172      x = c - d;
173      x.printRational();
174
175      cout << '\n';
176      c.printRational();
177      cout << " * " ;
178      d.printRational();
179      cout << " = ";
180      x = c * d;
181      x.printRational();
182
183      cout << '\n';
184      c.printRational();
185      cout << " / " ;
186      d.printRational();
187      cout << " = ";
188      x = c / d;
189      x.printRational();
190
191      cout << '\n';
192      c.printRational();
193      cout << " is:\n";
194
195      cout << ( ( c > d ) ? "  > " : "  <= " );
196      d.printRational();
197      cout << " according to the overloaded > operator\n";
198
199      cout << ( ( c < d ) ? "  < " : "  >= " );
200      d.printRational();
201      cout << " according to the overloaded < operator\n";
202
203      cout << ( ( c >= d ) ? "  >= " : "  < " );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   d.printRational();
   cout << " according to the overloaded >= operator\n";

   cout << ( ( c <= d ) ? "  <= " : "  > " );
   d.printRational();
   cout << " according to the overloaded <= operator\n";

   cout << ( ( c == d ) ? "  == " : "  != " );
   d.printRational();
   cout << " according to the overloaded == operator\n";

   cout << ( ( c != d ) ? "  != " : "  == " );
   d.printRational();
   cout << " according to the overloaded != operator" << endl;

   return 0;
}
```

```
7/3 + 1/3 = 8/3
7/3 - 1/3 = 2
7/3 * 1/3 = 7/9
7/3 / 1/3 = 7
7/3 is:
 > 1/3 according to the overloaded > operator
 >= 1/3 according to the overloaded < operator
 >= 1/3 according to the overloaded >= operator
 > 1/3 according to the overloaded <= operator
 != 1/3 according to the overloaded == operator
 != 1/3 according to the overloaded != operator
```

8.18 Study the C string-handling library functions and implement each of the functions as part of the **`String`** class. Then, use these functions to perform text manipulations.

8.19 Develop class **`Polynomial`**. The internal representation of a **`Polynomial`** is an array of terms. Each term contains a coefficient and an exponent. The term

$$2x^4$$

has a coefficient of 2 and an exponent of 4. Develop a full class containing proper constructor and destructor functions as well as *set* and *get* functions. The class should also provide the following overloaded operator capabilities:

a) Overload the addition operator (**+**) to add two **`Polynomials`**.
b) Overload the subtraction operator (**-**) to subtract two **`Polynomials`**.
c) Overload the assignment operator (=) to assign one **`Polynomial`** to another.
d) Overload the multiplication operator (*****) to multiply two **`Polynomials`**.
e) Overload the addition assignment operator (**+=**), the subtraction assignment operator (**-=**), and the multiplication assignment operator (***=**).

```
// P8_19P.H
#ifndef P8_19P_H
#define P8_19P_H

class Polynomial {
public:
   Polynomial();
   Polynomial operator+( const Polynomial& ) const;
   Polynomial operator-( const Polynomial& ) const;
   Polynomial operator*( const Polynomial& );
   const Polynomial operator=( const Polynomial&);
   Polynomial& operator+=( const Polynomial& );
   Polynomial& operator-=( const Polynomial& );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   Polynomial& operator*=( const Polynomial& );
   void enterTerms( void );
   void printPolynomial( void ) const;
private:
   int exponents[ 100 ];
   int coefficients[ 100 ];
   void polynomialCombine( Polynomial& );  // combine common terms
};

#endif
```

```
// P8_19M.cpp
// member function definitions for p8_19.cpp
// NOTE: The assignment operator does not need to be overloaded,
// because default member-wise copy can be used
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setiosflags;
using std::resetiosflags;

#include "p8_19p.h"

Polynomial::Polynomial()
{
   for ( int t = 0; t < 100; ++t ) {
      coefficients[ t ] = 0;
      exponents[ t ] = 0;
   }
}

void Polynomial::printPolynomial( void ) const
{
   int start;
   bool zero = false;

   if ( coefficients[ 0 ] ) {        // output constants
      cout << coefficients[ 0 ];
      start = 1;
      zero = true;    // at least one term exists
   }
   else {

      if ( coefficients[ 1 ] ) {
         cout << coefficients[ 1 ] << 'x';  // constant does not exist
                                            // so output first term
                                            // without a sign
         if ( ( exponents[ 1 ] != 0 ) && ( exponents[ 1 ] != 1 ) )
            cout << '^' << exponents[ 1 ];

         zero = true;  // at least one term exists
      }

      start = 2;
   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
74
75    // output remaining polynomial terms
76    for ( int x = start; x < 100; ++x ) {
77       if ( coefficients[ x ] != 0 ) {
78          cout << setiosflags( ios::showpos ) << coefficients[ x ]
79               << resetiosflags( ios::showpos ) << 'x';
80
81          if ( ( exponents[ x ] != 0 ) && ( exponents[ x ] != 1 ) )
82             cout << '^' << exponents[ x ];
83
84          zero = true;  // at least one term exists
85       }
86    }
87
88    if ( !zero )   // no terms exist in the polynomial
89       cout << '0';
90
91    cout << endl;
92 }
93
94 const Polynomial Polynomial::operator=( const Polynomial& r )
95 {
96    exponents[ 0 ] = r.exponents[ 0 ];
97    coefficients[ 0 ] = r.coefficients[ 0 ];
98
99    for ( int s = 1; ( s < 100 ); ++s ) {
100      if ( r.exponents[ s ] != 0 ) {
101         exponents[ s ] = r.exponents[ s ];
102         coefficients[ s ] = r.coefficients[ s ];
103      }
104      else {
105         if ( exponents[ s ] == 0 )
106            break;
107         exponents[ s ] = 0;
108         coefficients[ s ] = 0;
109      }
110   }
111
112   return *this;
113 }
114
115 Polynomial Polynomial::operator+( const Polynomial& r ) const
116 {
117    Polynomial temp;
118    bool exponentExists;
119
120    // process element with a zero exponent
121    temp.coefficients[ 0 ] = coefficients[ 0 ] + r.coefficients[ 0 ];
122
123    // copy right arrays into temp object s will be used to keep
124    // track of first open coefficient element
125    for ( int s = 1; ( s < 100 ) && ( r.exponents[ s ] != 0 ); ++s ) {
126       temp.coefficients[ s ] = r.coefficients[ s ];
127       temp.exponents[ s ] = r.exponents[ s ];
128    }
129
130    for ( int x = 1; x < 100; ++x ) {
131       exponentExists = false; // assume exponent will not be found
132
133       for ( int t = 1; ( t < 100 ) && ( !exponentExists ); ++t )
134          if ( exponents[ x ] == temp.exponents[ t ] ) {
135             temp.coefficients[ t ] += coefficients[ x ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
136             exponentExists = true;  // exponent found
137          }
138
139       // exponent was not found, insert into temp
140       if ( !exponentExists ) {
141          temp.exponents[ s ] = exponents[ x ];
142          temp.coefficients[ s ] += coefficients[ x ];
143          ++s;
144       }
145    }
146
147    return temp;
148 }
149
150 Polynomial &Polynomial::operator+=( const Polynomial &r )
151 {
152    *this = *this + r;
153    return *this;
154 }
155
156 Polynomial Polynomial::operator-( const Polynomial& r ) const
157 {
158    Polynomial temp;
159    bool exponentExists;
160
161    // process element with a zero exponent
162    temp.coefficients[ 0 ] = coefficients[ 0 ] - r.coefficients[ 0 ];
163
164    // copy left arrays into temp object s will be used to keep
165    // track of first open coefficient element
166    for ( int s = 1; ( s < 100 ) && ( exponents[ s ] != 0 ); ++s ) {
167       temp.coefficients[ s ] = coefficients[ s ];
168       temp.exponents[ s ] = exponents[ s ];
169    }
170
171    for ( int x = 1; x < 100; ++x) {
172       exponentExists = false; // assume exponent will not be found
173
174       for ( int t = 1; ( t < 100 ) && ( !exponentExists ); ++t )
175          if ( r.exponents[ x ] == temp.exponents[ t ] ) {
176             temp.coefficients[ t ] -= r.coefficients[ x ];
177             exponentExists = true;  // exponent found
178          }
179
180       // exponent was not found, insert into temp
181       if ( !exponentExists ) {
182          temp.exponents[ s ] = r.exponents[ x ];
183          temp.coefficients[ s ] -= r.coefficients[ x ];
184          ++s;
185       }
186    }
187
188    return temp;
189 }
190
191 Polynomial &Polynomial::operator-=( const Polynomial& r )
192 {
193    *this = *this - r;
194    return *this;
195 }
196
197 Polynomial Polynomial::operator*( const Polynomial& r )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   Polynomial temp;
   int s = 1;    // subscript location for temp coefficients and exponents

   for ( int x = 0; ( x < 100 ) && ( x == 0 || coefficients[ x ] != 0 ); ++x )
      for ( int y = 0; ( y < 100 ) && ( y == 0 || r.coefficients[ y ] != 0 ); ++y )
         if ( coefficients[ x ] * r.coefficients[ y ] )

            if ( ( exponents[ x ] == 0 ) && ( r.exponents[ y ] == 0 ) )
               temp.coefficients[ 0 ] += coefficients[ x ] * r.coefficients[ y ];
            else {
               temp.coefficients[ s ] = coefficients[ x ] * r.coefficients[ y ];
               temp.exponents[ s ] = exponents[ x ] + r.exponents[ y ];
               ++s;
            }

   polynomialCombine( temp );   // combine common terms
   return temp;
}

void Polynomial::polynomialCombine( Polynomial& w )
{
   Polynomial temp = w;
   int exp;

   // zero out elements of w
   for ( int x = 0; x < 100; ++x ) {
      w.coefficients[ x ] = 0;
      w.exponents[ x ] = 0;
   }

   for ( x = 1; x < 100; ++x ) {
      exp = temp.exponents[ x ];

      for ( int y = x + 1; y < 100; ++y )
         if ( exp == temp.exponents[ y ] ) {
            temp.coefficients[ x ] += temp.coefficients[ y ];
            temp.exponents[ y ] = 0;
            temp.coefficients[ y ] = 0;
         }
   }

   w = temp;
}

Polynomial &Polynomial::operator*=( const Polynomial& r )
{
   *this = *this * r;
   return *this;
}

void Polynomial::enterTerms( void )
{
   bool found = false;
   int numberOfTerms, c, e;

   cout << "\nEnter number of polynomial terms: ";
   cin >> numberOfTerms;

   for ( int n = 1; n <= numberOfTerms; ++n ) {
      cout << "\nEnter coefficient: ";
      cin >> c;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
260         cout << "Enter exponent: ";
261         cin >> e;
262
263         if ( c != 0 ) {
264            // exponents of zero are forced into first element
265            if ( e == 0 ) {
266               coefficients[ 0 ] += c;
267               continue;
268            }
269
270            for ( int term = 1; ( term < 100 ) &&
271                   ( coefficients[ term ] != 0 ); ++term )
272               if ( e == exponents[ term ] ) {
273                  coefficients[ term ] += c;
274                  exponents[ term ] = e;
275                  found = true;  // existing exponent updated
276               }
277
278            if ( !found ) {             // add term
279               coefficients[ term ] += c;
280               exponents[ term ] = e;
281            }
282         }
283      }
284   }
```

```
285   // driver for p8_19.cpp
286   #include <iostream>
287
288   using std::cout;
289   using std::endl;
290
291   #include "p8_19p.h"
292
293   int main()
294   {
295      Polynomial a, b, c, t;
296
297      a.enterTerms();
298      b.enterTerms();
299      t = a;   //save the value of a
300      cout << "First polynomial is:\n";
301      a.printPolynomial();
302      cout << "Second polynomial is:\n";
303      b.printPolynomial();
304      cout << "\nAdding the polynomials yields:\n";
305      c = a + b;
306      c.printPolynomial();
307      cout << "\n+= the polynomials yields:\n";
308      a += b;
309      a.printPolynomial();
310      cout << "\nSubtracting the polynomials yields:\n";
311      a = t;  // reset a to original value
312      c = a - b;
313      c.printPolynomial();
314      cout << "\n-= the polynomials yields:\n";
315      a -= b;
316      a.printPolynomial();
317      cout << "\nMultiplying the polynomials yields:\n";
318      a = t;  // reset a to original value
319      c = a * b;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   c.printPolynomial();
   cout << "\n*= the polynomials yields:\n";
   a *= b;
   a.printPolynomial();
   cout << endl;
   return 0;
}
```

```
Enter number of polynomial terms: 2

Enter coefficient: 2
Enter exponent: 2

Enter coefficient: 3
Enter exponent: 3

Enter number of polynomial terms: 3

Enter coefficient: 1
Enter exponent: 1

Enter coefficient: 2
Enter exponent: 2

Enter coefficient: 3
Enter exponent: 3
First polynomial is:
2x^2+3x^3
Second polynomial is:
1x+2x^2+3x^3

Adding the polynomials yields:
1x+4x^2+6x^3

+= the polynomials yields:
1x+4x^2+6x^3

Subtracting the polynomials yields:
-1x

-= the polynomials yields:
-1x

Multiplying the polynomials yields:
2x^3+7x^4+12x^5+9x^6

*= the polynomials yields:
2x^3+7x^4+12x^5+9x^6
```

8.20 The program of Fig. 8.3 contains the comment

```
// Overloaded stream-insertion operator (cannot be
// a member function if we would like to invoke it with
// cout << somePhoneNumber;)
```

Actually, it cannot be a member function of class **ostream**, but it can be a member function of class **PhoneNumber** if we were willing to invoke it in either of the following ways:

```
somePhoneNumber.operator<<( cout );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

or

```
somePhoneNumber << cout;
```

Rewrite the program of Fig. 8.3 with the overloaded stream-insertion **operator<<** as a member function and try the two preceding statements in the program to prove that they work.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Inheritance Solutions

Solutions

9.2 Consider the class **Bicycle**. Given your knowledge of some common components of bicycles, show a class hierarchy in which the class **Bicycle** inherits from other classes, which, in turn, inherit from yet other classes. Discuss the instantiation of various objects of class **Bicycle**. Discuss inheritance from class **Bicycle** for other closely related derived classes.

ANS: Possible classes are displayed in bold.

Bicycle composed of:
- **HandleBar**s
- **Seat**
- **Frame**
- **Wheel**s composed of:
  - **Tire**s
  - **Rim**s composed of:
    - **Spoke**s
- **Pedal**s
- **Chain** composed of:
  - **Link**s
- **Brake**s composed of:
  - **Wire**s
  - **BrakePad**s
  - **BrakeHandle**s

Classes that can be derived from **Bicycle** are **Unicycle**, **Tricycle**, **TandemBicycle**, etc.

9.3 Briefly define each of the following terms: inheritance, multiple inheritance, base class and derived class.

ANS:

inheritance: The process by which a class incorporates the attributes and behaviors of a previously defined class.

multiple inheritance: The process by which a class incorporates the attributes and behaviors of two or more previously defined classes.

base class: A class from which other classes inherit attributes and behaviors.

derived class: A class that has inherited attributes and behaviors from one or more base classes.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

9.4 Discuss why converting a base-class pointer to a derived-class pointer is considered dangerous by the compiler.
ANS: The pointer must "point" to the object of the derived class, before being dereferenced. When the compiler looks at an object through a derived-class pointer, it expects to see the all the pieces of the derived class. However, if the base-class pointer originally pointed to a base-class object, the additional pieces added by the derived class do not exist.

9.5 Distinguish between single inheritance and multiple inheritance.
ANS: Single inheritance inherits from one class only. Multiple inheritance inherits from two or more classes.

9.6 (True/False) A derived class is often called a subclass because it represents a subset of its base class (i.e., a derived class is generally smaller than its base class).
ANS: False. Derived classes are often larger than their base classes, because they need specific features in addition to those inherited from the base class. The term subclass means that the derived class is a more specific version of its base class. For example, a cat is a specific type of animal.

9.7 (True/False) A derived-class object is also an object of that derived class' base class.
ANS: True.

9.8 Some programmers prefer not to use **protected** access because it breaks the encapsulation of the base class. Discuss the relative merits of using **protected** access vs. insisting on using **private** access in base classes.
ANS: Inherited **private** data is hidden in the derived class and is accessible only through the **public** or **protected** member functions of the base class. Using **protected** access enables the derived class to manipulate the **protected** members without using the base class access functions. If the base class members are **private**, the **public** or **protected** member functions of the base class must be used to access **private** members. This can result in additional function calls—which can decrease performance.

9.9 Many programs written with inheritance could be solved with composition instead, and vice versa. Discuss the relative merits of these approaches in the context of the **Point**, **Circle**, **Cylinder** class hierarchy in this chapter. Rewrite the program of Fig. 9.10 (and the supporting classes) to use composition rather than inheritance. After you do this, reassess the relative merits of the two approaches both for the **Point**, **Circle**, **Cylinder** problem and for object-oriented programs in general.

```
1  // P9_09.H
2  #ifndef P9_09_H
3  #define P9_09_H
4
5  #include <iostream>
6  using std::ostream;
7
8  class Point {
9     friend ostream &operator<<( ostream &, const Point & );
10 public:
11    Point( double a = 0, double b = 0 ) { setPoint( a, b ); }
12    void setPoint( double, double );
13    void print( void ) const;
14    double getX( void ) const { return x; }
15    double getY( void ) const { return y; }
16 private:
17    double x, y;
18 };
19
20 #endif
```

```
21 // P9_09PM.cpp
22 // Member functions for class Point
23 #include <iostream>
24
25 using std::cout;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
using std::ostream;

#include "p9_09.h"

void Point::setPoint( double a, double b )
{
   x = a;
   y = b;
}

ostream &operator<<( ostream &output, const Point &p )
{
   p.print();
   return output;
}

void Point::print( void ) const
   { cout << '[' << getX() << ", " << getY() << ']'; }
```

```
// P9_09C.H
#ifndef P9_09C_H
#define P9_09C_H
#include "p9_09.h"

class Circle {
   friend ostream &operator<<( ostream &, const Circle & );
public:
   Circle( double = 0.0, double = 0.0, double = 0.0 );
   void setRadius( double r ) { radius = r; }
   double getRadius( void ) const { return radius; }
   double area( void ) const;
   void print( void ) const;
private:
   double radius;
   Point pointObject;
};

#endif
```

```
// P9_09CM.cpp
// Member function definitions for class Circle
#include <iostream>

using std::cout;
using std::ios;

#include <iomanip>

using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

#include "p9_09c.h"

Circle::Circle( double r, double a, double b ) : pointObject( a, b )
   { setRadius( r ); }

double Circle::area( void ) const
   { return 3.14159 * getRadius() * getRadius(); }

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
ostream &operator<<( ostream &output, const Circle &c )
{
   c.print();
   return output;
}

void Circle::print( void ) const
{
   cout << "Center = ";
   pointObject.print();
   cout << "; Radius = " << setiosflags( ios::fixed | ios::showpoint )
        << setprecision( 2 ) << getRadius()
        << resetiosflags( ios::fixed | ios::showpoint );
}
```

```
// P9_09CY.H
#ifndef P9_09CY_H
#define P9_09CY_H
#include "p9_09.h"
#include "p9_09c.h"

class Cylinder {
   friend ostream& operator<<(ostream&, const Cylinder&);
public:
   Cylinder(double = 0.0, double = 0.0, double = 0.0, double = 0.0);
   void setHeight(double h) { height = h; }
   double getHeight(void) const { return height; }
   void print(void) const;
   double area(void) const;
   double volume(void) const;
private:
   double height;
   Circle circleObject;
};

#endif
```

```
// P9_09CYM.cpp
// Member function definitions for class Cylinder.
#include <iostream>

using std::cout;
using std::ostream;

#include "p9_09cy.h"

Cylinder::Cylinder( double h, double r, double x, double y )
   : circleObject( r, x, y ) { height = h; }

double Cylinder::area( void ) const
   { return 2 * circleObject.area() + 2 * 3.14159 *
     circleObject.getRadius() * getHeight(); }

ostream& operator<<( ostream &output, const Cylinder& c )
{
   c.print();
   return output;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
140
141 double Cylinder::volume( void ) const
142    { return circleObject.area() * getHeight(); }
143
144 void Cylinder::print( void ) const
145 {
146    circleObject.print();
147    cout << "; Height = " << getHeight() << '\n';
148 }
```

```
149 // P9_09.cpp
150 #include <iostream>
151
152 using std::cout;
153 using std::endl;
154
155 #include "p9_09.h"
156 #include "p9_09c.h"
157 #include "p9_09cy.h"
158
159 int main()
160 {
161    Point p( 1.1, 8.5 );
162    Circle c( 2.0, 6.4, 9.8 );
163    Cylinder cyl( 5.7, 2.5, 1.2, 2.3 );
164
165    cout << "Point: " << p << "\nCircle: " << c
166         << "\nCylinder: " << cyl << endl;
167
168    return 0;
169 }
```

```
Point: [1.1, 8.5]
Circle: Center = [6.4, 9.8]; Radius = 2.00
Cylinder: Center = [1.2, 2.3]; Radius = 2.50; Height = 5.7
```

9.10 Rewrite the **Point**, **Circle**, **Cylinder** program of Fig. 9.10 as a **Point**, **Square**, **Cube** program. Do this two ways—once with inheritance and once with composition.

```
1  // P9_10.H
2  #ifndef P9_10_H
3  #define P9_10_H
4
5  #include <iostream>
6  using std::ostream;
7
8  class Point {
9     friend ostream &operator<<( ostream&, const Point& );
10 public:
11    Point( double = 0, double = 0, double = 0 );
12    void setPoint( double, double, double );
13    double getX( void ) const { return x; }
14    double getY( void ) const { return y; }
15    double getZ( void ) const { return z; }
16 private:
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   double x, y, z;
};

#endif
```

```
//P9_10MP.cpp
// member function defintions for class Point
#include <iostream>

using std::cout;
using std::ios;
using std::ostream;

#include <iomanip>

using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

#include "p9_10.h"

Point::Point( double a, double b, double c) { setPoint( a, b, c ); }

void Point::setPoint( double a, double b, double c )
{
   x = a;
   y = b;
   z = c;
}

ostream &operator<<( ostream &output, const Point &p )
{
   output << setiosflags( ios::fixed | ios::showpoint )
          << "The point is: [" << setprecision( 2 ) << p.x
          << ", " << setprecision( 2 ) << p.y << setprecision( 2 )
          << ", " << p.z << "]\n"
          << resetiosflags( ios::fixed | ios::showpoint );

   return output;
}
```

```
//P9_10S.H
#ifndef P9_10S_H
#define P9_10S_H
#include "p9_10.h"

#include <iostream>
using std::ostream;

class Square : public Point {
   friend ostream &operator<<( ostream &, const Square & );
public:
   Square( double = 0, double = 0, double = 0, double = 1.0 );
   void setSide( double s) { side = s > 0 && s <= 20.0 ? s : 1.0; }
   double area( void ) const { return side * side; }
   double getSide( void ) const { return side; }
protected:
   double side;
};

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#endif
```

```
//P9_10MS.cpp
//member functions for class Square
#include <iostream>

using std::cout;
using std::ios;
using std::ostream;

#include <iomanip>

using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

#include "p9_10s.h"

Square::Square( double x, double y, double z, double s ) : Point( x, y, z )
   { setSide( s ); }

ostream &operator<<( ostream &output, const Square &s )
{
   output << setiosflags( ios::fixed | ios::showpoint )
          << "The lower left coordinate of the square is: ["
          << setprecision( 2 ) << s.getX() << ", " << setprecision( 2 )
          << s.getY() << ", " << setprecision( 2 ) << s.getZ() << ']'
          << "\nThe square side is: " << setprecision( 2 ) << s.side
          << "\nThe area of the square is: " << setprecision( 2 )
          << s.area() << '\n'
          << resetiosflags( ios::fixed | ios::showpoint );

   return output;
}
```

```
// P9_10C.H
#ifndef P9_10C_H
#define P9_10C_H
#include "p9_10s.h"

#include <iostream>
using std::ostream;

class Cube : public Square {
   friend ostream &operator<<( ostream&, const Cube& );
public:
   Cube( double = 0, double = 0, double = 0, double = 1.0 );
   double area( void ) const { return 6 * Square::area(); }
   double volume( void ) const { return Square::area() * getSide(); }
};

#endif
```

```
//P9_10MC.cpp
//member function definitions for class Cube
#include <iostream>

using std::cout;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
130 using std::ios;
131 using std::ostream;
132
133 #include <iomanip>
134
135 using std::setprecision;
136 using std::setiosflags;
137 using std::resetiosflags;
138
139 #include "p9_10c.h"
140
141 Cube::Cube( double j, double k, double m, double s ) : Square( j, k, m, s ) { }
142
143 ostream &operator<<( ostream &output, const Cube &c )
144 {
145    output << setiosflags( ios::fixed | ios::showpoint )
146           << "The lower left coordinate of the cube is: ["
147           << setprecision( 2 ) << c.getX() << ", " << setprecision( 2 )
148           << c.getY() << ", " << setprecision( 2 ) << c.getZ()
149           << "]\nThe cube side is: " << setprecision( 2 ) << c.side
150           << "\nThe surface area of the cube is: " << setprecision( 2 )
151           << c.area() << "\nThe volume of the cube is: "
152           << setprecision( 2 ) << c.volume()
153           << resetiosflags( ios::showpoint | ios::fixed ) << '\n';
154
155    return output;
156 }
```

```
157 // driver for p9_10.cpp
158 #include <iostream>
159
160 using std::cout;
161
162 #include "p9_10.h"
163 #include "p9_10s.h"
164 #include "p9_10c.h"
165
166 int main()
167 {
168    Point p( 7.9, 12.5, 8.8 );
169    Square s( 0.0, 0.0, 0.0, 5.0 );
170    Cube c( 0.5, 8.3, 12.0, 2.0 );
171
172    cout << p << '\n' << s << '\n' << c << '\n';
173
174    return 0;
175 }
```

```
The point is: [7.90, 12.50, 8.80]

The lower left coordinate of the square is: [0.00, 0.00, 0.00]
The square side is: 5.00
The area of the square is: 25.00

The lower left coordinate of the cube is: [0.50, 8.30, 12.00]
The cube side is: 2.00
The surface area of the cube is: 24.00
The volume of the cube is: 8.00
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// P9_10B.H
#ifndef P9_10B_H
#define P9_10B_H

#include <iostream>
using std::ostream;

class Point {
   friend ostream &operator<<( ostream&, const Point& );
public:
   Point( double = 0, double = 0, double = 0 );
   void setPoint( double, double, double );
   void print( void ) const;
   double getX( void ) const { return x; }
   double getY( void ) const { return y; }
   double getZ( void ) const { return z; }
private:
   double x, y, z;
};

#endif
```

```
//P9_10BMP.cpp
// member function defintions for class Point
#include <iostream>

using std::cout;
using std::ios;
using std::ostream;

#include <iomanip>

using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

#include "p9_10b.h"

Point::Point( double a, double b, double c ) { setPoint( a, b, c ); }

void Point::setPoint( double a, double b, double c )
{
   x = a;
   y = b;
   z = c;
}

ostream &operator<<( ostream &output, const Point &p )
{
   output << "The point is: ";
   p.print();
   return output;
}

void Point::print( void ) const
{
   cout << setiosflags( ios::fixed | ios::showpoint )
        << '[' << setprecision( 2 ) << getX()
        << ", " << setprecision( 2 ) << getY() << setprecision( 2 )
        << ", " << getZ() << "]\n"
        << resetiosflags( ios::fixed | ios::showpoint );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}
```

```
//P9_10BS.H
#ifndef P9_10BS_H
#define P9_10BS_H
#include "p9_10B.h"

#include <iostream>
using std::ostream;

class Square {
   friend ostream &operator<<( ostream &, const Square & );
public:
   Square( double = 0, double = 0, double = 0, double = 1.0 );
   void setSide( double s ) { side = s > 0 && s <= 20.0 ? s : 1.0; }
   void print( void ) const;
   double getXCoord() const { return pointObject.getX(); }
   double getYCoord() const { return pointObject.getY(); }
   double getZCoord() const { return pointObject.getZ(); }
   double area( void ) const { return side * side; }
   double getSide( void ) const { return side; }
protected:
   double side;
   Point pointObject;
};

#endif
```

```
//P9_10BMS.cpp
//member functions for class Square
#include <iostream>

using std::cout;
using std::ios;
using std::ostream;

#include <iomanip>

using std::setprecision;
using std::setiosflags;

#include "p9_10bs.h"

Square::Square( double x, double y, double z, double s )
       : pointObject( x, y, z )
   { setSide( s ); }

ostream &operator<<( ostream &output, const Square &s )
{
   s.print();
   return output;
}

void Square::print( void ) const
{
   cout << setiosflags( ios::fixed | ios::showpoint )
        << "The lower left coordinate of the square is: ";
   pointObject.print();
   cout << "The square side is: " << setprecision( 2 ) << getSide()
        << "\nThe area of the square is: " << setprecision( 2 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
119         << area() << '\n';
120 }
```

```
121 // P9_10BC.H
122 #ifndef P9_10BC_H
123 #define P9_10BC_H
124 #include "p9_10bs.h"
125
126 #include <iostream>
127 using std::ostream;
128
129 class Cube {
130    friend ostream &operator<<( ostream&, const Cube& );
131 public:
132    Cube( double = 0, double = 0, double = 0, double = 1.0 );
133    void print( void ) const;
134    double area( void ) const;
135    double volume( void ) const;
136 private:
137    Square squareObject;
138 };
139
140 #endif
```

```
141 //P9_10BMC.cpp
142 //member function definitions for class Cube
143 #include <iostream>
144
145 using std::cout;
146 using std::ios;
147 using std::ostream;
148
149 #include <iomanip>
150
151 using std::setprecision;
152 using std::setiosflags;
153
154 #include "p9_10bc.h"
155
156 Cube::Cube( double j, double k, double m, double s )
157      : squareObject( j, k, m, s ) { }
158
159 ostream &operator<<( ostream &output, const Cube &c )
160 {
161    c.print();
162    return output;
163 }
164
165 void Cube::print( void ) const
166 {
167    cout << setiosflags( ios::fixed | ios::showpoint )
168         << "The lower left coordinate of the cube is: [" << setprecision( 2 )
169         << squareObject.getXCoord() << ", " << setprecision( 2 )
170         << squareObject.getYCoord() << ", " << setprecision( 2 )
171         << squareObject.getZCoord() << "]\nThe cube side is: "
172         << setprecision( 2 ) << squareObject.getSide()
173         << "\nThe surface area of the cube is: " << setprecision( 2 ) << area()
174        << "\nThe volume of the cube is: " << setprecision( 2 ) << volume() << '\n';
175 }
176
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
177 double Cube::area( void ) const  { return 6 * squareObject.area(); }
178
179 double Cube::volume( void ) const
180    { return squareObject.area() * squareObject.getSide(); }
```

```
181 // driver for p9_10b.cpp
182 #include <iostream>
183
184 using std::cout;
185 using std::endl;
186
187 #include "p9_10b.h"
188 #include "p9_10bs.h"
189 #include "p9_10bc.h"
190
191 int main()
192 {
193    Point p( 7.9, 12.5, 8.8 );
194    Square s( 0.0, 0.0, 0.0, 5.0 );
195    Cube c( 0.5, 8.3, 12.0, 2.0 );
196
197    cout << p << '\n' << s << '\n' << c << endl;
198
199    return 0;
200 }
```

```
The point is: [7.90, 12.50, 8.80]

The lower left coordinate of the square is: [0.00, 0.00, 0.00]
The square side is: 5
The area of the square is: 25

The lower left coordinate of the cube is: [0.50, 8.30, 12.00]
The cube side is: 2.00
The surface area of the cube is: 24.00
The volume of the cube is: 8.00
```

9.11 In the chapter, we stated, "When a base-class member is inappropriate for a derived class, that member can be overridden in the derived class with an appropriate implementation." If this is done, does the derived-class-is-a-base-class-object relationship still hold? Explain your answer.

9.12 Study the inheritance hierarchy of Fig. 9.2. For each class, indicate some common attributes and behaviors consistent with the hierarchy. Add some other classes (e.g., **UndergraduateStudent**, **GraduateStudent**, **Freshman**, **Sophomore**, **Junior**, **Senior**, etc.) to enrich the hierarchy.

9.13 Write an inheritance hierarchy for class **Quadrilateral**, **Trapezoid**, **Parallelogram**, **Rectangle** and **Square**. Use **Quadrilateral** as the base class of the hierarchy. Make the hierarchy as deep (i.e., as many levels) as possible. The **private** data of **Quadrilateral** should be the (*x*, *y*) coordinate pairs for the four endpoints of the **Quadrilateral**. Write a driver program that instantiates and displays objects of each of these classes.

```
1 // P9_13.H
2 #ifndef P9_13_H
3 #define P9_13_H
4
5 #include <iostream>
6 using std::ostream;
7
8 class Point {
9    friend ostream &operator<<( ostream&, const Point& );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
10 public:
11    Point( double = 0, double = 0 );
12    void setPoint( double, double );
13    void print( void ) const;
14    double getX( void ) const { return x; }
15    double getY( void ) const { return y; }
16 private:
17    double x, y;
18 };
19
20 #endif
```

```
21 //P9_13PM.cpp
22 // member function defintions for class Point
23 #include <iostream>
24
25 using std::cout;
26 using std::ios;
27 using std::ostream;
28
29 #include <iomanip>
30
31 using std::setprecision;
32 using std::setiosflags;
33 using std::resetiosflags;
34
35 #include "p9_13.h"
36
37 Point::Point( double a, double b ) { setPoint( a, b ); }
38
39 void Point::setPoint( double a, double b )
40 {
41    x = a;
42    y = b;
43 }
44
45 ostream &operator<<( ostream &output, const Point &p )
46 {
47    output << "The point is: ";
48    p.print();
49    return output;
50 }
51
52 void Point::print( void ) const
53 {
54    cout << setiosflags( ios::fixed | ios::showpoint )
55         << '[' << setprecision( 2 ) << getX()
56         << ", " << setprecision( 2 ) << getY() << "]\n"
57         << resetiosflags( ios::fixed | ios::showpoint );
58 }
```

```
59 // P9_13Q.H
60 #ifndef P9_13Q_H
61 #define P9_13Q_H
62 #include "p9_13.h"
63
64 #include <iostream>
65 using std::ostream;
66
67 class Quadrilateral {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
68    friend ostream &operator<<( ostream&, Quadrilateral& );
69 public:
70    Quadrilateral( double = 0, double = 0, double = 0, double = 0, double = 0,
71                   double = 0, double = 0, double = 0 );
72    void print( void ) const;
73 protected:
74    Point p1;
75    Point p2;
76    Point p3;
77    Point p4;
78 };
79
80 #endif
```

```
81 // P9_13QM.cpp
82 // member functions for class Quadrilateral
83 #include "p9_13q.h"
84
85 #include <iostream>
86 using std::cout;
87 using std::ostream;
88
89 Quadrilateral::Quadrilateral( double x1, double y1, double x2, double y2,
90                               double x3, double y3, double x4, double y4 )
91    : p1( x1, y1 ), p2( x2, y2 ), p3( x3, y3 ), p4( x4, y4 )  { }
92
93 ostream &operator<<( ostream& output, Quadrilateral& q )
94 {
95    output << "Coordinates of Quadrilateral are:\n";
96    q.print();
97    output << '\n';
98    return output;
99 }
100
101 void Quadrilateral::print( void ) const
102 {
103    cout << '(' << p1.getX()
104         << ", " << p1.getY() << ") , (" << p2.getX() << ", " << p2.getY()
105         << ") , (" << p3.getX() << ", " << p3.getY() << ") , ("
106         << p4.getX() << ", " << p4.getY() << ")\n";
107 }
```

```
108 // P9_13T.H
109 #ifndef P9_13T_H
110 #define P9_13T_H
111 #include "p9_13q.h"
112
113 #include <iostream>
114 using std::ostream;
115
116 class Trapazoid : public Quadrilateral {
117    friend ostream& operator<<( ostream&, Trapazoid& );
118 public:
119    Trapazoid( double = 0, double = 0, double = 0, double = 0, double = 0,
120               double = 0, double = 0, double = 0, double = 0 );
121    void print( void ) const;
122    void setHeight( double h ) { height = h; }
123    double getHeight( void ) const { return height; }
124 private:
125    double height;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
126 };
127
128 #endif
```

```
129 // P9_13TM.cpp
130 // member function definitions for class Trapazoid
131 #include "p9_13t.h"
132
133 #include <iostream>
134
135 using std::cout;
136 using std::ostream;
137
138
139 Trapazoid::Trapazoid( double h, double x1, double y1, double x2, double y2,
140                       double x3, double y3, double x4, double y4 )
141           : Quadrilateral( x1, y1, x2, y2, x3, y3, x4, y4 )
142 { setHeight( h ); }
143
144 ostream& operator<<( ostream& out, Trapazoid& t )
145 {
146    out << "The Coordinates of the Trapazoid are:\n";
147    t.print();
148    return out;
149 }
150
151 void Trapazoid::print( void ) const
152 {
153    Quadrilateral::print();
154    cout << "Height is : " << getHeight() << "\n\n";
155 }
```

```
156 // P9_13PA_H
157 #ifndef P9_13PA_H
158 #define P9_13PA_H
159 #include "p9_13q.h"
160
161 #include <iostream>
162 using std::ostream;
163
164 class Parallelogram : public Quadrilateral {
165    friend ostream& operator<<( ostream&, Parallelogram& );
166 public:
167    Parallelogram( double = 0, double = 0, double = 0, double = 0,
168                   double = 0, double = 0, double = 0, double = 0 );
169    void print( void ) const;
170 private:
171    // no private data members
172 };
173
174 #endif
```

```
175 // P9_13PAM.cpp
176 #include "p9_13q.h"
177 #include "p9_13pa.h"
178
179 #include <iostream>
180 using std::ostream;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
181
182 Parallelogram::Parallelogram( double x1, double y1, double x2, double y2,
183                               double x3, double y3, double x4, double y4 )
184               : Quadrilateral( x1, y1, x2, y2, x3, y3, x4, y4 ) { }
185
186 ostream& operator<<( ostream& out, Parallelogram& pa )
187 {
188    out << "The coordinates of the Parallelogram are:\n";
189    pa.print();
190    return out;
191 }
192
193 void Parallelogram::print( void ) const
194    {   Quadrilateral::print();   }
```

```
195 // P9_13R.H
196 #ifndef P9_13R_H
197 #define P9_13R_H
198 #include "p9_13pa.h"
199
200 #include <iostream>
201 using std::ostream;
202
203 class Rectangle : public Parallelogram {
204    friend ostream& operator<<( ostream&, Rectangle& );
205 public:
206    Rectangle( double = 0, double = 0, double = 0, double = 0,
207               double = 0, double = 0, double = 0, double = 0 );
208    void print( void ) const;
209 private:
210    // no private data members
211 };
212
213 #endif
```

```
214 // P9_13RM.cpp
215 #include "p9_13r.h"
216 #include "p9_13pa.h"
217
218 #include <iostream>
219 using std::ostream;
220
221 Rectangle::Rectangle( double x1, double y1, double x2, double y2,
222                       double x3, double y3, double x4, double y4 )
223    : Parallelogram( x1, y1, x2, y2, x3, y3, x4, y4 ) { }
224
225 ostream& operator<<( ostream& out, Rectangle& r )
226 {
227    out << "\nThe coordinates of the Rectangle are:\n";
228    r.print();
229    return out;
230 }
231
232 void Rectangle::print( void ) const
233    {   Parallelogram::print(); }
```

```
234 / P9_13RH.H
235 #ifndef P9_13RH_H
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#define P9_13RH_H
#include "p9_13pa.h"

#include <iostream>
using std::ostream;

class Rhombus : public Parallelogram {
   friend ostream& operator<<(ostream&, Rhombus&);
public:
   Rhombus( double = 0, double = 0, double = 0, double = 0,
            double = 0, double = 0, double = 0, double = 0 );
   void print( void ) const { Parallelogram::print(); }
private:
   // no private data members
};

#endif
```

```
//P9_13HM.cpp
#include "p9_13rh.h"
#include "p9_13pa.h"

#include <iostream>
using std::ostream;

Rhombus::Rhombus( double x1, double y1, double x2, double y2,
                  double x3, double y3, double x4, double y4 )
   : Parallelogram( x1, y1, x2, y2, x3, y3, x4, y4 ) { }

ostream& operator<<( ostream& out, Rhombus& r )
{
   out << "\nThe coordinates of the Rhombus are:\n";
   r.print();
   return out;
}
```

```
// P9_13S.H
#ifndef P9_13S_H
#define P9_13S_H
#include "p9_13pa.h"

#include <iostream>
using std::ostream;

class Square : public Parallelogram {
   friend ostream& operator<<( ostream&, Square& );
public:
   Square( double = 0, double = 0, double = 0, double = 0,
           double = 0, double = 0, double = 0, double = 0 );
   void print( void ) const { Parallelogram::print(); }
private:
   // no private data members
};

#endif
```

```
// P9_13SM.cpp
#include "p9_13s.h"
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#include "p9_13pa.h"

#include <iostream>
using std::ostream;

Square::Square( double x1, double y1, double x2, double y2,
                double x3, double y3, double x4, double y4 )
   : Parallelogram( x1, y1, x2, y2, x3, y3, x4, y4 ) { }

ostream& operator<<( ostream& out, Square& s )
{
   out << "\nThe coordinates of the Square are:\n";
   s.print();
   return out;
}
```

```
// P9_13.cpp
#include "p9_13.h"
#include "p9_13q.h"
#include "p9_13t.h"
#include "p9_13pa.h"
#include "p9_13rh.h"
#include "p9_13r.h"
#include "p9_13s.h"

#include <iostream>
using std::cout;
using std::endl;

int main()
{
   // NOTE: All coordinates are assumed to form the proper shapes

   // A quadrilateral is a four-sided polygon
   Quadrilateral q( 1.1, 1.2, 6.6, 2.8, 6.2, 9.9, 2.2, 7.4 );
   // A trapazoid is a quadrilateral having two and only two parallel sides
   Trapazoid t( 5.0, 0.0, 0.0, 10.0, 0.0, 8.0, 5.0, 3.3, 5.0 );
   // A parallelogram is a quadrilateral whose opposite sides are parallel
   Parallelogram p( 5.0, 5.0, 11.0, 5.0, 12.0, 20.0, 6.0, 20.0 );
   // A rhombus is an equilateral parallelogram
   Rhombus rh( 0.0, 0.0, 5.0, 0.0, 8.5, 3.5, 3.5, 3.5 );
   // A rectangle is an equiangular parallelogram
   Rectangle r( 17.0, 14.0, 30.0, 14.0, 30.0, 28.0, 17.0, 28.0 );
   // A square is an equiangular and equilateral parallelogram
   Square s( 4.0, 0.0, 8.0, 0.0, 8.0, 4.0, 4.0, 4.0 );

   cout << q << t << p << rh << r << s << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Coordinates of Quadrilateral are:
(1.1, 1.2) , (6.6, 2.8) , (6.2, 9.9) , (2.2, 7.4)

The Coordinates of the Trapazoid are:
(0, 0) , (10, 0) , (8, 5) , (3.3, 5)
Height is : 5

The coordinates of the Parallelogram are:
(5, 5) , (11, 5) , (12, 20) , (6, 20)

The coordinates of the Rhombus are:
(0, 0) , (5, 0) , (8.5, 3.5) , (3.5, 3.5)

The coordinates of the Rectangle are:
(17, 14) , (30, 14) , (30, 28) , (17, 28)

The coordinates of the Square are:
(4, 0) , (8, 0) , (8, 4) , (4, 4)
```

9.14 Write down all the shapes you can think of—both two-dimensional and three-dimensional—and form those shapes into a shape hierarchy. Your hierarchy should have base class **`Shape`** from which class **`TwoDimensionalShape`** and class **`ThreeDimensionalShape`** are derived. Once you have developed the hierarchy, define each of the classes in the hierarchy. We will use this hierarchy in the exercises of Chapter 10 to process all shapes as objects of base-class **`Shape`**. This is a technique called polymorphism.

ANS: Shape
- TwoDimensionalShape
  - Quadrilateral
    - Parallelogram
      - Rectangle
        - Square
      - Rhombus
  - Ellipse
    - Circle
  - Triangle
    - RightTriangle
    - EquilateralTriangle
    - IsocelesTriangle
  - Parabola
  - Line
  - Hyperbola
- ThreeDimensionalShape
  - Ellipsoid
    - Sphere
  - Prism
  - Cylinder
  - Cone
  - Cube
  - Tetrahedron
  - Hyperboloid
    - OneSheetHyperboloid
    - TwoSheetHyperboloid
  - Plane

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

10

Virtual Functions and Polymorphism Solutions

Solutions

10.2 What are **`virtual`** functions? Describe a circumstance in which **`virtual`** functions would be appropriate.

ANS: Virtual functions are functions with the same function prototype that are defined throughout a class hierarchy. At least the base class occurrence of the function is preceded by the keyword **`virtual`**. Virtual functions are used to enable generic processing of an entire class hierarchy of objects through a base class pointer. For example, in a shape hierarchy, all shapes can be drawn. If all shapes are derived from a base class **`Shape`** which contains a **`virtual draw`** function, then generic processing of the hierarchy can be performed by calling every shape's **`draw`** generically through a base class **`Shape`** pointer.

10.3 Given that constructors cannot be **`virtual`**, describe a scheme for how you might achieve a similar effect.

ANS: Create a virtual function called **`initialize`** that the constructor invokes.

10.4 How is it that polymorphism enables you to program "in the general" rather than "in the specific." Discuss the key advantages of programming "in the general."

ANS: Polymorphism enables the programmer to concentrate on the processing of common operations that are applied to all data types in the system without going into the individual details of each data type. The general processing capabilities are separated from the internal details of each type.

10.5 Discuss the problems of programming with **`switch`** logic. Explain why polymorphism is an effective alternative to using **`switch`** logic.

ANS: The main problem with programming using the **`switch`** structure is extensibility and maintainability of the program. A program containing many **`switch`** structures is difficult to modify. Many, but not necessarily all, **`switch`** structures will need to add or remove cases for a specified type. Note: switch logic includes if/else structures which are more flexible than the **`switch`** structure.

10.6 Distinguish between static binding and dynamic binding. Explain the use of **`virtual`** functions and the vtable in dynamic binding.

ANS: Static binding is performed at compile-time when a function is called via a specific object or via a pointer to an object. Dynamic binding is performed at run-time when a **`virtual`** function is called via a base class pointer to a derived class object (the object can be of any derived class). The **`virtual`** functions table (vtable) is used at run-time to enable the proper function to be called for the object to which the base class pointer "points". Each class containing **`virtual`** functions has its own vtable that specifies where the **`virtual`** functions for that class are located. Every object of a class with **`virtual`** functions contains a hidden pointer to the class's vtable. When a **`virtual`** function is called via a base class pointer, the hidden pointer is dereferenced to locate the vtable, then the vtable is searched for the proper function call.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

10.7 Distinguish between inheriting interface and inheriting implementation. How do inheritance hierarchies designed for inheriting interface differ from those designed for inheriting implementation?

ANS: When a class inherits implementation, it inherits previously defined functionality from another class. When a class inherits interface, it inherits the definition of what the interface to the new class type should be. The implementation is then provided by the programmer defining the new class type. Inheritance hierarchies designed for inheriting implementation are used to reduce the amont of new code that is being written. Such hierarchies are used to facilitate software reusability. Inheritance hierarchies designed for inheriting interface are used to write programs that perform generic processing of many class types. Such hierarchies are commonly used to facilitate software extensibility (i.e., new types can be added to the hierarchy without changing the generic processing capabilitiesof the program.)

10.8 Distinguish between **`virtual`** functions and pure **`virtual`** functions.

ANS: A **`virtual`** function must have a definition in the class in which it is declared. A pure **`virtual`** function does not provide a definition. Classes derived directly from the abstract class must provide definitions for the inherited pure **`virtual`** functions in order to avoid becoming an abstract base class.

10.9 (True/False) All **`virtual`** functions in an abstract base class must be declared as pure **`virtual`** functions.

ANS: False.

10.10 Suggest one or more levels of abstract base classes for the **`Shape`** hierarchy discussed in this chapter (the first level is **`Shape`** and the second level consists of the classes **`TwoDimensionalShape`** and **`ThreeDimensionalShape`**).

10.11 How does polymorphism promote extensibility?

ANS: Polymorphism makes programs more extensible by making all function calls generic. When a new class type with the appropriate **`virtual`** functions is added to the hierarchy, no changes need to be made to the generic function calls.

10.12 You have been asked to develop a flight simulator that will have elaborate graphical outputs. Explain why polymorphic programming would be especially effective for a problem of this nature.

10.13 Develop a basic graphics package. Use the **`Shape`** class inheritance hierarchy from Chapter 9. Limit yourself to two-dimensional shapes such as squares, rectangles, triangles and circles. Interact with the user. Let the user specify the position, size, shape and fill characters to be used in drawing each shape. The user can specify many items of the same shape. As you create each shape, place a **`Shape *`** pointer to each new **`Shape`** object into an array. Each class has its own **`draw`** member function. Write a polymorphic screen manager that walks through the array (preferably using an iterator) sending **`draw`** messages to each object in the array to form a screen image. Redraw the screen image each time the user specifies an additional shape.

10.14 Modify the payroll system of Fig. 10.1 to add private data members **`birthDate`** (a **`Date`** object) and **`departmentCode`** (an **`int`**) to class **`Employee`**. Assume this payroll is processed once per month. Then, as your program calculates the payroll for each **`Employee`** (polymorphically), add a $100.00 bonus to the person's payroll amount if this is the month in which the **`Employee`**'s birthday occurs.

```
// EMPLOY.H
// Abstract base class Employee
#ifndef EMPLOY_H
#define EMPLOY_H

#include "date.h"

class Employee {
public:
   Employee( const char * const, const char * const,
             int, int, int, int);
   ~Employee();
   const char *getFirstName() const;
   const char *getLastName() const;
   Date getBirthDate() const;
   int getDepartmentCode() const;

   // Pure virtual functions make Employee abstract base class.
   virtual double earnings() const = 0; // pure virtual
   virtual void print() const = 0;      // pure virtual
private:
   char *firstName;
   char *lastName;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   Date birthDate;
   int departmentCode;
};

#endif
```

```
// EMPLOY.CPP
// Member function definitions for
// abstract base class Employee.
//
// Note: No definitions given for pure virtual functions.

#include <cstring>

#include <assert.h>
#include "employ.h"

// Constructor dynamically allocates space for the
// first and last name and uses strcpy to copy
// the first and last names into the object.
Employee::Employee( const char * const first, const char * const last,
                    int mn, int dy, int yr, int dept )
   birthDate( mn, dy, yr ), departmentCode( dept )
{
   firstName = new char[ strlen( first ) + 1 ];
   assert( firstName != 0 );    // test that new worked
   strcpy( firstName, first );

   lastName = new char[ strlen( last ) + 1 ];
   assert( lastName != 0 );     // test that new worked
   strcpy( lastName, last );
}

// Destructor deallocates dynamically allocated memory
Employee::~Employee()
{
   delete [] firstName;
   delete [] lastName;
}

// Return a pointer to the first name
const char *Employee::getFirstName() const
{
   // Const prevents caller from modifying private data.
   // Caller should copy returned string before destructor
   // deletes dynamic storage to prevent undefined pointer.

   return firstName;   // caller must delete memory
}

// Return a pointer to the last name
const char *Employee::getLastName() const
{
   // Const prevents caller from modifying private data.
   // Caller should copy returned string before destructor
   // deletes dynamic storage to prevent undefined pointer.

   return lastName;   // caller must delete memory
}

// Return the employee's birth date
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Date Employee::getBirthDate() const { return birthDate; }

// Return the employee's department code
int Employee::getDepartmentCode() const { return departmentCode; }
```

```
// BOSS.H
// Boss class derived from Employee
#ifndef BOSS_H
#define BOSS_H
#include "employ.h"

class Boss : public Employee {
public:
   Boss( const char * const, const char * const, int, int, int,
         double = 0.0, int = 0 );
   void setWeeklySalary( double );
   virtual double earnings() const;
   virtual void print() const;
private:
   double weeklySalary;
};

#endif
```

```
// BOSS.CPP
// Member function definitions for class Boss
#include <iostream>

using std::cout;

#include "boss.h"

// Constructor function for class Boss
Boss::Boss( const char * const first, const char * const last,
            int mn, int dy, int yr, double s, int dept )
   : Employee( first, last, mn, dy, yr, dept )
{ weeklySalary = s > 0 ? s : 0; }

// Set the Boss's salary
void Boss::setWeeklySalary( double s )
   { weeklySalary = s > 0 ? s : 0; }

// Get the Boss's pay
double Boss::earnings() const { return weeklySalary; }

// Print the Boss's name
void Boss::print() const
{
   cout << "\nBoss: " << getFirstName()
        << ' ' << getLastName();
}
```

```
// HOURLY.H
// Definition of class HourlyWorker
#ifndef HOURLY_H
#define HOURLY_H
#include "employ.h"

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
139 class HourlyWorker : public Employee {
140 public:
141    HourlyWorker( const char * const, const char * const, int, int, int,
142                  double = 0.0, double = 0.0, int = 0 );
143    void setWage( double );
144    void setHours( double );
145    virtual double earnings() const;
146    virtual void print() const;
147 private:
148    double wage;   // wage per hour
149    double hours;  // hours worked for week
150 };
151
152 #endif
```

```
153 // HOURLY.CPP
154 // Member function definitions for class HourlyWorker
155 #include <iostream>
156
157 using std::cout;
158
159 #include "hourly.h"
160
161 // Constructor for class HourlyWorker
162 HourlyWorker::HourlyWorker( const char * const first, const char * const last,
163                             int mn, int dy, int yr, double w, double h, int dept )
164      : Employee( first, last, mn, dy, yr, dept )
165 {
166    wage = w > 0 ? w : 0;
167    hours = h >= 0 && h < 168 ? h : 0;
168 }
169
170 // Set the wage
171 void HourlyWorker::setWage( double w ) { wage = w > 0 ? w : 0; }
172
173 // Set the hours worked
174 void HourlyWorker::setHours( double h )
175    { hours = h >= 0 && h < 168 ? h : 0; }
176
177 // Get the HourlyWorker's pay
178 double HourlyWorker::earnings() const { return wage * hours; }
179
180 // Print the HourlyWorker's name
181 void HourlyWorker::print() const
182 {
183    cout << "\nHourly worker: " << getFirstName()
184         << ' ' << getLastName();
185 }
```

```
186 // PIECE.H
187 // PieceWorker class derived from Employee
188 #ifndef PIECE_H
189 #define PIECE_H
190 #include "employ.h"
191
192 class PieceWorker : public Employee {
193 public:
194    PieceWorker( const char * const, const char * const, int, int, int,
195                 double = 0.0, unsigned = 0, int = 0 );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
196    void setWage( double );
197    void setQuantity( unsigned );
198    virtual double earnings() const;
199    virtual void print() const;
200 private:
201    double wagePerPiece; // wage for each piece output
202    unsigned quantity;  // output for week
203 };
204
205 #endif
```

```
206 // PIECE.CPP
207 // Member function definitions for class PieceWorker
208 #include <iostream>
209
210 using std::cout;
211
212 #include "piece.h"
213
214 // Constructor for class PieceWorker
215 PieceWorker::PieceWorker( const char * const first, const char * const last,
216     int mn, int dy, int yr, double w, unsigned q, int dept )
217     : Employee( first, last, mn, dy, yr, dept )
218 {
219    wagePerPiece = w > 0 ? w : 0;
220    quantity = q > 0 ? q : 0;
221 }
222
223 // Set the wage
224 void PieceWorker::setWage( double w )
225    { wagePerPiece = w > 0 ? w : 0; }
226
227 // Set the number of items output
228 void PieceWorker::setQuantity( unsigned q )
229    { quantity = q > 0 ? q : 0; }
230
231 // Determine the PieceWorker's earnings
232 double PieceWorker::earnings() const
233    { return quantity * wagePerPiece; }
234
235 // Print the PieceWorker's name
236 void PieceWorker::print() const
237 {
238    cout << "\nPiece worker: " << getFirstName()
239         << ' ' << getLastName();
240 }
```

```
241 // COMMIS.H
242 // CommissionWorker class derived from Employee
243 #ifndef COMMIS_H
244 #define COMMIS_H
245 #include "employ.h"
246
247 class CommissionWorker : public Employee {
248 public:
249    CommissionWorker(const char * const, const char * const, int, int, int,
250                     double = 0.0, double = 0.0, unsigned = 0, int = 0 );
251    void setSalary( double );
252    void setCommission( double );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
253    void setQuantity( unsigned );
254    virtual double earnings() const;
255    virtual void print() const;
256 private:
257    double salary;       // base salary per week
258    double commission;   // amount per item sold
259    unsigned quantity;  // total items sold for week
260 };
261
262 #endif
```

```
263 // COMMIS.CPP
264 // Member function definitions for class CommissionWorker
265 #include <iostream>
266
267 using std::cout;
268
269 #include "commis.h"
270
271 // Constructor for class CommissionWorker
272 CommissionWorker::CommissionWorker( const char * const first,
273    const char * const last, int mn, int dy, int yr,
274    double s, double c, unsigned q, int dept )
275    : Employee( first, last, mn, dy, yr, dept )
276 {
277    salary = s > 0 ? s : 0;
278    commission = c > 0 ? c : 0;
279    quantity = q > 0 ? q : 0;
280 }
281
282 // Set CommissionWorker's weekly base salary
283 void CommissionWorker::setSalary( double s )
284    { salary = s > 0 ? s : 0; }
285
286 // Set CommissionWorker's commission
287 void CommissionWorker::setCommission( double c )
288    { commission = c > 0 ? c : 0; }
289
290 // Set CommissionWorker's quantity sold
291 void CommissionWorker::setQuantity( unsigned q )
292    { quantity = q > 0 ? q : 0; }
293
294 // Determine CommissionWorker's earnings
295 double CommissionWorker::earnings() const
296    { return salary + commission * quantity; }
297
298 // Print the CommissionWorker's name
299 void CommissionWorker::print() const
300 {
301    cout << "\nCommission worker: " << getFirstName()
302         << ' ' << getLastName();
303 }
```

```
304 // DATE.H
305 // Declaration of the Date class.
306 // Member functions defined in DATE1.CPP
307 #ifndef DATE_H
308 #define DATE_H
309
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
class Date {
public:
   Date( int = 1, int = 1, int = 1900 );  // default constructor
   int getMonth() const; // return the month
   int getDay() const;   // return the day
   int getYear()const;   // return the year
   void print() const;   // print date in month/day/year format
private:
   int month;  // 1-12
   int day;    // 1-31 based on month
   int year;   // any year

   // utility function to test proper day for month and year
   int checkDay( int ) const;
};

#endif
```

```
// DATE.CPP
// Member function definitions for Date class.
#include <iostream>

using std::cout;

#include "date.h"

// Constructor: Confirm proper value for month;
// call utility function checkDay to confirm proper
// value for day.
Date::Date( int mn, int dy, int yr )
{
   if ( mn > 0 && mn <= 12 )         // validate the month
      month = mn;
   else {
      month = 1;
      cout << "Month " << mn << " invalid. Set to month 1.\n";
   }

   year = yr >= 1900 && yr <= 2100 ? yr : 1990;
   day = checkDay( dy );             // validate the day
}

// Utility function to confirm proper day value
// based on month and year.
int Date::checkDay( int testDay ) const
{
   int daysPerMonth[ 13 ] = { 0, 31, 28, 31, 30, 31, 30,
                              31, 31, 30, 31, 30, 31 };

   if ( testDay > 0 && testDay <= daysPerMonth[ month ] )
      return testDay;

   if ( month == 2 &&     // February: Check for possible leap year
       testDay == 29 &&
       ( year % 400 == 0 || (year % 4 == 0 && year % 100 != 0 ) ) )
      return testDay;

   cout << "Day " << testDay << " invalid. Set to day 1.\n";

   return 1;  // leave object in consistent state if bad value
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
370
371 // Return the month
372 int Date::getMonth() const { return month; }
373
374 // Return the day
375 int Date::getDay() const { return day; }
376
377 // Return the year
378 int Date::getYear() const { return year; }
379
380 // Print Date object in form  month/day/year
381 void Date::print() const
382    { cout << month << '/' << day << '/' << year; }
```

```
383 // Exercise 10.14 solution
384 // Driver for Employee hierarchy
385 #include <iostream>
386
387 using std::cout;
388 using std::endl;
389 using std::ios;
390
391 #include <iomanip>
392
393 using std::setprecision;
394 using std::setiosflags;
395
396 #include <ctime>
397 #include <cstdlib>
398 #include "employ.h"
399 #include "boss.h"
400 #include "commis.h"
401 #include "piece.h"
402 #include "hourly.h"
403
404 int determineMonth();
405
406 int main()
407 {
408 // set output formatting
409    cout << setiosflags( ios::fixed | ios::showpoint )
410              << setprecision( 2 );
411
412    Boss b( "John", "Smith", 6, 15, 1944, 800.00, 1 );
413    CommissionWorker c( "Sue", "Jones", 9, 8, 1954, 200.0, 3.0, 150, 1 );
414    PieceWorker p( "Bob", "Lewis", 3, 2, 1965, 2.5, 200, 1 );
415    HourlyWorker h( "Karen", "Price", 12, 29, 1960, 13.75, 40, 1 );
416
417    Employee *ptr[ 4 ] = { &b, &c, &p, &h };
418
419    int month = determineMonth();
420
421    cout << "The month is " << month << "\nThe payroll is:\n";
422
423    for ( int x = 0; x < 4; ++x ) {
424    ptr[ x ]->print();
425    cout << " of department " << ptr[ x ]->getDepartmentCode()
426            << "\n whose birthday is ";
427    ptr[ x ]->getBirthDate().print();
428    cout << " earned ";
429
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
430    if ( ptr[ x ]->getBirthDate().getMonth() == month )
431        cout << ptr[ x ]->earnings() + 100.0
432                        << " HAPPY BIRTHDAY!\n";
433    else
434       cout << ptr[x]->earnings() << endl;
435
436
437    return 0;
438 }
439
440 // Determine the current month using standard library functions
441 // of ctime.
442 int determineMonth()
443 {
444    time_t currentTime;
445    char monthString[ 3 ];
446
447    time( &currentTime );
448            strftime( monthString, 3, "%m", localtime( &currentTime ) );
449 return atoi( monthString );
450 }
```

```
The month is 5
The payroll is:

Boss: John Smith of department 1
 whose birthday is 6/15/1944 earned 800.00

Commission worker: Sue Jones of department 1
 whose birthday is 9/8/1954 earned 650.00

Piece worker: Bob Lewis of department 1
 whose birthday is 3/2/1965 earned 500.00

Hourly worker: Karen Price of department 1
 whose birthday is 12/29/1960 earned 550.00
```

10.15 In Exercise 9.14, you developed a **Shape** class hierarchy and defined the classes in the hierarchy. Modify the hierarchy so that class **Shape** is an abstract base class containing the interface to the hierarchy. Derive **TwoDimensionalShape** and **ThreeDimensionalShape** from class **Shape**—these classes should also be abstract. Use a **virtual print** function to output the type and dimensions of each class. Also include **virtual area** and **volume** functions so these calculations can be performed for objects of each concrete class in the hierarchy. Write a driver program that tests the **Shape** class hierarchy.

```
1  // SHAPE.H
2  // Definition of base-class Shape
3  #ifndef SHAPE_H
4  #define SHAPE_H
5
6  #include <iostream>
7  using std::ostream;
8
9  class Shape {
10    friend ostream & operator<<( ostream &, Shape & );
11 public:
12    Shape( double = 0, double = 0 );
13    double getCenterX() const;
14    double getCenterY() const;
15    virtual void print() const = 0;
16 protected:
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
17       double xCenter;
18       double yCenter;
19    };
20
21    #endif
```

```
22    // SHAPE.CPP
23    // Member and friend definitions for Shape
24    #include "shape.h"
25
26    Shape::Shape( double x, double y )
27    {
28       xCenter = x;
29       yCenter = y;
30    }
31
32    double Shape::getCenterX() const { return xCenter; }
33
34    double Shape::getCenterY() const { return yCenter; }
35
36    ostream & operator<<( ostream &out, Shape &s )
37    {
38       s.print();
39       return out;
40    }
```

```
41    // TWODIM.H
42    // Defnition of class TwoDimensionalShape
43    #ifndef TWODIM_H
44    #define TWODIM_H
45
46    #include "shape.h"
47
48    class TwoDimensionalShape : public Shape {
49    public:
50       TwoDimensionalShape( double x, double y ) : Shape( x, y ) { }
51       virtual double area() const = 0;
52    };
53
54    #endif
```

```
55    // THREEDIM.H
56    // Defnition of class ThreeDimensionalShape
57    #ifndef THREEDIM_H
58    #define THREEDIM_H
59
60    #include "shape.h"
61
62    class ThreeDimensionalShape : public Shape {
63    public:
64       ThreeDimensionalShape( double x, double y ) : Shape( x, y ) { }
65       virtual double area() const = 0;
66       virtual double volume() const = 0;
67    };
68
69    #endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// CIRCLE.H
// Definition of class Circle
#ifndef CIRCLE_H
#define CIRCLE_H

#include "twodim.h"

class Circle : public TwoDimensionalShape {
public:
   Circle( double = 0, double = 0, double = 0 );
   double getRadius() const;
   double area() const;
   void print() const;
private:
   double radius;
};

#endif
```

```
// CIRCLE.CPP
// Member function definitions for Circle
#include "circle.h"

#include <iostream>
using std::cout;

Circle::Circle( double r, double x, double y )
   : TwoDimensionalShape( x, y ) { radius = r > 0 ? r : 0; }

double Circle::getRadius() const { return radius; }

double Circle::area() const { return 3.14159 * radius * radius; }

void Circle::print() const
{
   cout << "Circle with radius " << radius << "; center at ("
        << xCenter << ", " << yCenter << ");\narea of " << area() << '\n';
}
```

```
// SQUARE.H
// Definition of class Square
#ifndef SQUARE_H
#define SQUARE_H

#include "twodim.h"

class Square : public TwoDimensionalShape {
public:
   Square( double = 0, double = 0, double = 0 );
   double getSideLength() const;
   double area() const;
   void print() const;
private:
   double sideLength;
};

#endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// SQUARE.CPP
// Member function definitions for Square
#include "square.h"

#include <iostream>
using std::cout;

Square::Square( double s, double x, double y )
   : TwoDimensionalShape( x, y ) { sideLength = s > 0 ? s : 0; }

double Square::getSideLength() const { return sideLength; }

double Square::area() const { return sideLength * sideLength; }

void Square::print() const
{
   cout << "Square with side length " << sideLength << "; center at ("
        << xCenter << ", " << yCenter << ");\narea of " << area() << '\n';
}
```

```
// SPHERE.H
// Definition of class Shere
#ifndef SPHERE_H
#define SPHERE_H

#include "threedim.h"

class Sphere : public ThreeDimensionalShape {
public:
   Sphere( double = 0, double = 0, double = 0 );
   double area() const;
   double volume() const;
   double getRadius() const;
   void print() const;
private:
   double radius;
};

#endif
```

```
// SPHERE.CPP
// Member function definitions for Sphere
#include "sphere.h"

#include <iostream>
using std::cout;

Sphere::Sphere( double r, double x, double y )
   : ThreeDimensionalShape( x, y ) { radius = r > 0 ? r : 0; }

double Sphere::area() const
   { return 4.0 * 3.14159 * radius * radius; }

double Sphere::volume() const
   { return 4.0/3.0 * 3.14159 * radius * radius * radius; }

double Sphere::getRadius() const { return radius; }

void Sphere::print() const
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   cout << "Sphere with radius " << radius << "; center at ("
        << xCenter << ", " << yCenter << ");\narea of "
        << area() << "; volume of " << volume() << '\n';
}
```

```
// CUBE.H
// Definition of class Cube
#ifndef CUBE_H
#define CUBE_H

#include "threedim.h"

class Cube : public ThreeDimensionalShape {
public:
   Cube( double = 0, double = 0, double = 0 );
   double area() const;
   double volume() const;
   double getSideLength() const;
   void print() const;
private:
   double sideLength;
};

#endif
```

```
// CUBE.CPP
// Member function definitions for Cube
#include "cube.h"

#include <iostream>
using std::cout;

Cube::Cube( double s, double x, double y )
   : ThreeDimensionalShape( x, y ) { sideLength = s > 0 ? s : 0; }

double Cube::area() const { return 6 * sideLength * sideLength; }

double Cube::volume() const
   { return sideLength * sideLength * sideLength; }

double Cube::getSideLength() const { return sideLength; }

void Cube::print() const
{
   cout << "Cube with side length " << sideLength << "; center at ("
        << xCenter << ", " << yCenter << ");\narea of "
        << area() << "; volume of " << volume() << '\n';
}
```

```
// Exercise 10.15 solution
// Driver to test Shape hierarchy
#include <iostream>

using std::cout;

#include "circle.h"
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
236 #include "square.h"
237 #include "sphere.h"
238 #include "cube.h"
239
240 int main()
241 {
242    Circle cir( 3.5, 6, 9 );
243    Square sqr( 12, 2, 2 );
244    Sphere sph( 5, 1.5, 4.5 );
245    Cube cub( 2.2 );
246    Shape *ptr[ 4 ] = { &cir, &sqr, &sph, &cub };
247
248    for ( int x = 0; x < 4; ++x )
249       cout << *( ptr[ x ] ) << '\n';
250
251    return 0;
252 }
```

```
Circle with radius 3.5; center at (6, 9);
area of 38.4845

Square with side length 12; center at (2, 2);
area of 144

Sphere with radius 5; center at (1.5, 4.5);
area of 314.159; volume of 523.598

Cube with side length 2.2; center at (0, 0);
area of 29.04; volume of 10.648
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

11

C++ Stream Input/Output Solutions

Solutions

11.6 Write a statement for each of the following:

a) Print integer **40000** left-justified in a **15**-digit field.

ANS:
```
cout << setiosflags( ios::left ) << setw( 15 ) << 40000 << '\n';
```

b) Read a string into character array variable **state**.

ANS:
```
cin >> state;
```

c) Print **200** with and without a sign.

ANS:
```
cout << setiosflags( ios::showpos ) << 200 << setw( 4 )  << '\n'
          << resetiosflags( ios::showpos ) << 200 << '\n';
```

d) Print the decimal value **100** in hexadecimal form preceded by **0x**.

ANS:
```
cout << setiosflags( ios::showbase ) << hex << 100 << '\n';
```

e) Read characters into array **s** until the character **'p'** is encountered up to a limit of 10 characters (including the terminating null character). Extract the delimiter from the input stream and discard it.

ANS:
```
cin.getline( s, 10, 'p' );
```

f) Print **1.234** in a **9**-digit field with preceding zeros.

ANS:
```
cout << setiosflags( ios::fixed | ios::showpoint ) << setw( 9 )
     << setfill( '0' ) << setiosflags( ios::internal ) << 1.234 << '\n';
```

g) Read a string of the form **"characters"** from the standard input. Store the string in character array **s**. Eliminate the quotation marks from the input stream. Read a maximum of 50 characters (including the terminating null character).

11.7 Write a program to test inputting integer values in decimal, octal and hexadecimal format. Output each integer read by the program in all three formats. Test the program with the following input data: 10, 010, 0x10.

```
1  // Exercise 11.7 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#include <iomanip>

using std::setiosflags;
using std::hex;
using std::oct;
using std::dec;

int main()
{
   int integer;

   cout << "Enter an integer: ";
   cin >> integer;

   cout << setiosflags( ios::showbase ) << "As a decimal number "  << dec
        << integer << "\nAs an octal number " << oct << integer
        << "\nAs a hexadecimal number " << hex << integer << endl;

   cout << "\nEnter an integer in hexadecimal format\n";
   cin >> hex >> integer;

   cout << setiosflags( ios::showbase ) << "As a decimal number "  << dec
        << integer << "\nAs an octal number " << oct << integer
        << "\nAs a hexadecimal number " << hex << integer << endl;

   cout << "\nEnter an integer in octal format\n";
   cin >> oct >> integer;

   cout << setiosflags( ios::showbase ) << "As a decimal number "  << dec
        << integer << "\nAs an octal number " << oct << integer
        << "\nAs a hexadecimal number " << hex << integer << endl;


   return 0;
}
```

```
Enter an integer: 10
As a decimal number 10
As an octal number 012
As a hexadecimal number 0xa

Enter an integer in hexadecimal format
0x10
As a decimal number 16
As an octal number 020
As a hexadecimal number 0x10

Enter an integer in octal format
010
As a decimal number 8
As an octal number 010
As a hexadecimal number 0x8
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

11.8 Write a program that prints pointer values using casts to all the integer data types. Which ones print strange values? Which ones cause errors?

```
// Exercise 11.8 Solution
#include <iostream>

using std::cout;
using std::endl;

int main()
{
   char *string = "test";

   cout << "Value of string is            : " << string << '\n'
        << "Value of static_cast<void *>( string ) is    : "
        << static_cast<void *>( string ) << '\n'

        // The Following generate errors.
        // reinterpret_cast will allow this
        // type of casting. See Chap. 21 for
        // a discussion of reinterpret_cast.

/*      << "Value of static_cast<char>(string) is      : "
        << static_cast<char>( string ) << '\n'
        << "Value of static_cast<int>(string) is       : "
        << static_cast<int>( string ) << '\n'
        << "Value of static_cast<long>(string) is      : "
        << static_cast<long>( string ) << '\n'
        << "Value of static_cast<short>(string) is     : "
        << static_cast<short>( string ) << '\n'
        << "Value of static_cast<unsigned>(string) is  : "
        << static_cast<unsigned>( string )
*/
        << endl;

   return 0;
}
```

```
Value of string is            : test
Value of static_cast<void *>(string) is    : 0046C07C
```

11.9 Write a program to test the results of printing the integer value **12345** and the floating-point value **1.2345** in various-size fields. What happens when the values are printed in fields containing fewer digits than the values?

```
// Exercise 11.9 Solution
#include <iostream>

using std::cout;

#include <iomanip>

using std::setw;

int main()
{
   int x = 12345;
   double y = 1.2345;

   for ( int loop = 0; loop <= 10; ++loop )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cout << x << "  printed in a field of size " << loop << " is "
           << setw( loop ) << x << '\n' << y << " printed in a field "
           << "of size " << loop << " is " << setw( loop ) << y << '\n';

   return 0;
}
```

```
12345  printed in a field of size 0 is 12345
1.2345 printed in a field of size 0 is 1.2345
12345  printed in a field of size 1 is 12345
1.2345 printed in a field of size 1 is 1.2345
12345  printed in a field of size 2 is 12345
1.2345 printed in a field of size 2 is 1.2345
12345  printed in a field of size 3 is 12345
1.2345 printed in a field of size 3 is 1.2345
12345  printed in a field of size 4 is 12345
1.2345 printed in a field of size 4 is 1.2345
12345  printed in a field of size 5 is 12345
1.2345 printed in a field of size 5 is 1.2345
12345  printed in a field of size 6 is  12345
1.2345 printed in a field of size 6 is 1.2345
12345  printed in a field of size 7 is   12345
1.2345 printed in a field of size 7 is  1.2345
12345  printed in a field of size 8 is    12345
1.2345 printed in a field of size 8 is   1.2345
12345  printed in a field of size 9 is     12345
1.2345 printed in a field of size 9 is    1.2345
12345  printed in a field of size 10 is      12345
1.2345 printed in a field of size 10 is     1.2345
```

11.10 Write a program that prints the value **100.453627** rounded to the nearest digit, tenth, hundredth, thousandth and ten thousandth.

```
// Exercise 11.10 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <iomanip>

using std::setprecision;
using std::setiosflags;

int main()
{
   double x = 100.453627;

   cout << setiosflags( ios::fixed );
   for ( int loop = 0; loop <= 5; ++loop )
       cout << setprecision( loop ) << "Rounded to " << loop
            << " digit(s) is " << x << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Rounded to 0 digit(s) is 100
Rounded to 1 digit(s) is 100.5
Rounded to 2 digit(s) is 100.45
Rounded to 3 digit(s) is 100.454
Rounded to 4 digit(s) is 100.4536
Rounded to 5 digit(s) is 100.45363
```

11.11 Write a program that inputs a string from the keyboard and determines the length of the string. Print the string using twice the length as the field width

```
1  // Exercise 11.11 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <iomanip>
9
10 using std::setw;
11
12 #include <cstring>
13
14 const int SIZE = 80;
15
16 int main()
17 {
18    char string[ SIZE ];
19    int stringLength;
20
21    cout << "Enter a string: ";
22    cin >> string;
23
24    stringLength = strlen( string );
25
26    cout << "the length of the string is " << strlen( string ) << endl;
27
28    // print string using twice the length as field with
29    cout << setw( 2 * stringLength ) << string << endl;
30
31    return 0;
32 }
```

```
Enter a string: castle
the length of the string is 6
     castle
```

11.12 Write a program that converts integer Fahrenheit temperatures from **0** to **212** degrees to floating-point Celsius temperatures with **3** digits of precision. Use the formula

```
celsius = 5.0 / 9.0 * ( fahrenheit - 32 );
```

to perform the calculation. The output should be printed in two right-justified columns and the Celsius temperatures should be preceded by a sign for both positive and negative values.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 11.12 Solution
#include <iostream>

using std::cout;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

int main()
{
   double celsius;

   cout << setw( 20 ) << "Fahrenheit " << setw( 20 ) << "Celsius\n"
        << setiosflags( ios::fixed | ios::showpoint );

   for ( int fahrenheit = 0; fahrenheit <= 212; ++fahrenheit ) {
       celsius = 5.0 / 9.0 * ( fahrenheit - 32 );
       cout << setw( 15 ) << resetiosflags( ios::showpos ) << fahrenheit
            << setw( 23 ) << setprecision( 3 ) << setiosflags( ios::showpos )
            << celsius << '\n';
   }

   return 0;
}
```

```
          Fahrenheit             Celsius
              0                -17.778
              1                -17.222
              2                -16.667
              3                -16.111
              4                -15.556
...
            206                +96.667
            207                +97.222
            208                +97.778
            209                +98.333
            210                +98.889
            211                +99.444
            212               +100.000
```

11.13 In some programming languages, strings are entered surrounded by either single or double quotation marks. Write a program that reads the three strings **`suzy`**, **`"suzy"`** and **`'suzy'`**. Are the single and double quotes ignored or read as part of the string?

```
// Exercise 11.13 Solution
#include <iostream>

using std::cout;
using std::cin;

const int SIZE = 80;

int main()
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   char string[ SIZE ];

   for ( int k = 0; k < 3; ++k ) {
      cout << "Enter a string: ";
      cin >> string;
      cout << "String is " << string << '\n';
   }

   return 0;
}
```

```
Enter a string: "vacuum"
String is "vacuum"
Enter a string: 'grape'
String is 'grape'
Enter a string: water
String is water
```

11.14 In Fig. 8.3, the stream-extraction and -insertion operators were overloaded for input and output of objects of the **PhoneNumber** class. Rewrite the stream-extraction operator to perform the following error checking on input. The **operator>>** function will need to be entirely recoded.

a) Input the entire phone number into an array. Test that the proper number of characters has been entered. There should be a total of 14 characters read for a phone number of the form **(800) 555-1212**. Use the stream member function **clear** to set **ios::failbit** for improper input.

b) The area code and exchange do not begin with **0** or **1**. Test the first digit of the area code and exchange portions of the phone number to be sure that neither begins with **0** or **1**. Use stream member function **clear** to set **ios::failbit** for improper input.

c) The middle digit of an area code used to always be **0** or **1** (although this has changed recently). Test the middle digit for a value of **0** or **1**. Use the stream member function **clear** to set **ios::failbit** for improper input. If none of the above operations results in **ios::failbit** being set for improper input, copy the three parts of the telephone number into the **areaCode**, **exchange** and **line** members of the **PhoneNumber** object. In the main program, if **ios::failbit** has been set on the input, have the program print an error message and end rather than print the phone number.

```
// P11_14.H
#ifndef P11_14_H
#define P11_14_H
#include <iostream>
using std::cout;
using std::endl;
using std::cin;
using std::ios;
using std::ostream;
using std::istream;
using std::cerr;

#include <cstring>
#include <cstdlib>

class PhoneNumber {
   friend ostream& operator<<( ostream&, PhoneNumber& );
   friend istream& operator>>( istream&, PhoneNumber& );
public:
   PhoneNumber();
private:
   char phone[ 15 ];
   char areaCode[ 4 ];
   char exchange[ 4 ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
25    char line[ 5 ];
26 };
27
28 #endif
```

```
29 // P11_14M.cpp
30 // member function definition definition for p11_14.cpp
31 #include "p11_14.h"
32
33 PhoneNumber::PhoneNumber()
34 {
35    phone[ 0 ] = '\0';
36    areaCode[ 0 ] = '\0';
37    exchange[ 0 ] = '\0';
38    line[ 0 ] = '\0';
39 }
40
41 ostream &operator<<( ostream &output, PhoneNumber &number )
42 {
43    output << "(" << number.areaCode << ") " << number.exchange
44           << "-" << number.line << '\n';
45
46    return output;
47 }
48
49 istream &operator>>( istream &input, PhoneNumber &number )
50 {
51    cin.getline( number.phone, 15 );
52
53    if ( strlen( number.phone ) != 14 )
54       cin.clear( ios::failbit );
55
56    if ( number.phone[ 1 ] == '0' || number.phone[ 6 ] == '0' ||
57         number.phone[ 1 ] == '1' || number.phone[ 6 ] == '1')
58       cin.clear( ios::failbit );
59
60    if ( number.phone[ 2 ] != '0' && number.phone[ 2 ] != '1' )
61       cin.clear( ios::failbit );
62
63    if ( !cin.fail() ) {
64       for ( int loop = 0; loop <= 2; ++loop ) {
65          number.areaCode[ loop ] = number.phone[ loop + 1 ];
66          number.exchange[ loop ] = number.phone[ loop + 6 ];
67       }
68
69       number.areaCode[ loop ] = number.exchange[ loop ] = '\0';
70
71       for ( loop = 0; loop <= 3; ++loop )
72          number.line[ loop ] = number.phone[ loop + 10 ];
73
74       number.line[ loop ] = '\0';
75    }
76    else {
77       cerr << "Invalid phone number entered.\n";
78       exit( 1 );
79    }
80
81    return input;
82 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// driver for p11_14.cpp
#include "p11_14.h"

int main()
{
   PhoneNumber telephone;

   cout << "Enter a phone number in the form (123) 456-7890:\n";
   cin >> telephone;

   cout << "The phone number entered was:  " << telephone << endl;

   cout << "Now enter an invalid phone number:\n";
   cin >> telephone;

   return 0;
}
```

```
Enter a phone number in the form (123) 456-7890:
(800) 987-4567
The phone number entered was:  (800) 987-4567

Now enter an invalid phone number:
(000) 000-0000
Invalid phone number entered.
```

11.15 Write a program that accomplishes each of the following:

a) Create the user-defined class **Point** that contains the private integer data members **xCoordinate** and **yCoordinate** and declares stream-insertion and stream-extraction overloaded operator functions as **friend**s of the class.

b) Define the stream-insertion and stream-extraction operator functions. The stream-extraction operator function should determine if the data entered are valid data, and if not, it should set the **ios::failbit** to indicate improper input. The stream-insertion operator should not be able to display the point after an input error occurred.

c) Write a **main** function that tests input and output of user-defined class **Point** using the overloaded stream-extraction and stream-insertion operators.

```
// P11_15.H
#ifndef P11_15_H
#define P11_15_H
#include <iostream.h>

class Point {
   friend ostream &operator<<( ostream&, Point& );
   friend istream &operator>>( istream&, Point& );
private:
   int xCoordinate;
   int yCoordinate;
};

#endif
```

```
// P11_15M.cpp
// member function definitions for p11_15.cpp
#include "p11_15.h"

ostream& operator<<( ostream& out, Point& p )
{
   if ( !cin.fail() )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cout << "(" << p.xCoordinate << ", " << p.yCoordinate << ")" << '\n';
   else
      cout << "\nInvalid data\n";

   return out;
}

istream& operator>>( istream& i, Point& p )
{
   if ( cin.peek() != '(' )
      cin.clear( ios::failbit );
   else
      i.ignore();  // skip (

   cin >> p.xCoordinate;

   if ( cin.peek() != ',' )
      cin.clear( ios::failbit );
   else {
      i.ignore(); // skip ,

      if ( cin.peek() == ' ' )
         i.ignore(); // skip space
      else
         cin.clear( ios::failbit );
   }

   cin >> p.yCoordinate;

   if ( cin.peek() == ')' )
         i.ignore();  // skip )
      else
         cin.clear( ios::failbit );

   return i;
}
```

```
// driver for p11_15.cpp
#include "p11_15.h"

int main()
{
   Point pt;

   cout << "Enter a point in the form (x, y):\n";
   cin >> pt;

   cout << "Point entered was: " << pt << endl;
   return 0;
}
```

```
Enter a point in the form (x, y):
(7, 8)
Point entered was: (7, 8)
```

11.16 Write a program that accomplishes each of the following:

a) Create the user-defined class **`Complex`** that contains the private integer data members **`real`** and **`imaginary`**, and declares stream-insertion and stream-extraction overloaded operator functions as **`friend`**s of the class.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

b) Define the stream-insertion and -extraction operator functions. The stream-extraction operator function should determine if the data entered are valid, and if not, it should set **ios::failbit** to indicate improper input. The input should be of the form

```
3 + 8i
```

c) The values can be negative or positive, and it is possible that one of the two values is not provided. If a value is not provided, the appropriate data member should be set to 0. The stream-insertion operator should not be able to display the point if an input error occurred. The output format should be identical to the input format shown above. For negative imaginary values, a minus sign should be printed rather than a plus sign.

d) Write a **main** function that tests input and output of user-defined class **Complex** using the overloaded stream-extraction and stream-insertion operators.

```
1  // P11_16.H
2  #ifndef P11_16_H
3  #define P11_16_H
4  #include <iostream>
5
6  using std::ostream;
7  using std::istream;
8
9  class Complex {
10    friend ostream &operator<<( ostream&, Complex& );
11    friend istream &operator>>( istream&, Complex& );
12 public:
13    Complex( void );    // constructor
14 private:
15    int real;
16    int imaginary;
17 };
18
19 #endif
```

```
20 // P11_16M.cpp
21 // member function definitions for p11_16.cpp
22
23 #include <iostream>
24
25 using std::cout;
26 using std::cin;
27 using std::ios;
28 using std::ostream;
29 using std::istream;
30
31 #include <iomanip>
32
33 using std::setiosflags;
34 using std::resetiosflags;
35
36 #include "p11_16.h"
37
38 Complex::Complex( void )
39 {
40    real = 0;
41    imaginary = 0;
42 }
43
44 ostream &operator<<( ostream &output, Complex &c )
45 {
46    if ( !cin.fail() )
47       output << c.real
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
48                << setiosflags( ios::showpos )
49                << c.imaginary << "i\n"
50                << resetiosflags( ios::showpos );
51     else
52        output << "Invalid Data Entered" << '\n';
53
54     return output;
55  }
56
57  istream &operator>>( istream &input, Complex &c )
58  {
59     int number, multiplier;
60     char temp;
61
62     input >> number;
63
64     if ( cin.peek() == ' ' ) {              // case a + bi
65        c.real = number;
66        cin >> temp;
67
68        multiplier = ( temp == '+' ) ? 1 : -1;
69
70        if ( cin.peek() != ' ' )
71           cin.clear( ios::failbit );       // set bad bit
72        else {
73
74           if ( cin.peek() == ' ' ) {
75              input >> c.imaginary;
76              c.imaginary *= multiplier;
77
78              cin >> temp;
79              if ( cin.peek() != '\n' )
80                 cin.clear( ios::failbit ); // set bad bit
81           }
82           else
83              cin.clear( ios::failbit );    // set bad bit
84        }
85     }
86     else if ( cin.peek() == 'i' ) {         // case bi
87           cin >> temp;
88
89           if ( cin.peek() == '\n' ) {
90              c.real = 0;
91              c.imaginary = number;
92           }
93           else
94              cin.clear( ios::failbit );    // set bad bit
95     }
96
97     else if ( cin.peek() == '\n' ) {        // case a
98        c.real = number;
99        c.imaginary = 0;
100    }
101    else
102       cin.clear( ios::failbit );           // set bad bit
103
104    return input;
105 }
```

```
106 // driver for p11_16.cpp
107 #include "p11_16.h"
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
108
109 int main()
110 {
111    Complex complex;
112
113    cout << "Input a complex number in the form A + Bi:\n";
114    cin >> complex;
115
116    cout << "Complex number entered was:\n" << complex << endl;
117    return 0;
118 }
```

```
Input a complex number in the form A + Bi:
7 - 7777i
Complex number entered was:
7-7777i
```

11.17 Write a program that uses a **for** structure to print a table of ASCII values for the characters in the ASCII character set from **33** to **126**. The program should print the decimal value, octal value, hexadecimal value and character value for each character. Use the stream manipulators **dec**, **oct** and **hex** to print the integer values.

```
 1 // Exercise 11.17 Solution
 2 #include <iostream>
 3
 4 using std::cout;
 5 using std::endl;
 6 using std::ios;
 7
 8 #include <iomanip>
 9
10 using std::setw;
11 using std::setiosflags;
12 using std::dec;
13 using std::oct;
14 using std::hex;
15
16 int main()
17 {
18    cout << setw( 7 ) << "Decimal" << setw( 9 ) << "Octal " << setw( 15 )
19         << "Hexadecimal " << setw( 13 ) << "Character"
20         << setiosflags( ios::showbase ) << '\n';
21
22    for ( int loop = 33; loop <= 126; ++loop )
23        cout << setw( 7 ) << dec << loop << setw( 9 ) << oct << loop
24             << setw( 15 ) << hex << loop << setw(13)
25             << static_cast<char>( loop ) << endl;
26
27    return 0;
28 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 Decimal    Octal    Hexadecimal      Character
      33       041           0x21            !
      34       042           0x22            "
      35       043           0x23            #
      36       044           0x24            $
      37       045           0x25            %
      38       046           0x26            &
      39       047           0x27            '
...
     120      0170           0x78            x
     121      0171           0x79            y
     122      0172           0x7a            z
     123      0173           0x7b            {
     124      0174           0x7c            |
     125      0175           0x7d            }
     126      0176           0x7e            ~
```

11.18 Write a program to show that the **getline** and three-argument **get istream** member functions each end the input string with a string-terminating null character. Also, show that **get** leaves the delimiter character on the input stream while **getline** extracts the delimiter character and discards it. What happens to the unread characters in the stream?

```
1  // Exercise 11.18 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <cctype>
10
11 const int SIZE = 80;
12
13 int main()
14 {
15    char array[ SIZE ], array2[ SIZE ], c;
16
17    cout << "Enter a sentence to test getline() and get():\n";
18    cin.getline( array, SIZE, '*' );
19    cout << array << '\n';
20
21    cin >> c;  // read next character in input
22    cout << "The next character in the input is: " << c << '\n';
23
24    cin.get( array2, SIZE, '*' );
25    cout << array2 << '\n';
26
27    cin >> c;  // read next character in input
28    cout << "The next character in the input is: " << c << '\n';
29
30    return 0;
31 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter a sentence to test getline() and get():
wishing*on*a*star
wishing
The next character in the input is: o
n
The next character in the input is: *
```

11.19 Write a program that creates the user-defined manipulator **skipwhite** to skip leading whitespace characters in the input stream. The manipulator should use the **isspace** function from the **<cctype>** library to test if the character is a whitespace character. Each character should be input using the **istream** member function **get**. When a nonwhitespace character is encountered, the **skipwhite** manipulator finishes its job by placing the character back on the input stream and returning an **istream** reference.

Test the manipulator by creating a **main** function in which the **ios::skipws** flag is unset so that the stream-extraction operator does not automatically skip whitespace. Then test the manipulator on the input stream by entering a character preceded by whitespace as input. Print the character that was input to confirm that a whitespace character was not input.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

12

Templates Solutions

Solutions

12.3 Write a function template **bubbleSort** based on the sort program of Fig. 5.15. Write a driver program that inputs, sorts and outputs an **int** array and a **float** array.

```
// Exercise 12.3 solution
// This program puts values into an array, sorts the values into
// ascending order, and prints the resulting array.
#include <iostream>

using std::cout;
using std::endl;

#include <iomanip>

using std::setw;

template < class T >
void swap( T * const, T * const);

// Function template for bubbleSort
template < class T >
void bubbleSort( T * const array, int size )
{

   for ( int pass = 1; pass < size; ++pass )
      for ( int j = 0; j < size - pass; ++j )
         if ( array[ j ] > array[ j + 1 ] )
            swap( array + j, array + j + 1  );

}

template < class T >
void swap( T * const element1Ptr, T * const element2Ptr )
{
   T temp = *element1Ptr;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   *element1Ptr = *element2Ptr;
   *element2Ptr = temp;
}

int main()
{
   const int arraySize = 10;
   int a[ arraySize ] = { 10, 9, 8, 7, 6, 5, 4, 3, 2, 1 }, i;

   // Process an array of integers
   cout << "Integer data items in original order\n";

   for ( i = 0; i < arraySize; ++i )
      cout << setw( 6 ) << a[ i ];

   bubbleSort( a, arraySize );          // sort the array
   cout << "\nInteger data items in ascending order\n";

   for ( i = 0; i < arraySize; ++i )
      cout << setw( 6 ) << a[ i ];

   cout << "\n\n";

   // Process an array of doubleing point values
   double b[ arraySize ] = { 10.1, 9.9, 8.8, 7.7, 6.6, 5.5,
                             4.4, 3.3, 2.2, 1.1 };

   cout << "doubleing point data items in original order\n";

   for ( i = 0; i < arraySize; ++i )
      cout << setw( 6 ) << b[ i ];

   bubbleSort( b, arraySize );          // sort the array
   cout << "\ndoubleing point data items in ascending order\n";

   for ( i = 0; i < arraySize; ++i )
      cout << setw( 6 ) << b[ i ];

   cout << endl;

   return 0;
}
```

```
Integer data items in original order
    10     9     8     7     6     5     4     3     2     1
Integer data items in ascending order
     1     2     3     4     5     6     7     8     9    10

doubleing point data items in original order
  10.1   9.9   8.8   7.7   6.6   5.5   4.4   3.3   2.2   1.1
doubleing point data items in ascending order
   1.1   2.2   3.3   4.4   5.5   6.6   7.7   8.8   9.9  10.1
```

12.4 Overload function template **printArray** of Fig.12.2 so that it takes two additional integer arguments, namely **int lowSubscript** and **int highSubscript**. A call to this function will print only the designated portion of the array. Validate **lowSubscript** and **highSubscript**; if either is out-of-range or if **highSubscript** is less than or equal to **low-**

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Subscript, the overloaded **printArray** function should return 0; otherwise, **printArray** should return the number of elements printed. Then modify **main** to exercise both versions of **printArray** on arrays **a**, **b** and **c**. Be sure to test all capabilities of both versions of **printArray**.

```
// Exercise 12.4 solution
// Using template functions
#include <iostream>

using std::cout;
using std::endl;


template< class T >
int printArray( T const * const array, int size, int lowSubscript,
                int highSubscript )
{
   if ( size < 0 || lowSubscript < 0 || highSubscript >= size )
      return 0;   // negative size or subscript out of range

   for ( int i = lowSubscript, count = 0; i <= highSubscript; ++i ) {
      ++count;
      cout << array[ i ] << ' ';
   }

   cout << '\n';

   return count;  // number or elements output
}

int main()
{
   const int aCount = 5, bCount = 7, cCount = 6;
   int a[ aCount ] = { 1, 2, 3, 4, 5 };
   double b[ bCount ] = { 1.1, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7 };
   char c[ cCount ] = "HELLO";  // 6th position for null
   int elements;

   cout << "\nArray a contains:\n";
   elements = printArray( a, aCount, 0, aCount - 1 );
   cout << elements << " elements were output\n";

   cout << "Array a from 1 to 3 is:\n";
   elements = printArray( a, aCount, 1, 3 );
   cout << elements << " elements were output\n";

   cout << "Array a output with invalid subscripts:\n";
   elements = printArray( a, aCount, -1, 10 );
   cout << elements << " elements were output\n\n";

   cout << "Array b contains:\n";
   elements = printArray( b, bCount, 0, bCount - 1 );
   cout << elements << " elements were output\n";

   cout << "Array b from 1 to 3 is:\n";
   elements = printArray( b, bCount, 1, 3 );
   cout << elements << " elements were output\n";

   cout << "Array b output with invalid subscripts:\n";
   elements = printArray( b, bCount, -1, 10 );
   cout << elements << " elements were output\n\n";

   cout << "Array c contains:\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   elements = printArray( c, cCount, 0, cCount - 1 );
   cout << elements << " elements were output\n";

   cout << "Array c from 1 to 3 is:\n";
   elements = printArray( c, cCount, 1, 3 );
   cout << elements << " elements were output\n";

   cout << "Array c output with invalid subscripts:\n";
   elements = printArray( c, cCount, -1, 10 );
   cout << elements << " elements were output" << endl;

   return 0;
}
```

```
Array a contains:
1 2 3 4 5
5 elements were output
Array a from 1 to 3 is:
2 3 4
3 elements were output
Array a output with invalid subscripts:
0 elements were output

Array b contains:
1.1 2.2 3.3 4.4 5.5 6.6 7.7
7 elements were output
Array b from 1 to 3 is:
2.2 3.3 4.4
3 elements were output
Array b output with invalid subscripts:
0 elements were output

Array c contains:
H E L L O
6 elements were output
Array c from 1 to 3 is:
E L L
3 elements were output
Array c output with invalid subscripts:
0 elements were output
```

12.5 Overload function template **printArray** of Fig.12.2 with a nontemplate version that specifically prints an array of character strings in neat, tabular, column format.

```
// Exercise 12.5 solution
// Using template functions
#include <iostream>

using std::cout;

#include <iomanip>

using std::setw;

template< class T >
void printArray( T const * const array, int size )
{
   for ( int i = 0; i < size; ++i )
      cout << array[ i ] << ' ';
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
16
17    cout << '\n';
18 }
19
20 void printArray( char const * const stringArray[], int size )
21 {
22    for ( int i = 0; i < size; ++i ) {
23       cout << setw( 10 ) << stringArray[ i ];
24
25       if ( ( i + 1 ) % 4 == 0 )
26          cout << '\n';
27    }
28
29    cout << '\n';
30 }
31
32 int main()
33 {
34    const int aCount = 5, bCount = 7, cCount = 6, sCount = 8;
35    int a[ aCount ] = { 1, 2, 3, 4, 5 };
36    double b[ bCount ] = { 1.1, 2.2, 3.3, 4.4, 5.5, 6.6, 7.7 };
37    char c[ cCount ] = "HELLO";  // 6th position for null
38    const char *strings[ sCount ] = { "one", "two", "three", "four",
39                                      "five", "six", "seven", "eight" };
40
41    cout << "Array a contains:\n";
42    printArray( a, aCount );  // integer template function
43
44    cout << "\nArray b contains:\n";
45    printArray( b, bCount );  // float template function
46
47    cout << "\nArray c contains:\n";
48    printArray( c, cCount );  // character template function
49
50    cout << "\nArray strings contains:\n";
51    printArray( strings, sCount );  // function specific to string arrays
52
53    return 0;
54 }
```

```
Array a contains:
1 2 3 4 5

Array b contains:
1.1 2.2 3.3 4.4 5.5 6.6 7.7

Array c contains:
H E L L O

Array strings contains:
       one       two     three      four
      five       six     seven     eight
```

12.6 Write a simple function template for predicate function **isEqualTo** that compares its two arguments with the equality operator (**==**) and returns **true** if they are equal and **false** if they are not equal. Use this function template in a program that calls **isEqualTo** only with a variety of built-in types. Now write a separate version of the program that calls **isEqualTo** with a user-

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

defined class type, but does not overload the equality operator. What happens when you attempt to run this program? Now overload the equality operator (with operator function **operator==**). Now what happens when you attempt to run this program?

```
// Exercise 12.6 solution
// Combined solution to entire problem
#include <iostream>

using std::cout;
using std::cin;
using std::ostream;

template < class T >
bool isEqualTo( const T &arg1, const T &arg2 ) { return arg1 == arg2; }

class SomeClass {
   friend ostream &operator<<(ostream &, SomeClass &);
public:
   SomeClass( int s, double t )
   {
      x = s;
      y = t;
   }

   // Overloaded equality operator. If this is not provided, the
   // program will not compile.
   bool operator==( const SomeClass &right ) const
      { return x == right.x && y == right.y; }
private:
   int x;
   double y;
};

ostream &operator<<( ostream &out, SomeClass &obj )
{
   out << '(' << obj.x << ", " << obj.y << ')';
   return out;
}

int main()
{
   int a, b;

   cout << "Enter two integer values: ";
   cin >> a >> b;
   cout << a << " and " << b << " are "
        << ( isEqualTo( a, b ) ? "equal" : "not equal" ) << '\n';

   char c, d;

   cout << "\nEnter two character values: ";
   cin >> c >> d;
   cout << c << " and " << d << " are "
        << ( isEqualTo( c, d ) ? "equal" : "not equal" ) << '\n';

   double e, f;

   cout << "\nEnter two double values: ";
   cin >> e >> f;

   cout << e << " and " << f << " are "
        << ( isEqualTo( e, f ) ? "equal" : "not equal") << '\n';

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   SomeClass g( 1, 1.1 ), h( 1, 1.1 );

   cout << "\nThe class objects " << g << " and " << h << " are "
        << ( isEqualTo( g, h ) ? "equal" : "not equal" ) << '\n';
   return 0;
}
```

```
Enter two integer values: 8 22
8 and 22 are not equal

Enter two character values: Y Y
Y and Y are equal

Enter two double values: 3.3 8.7
3.3 and 8.7 are not equal

The class objects (1, 1.1) and (1, 1.1) are equal
```

12.7 Use a nontype parameter **numberOfElements** and a type parameter **elementType** to help create a template for the **Array** class we developed in Chapter 8, "Operator Overloading." This template will enable **Array** objects to be instantiated with a specified number of elements of a specified element type at compile time.

```
#ifndef ARRAY1_H
#define ARRAY1_H

#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstdlib>
#include <cassert>

template < class elementType, int numberOfElements >
class Array {
public:
   Array();                                 // default constructor
   ~Array();                                // destructor
   int getSize() const;                     // return size
   bool operator==( const Array & ) const; // compare equal
   bool operator!=( const Array & ) const; // compare !equal
   elementType &operator[]( int );          // subscript operator
   static int getArrayCount();              // Return count of
                                            // arrays instantiated.
   void inputArray();                       // input the array elements
   void outputArray() const;                // output the array elements
private:
   elementType ptr[ numberOfElements ]; // pointer to first element of array
   int size; // size of the array
   static int arrayCount;  // # of Arrays instantiated
};

// Initialize static data member at file scope
template < class elementType, int numberOfElements >
int Array< elementType, numberOfElements >::arrayCount = 0;    // no objects yet

// Default constructor for class Array
template < class elementType, int numberOfElements >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
38 Array< elementType, numberOfElements >::Array()
39 {
40    ++arrayCount;                 // count one more object
41    size = numberOfElements;
42
43    for ( int i = 0; i < size; ++i )
44       ptr[ i ] = 0;                // initialize array
45 }
46
47 // Destructor for class Array
48 template < class elementType, int numberOfElements >
49 Array< elementType, numberOfElements >::~Array() { --arrayCount; }
50
51 // Get the size of the array
52 template < class elementType, int numberOfElements >
53 int Array< elementType, numberOfElements >::getSize() const { return size; }
54
55 // Determine if two arrays are equal and
56 // return true or false.
57 template < class elementType, int numberOfElements >
58 bool Array< elementType, numberOfElements >::
59             operator==( const Array &right ) const
60 {
61    if ( size != right.size )
62       return false;    // arrays of different sizes
63
64    for ( int i = 0; i < size; ++i )
65       if ( ptr[ i ] != right.ptr[ i ] )
66          return false; // arrays are not equal
67
68    return true;       // arrays are equal
69 }
70
71 // Determine if two arrays are not equal and
72 // return true or false.
73 template < class elementType, int numberOfElements >
74 bool Array< elementType, numberOfElements >::
75           operator!=( const Array &right ) const
76 {
77    if ( size != right.size )
78       return true;         // arrays of different sizes
79
80    for ( int i = 0; i < size; ++i )
81       if ( ptr[ i ] != right.ptr[ i ] )
82          return true;      // arrays are not equal
83
84    return false;            // arrays are equal
85 }
86
87 // Overloaded subscript operator
88 template < class elementType, int numberOfElements >
89 elementType &Array< elementType, numberOfElements >::
90             operator[]( int subscript )
91 {
92    // check for subscript out of range error
93    assert( 0 <= subscript && subscript < size );
94
95    return ptr[ subscript ];   // reference return creates lvalue
96 }
97
98 // Return the number of Array objects instantiated
99 template < class elementType, int numberOfElements >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
100 int Array< elementType, numberOfElements >::getArrayCount()
101    { return arrayCount; }
102
103 // Input values for entire array.
104 template < class elementType, int numberOfElements >
105 void Array< elementType, numberOfElements >::inputArray()
106 {
107    for ( int i = 0; i < size; ++i )
108       cin >> ptr[ i ];
109 }
110
111 // Output the array values
112 template < class elementType, int numberOfElements >
113 void Array< elementType, numberOfElements >::outputArray() const
114 {
115    for ( int i = 0; i < size; ++i ) {
116       cout << ptr[ i ] << ' ';
117
118       if ( ( i + 1 ) % 10 == 0 )
119          cout << '\n';
120    }
121
122    if ( i % 10 != 0 )
123       cout << '\n';
124 }
125
126 #endif
```

```
127 // Exercise 12.7 solution
128 #include <iostream>
129
130 using std::cout;
131
132 #include "arraytmp.h"
133
134 int main()
135 {
136    Array< int, 5 > intArray;
137
138    cout << "Enter " << intArray.getSize() << " integer values:\n";
139    intArray.inputArray();
140
141    cout << "\nThe values in intArray are:\n";
142    intArray.outputArray();
143
144    Array< float, 5 > floatArray;
145
146    cout << "\nEnter " << floatArray.getSize()
147         << " floating point values:\n";
148    floatArray.inputArray();
149
150    cout << "\nThe values in the double array are:\n";
151    floatArray.outputArray();
152
153    return 0;
154 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter 5 integer values:
99 98 97 96 95

The values in intArray are:
99 98 97 96 95

Enter 5 floating point values:
1.12 1.13 1.45 1.22 9.11

The values in the doubleArray are:
1.12 1.13 1.45 1.22 9.11
```

12.8 Write a program with class template **Array**. The template can instantiate an **Array** of any element type. Override the template with a specific definition for an **Array** of **float** elements (**class Array< float >**). The driver should demonstrate the instantiation of an **Array** of **int** through the template and should show that an attempt to instantiate an **Array** of **float** uses the definition provided in **class Array< float >**.

12.9 Distinguish between the terms "function template" and "template function."

ANS: A function template is used to instantiate template functions.

12.10 Which is more like a stencil—a class template or a template class? Explain your answer.

ANS: A class template can be viewed as a stencil from which a template class can be created. A template class can be viewed as a stencil from which objects of that class can be created. So, in a way, both can be viewed as stencils.

12.11 What is the relationship between function templates and overloading?

ANS: Function templates create overloaded versions of a function. The main difference is at compile time, where the compiler automatically creates the code for the template functions from the function template rather than the programmer creating the code.

12.12 Why might you choose to use a function template instead of a macro?

ANS: A macro is a text substitution done by the preprocessor. A function template provides real function definitions with all the type checking to ensure proper function calls.

12.13 What performance problem can result from using function templates and class templates?

ANS: There can be a tremendous proliferation of code in the program due to many copies of code generated by the compiler.

12.14 The compiler performs a matching process to determine which template function to call when a function is invoked. Under what circumstances does an attempt to make a match result in a compile error?

ANS: If the compiler cannot match the function call made to a template or if the matching process results in multiple matches at compile time, the compiler generates an error.

12.15 Why is it appropriate to call a class template a parameterized type?

ANS: When creating template classes from a class template, it is necessary to provide a type (or possibly several types) to complete the definition of the new type being declared. For example, when creating an "array of integers" from an **Array** class template, the type **int** is provided to the class template to complete the definition of an array of integers.

12.16 Explain why you might use the statement

```
Array< Employee > workerList( 100 );
```

in a C++ program.

ANS: When creating template classes from a class template, it is necessary to provide a type (or possibly several types) to complete the definition of the new type being declared. For example, when creating an "array of integers" from an **Array** class template, the type **int** is provided to the class template to complete the definition of an array of integers.

12.17 Review your answer to Exercise 12.16. Now, why might you use the statement

```
Array< Employee > workerList;
```

in a C++ program?

ANS: Declares an **Array** object to store an **Employee**. The default constructor is used.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

12.18 Explain the use of the following notation in a C++ program:

```
template< class T > Array< T >::Array( int s )
```

ANS: This notation is used to begin the definition of the **`Array( int )`** constructor for the class template **`Array`**.

12.19 Why might you typically use a nontype parameter with a class template for a container such as an array or stack?
ANS: To specify at compile time the size of the container class object being declared.

12.20 Describe how to provide a class for a specific type to override the class template for that type.

12.21 Describe the relationship between class templates and inheritance.

12.22 Suppose a class template has the header

```
template< class T1 > class C1
```

Describe the friendship relationships established by placing each of the following friendship declarations inside this class template header. Identifiers beginning with "**`f`**" are functions, identifiers beginning with "**`C`**" are classes and identifiers beginning with "**`T`**" can represent any type (i.e., built-in types or class types).

a) **`friend void f1();`**
ANS: To specify at compile time the size of the container class object being declared.
b) **`friend void f2( C1< T1 > &);`**
ANS: Function **`f2`** for a specific type of **`T1`** is a **`friend`** of the template class of type **`T1`**. For example, if **`T1`** is of type **`int`**, the function with the prototype

```
void f2( C1< int > & );
```

is a **`friend`** of the class **`C1< int >`**.
c) **`friend void C2::f4();`**
ANS: Function **`f4`** of class **`C2`** is a **`friend`** of all template classes instantiated from class template **`C1`**.
d) **`friend void C3< T1 >::f5( C1< T1 > & );`**
ANS: Function **`f5`** of class **`C3`** for a specific type of **`T1`** is a **`friend`** of the template class of type **`T1`**. For example, if **`T1`** is **`int`**, the function with the prototype

```
void c3< int >::f5( C1< int > & );
```

e) **`friend class C5;`**
ANS: Makes every member function of class **`C5`** a **`friend`** of all template classes instantiated from the class template **`C1`**.
f) **`friend class C6< T1 >;`**
ANS: For a specific type **`T1`**, makes every member function of **`C6< T1 >`** a **`friend`** of class **`C1< T1 >`**. For example, if **`T1`** is **`int`**, every member function of class **`C6< int >`** is a **`friend`** of **`C1< int >`**.

12.23 Suppose class template **`Employee`** has a **`static`** data member **`count`**. Suppose three template classes are instantiated from the class template. How many copies of the **`static`** data member will exist? How will the use of each be constrained (if at all)?

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

13

Exception Handling Solutions

Solutions

13.20 List the various exceptional conditions that have occurred in programs throughout this text. List as many additional exceptional conditions as you can. For each of these, describe briefly how a program would typically handle the exception using the exception-handling techniques discussed in this chapter. Some typical exceptions are division by zero, arithmetic overflow, array subscript out of bounds, exhaustion of the free store, etc.

13.21 Under what circumstances would the programmer not provide a parameter name when defining the type of the object that will be caught by a handler?

ANS: If there is no information in the object that is required in the handler, a parameter name is not required in the handler.

13.22 A program contains the statement

```
throw;
```

Where would you normally expect to find such a statement? What if that statement appeared in a different part of the program?

ANS: The statement would be found in an exception handler to rethrow an exception. If any **`throw`** expression occurs outside a **`try`** block, the function **`unexpected`** is called.

13.23 Under what circumstances would you use the following statement?

```
catch(...) { throw; }
```

ANS: The preceding statement is used to **`catch`** any exception and rethrow it for handling by an exception handler in a function within the call stack.

13.24 Compare and contrast exception handling with the various other error-processing schemes discussed in the text.

ANS: Exception handling enables the programmer to build more robust classes with built-in error processing capabilities. Once created, such classes allow clients of classes to concentrate on using the classes rather than defining what should happen if an error occurs while using the class. Exception handling offers the possibility that an error can be processed and that the program can continue execution. Other forms of error checking such as **`assert`** exit the program immediately without any further processing.

13.25 List the advantages of exception handling over conventional means of error processing.

13.26 Provide reasons why exceptions should not be used as an alternate form of program control.

ANS: Exceptions were designed for "exceptional cases." Exceptions do not follow conventional forms of program control. Therefore, using exceptions for anything other than error processing will not be easily recognized by others reading the code. This may make the program more difficult to modify and maintain.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

13.27 Describe a technique for handling related exceptions.

ANS: Create a base class for all related exceptions. In the base class, derive all the related exception classes. Once the exception class hierarchy is created, exceptions from the hierarchy can be caught as the base class exception type or as one of the derived class exception types.

13.28 Until this chapter, we have found that dealing with errors detected by constructors is a bit awkward. Exception handling gives us a much better means of dealing with such errors. Consider a constructor for a **String** class. The constructor uses **new** to obtain space from the free store. Suppose **new** fails. Show how you would deal with this without exception handling. Discuss the key issues. Show how you would deal with such memory exhaustion with exception handling. Explain why the exception handling method is superior.

```
// Exercise 13.28 Solution
#include <iostream>

using std::cout;
using std::cerr;

#include <new>
#include <cstdlib>

void message( void );

int main()
{
   long double *d[ 50 ];
   set_new_handler( message );

   for ( int q = 0; q < 50; ++q ){
      d[ q ] = new long double[ 10000000 ];
  cout << "allocated 10000000 long doubles to d[" << q << "]\n";
   }

   cout << "Memory Allocated\n";

   return 0;
}

void message( void )
{
   cerr << "Memory Allocation Failed\n";
   exit( EXIT_FAILURE );
}
```

```
Assertion failed: new_p == 0, file setnewh.cpp, line 52

abnormal program termination
```

13.29 Suppose a program **throw**s an exception and the appropriate exception handler begins executing. Now suppose that the exception handler itself **throw**s the same exception. Does this create an infinite recursion? Write a program to check your observation.

```
// Exercise 13.29 solution
#include <iostream>

using std::cout;

class TestException {
public:
   TestException( char *mPtr ) : message( mPtr ) {}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   void print() const { cout << message << '\n'; }
private:
   char *message;
};

int main()
{
   try {
      throw TestException( "This is a test" );
   }
   catch ( TestException &t ) {
      t.print();
      throw TestException( "This is another test" );
   }

   return 0;
}
```

```
This is a test

abnormal program termination
```

13.30 Use inheritance to create a base exception class and various derived exception classes. Then show that a **catch** handler specifying the base class can **catch** derived-class exceptions.

```
// Exercise 13.30 Solution
#include <iostream>

using std::cout;

#include <cstdlib>
#include <ctime>

class BaseException {
public:
   BaseException( char *mPtr ) : message( mPtr ) {}
   void print() const { cout << message << '\n'; }
private:
   char *message;
};

class DerivedException : public BaseException {
public:
   DerivedException( char *mPtr ) : BaseException( mPtr ) {}
};

class DerivedException2 : public DerivedException {
public:
   DerivedException2( char *mPtr ) : DerivedException( mPtr ) {}
};

int main()
{
   srand( time( 0 ) );

   try {
      throw ( rand() % 2 ? DerivedException( "DerivedException" ) :
                           DerivedException2( "DerivedException2" ) );
   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   catch ( BaseException &b ) {
      b.print();
   }

   return 0;
}
```

```
DerivedException2
```

13.31 Show a conditional expression that returns either a **double** or an **int**. Provide an **int catch** handler and a **double catch** handler. Show that only the **double catch** handler executes regardless of whether the **int** or the **double** is returned.

```
// Exercise 13.31 Solution
#include <iostream>
using std::cerr;

int main()
{
   try {
      int a = 7;
      double b = 9.9;

      throw a < b ? a : b;
   }
   catch ( int x ) {
      cerr << "The int value " << x << " was thrown\n";
   }
   catch ( double y ) {
      cerr << "The double value " << y << " was thrown\n";
   }

   return 0;
}
```

```
The double value 7 was thrown
```

13.32 Write a program designed to generate and handle a memory exhaustion error. Your program should loop on a request to create dynamic storage through operator **new**.

```
// Exercise 13.32 solution
#include <iostream>

using std::cout;
using std::cerr;

#include <new>
using std::bad_alloc;

#include <cstdlib>

int main()
{
   long double *ptr[ 10 ];

   try {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      for ( int i = 0; i < 10; ++i ) {
         ptr[ i ] = new long double[ 50000000 ];
         cout << "Allocated 50000000 long doubles in ptr[ "
              << i << " ]\n";
      }
   }
   catch ( bad_alloc ex ) {
      cerr << "Memory Allocation Failed.\n";
      exit( EXIT_FAILURE );
   }

   return 0;
}
```

```
Allocated 5000000 long doubles in ptr[ 0 ]
Allocated 5000000 long doubles in ptr[ 1 ]
Allocated 5000000 long doubles in ptr[ 2 ]
Allocated 5000000 long doubles in ptr[ 3 ]
Allocated 5000000 long doubles in ptr[ 4 ]
Allocated 5000000 long doubles in ptr[ 5 ]
Allocated 5000000 long doubles in ptr[ 6 ]
Allocated 5000000 long doubles in ptr[ 7 ]
Allocated 5000000 long doubles in ptr[ 8 ]
Allocated 5000000 long doubles in ptr[ 9 ]
```

13.33 Write a program which shows that all destructors for objects constructed in a block are called before an exception is thrown from that block.

```
// Exercise 13.33 Solution
#include <iostream>

using std::cout;
using std::cerr;


class Object {
public:
   Object( int val ) : value( val )
{ cout << "Object " << value << " constructor\n"; }
   ~Object()
{ cout << "Object " << value << " destructor\n"; }
private:
   int value;
};

class Error {
public:
   Error( char *s ) : string( s ) {}
   void print() const { cerr << '\n' << string << '\n'; }
private:
   char *string;
};

int main()
{
   try {
      Object a( 1 ), b( 2 ), c( 3 );
      cout << '\n';
      throw Error( "This is a test exception" );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   }
   catch ( Error &e ) {
      e.print();
   }

   return 0;
}
```

```
Object 1 constructor
Object 2 constructor
Object 3 constructor

Object 3 destructor
Object 2 destructor
Object 1 destructor

This is a test exception
```

13.34 Write a program which shows that member object destructors are called for only those member objects that were constructed before an exception occurred.

```
// Exercise 13_34 Solution
#include <iostream>

using std::cout;
using std::cerr;

// A sample exception class
class ExceptionClass {
public:
   ExceptionClass() : message( "An exception was thrown" ) {}
   void print() const { cerr << '\n' << message << '\n'; }
private:
   char *message;
};

// A class from which to build member objects
class Member {
public:
   Member( int val ) : value( val )
   {
      cout << "Member object " << value << " constructor called\n";

      // If value is 3, throw an exception for demonstration purposes.
      if ( value == 3 )
         throw ExceptionClass();
   }

   ~Member()
   { cout << "Member object " << value << " destructor called\n"; }
private:
   int value;
};

// A class to encapsulate objects of class Member
class Encapsulate {
public:
   Encapsulate() : m1( 1 ), m2( 2 ), m3( 3 ), m4( 4 ), m5( 5 ) {}
private:
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   Member m1, m2, m3, m4, m5;
};

int main()
{
   cout << "Constructing an object of class Encapsulate\n";

   try {
      Encapsulate e;
   }
   catch( ExceptionClass &except ) {
      except.print();
   }

   return 0;
}
```

```
Constructing an object of class Encapsulate
Member object 1 constructor called
Member object 2 constructor called
Member object 3 constructor called
Member object 2 destructor called
Member object 1 destructor called

An exception was thrown
```

13.35 Write a program that demonstrates how any exception is caught with **`catch(...)`**.

```
// Exercise 13.35 Solution
#include <iostream>

using std::cout;
using std::cerr;


// A sample exception class
class ExceptionClass {
public:
   ExceptionClass() : message( "An exception was thrown" ) {}
   void print() const { cerr << '\n' << message << '\n'; }
private:
   char *message;
};

void generateException();

int main()
{
   try {
      generateException();
   }
   catch( ... ) {
      cerr << "The \"catch all\" exception handler was invoked\n";
   }

   return 0;
}

void generateException()
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   throw ExceptionClass();
}
```

```
The "catch all" exception handler was invoked
```

13.36 Write a program which shows that the order of exception handlers is important. The first matching handler is the one that executes. Compile and run your program two different ways to show that two different handlers execute with two different effects.

13.37 Write a program that shows a constructor passing information about constructor failure to an exception handler after a `try` block.

```
// Exercise 13.37 Solution
#include <iostream>

using std::cout;
using std::cerr;

class InvalidIDNumberError {
public:
   InvalidIDNumberError( char *s ) : errorMessage( s ) {}
   void print() const { cerr << errorMessage; }
private:
   char *errorMessage;
};

class TestInvalidIDNumberError {
public:
   TestInvalidIDNumberError( int id ) : idNumber( id )
   {
      cout << "Constructor for object " << idNumber << '\n';

      if ( idNumber < 0 )
         throw InvalidIDNumberError( "ERROR: Negative ID number" );
   }
private:
   int idNumber;
};

int main()
{
   try {
      TestInvalidIDNumberError valid( 10 ), invalid( -1 );
   }
   catch ( InvalidIDNumberError &error ) {
      error.print();
      cerr << '\n';
   }

   return 0;
}
```

```
Constructor for object 10
Constructor for object -1
ERROR: Negative ID number
```

13.38 Write a program that uses a multiple inheritance hierarchy of exception classes to create a situation in which the order of exception handlers matters.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

13.39 Using **setjmp/longjmp**, a program can transfer control immediately to an error routine from a deeply nested function invocation. Unfortunately, as the stack is unwound, destructors are not called for the automatic objects that were created during the sequence of nested function calls. Write a program which demonstrates that these destructors are, in fact, not called.

13.40 Write a program that illustrates rethrowing an exception.

```
// Exercise 13.40 Solution
#include <iostream>

using std::cout;
using std::cerr;

class TestException {
public:
   TestException( char *m ) : message( m ) {}
   void print() const { cout << message << '\n'; }
private:
   char *message;
};

void f() { throw TestException( "Test exception thrown" ); }

void g()
{
   try {
      f();
   }
   catch ( ... ) {
      cerr << "Exception caught in function g(). Rethrowing...\n";
      throw;
   }
}

int main()
{
   try {
      g();  // start function call chain
   }
   catch ( ... ) {
      cerr << "Exception caught in function main()\n";
   }

   return 0;
}
```

```
Exception caught in function g(). Rethrowing...
Exception caught in function main()
```

13.41 Write a program that uses **set_unexpected** to set a user-defined function for **unexpected**, uses **set_unexpected** again, and then resets **unexpected** back to its previous function. Write a similar program to test **set_terminate** and **terminate**.

13.42 Write a program which shows that a function with its own **try** block does not have to catch every possible error generated within the **try**. Some exceptions can slip through to, and be handled in, outer scopes.

```
// Exercise 13.42 Solution
#include <iostream>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
3
4  using std::cout;
5  using std::cerr;
6
7  class TestException1 {
8  public:
9     TestException1( char *m ) : message( m ) {}
10    void print() const { cerr << message << '\n'; }
11 private:
12    char *message;
13 };
14
15 class TestException2 {
16 public:
17    TestException2( char *m ) : message( m ) {}
18    void print() const { cout << message << '\n'; }
19 private:
20    char *message;
21 };
22
23 void f()
24 {
25    throw TestException1( "TestException1" );
26 }
27
28 void g()
29 {
30    try {
31       f();
32    }
33    catch ( TestException2 &t2 ) {
34       cerr << "In g: Caught ";
35       t2.print();
36    }
37 }
38
39 int main()
40 {
41    try {
42       g();
43    }
44    catch ( TestException1 &t1 ) {
45       cerr << "In main: Caught ";
46       t1.print();
47    }
48
49    return 0;
50 }
```

```
In main: Caught TestException1
```

13.43 Write a program that **throw**s an error from a deeply nested function call and still has the **catch** handler following the **try** block enclosing the call chain catch the exception.

```
1  // Exercise 13.43 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cerr;
6
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
class TestException {
public:
   TestException( char *m ) : message( m ) {}
   void print() const { cout << message << '\n'; }
private:
   char *message;
};

void f() { throw TestException( "TestException" ); }

void g() { f(); }

void h() { g(); }

int main()
{
   try {
      h();
   }
   catch ( TestException &t ) {
      cerr << "In main: Caught ";
      t.print();
   }

   return 0;
}
```

```
In main: Caught TestException
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

14

File Processing Solutions

Solutions

14.5 Fill in the blanks in each of the following:

a) Computers store large amounts of data on secondary storage devices as _____.

ANS: files.

b) A _____ is composed of several fields.

ANS: record.

c) A field that may contain only digits, letters and blanks is called an _____ field.

ANS: alphanumeric.

d) To facilitate the retrieval of specific records from a file, one field in each record is chosen as a _____.

ANS: key.

e) The vast majority of information stored in computer systems is stored in _____ files.

ANS: sequential.

f) A group of related characters that conveys meaning is called a _____.

ANS: field.

g) The standard stream objects declared by header file **<iostream>** are _____, _____, _____ and _____.

ANS: **cin**, **cout**, **cerr**, **clog**.

h) **ostream** member function _____ outputs a character to the specified stream.

ANS: **put**.

i) **ostream** member function _____ is generally used to write data to a randomly accessed file.

ANS: **write**.

j) **istream** member function _____ repositions the file position pointer in a file.

ANS: **seekg**.

14.6 State which of the following are *true* and which are *false*. If *false*, explain why.

a) The impressive functions performed by computers essentially involve the manipulation of zeros and ones.

ANS: True.

b) People prefer to manipulate bits instead of characters and fields because bits are more compact.

ANS: False. People prefer to manipulate characters and fields because they are less cumbersome and more understandable.

c) People specify programs and data items as characters; computers then manipulate and process these characters as groups of zeros and ones.

ANS: True.

d) A person's 5-digit zip code is an example of a numeric field.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS: True.

e) A person's street address is generally considered to be an alphabetic field in computer applications.

ANS: False. A street address is generally considered to be alphanumeric.

f) Data items represented in computers form a data hierarchy in which data items become larger and more complex as we progress from fields to characters to bits, etc.

ANS: False. Data items processed by a computer form a data hierarchy in which data items become larger and more complex as we progress from bits to characters to fields, etc.

g) A record key identifies a record as belonging to a particular field.

ANS: False. A record key identifies a record as belonging to a particular person or entity.

h) Most organizations store all information in a single file to facilitate computer processing.

ANS: False. Most organizations have many files in which they store their information.

i) Each statement that processes a file in a C++ program explicitly refers to that file by name.

ANS: False. A pointer to each file is used to refer to the file.

j) When a program creates a file, the file is automatically retained by the computer for future reference.

ANS: True.

14.7 Exercise 14.3 asked the reader to write a series of single statements. Actually, these statements form the core of an important type of file processing program, namely, a file-matching program. In commercial data processing, it is common to have several files in each application system. In an accounts receivable system, for example, there is generally a master file containing detailed information about each customer such as the customer's name, address, telephone number, outstanding balance, credit limit, discount terms, contract arrangements, and possibly a condensed history of recent purchases and cash payments.

As transactions occur (e.g., sales are made and cash payments arrive), they are entered into a file. At the end of each business period (a month for some companies, a week for others, and a day in some cases) the file of transactions (called **"trans.dat"** in Exercise 14.3) is applied to the master file (called **"oldmast.dat"** in Exercise 14.3), thus updating each account's record of purchases and payments. During an updating run, the master file is rewritten as a new file (**"newmast.dat"**), which is then used at the end of the next business period to begin the updating process again.

File-matching programs must deal with certain problems that do not exist in single-file programs. For example, a match does not always occur. A customer on the master file may not have made any purchases or cash payments in the current business period, and therefore no record for this customer will appear on the transaction file. Similarly, a customer who did make some purchases or cash payments may have just moved to this community, and the company may not have had a chance to create a master record for this customer.

Use the statements from Exercise 14.3 as a basis for writing a complete file-matching accounts receivable program. Use the account number on each file as the record key for matching purposes. Assume that each file is a sequential file with records stored in increasing order by account number.

When a match occurs (i.e., records with the same account number appear on both the master and transaction files), add the dollar amount on the transaction file to the current balance on the master file, and write the **"newmast.dat"** record. (Assume purchases are indicated by positive amounts on the transaction file and payments are indicated by negative amounts.) When there is a master record for a particular account but no corresponding transaction record, merely write the master record to **"newmast.dat"**. When there is a transaction record but no corresponding master record, print the message **"Unmatched transaction record for account number …"** (fill in the account number from the transaction record).

```
1  // Exercise 14.7 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::ios;
6  using std::cerr;
7
8
9  #include <iomanip>
10
11 using std::setprecision;
12
13 #include <fstream>
14
15 using std::ofstream;
16 using std::ifstream;
17
18 #include <cstdlib>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
19
20 void printOutput( ofstream&, int, const char *, const char *, double );
21
22 int main()
23 {
24    int masterAccount, transactionAccount;
25    double masterBalance, transactionBalance;
26    char masterFirstName[ 20 ], masterLastName[ 20 ];
27
28    ifstream inOldMaster( "oldmast.dat" ),
29             inTransaction( "trans.dat" );
30    ofstream outNewMaster( "newmast.dat" );
31
32    if ( !inOldMaster ) {
33       cerr << "Unable to open oldmast.dat\n";
34       exit( EXIT_FAILURE );
35    }
36
37    if ( !inTransaction ) {
38       cerr << "Unable to open trans.dat\n";
39       exit( EXIT_FAILURE );
40    }
41
42    if ( !outNewMaster ) {
43       cerr << "Unable to open newmast.dat\n";
44       exit( EXIT_FAILURE );
45    }
46
47    cout << "Processing...\n";
48    inTransaction >> transactionAccount >> transactionBalance;
49
50    while ( !inTransaction.eof() ) {
51       inOldMaster >> masterAccount >> masterFirstName
52                   >> masterLastName >> masterBalance;
53
54       while ( masterAccount < transactionAccount && !inOldMaster.eof() ) {
55          printOutput( outNewMaster, masterAccount, masterFirstName,
56                       masterLastName, masterBalance );
57          inOldMaster >> masterAccount >> masterFirstName
58                      >> masterLastName >> masterBalance;
59       }
60
61       if ( masterAccount > transactionAccount ) {
62          cout << "Unmatched transaction record for account "
63               << transactionAccount << '\n';
64
65          inTransaction >> transactionAccount >> transactionBalance;
66       }
67
68       if ( masterAccount == transactionAccount ) {
69          masterBalance += transactionBalance;
70          printOutput( outNewMaster, masterAccount, masterFirstName,
71                       masterLastName, masterBalance );
72       }
73
74       inTransaction >> transactionAccount >> transactionBalance;
75    }
76
77    inTransaction.close();
78    outNewMaster.close();
79    inOldMaster.close();
80
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   return 0;
}

void printOutput( ofstream &oRef, int mAccount, const char *mfName,
                  const char *mlName, double mBalance )
{
      cout.setf( ios::fixed | ios::showpoint );
      oRef.setf( ios::fixed | ios::showpoint );

      oRef << mAccount << ' ' << mfName << ' ' << mlName << ' '
           << setprecision( 2 ) << mBalance << '\n';
      cout << mAccount << ' ' << mfName << ' ' << mlName << ' '
           << setprecision( 2 ) << mBalance << '\n';
}
```

```
Processing...
100 Ajax Guppie 678.06
300 Sue Pirhana 650.07
400 Clint Bass 994.22
Unmatched transaction record for account 445
500 Aias Shark 895.80
700 Tom Mahi-Mahi -23.57
900 Marisal Carp 200.55
```

Contents of “oldmast.dat”

```
100 Ajax Guppie 543.89
300 Sue Pirhana 22.88
400 Clint Bass -6.32
500 Aias Shark 888.71
700 Tom Mahi-Mahi 76.09
900 Marisal Carp 100.55
```

Contents of “trans.dat”

```
100 134.17
300 627.19
400 1000.54
445 55.55
500 7.09
700 -99.66
900 100.00
```

Contents of “newmast.dat”

```
100 Ajax Guppie 678.06
300 Sue Pirhana 650.07
400 Clint Bass 994.22
500 Aias Shark 895.80
700 Tom Mahi-Mahi -23.57
900 Marisal Carp 200.55
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

14.8 After writing the program of Exercise 14.7, write a simple program to create some test data for checking out the program. Use the following sample account data:

Master file Account number	Name	Balance
100	Alan Jones	348.17
300	Mary Smith	27.19
500	Sam Sharp	0.00
700	Suzy Green	-14.22

Transaction file Account number	Transaction amount
100	27.14
300	62.11
400	100.56
900	82.17

```
// Exercise 14.8 Solution
#include <iostream>

using std::cout;
using std::ios;
using std::cerr;

#include <iomanip>

using std::setprecision;
using std::setiosflags;

#include <fstream>

using std::ofstream;
using std::ifstream;

#include <cstdlib>
#include <ctime>

int main()
{
   const char *firstNames[] = { "Walter", "Alice", "Alan", "Mary", "Steve",
                                "Gina", "Tom", "Cindy", "Ilana", "Pam" },
              *lastNames[] = { "Red", "Blue", "Yellow", "Orange", "Purple",
                               "Green", "Violet", "White", "Black", "Brown" };
   ofstream outOldMaster( "oldMast.dat" ),
            outTransaction( "trans.dat" );

   int z;

   srand( time( 0 ) );

   if ( !outOldMaster ) {
      cerr << "Unable to open oldmast.dat\n";
      exit( EXIT_SUCCESS );
   }

   if ( !outTransaction ) {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
40          cerr << "Unable to open trans.dat\n";
41          exit( EXIT_SUCCESS );
42       }
43
44       // write data to "oldmast.dat"
45       cout << setiosflags( ios::fixed | ios::showpoint )
46            << "Contents of \"oldmast.dat\":\n";
47
48       outOldMaster.setf( ios::fixed | ios::showpoint );
49       for ( z = 1; z < 11; ++z ) {
50          int value = rand() % 10, value2 = rand() % 50;
51          outOldMaster << z * 100 << ' ' << firstNames[ z - 1 ] << ' '
52                       << lastNames[ value ] << ' ' << setprecision( 2 )
53                       << ( value * 100 ) / ( value2 / 3 + 4.32 ) << '\n';
54          cout << z * 100 << ' ' << firstNames[ z - 1 ] << ' '
55               << lastNames[ value ] << ' ' << setprecision( 2 )
56               << ( value * 100 ) / ( value2 / 3 + 4.32 ) << '\n';
57       }
58
59       // write data to "trans.dat"
60       cout << "\nContents of \"trans.dat\":\n";
61       outTransaction.setf( ios::fixed | ios::showpoint );
62
63       for ( z = 1; z < 11; ++z ) {
64          int value = 25 - rand() % 50;
65          outTransaction << z * 100 << ' ' << setprecision( 2 )
66                         << ( value * 100 ) / ( 2.667 * ( 1 + rand() % 10 ) )
67                         << '\n';
68          cout << z * 100 << ' ' << setprecision( 2 )
69               << ( value * 100 ) / ( 2.667 * ( 1 + rand() % 10 ) ) << '\n';
70       }
71
72       outTransaction.close();
73       outOldMaster.close();
74
75       ifstream inMaster( "oldmast.dat" ), inTrans( "trans.dat" );
76       ofstream newMaster( "newMast.dat" );
77
78       if ( !inMaster ) {
79          cerr << "Unable to open oldmast.dat\n";
80          exit( EXIT_SUCCESS );
81       }
82
83       if ( !inTrans ) {
84          cerr << "Unable to open trans.dat\n";
85          exit( EXIT_SUCCESS );
86       }
87
88       if ( !newMaster ) {
89          cerr << "Unable to open newmast.dat\n";
90          exit( EXIT_SUCCESS );
91       }
92
93       int account, mAccount;
94       double balance, mBalance;
95       char mFirst[ 20 ], mLast[ 20 ];
96
97       cout << "Processing...\n";
98       inTrans >> account >> balance;
99
100      while ( !inTrans.eof() ) {
101         inMaster >> mAccount >> mFirst >> mLast >> mBalance;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
102
103         while ( mAccount < account && !inMaster.eof() )
104            inMaster >> mAccount >> mFirst >> mLast >> mBalance;
105
106         if ( mAccount > account ) {
107            cout << "Unmatched transaction record: account " << account << '\n';
108
109            inTrans >> account >> balance;
110         }
111
112         if ( mAccount == account ) {
113            mBalance += balance;
114            newMaster << mAccount << ' ' << mFirst << ' ' << mLast
115                      << ' ' << mBalance << '\n';
116         }
117
118         inTrans >> account >> balance;
119      }
120
121      newMaster.close();
122      inTrans.close();
123      inMaster.close();
124
125      return 0;
126   }
```

```
Contents of "oldmast.dat":
100 Walter Brown 46.58
200 Alice Orange 47.47
300 Alan Green 28.87
400 Mary Black 49.02
500 Steve White 67.83
600 Gina Orange 56.39
700 Tom White 38.21
800 Cindy Red 0.00
900 Ilana Brown 87.21
1000 Pam Red 0.00

Contents of "trans.dat":
100 -149.98
200 262.47
300 -41.24
400 -412.45
500 23.43
600 318.71
700 -224.97
800 -33.33
900 -249.97
1000 -71.24
```

Contents of “oldmast.dat”

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
100 Walter Brown 46.58
200 Alice Orange 47.47
300 Alan Green 28.87
400 Mary Black 49.02
500 Steve White 67.83
600 Gina Orange 56.39
700 Tom White 38.21
800 Cindy Red 0.00
900 Ilana Brown 87.21
1000 Pam Red 0.00
```

Contents of "trans.dat"

```
100 -149.98
200 262.47
300 -41.24
400 -412.45
500 23.43
600 318.71
700 -224.97
800 -33.33
900 -249.97
1000 -71.24
```

14.9 Run the program of Exercise 14.7 using the files of test data created in Exercise 14.8. Print the new master file. Check that the accounts have been updated correctly.

ANS: Contents of newmast.dat

```
100 Walter Brown -103.40
200 Alice Orange 309.94
300 Alan Green -12.37
400 Mary Black -363.43
500 Steve White 91.26
600 Gina Orange 375.10
700 Tom White -186.76
800 Cindy Red -33.33
900 Ilana Brown -162.76
1000 Pam Red -71.24
```

14.10 It is possible (actually common) to have several transaction records with the same record key. This occurs because a particular customer might make several purchases and cash payments during a business period. Rewrite your accounts receivable file-matching program of Exercise 14.7 to provide for the possibility of handling several transaction records with the same record key. Modify the test data of Exercise 14.8 to include the following additional transaction records:

Account number	Dollar amount
300	83.89
700	80.78
700	1.53

```
1  // Exercise 14.10 Solution
2  #include <iostream>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
3
4  using std::cout;
5  using std::ios;
6  using std::cerr;
7
8  #include <fstream>
9  using std::ofstream;
10 using std::ifstream;
11
12 #include <iomanip>
13
14 using std::setprecision;
15 using std::setiosflags;
16
17 #include <cstdlib>
18
19 void printOutput( ofstream &, int, const char *, const char *, double );
20
21 int main()
22 {
23    int masterAccount, transactionAccount;
24    double masterBalance, transactionBalance;
25    char masterFirstName[ 20 ], masterLastName[ 20 ];
26
27    ifstream inOldmaster( "oldmast.dat" ),
28             inTransaction( "trans.dat" );
29    ofstream outNewmaster( "newmast.dat" );
30
31    if ( !inOldmaster ) {
32       cerr << "Unable to open oldmast.dat\n";
33       exit( EXIT_FAILURE );
34    }
35
36    if ( !inTransaction ) {
37       cerr << "Unable to open trans.dat\n";
38       exit( EXIT_FAILURE );
39    }
40
41    if ( !outNewmaster ) {
42       cerr << "Unable to open newmast.dat\n";
43       exit( EXIT_FAILURE );
44    }
45
46    cout << "Processing....\n";
47    inTransaction >> transactionAccount >> transactionBalance;
48
49    while ( !inTransaction.eof() ) {
50       inOldmaster >> masterAccount >> masterFirstName >> masterLastName
51                   >> masterBalance;
52
53       while ( masterAccount < transactionAccount && !inOldmaster.eof() ) {
54          printOutput( outNewmaster, masterAccount, masterFirstName,
55                       masterLastName, masterBalance );
56          inOldmaster >> masterAccount >> masterFirstName >> masterLastName
57                      >> masterBalance;
58       }
59
60       if ( masterAccount > transactionAccount ) {
61          cout << "Unmatched transaction record for account "
62               << transactionAccount << '\n';
63          inTransaction >> transactionAccount >> transactionBalance;
64       }
65       else if ( masterAccount < transactionAccount ) {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
66             cout << "Unmatched transaction record for account "
67                  << transactionAccount << '\n';
68             inTransaction >> transactionAccount >> transactionBalance;
69          }
70
71          while ( masterAccount == transactionAccount &&
72                  !inTransaction.eof() ) {
73             masterBalance += transactionBalance;
74             inTransaction >> transactionAccount >> transactionBalance;
75          }
76
77          printOutput( outNewmaster, masterAccount, masterFirstName,
78                       masterLastName, masterBalance );
79       }
80
81       inTransaction.close();
82       outNewmaster.close();
83       inOldmaster.close();
84
85       return 0;
86    }
87
88    void printOutput( ofstream &oRef, int mAccount, const char *mfName,
89                      const char *mlName, double mBalance )
90    {
91          cout.setf( ios::showpoint | ios::fixed );
92          oRef.setf( ios::showpoint | ios::fixed );
93          oRef << mAccount << ' ' << mfName << ' ' << mlName << ' '
94               << setprecision( 2 ) << mBalance << '\n';
95          cout << mAccount << ' ' << mfName << ' ' << mlName << ' '
96               << setprecision( 2 ) << mBalance << '\n';
97          cout.unsetf( ios::showpoint | ios::fixed );
98    }
```

```
Processing....
100 Walter Brown -103.40
200 Alice Orange 309.94
300 Alan Green 71.52
400 Mary Black -363.43
500 Steve White 91.26
600 Gina Orange 375.10
700 Tom White -104.45
800 Cindy Red -33.33
900 Ilana Brown -162.76
1000 Pam Red -71.24
```

Contents of “oldmast.dat”

```
100 Walter Brown 46.58
200 Alice Orange 47.47
300 Alan Green 28.87
400 Mary Black 49.02
500 Steve White 67.83
600 Gina Orange 56.39
700 Tom White 38.21
800 Cindy Red 0.00
900 Ilana Brown 87.21
1000 Pam Red 0.00
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Contents of "trans.dat"

```
100 -149.98
200 262.47
300 -41.24
300 83.89
400 -412.45
500 23.43
600 318.71
700 -224.97
700 80.78
700 1.53
800 -33.33
900 -249.97
1000 -71.24
```

Contents of "newmast.dat"

```
100 Walter Brown -103.40
200 Alice Orange 309.94
300 Alan Green 71.52
400 Mary Black -363.43
500 Steve White 91.26
600 Gina Orange 375.10
700 Tom White -104.45
800 Cindy Red -33.33
900 Ilana Brown -162.76
1000 Pam Red -71.24
```

14.11 Write a series of statements that accomplish each of the following. Assume the structure

```
struct Person {
   char lastName[ 15 ];
   char firstName[ 15 ];
   char age[ 4 ];
};
```

has been defined, and that the random-access file has been opened properly.

a) Initialize the file **"nameage.dat"** with 100 records containing **lastName = "unassigned"**, **firstName = ""** and **age = "0"**.

ANS:

```
// fstream object "fileObject" corresponds to file "nameage.dat"
Person personInfo = { "unassigned", "", 0 };
for ( int r = 0; r < 100; ++r )
   fileObject.write( reinterpret_cast< char * >( &personInfo,
                     sizeof( personInfo ) );
```

b) Input 10 last names, first names and ages, and write them to the file.

ANS:

```
fileObject.seekp( 0 );
for ( int x = 1; x <= 10; ++x ) {
    cout << "Enter last name, first name, and age: ";
    cin >> personInfo.lastName >> personInfo.firstName >> personInfo.age;
    fileObject.write( reinterpret_cast< char * > &personInfo,
                      sizeof( personInfo ) );
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

c) Update a record that has information in it, and if there is none, tell the user "No info."
d) Delete a record that has information by reinitializing that particular record.

14.12 You are the owner of a hardware store and need to keep an inventory that can tell you what different tools you have, how many of each you have on hand and the cost of each one. Write a program that initializes the random-access file **"hardware.dat"** to one hundred empty records, lets you input the data concerning each tool, enables you to list all your tools, lets you delete a record for a tool that you no longer have and lets you update *any* information in the file. The tool identification number should be the record number. Use the following information to start your file:

Record #	Tool name	Quantity	Cost
3	Electric sander	7	57.98
17	Hammer	76	11.99
24	Jig saw	21	11.00
39	Lawn mower	3	79.50
56	Power saw	18	99.99
68	Screwdriver	106	6.99
77	Sledge hammer	11	21.50
83	Wrench	34	7.50

```
1  // Exercise 14.12 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8  using std::cerr;
9
10 #include <iomanip>
11
12 using std::setw;
13 using std::setprecision;
14 using std::setiosflags;
15
16 #include <fstream>
17 using std::ofstream;
18 using std::ifstream;
19
20 #include <cstring>
21 #include <cctype>
22 #include <cstdlib>
23
24 void initializeFile( fstream & );
25 void inputData( fstream & );
26 void listTools( fstream & );
27 void updateRecord( fstream & );
28 void insertRecord( fstream & );
29 void deleteRecord( fstream & );
30 int instructions( void );
31
32 const int LENGTH = 30;
33
34 struct Data {
35    int partNumber;
36    char toolName[ LENGTH ];
37    int inStock;
38    double unitPrice;
39 };
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
40
41 int main()
42 {
43    int choice;
44    char response;
45    fstream file( "hardware.dat", ios::in | ios::out );
46    void ( *f[] )( fstream & ) = { listTools, updateRecord, insertRecord,
47                                   deleteRecord };
48
49    if ( !file ) {
50       cerr << "File could not be opened.\n";
51       exit( EXIT_FAILURE );
52    }
53
54    cout << "Should the file be initialized (Y or N): ";
55    cin >> response;
56
57    while ( toupper( response ) != 'Y' && toupper( response ) != 'N' ) {
58       cout << "Invalid response. Enter Y or N: ";
59       cin >> response;
60    }
61
62    if ( toupper( response ) == 'Y' ) {
63       initializeFile( file );
64       inputData( file );
65    }
66
67    while ( ( choice = instructions() ) != 5 ) {
68       ( *f[ choice - 1 ] )( file );
69       file.clear();    // reset eof indicator
70    }
71
72    file.close();
73
74    return 0;
75 }
76
77 void initializeFile( fstream &fRef )
78 {
79    Data blankItem = { -1, "", 0, 0.0 };
80
81    // See Chapter 21 for a discussion of reinterpret_cast
82    for ( int i = 0; i < 100; ++i )
83       fRef.write( reinterpret_cast< char * >( &blankItem ), sizeof( Data ) );
84 }
85
86 void inputData( fstream &fRef )
87 {
88    Data temp;
89
90    cout << "Enter the partnumber (0 - 99, -1 to end input): ";
91    cin >> temp.partNumber;
92
93    while ( temp.partNumber != -1 ) {
94       cout << "Enter the tool name: ";
95       cin.ignore();  // ignore the newline on the input stream
96       cin.get( temp.toolName, LENGTH );
97       cout << "Enter quantity and price: ";
98       cin >> temp.inStock >> temp.unitPrice;
99       fRef.seekp( ( temp.partNumber ) * sizeof( Data ) );
100      fRef.write( reinterpret_cast< char * >( &temp ), sizeof( Data ) );
101
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
102         cout << "Enter the partnumber (0 - 99, -1 to end input): ";
103         cin >> temp.partNumber;
104      }
105   }
106
107   int instructions( void )
108   {
109      int choice;
110
111      cout << "\nEnter a choice:\n1  List all tools."
112           << "\n2  Update record.\n3  Insert record."
113           << "\n4  Delete record.\n5  End program.\n";
114
115      do {
116         cout << "? ";
117         cin >> choice;
118      } while ( choice < 1 || choice > 5 );
119
120      return choice;
121   }
122
123   void listTools( fstream &fRef )
124   {
125      Data temp;
126
127      cout << setw( 7 ) << "Record#" << "    " << setiosflags( ios::left )
128           << setw( 30 ) << "Tool name" << resetiosflags( ios::left )
129           << setw( 13 ) << "Quantity" << setw( 10 ) << "Cost\n";
130
131      for ( int count = 0; count < 100 && !fRef.eof(); ++count ) {
132         fRef.seekg( count * sizeof( Data ) );
133         fRef.read( reinterpret_cast< char * >( &temp ), sizeof( Data ) );
134
135         if ( temp.partNumber >= 0 && temp.partNumber < 100 ) {
136            cout.setf( ios::fixed | ios::showpoint );
137            cout << setw( 7 ) << temp.partNumber << "    "
138                 << setiosflags( ios::left ) << setw( 30 ) << temp.toolName
139                 << resetiosflags( ios::left ) << setw( 13 ) << temp.inStock
140                 << setprecision( 2 ) << setw( 10 ) << temp.unitPrice << '\n';
141         }
142      }
143   }
144
145   void updateRecord( fstream &fRef )
146   {
147      Data temp;
148      int part;
149
150      cout << "Enter the part number for update: ";
151      cin >> part;
152      fRef.seekg( part * sizeof( Data ) );
153      fRef.read( reinterpret_cast< char * >( &temp ), sizeof( Data ) );
154
155      if ( temp.partNumber != -1 ) {
156         cout << setw( 7 ) << "Record#" << "    " << setiosflags( ios::left )
157              << setw( 30 ) << "Tool name" << resetiosflags( ios::left )
158              << setw( 13 ) << "Quantity" << setw( 10 ) << "Cost\n";
159
160         cout.setf( ios::fixed | ios::showpoint );
161         cout << setw( 7 ) << temp.partNumber << "    "
162              << setiosflags( ios::left ) << setw( 30 ) << temp.toolName
163              << resetiosflags( ios::left ) << setw( 13 ) << temp.inStock
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
164            << setprecision( 2 ) << setw( 10 ) << temp.unitPrice << '\n'
165            << "Enter the tool name: ";
166
167       cin.ignore();  // ignore the newline on the input stream
168       cin.get( temp.toolName, LENGTH );
169       cout << "Enter quantity and price: ";
170       cin >> temp.inStock >> temp.unitPrice;
171
172       fRef.seekp( ( temp.partNumber ) * sizeof( Data ) );
173       fRef.write( reinterpret_cast< char * > ( &temp ), sizeof( Data ) );
174    }
175    else
176       cerr << "Cannot update. The record is empty.\n";
177 }
178
179 void insertRecord( fstream &fRef )
180 {
181    Data temp;
182    int part;
183
184    cout << "Enter the partnumber for insertion: ";
185    cin >> part;
186    fRef.seekg( ( part ) * sizeof( Data ) );
187    fRef.read( reinterpret_cast< char * > ( &temp ), sizeof( Data ) );
188
189    if ( temp.partNumber == -1 ) {
190       temp.partNumber = part;
191       cout << "Enter the tool name: ";
192       cin.ignore();  // ignore the newline on the input stream
193       cin.get( temp.toolName, LENGTH );
194       cout << "Enter quantity and price: ";
195       cin >> temp.inStock >> temp.unitPrice;
196
197       fRef.seekp( ( temp.partNumber ) * sizeof( Data ) );
198       fRef.write( reinterpret_cast< char * >( &temp ), sizeof( Data ) );
199    }
200    else
201       cerr << "Cannot insert. The record contains information.\n";
202 }
203
204 void deleteRecord( fstream &fRef )
205 {
206    Data blankItem = { -1, "", 0, 0.0 }, temp;
207    int part;
208
209    cout << "Enter the partnumber for deletion: ";
210    cin >> part;
211
212    fRef.seekg( part * sizeof( Data ) );
213    fRef.read( reinterpret_cast< char * >( &temp ), sizeof( Data ) );
214
215    if ( temp.partNumber != -1 ) {
216       fRef.seekp( part * sizeof( Data ) );
217       fRef.write( reinterpret_cast< char * >( &blankItem ), sizeof( Data ) );
218       cout << "Record deleted.\n";
219    }
220    else
221       cerr << "Cannot delete. The record is empty.\n";
222 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Should the file be initialized (Y or N): Y
Enter the partnumber (0 - 99, -1 to end input): 77
Enter the tool name: Sledge hammer

Enter quantity and price: 11 21.50
Enter the partnumber (0 - 99, -1 to end input): -1

Enter a choice:
1  List all tools.
2  Update record.
3  Insert record.
4  Delete record.
5  End program.
? 1
Record#    Tool name                          Quantity     Cost
     77    Sledge hammer                            11     21.50

Enter a choice:
1  List all tools.
2  Update record.
3  Insert record.
4  Delete record.
5  End program.
? 3

Enter the partnumber for insertion: 44
Enter the tool name: Pipe wrench
Enter quantity and price: 1 19.99

Enter a choice:
1  List all tools.
2  Update record.
3  Insert record.
4  Delete record.
5  End program.
? 2
Enter the part number for update: 44
Record#    Tool name                          Quantity     Cost
     44    Pipe wrench                              1     19.99

Enter the tool name: Pipe wrench
Enter quantity and price: 1 14.99

Enter a choice:
1  List all tools.
2  Update record.
3  Insert record.
4  Delete record.
5  End program.
? 1

Record#    Tool name                          Quantity     Cost
     44    Pipe wrench                              1     14.99
     77    Sledge hammer                           11     21.50

Enter a choice:
1  List all tools.
2  Update record.
3  Insert record.
4  Delete record.
5  End program.
? 4
Enter the partnumber for deletion: 44
Record deleted.
...
```

http://librosysolucionarios.net

14.13 Modify the telephone number word-generating program you wrote in Chapter 4 so that it writes its output to a file. This allows you to read the file at your convenience. If you have a computerized dictionary available, modify your program to look up the thousands of seven-letter words in the dictionary. Some of the interesting seven-letter combinations created by this program may consist of two or more words. For example, the phone number 8432677 produces "THEBOSS." Modify your program to use the computerized dictionary to check each possible seven-letter word to see if it is a valid one-letter word followed by a valid six-letter word, a valid two-letter word followed by a valid five-letter word, etc.

```
// Exercise 14.13 Solution
#include <iostream>

using std::cout;
using std::cin;
using std::ios;
using std::cerr;

#include <fstream>
using std::ofstream;
using std::ifstream;

#include <cstdlib>
#include <cctype>

void wordGenerator( const int * const );

int main()
{
   int phoneNumber[ 7 ] = { 0 };

   cout << "Enter a phone number (digits 2 through 9) "
        << "in the form: xxx-xxxx\n";

   // loop 8 times: 7 digits plus hyphen
   // hyphen is is not placed in phoneNumber
   for ( int u = 0, v = 0; u < 8; ++u ) {
      int i = cin.get();

      // See chapter 16 for a discussion of isdigit
      if ( isdigit( i ) )  // ctype library
         phoneNumber[ v++ ] = i - '0';
   }

   wordGenerator( phoneNumber );

   return 0;
}

void wordGenerator( const int * const n )
{
   ofstream outFile( "phone.dat" );
   const char *phoneLetters[ 10 ] = { "", "", "ABC", "DEF", "GHI", "JKL",
                                      "MNO", "PRS", "TUV", "WXY" };

   if ( !outFile ) {
      cerr << "\"phone.dat\" could not be opened.\n";
      exit( EXIT_FAILURE );
   }

   int count = 0;

   // output all possible combinations
   for ( int i1 = 0; i1 <= 2; ++i1 )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
55          for ( int i2 = 0; i2 <= 2; ++i2 )
56             for ( int i3 = 0; i3 <= 2; ++i3 )
57                for ( int i4 = 0; i4 <= 2; ++i4 )
58                   for ( int i5 = 0; i5 <= 2; ++i5 )
59                      for ( int i6 = 0; i6 <= 2; ++i6 )
60                         for ( int i7 = 0; i7 <= 2; ++i7 ) {
61                            outFile << phoneLetters[ n[ 0 ] ][ i1 ]
62                                    << phoneLetters[ n[ 1 ] ][ i2 ]
63                                    << phoneLetters[ n[ 2 ] ][ i3 ]
64                                    << phoneLetters[ n[ 3 ] ][ i4 ]
65                                    << phoneLetters[ n[ 4 ] ][ i5 ]
66                                    << phoneLetters[ n[ 5 ] ][ i6 ]
67                                    << phoneLetters[ n[ 6 ] ][ i7 ] << ' ';
68
69                            if ( ++count % 9 == 0 )
70                               outFile << '\n';
71                         }
72
73       outFile << "\nPhone number is ";
74
75       for ( int i = 0; i < 7; ++i ) {
76          if ( i == 3 )
77             outFile << '-';
78
79          outFile << n[ i ];
80       }
81
82       outFile.close();
83    }
```

Contents of phone.dat

```
TMPJDPW TMPJDPX TMPJDPY TMPJDRW TMPJDRX TMPJDRY TMPJDSW TMPJDSX TMPJDSY
TMPJEPW TMPJEPX TMPJEPY TMPJERW TMPJERX TMPJERY TMPJESW TMPJESX TMPJESY
TMPJFPW TMPJFPX TMPJFPY TMPJFRW TMPJFRX TMPJFRY TMPJFSW TMPJFSX TMPJFSY
TMPKDPW TMPKDPX TMPKDPY TMPKDRW TMPKDRX TMPKDRY TMPKDSW TMPKDSX TMPKDSY
TMPKEPW TMPKEPX TMPKEPY TMPKERW TMPKERX TMPKERY TMPKESW TMPKESX TMPKESY
...
VOSLDPW VOSLDPX VOSLDPY VOSLDRW VOSLDRX VOSLDRY VOSLDSW VOSLDSX VOSLDSY
VOSLEPW VOSLEPX VOSLEPY VOSLERW VOSLERX VOSLERY VOSLESW VOSLESX VOSLESY
VOSLFPW VOSLFPX VOSLFPY VOSLFRW VOSLFRX VOSLFRY VOSLFSW VOSLFSX VOSLFSY

Phone number is 867-5379
```

14.14 Write a program that uses the **`sizeof`** operator to determine the sizes in bytes of the various data types on your computer system. Write the results to the file **`"datasize.dat"`** so you may print the results later. The format for the results in the file should be

Data type	Size
`char`	1
`unsigned char`	1
`short int`	2
`unsigned short int`	2
`int`	4
`unsigned int`	4

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Data type	Size
long int	4
unsigned long int	4
float	4
double	8
long double	16

Note: The sizes of the built-in data types on your computer may differ from those listed above.

```
// Exercise 14.14 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cerr;

#include <iomanip>

using std::setw;

#include <fstream>

using std::ofstream;
using std::ifstream;

#include <cstdlib>

int main()
{
   ofstream outFile( "datasize.dat" );

   if ( !outFile ) {
      cerr << "Unable to open \"datasize.dat\".\n";
      exit( EXIT_FAILURE );
   }

   outFile << "Data type" << setw( 16 ) << "Size\nchar"
           << setw( 21 ) << sizeof( char )
           << "\nunsigned char" << setw( 12 ) << sizeof( unsigned char )
           << "\nshort int" << setw(16) << sizeof( short int )
           << "\nunsigned short int" << setw( 7 ) << sizeof( unsigned short )
           << "\nint" << setw( 22 ) << sizeof( int ) << '\n';

   outFile << "unsigned int" << setw( 13 ) << sizeof( unsigned )
           << "\nlong int" << setw( 17 ) << sizeof( long )
           << "\nunsigned long int" << setw( 8 ) << sizeof( unsigned long )
           << "\ndouble" << setw( 20 ) << sizeof( double )
           << "\ndouble" << setw( 19 ) << sizeof( double )
           << "\nlong double" << setw( 14 ) << sizeof( long double ) << endl;

   outFile.close();

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Contents of datasize.dat

```
Data type             Size
char                     1
unsigned char            1
short int                2
unsigned short int       2
int                      4
unsigned int             4
long int                 4
unsigned long int        4
float                    4
double                   8
long double              8
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

15

Data Structures Solutions

Solutions

15.6 Write a program that concatenates two linked list objects of characters. The program should include function **concatenate**, which takes references to both list objects as arguments and concatenates the second list to the first list.

```
// LIST.H
// Template List class definition
// Added copy constructor to member functions (not included in chapter).
#ifndef LIST_H
#define LIST_H

#include <iostream>

using std::cout;

#include <cassert>
#include "listnd.h"

template< class NODETYPE >
class List {
public:
   List();                              // default constructor
   List( const List< NODETYPE > & );  // copy constructor
   ~List();                             // destructor
   void insertAtFront( const NODETYPE & );
   void insertAtBack( const NODETYPE & );
   bool removeFromFront( NODETYPE & );
   bool removeFromBack( NODETYPE & );
   bool isEmpty() const;
   void print() const;
protected:
   ListNode< NODETYPE > *firstPtr;  // pointer to first node
   ListNode< NODETYPE > *lastPtr;   // pointer to last node

   // Utility function to allocate a new node
   ListNode< NODETYPE > *getNewNode( const NODETYPE & );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
};

// Default constructor
template< class NODETYPE >
List< NODETYPE >::List() { firstPtr = lastPtr = 0; }

// Copy constructor
template< class NODETYPE >
List< NODETYPE >::List( const List<NODETYPE> &copy )
{
   firstPtr = lastPtr = 0;  // initialize pointers

   ListNode< NODETYPE > *currentPtr = copy.firstPtr;

   while ( currentPtr != 0 ) {
      insertAtBack( currentPtr -> data );
      currentPtr = currentPtr -> nextPtr;
   }
}

// Destructor
template< class NODETYPE >
List< NODETYPE >::~List()
{
   if ( !isEmpty() ) {    // List is not empty
      cout << "Destroying nodes ...\n";

      ListNode< NODETYPE > *currentPtr = firstPtr, *tempPtr;

      while ( currentPtr != 0 ) {  // delete remaining nodes
         tempPtr = currentPtr;
         cout << tempPtr -> data << ' ';
         currentPtr = currentPtr -> nextPtr;
         delete tempPtr;
      }
   }

   cout << "\nAll nodes destroyed\n\n";
}

// Insert a node at the front of the list
template< class NODETYPE >
void List< NODETYPE >::insertAtFront( const NODETYPE &value )
{
   ListNode<NODETYPE> *newPtr = getNewNode( value );

   if ( isEmpty() )  // List is empty
      firstPtr = lastPtr = newPtr;
   else {           // List is not empty
      newPtr -> nextPtr = firstPtr;
      firstPtr = newPtr;
   }
}

// Insert a node at the back of the list
template< class NODETYPE >
void List< NODETYPE >::insertAtBack( const NODETYPE &value )
{
   ListNode< NODETYPE > *newPtr = getNewNode( value );

   if ( isEmpty() )  // List is empty
      firstPtr = lastPtr = newPtr;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
94     else {          // List is not empty
95        lastPtr -> nextPtr = newPtr;
96        lastPtr = newPtr;
97     }
98  }
99
100 // Delete a node from the front of the list
101 template< class NODETYPE >
102 bool List< NODETYPE >::removeFromFront( NODETYPE &value )
103 {
104    if ( isEmpty() )             // List is empty
105       return false;             // delete unsuccessful
106    else {
107       ListNode< NODETYPE > *tempPtr = firstPtr;
108
109       if ( firstPtr == lastPtr )
110          firstPtr = lastPtr = 0;
111       else
112          firstPtr = firstPtr -> nextPtr;
113
114       value = tempPtr -> data;  // data being removed
115       delete tempPtr;
116       return true;              // delete successful
117    }
118 }
119
120 // Delete a node from the back of the list
121 template< class NODETYPE >
122 bool List< NODETYPE >::removeFromBack( NODETYPE &value )
123 {
124    if ( isEmpty() )
125       return false;   // delete unsuccessful
126    else {
127       ListNode< NODETYPE > *tempPtr = lastPtr;
128
129       if ( firstPtr == lastPtr )
130          firstPtr = lastPtr = 0;
131       else {
132          ListNode< NODETYPE > *currentPtr = firstPtr;
133
134          while ( currentPtr -> nextPtr != lastPtr )
135             currentPtr = currentPtr -> nextPtr;
136
137          lastPtr = currentPtr;
138          currentPtr -> nextPtr = 0;
139       }
140
141       value = tempPtr -> data;
142       delete tempPtr;
143       return true;   // delete successful
144    }
145 }
146
147 // Is the List empty?
148 template< class NODETYPE >
149 bool List< NODETYPE >::isEmpty() const { return firstPtr == 0; }
150
151 // Return a pointer to a newly allocated node
152 template< class NODETYPE >
153 ListNode< NODETYPE > *List< NODETYPE >::getNewNode( const NODETYPE &value )
154 {
155    ListNode< NODETYPE > *ptr = new ListNode< NODETYPE >( value );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
156    assert( ptr != 0 );
157    return ptr;
158 }
159
160 // Display the contents of the List
161 template< class NODETYPE >
162 void List< NODETYPE >::print() const
163 {
164    if ( isEmpty() ) {
165       cout << "The list is empty\n\n";
166       return;
167    }
168
169    ListNode< NODETYPE > *currentPtr = firstPtr;
170
171    cout << "The list is: ";
172
173    while ( currentPtr != 0 ) {
174       cout << currentPtr -> data << ' ';
175       currentPtr = currentPtr -> nextPtr;
176    }
177
178    cout << "\n\n";
179 }
180
181 #endif
```

```
182 // LISTND.H
183 // ListNode template definition
184 #ifndef LISTND_H
185 #define LISTND_H
186
187 template< class T > class List;  // forward declaration
188
189 template< class NODETYPE >
190 class ListNode {
191    friend class List< NODETYPE >; // make List a friend
192 public:
193    ListNode( const NODETYPE & );  // constructor
194    NODETYPE getData() const;    // return the data in the node
195    void setNextPtr( ListNode *nPtr ) { nextPtr = nPtr; }
196    ListNode *getNextPtr() const { return nextPtr; }
197 private:
198    NODETYPE data;               // data
199    ListNode *nextPtr;           // next node in the list
200 };
201
202 // Constructor
203 template< class NODETYPE >
204 ListNode< NODETYPE >::ListNode( const NODETYPE &info )
205 {
206    data = info;
207    nextPtr = 0;
208 }
209
210 // Return a copy of the data in the node
211 template< class NODETYPE >
212 NODETYPE ListNode< NODETYPE >::getData() const { return data; }
213
214 #endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 15.6 solution
#include <iostream>

using std::cout;

#include "list.h"

template< class T >
void concatenate( List< T > &first, List< T > &second )
{
   List< T > temp( second ); // create a copy of second
   T value;              // variable to store removed item from temp

   while ( !temp.isEmpty() ) {
      temp.removeFromFront( value );  // remove value from temp list
      first.insertAtBack( value );    // insert at end of first list
   }
}

int main()
{
   List< char > list1, list2;
   char c;

   for ( c = 'a'; c <= 'e'; ++c )
      list1.insertAtBack( c );

   list1.print();

   for ( c = 'f'; c <= 'j'; ++c )
      list2.insertAtBack( c );

   list2.print();

   concatenate( list1, list2 );
   cout << "The new list1 after concatenation is:\n";
   list1.print();

   return 0;
}
```

```
The list is: a b c d e

The list is: f g h i j


All nodes destroyed

The new list1 after concatenation is:
The list is: a b c d e f g h i j

Destroying nodes ...
f g h i j
All nodes destroyed

Destroying nodes ...
a b c d e f g h i j
All nodes destroyed
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

15.7 Write a program that merges two ordered list objects of integers into a single ordered list object of integers. Function **merge** should receive references to each of the list objects to be merged, and should return an object containing the merged list.

```
// LIST.H
// Template List class definition
#ifndef LIST_H
#define LIST_H

#include <iostream>

using std::cout;

#include <cassert>
#include "listnd.h"

template< class NODETYPE >
class List {
public:
   List();                              // default constructor
   List( const List< NODETYPE > & );  // copy constructor
   ~List();                             // destructor
   void insertAtFront( const NODETYPE & );
   void insertAtBack( const NODETYPE & );
   bool removeFromFront( NODETYPE & );
   bool removeFromBack( NODETYPE & );
   bool isEmpty() const;
   void print() const;
protected:
   ListNode< NODETYPE > *firstPtr;  // pointer to first node
   ListNode< NODETYPE > *lastPtr;   // pointer to last node

   // Utility function to allocate a new node
   ListNode< NODETYPE > *getNewNode( const NODETYPE & );
};

// Default constructor
template< class NODETYPE >
List< NODETYPE >::List() { firstPtr = lastPtr = 0; }

// Copy constructor
template< class NODETYPE >
List< NODETYPE >::List( const List<NODETYPE> &copy )
{
   firstPtr = lastPtr = 0;  // initialize pointers

   ListNode< NODETYPE > *currentPtr = copy.firstPtr;

   while ( currentPtr != 0 ) {
      insertAtBack( currentPtr -> data );
      currentPtr = currentPtr -> nextPtr;
   }
}

// Destructor
template< class NODETYPE >
List< NODETYPE >::~List()
{
   if ( !isEmpty() ) {    // List is not empty
      cout << "Destroying nodes ...\n";

      ListNode< NODETYPE > *currentPtr = firstPtr, *tempPtr;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
59
60          while ( currentPtr != 0 ) {  // delete remaining nodes
61             tempPtr = currentPtr;
62             cout << tempPtr -> data << ' ';
63             currentPtr = currentPtr -> nextPtr;
64             delete tempPtr;
65          }
66       }
67
68       cout << "\nAll nodes destroyed\n\n";
69    }
70
71    // Insert a node at the front of the list
72    template< class NODETYPE >
73    void List< NODETYPE >::insertAtFront( const NODETYPE &value )
74    {
75       ListNode<NODETYPE> *newPtr = getNewNode( value );
76
77       if ( isEmpty() )  // List is empty
78          firstPtr = lastPtr = newPtr;
79       else {           // List is not empty
80          newPtr -> nextPtr = firstPtr;
81          firstPtr = newPtr;
82       }
83    }
84
85    // Insert a node at the back of the list
86    template< class NODETYPE >
87    void List< NODETYPE >::insertAtBack( const NODETYPE &value )
88    {
89       ListNode< NODETYPE > *newPtr = getNewNode( value );
90
91       if ( isEmpty() )  // List is empty
92          firstPtr = lastPtr = newPtr;
93       else {           // List is not empty
94          lastPtr -> nextPtr = newPtr;
95          lastPtr = newPtr;
96       }
97    }
98
99    // Delete a node from the front of the list
100   template< class NODETYPE >
101   bool List< NODETYPE >::removeFromFront( NODETYPE &value )
102   {
103      if ( isEmpty() )              // List is empty
104         return false;              // delete unsuccessful
105      else {
106         ListNode< NODETYPE > *tempPtr = firstPtr;
107
108         if ( firstPtr == lastPtr )
109            firstPtr = lastPtr = 0;
110         else
111            firstPtr = firstPtr -> nextPtr;
112
113         value = tempPtr -> data;  // data being removed
114         delete tempPtr;
115         return true;              // delete successful
116      }
117   }
118
119   // Delete a node from the back of the list
120   template< class NODETYPE >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
121 bool List< NODETYPE >::removeFromBack( NODETYPE &value )
122 {
123    if ( isEmpty() )
124       return false;   // delete unsuccessful
125    else {
126       ListNode< NODETYPE > *tempPtr = lastPtr;
127
128       if ( firstPtr == lastPtr )
129          firstPtr = lastPtr = 0;
130       else {
131          ListNode< NODETYPE > *currentPtr = firstPtr;
132
133          while ( currentPtr -> nextPtr != lastPtr )
134             currentPtr = currentPtr -> nextPtr;
135
136          lastPtr = currentPtr;
137          currentPtr -> nextPtr = 0;
138       }
139
140       value = tempPtr -> data;
141       delete tempPtr;
142       return true;   // delete successful
143    }
144 }
145
146 // Is the List empty?
147 template< class NODETYPE >
148 bool List< NODETYPE >::isEmpty() const { return firstPtr == 0; }
149
150 // Return a pointer to a newly allocated node
151 template< class NODETYPE >
152 ListNode< NODETYPE > *List< NODETYPE >::getNewNode( const NODETYPE &value )
153 {
154    ListNode< NODETYPE > *ptr = new ListNode< NODETYPE >( value );
155    assert( ptr != 0 );
156    return ptr;
157 }
158
159 // Display the contents of the List
160 template< class NODETYPE >
161 void List< NODETYPE >::print() const
162 {
163    if ( isEmpty() ) {
164       cout << "The list is empty\n\n";
165       return;
166    }
167
168    ListNode< NODETYPE > *currentPtr = firstPtr;
169
170    cout << "The list is: ";
171
172    while ( currentPtr != 0 ) {
173       cout << currentPtr -> data << ' ';
174       currentPtr = currentPtr -> nextPtr;
175    }
176
177    cout << "\n\n";
178 }
179
180 #endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// LISTND.H
// ListNode template definition
#ifndef LISTND_H
#define LISTND_H

template< class T > class List;  // forward declaration

template< class NODETYPE >
class ListNode {
   friend class List< NODETYPE >; // make List a friend
public:
   ListNode( const NODETYPE & );  // constructor
   NODETYPE getData() const;    // return the data in the node
   void setNextPtr( ListNode *nPtr ) { nextPtr = nPtr; }
   ListNode *getNextPtr() const { return nextPtr; }
private:
   NODETYPE data;               // data
   ListNode *nextPtr;           // next node in the list
};

// Constructor
template< class NODETYPE >
ListNode< NODETYPE >::ListNode( const NODETYPE &info )
{
   data = info;
   nextPtr = 0;
}

// Return a copy of the data in the node
template< class NODETYPE >
NODETYPE ListNode< NODETYPE >::getData() const { return data; }

#endif
```

```
// Exercise 15.7 solution
#include <iostream>

using std::cout;

#include "list.h"

template< class T >
List< T > &merge( List< T > &first, List< T > &second )
{
   // If both lists are empty, return an empty result
   if ( first.isEmpty() && second.isEmpty() ) {
      List< T > *ptr = new List< T >;         // dynamically allocated
      return *ptr;
   }

   // If first list is empty, return result containing second list
   if ( first.isEmpty() ) {
      List< T > *ptr = new List< T >( second ); // dynamically allocated
      return *ptr;
   }

   // If second list is empty, return result containing first list
   if ( second.isEmpty() ) {
      List< T > *ptr = new List< T >( first ); // dynamically allocated
      return *ptr;
   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
241
242    List< T > tempFirst( first ),   // create a copy of first
243              tempSecond( second ); // create a copy of second
244    List< T > *ptr = new List< T >; // dynamically allocated result object
245    T value1, value2;
246
247    tempFirst.removeFromFront( value1 );
248    tempSecond.removeFromFront( value2 );
249
250    while ( !tempFirst.isEmpty() && !tempSecond.isEmpty() ) {
251       if ( value1 <= value2 ) {
252          ptr -> insertAtBack( value1 );
253          tempFirst.removeFromFront( value1 );
254       }
255       else {
256          ptr -> insertAtBack( value2 );
257          tempSecond.removeFromFront( value2 );
258       }
259    }
260
261    // Insert the values currently in value1 and value2
262    if ( value1 < value2 ) {
263       ptr -> insertAtBack( value1 );
264       ptr -> insertAtBack( value2 );
265    }
266    else {
267       ptr -> insertAtBack( value2 );
268       ptr -> insertAtBack( value1 );
269    }
270
271    // Complete the insertion of the list that is not empty.
272    // NOTE: Only one of the following 2 while structures will execute
273    // because one of the lists must be empty to exit the preceding while.
274    if ( !tempFirst.isEmpty() )  // Items left in tempFirst? Insert in result.
275       do {
276          tempFirst.removeFromFront( value1 );
277          ptr -> insertAtBack( value2 );
278       } while ( !tempFirst.isEmpty() );
279    else                        // Items left in tempSecond? Insert in result.
280       do {
281          tempSecond.removeFromFront( value2 );
282          ptr -> insertAtBack( value2 );
283       } while ( !tempSecond.isEmpty() );
284
285    return *ptr;
286 }
287
288 int main()
289 {
290    List< int > list1, list2;
291    int i;
292
293    for ( i = 1; i <= 9; i += 2 )
294       list1.insertAtBack( i );
295
296    list1.print();
297
298    for ( i = 2; i <= 10; i += 2 )
299       list2.insertAtBack( i );
300
301    list2.print();
302
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   List< int > &listRef = merge( list1, list2 );

   cout <<  "The merged list is:\n";
   listRef.print();

   delete &listRef;   // delete the dynamically allocated list

   return 0;
}
```

```
The list is: 1 3 5 7 9

The list is: 2 4 6 8 10


All nodes destroyed


All nodes destroyed

The merged list is:
The list is: 1 2 3 4 5 6 7 8 9 10

Destroying nodes ...
1 2 3 4 5 6 7 8 9 10
All nodes destroyed

Destroying nodes ...
2 4 6 8 10
All nodes destroyed

Destroying nodes ...
1 3 5 7 9
All nodes destroyed
```

15.8 Write a program that inserts 25 random integers from 0 to 100 in order in a linked list object. The program should calculate the sum of the elements and the floating-point average of the elements.

```
// LIST
// Template List class definition
// Added copy constructor to member functions (not included in chapter).
#ifndef LIST_H
#define LIST_H

#include <iostream>

using std::cout;

#include <cassert>
#include "Listnd.h"

template< class NODETYPE >
class List {
public:
   List();                            // default constructor
   List( const List< NODETYPE > & );  // copy constructor
   ~List();                           // destructor
   void insertAtFront( const NODETYPE & );
   void insertAtBack( const NODETYPE & );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
22     bool removeFromFront( NODETYPE & );
23     bool removeFromBack( NODETYPE & );
24     bool isEmpty() const;
25     void print() const;
26  protected:
27     ListNode< NODETYPE > *firstPtr;  // pointer to first node
28     ListNode< NODETYPE > *lastPtr;   // pointer to last node
29
30     // Utility function to allocate a new node
31     ListNode< NODETYPE > *getNewNode( const NODETYPE & );
32  };
33
34  // Default constructor
35  template< class NODETYPE >
36  List< NODETYPE >::List() { firstPtr = lastPtr = 0; }
37
38  // Copy constructor
39  template< class NODETYPE >
40  List< NODETYPE >::List( const List<NODETYPE> &copy )
41  {
42     firstPtr = lastPtr = 0;  // initialize pointers
43
44     ListNode< NODETYPE > *currentPtr = copy.firstPtr;
45
46     while ( currentPtr != 0 ) {
47        insertAtBack( currentPtr -> data );
48        currentPtr = currentPtr -> nextPtr;
49     }
50  }
51
52  // Destructor
53  template< class NODETYPE >
54  List< NODETYPE >::~List()
55  {
56     if ( !isEmpty() ) {    // List is not empty
57        cout << "Destroying nodes ...\n";
58
59        ListNode< NODETYPE > *currentPtr = firstPtr, *tempPtr;
60
61        while ( currentPtr != 0 ) {  // delete remaining nodes
62           tempPtr = currentPtr;
63           cout << tempPtr -> data << ' ';
64           currentPtr = currentPtr -> nextPtr;
65           delete tempPtr;
66        }
67     }
68
69     cout << "\nAll nodes destroyed\n\n";
70  }
71
72  // Insert a node at the front of the list
73  template< class NODETYPE >
74  void List< NODETYPE >::insertAtFront( const NODETYPE &value )
75  {
76     ListNode<NODETYPE> *newPtr = getNewNode( value );
77
78     if ( isEmpty() )  // List is empty
79        firstPtr = lastPtr = newPtr;
80     else {           // List is not empty
81        newPtr -> nextPtr = firstPtr;
82        firstPtr = newPtr;
83     }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
84  }
85
86  // Insert a node at the back of the list
87  template< class NODETYPE >
88  void List< NODETYPE >::insertAtBack( const NODETYPE &value )
89  {
90     ListNode< NODETYPE > *newPtr = getNewNode( value );
91
92     if ( isEmpty() )  // List is empty
93        firstPtr = lastPtr = newPtr;
94     else {           // List is not empty
95        lastPtr -> nextPtr = newPtr;
96        lastPtr = newPtr;
97     }
98  }
99
100 // Delete a node from the front of the list
101 template< class NODETYPE >
102 bool List< NODETYPE >::removeFromFront( NODETYPE &value )
103 {
104    if ( isEmpty() )              // List is empty
105       return false;              // delete unsuccessful
106    else {
107       ListNode< NODETYPE > *tempPtr = firstPtr;
108
109       if ( firstPtr == lastPtr )
110          firstPtr = lastPtr = 0;
111       else
112          firstPtr = firstPtr -> nextPtr;
113
114       value = tempPtr -> data;  // data being removed
115       delete tempPtr;
116       return true;              // delete successful
117    }
118 }
119
120 // Delete a node from the back of the list
121 template< class NODETYPE >
122 bool List< NODETYPE >::removeFromBack( NODETYPE &value )
123 {
124    if ( isEmpty() )
125       return false;   // delete unsuccessful
126    else {
127       ListNode< NODETYPE > *tempPtr = lastPtr;
128
129       if ( firstPtr == lastPtr )
130          firstPtr = lastPtr = 0;
131       else {
132          ListNode< NODETYPE > *currentPtr = firstPtr;
133
134          while ( currentPtr -> nextPtr != lastPtr )
135             currentPtr = currentPtr -> nextPtr;
136
137          lastPtr = currentPtr;
138          currentPtr -> nextPtr = 0;
139       }
140
141       value = tempPtr -> data;
142       delete tempPtr;
143       return true;   // delete successful
144    }
145 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
146
147 // Is the List empty?
148 template< class NODETYPE >
149 bool List< NODETYPE >::isEmpty() const { return firstPtr == 0; }
150
151 // Return a pointer to a newly allocated node
152 template< class NODETYPE >
153 ListNode< NODETYPE > *List< NODETYPE >::getNewNode( const NODETYPE &value )
154 {
155    ListNode< NODETYPE > *ptr = new ListNode< NODETYPE >( value );
156    assert( ptr != 0 );
157    return ptr;
158 }
159
160 // Display the contents of the List
161 template< class NODETYPE >
162 void List< NODETYPE >::print() const
163 {
164    if ( isEmpty() ) {
165       cout << "The list is empty\n\n";
166       return;
167    }
168
169    ListNode< NODETYPE > *currentPtr = firstPtr;
170
171    cout << "The list is: ";
172
173    while ( currentPtr != 0 ) {
174       cout << currentPtr -> data << ' ';
175       currentPtr = currentPtr -> nextPtr;
176    }
177
178    cout << "\n\n";
179 }
180
181 #endif
```

```
182 // LIST2
183 // Template List2 class definition
184 // Enhances List by adding insertInOrder
185 #ifndef LIST2_H
186 #define LIST2_H
187
188 #include <cassert>
189 #include "Listnd.h"
190 #include "List.h"
191
192 template< class NODETYPE >
193 class List2 : public List< NODETYPE > {
194 public:
195    void insertInOrder( const NODETYPE & );
196 };
197
198 // Insert a node in order
199 template< class NODETYPE >
200 void List2< NODETYPE >::insertInOrder( const NODETYPE &value )
201 {
202    if ( isEmpty() ) { // List is empty
203       ListNode< NODETYPE > *newPtr = getNewNode( value );
204       firstPtr = lastPtr = newPtr;
205    }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   else {           // List is not empty
      if ( firstPtr -> getData() > value )
         insertAtFront( value );
      else if ( lastPtr -> getData() < value )
         insertAtBack( value );
      else {
         ListNode< NODETYPE > *currentPtr = firstPtr -> getNextPtr(),
                              *previousPtr = firstPtr,
                              *newPtr = getNewNode( value );

         while ( currentPtr != lastPtr && currentPtr -> getData() < value ) {
            previousPtr = currentPtr;
            currentPtr = currentPtr -> getNextPtr();
         }

         previousPtr -> setNextPtr( newPtr );
         newPtr -> setNextPtr( currentPtr );
      }
   }
}

#endif
```

```
// LISTND.H
// ListNode template definition
#ifndef LISTND_H
#define LISTND_H

template< class T > class List;  // forward declaration

template< class NODETYPE >
class ListNode {
   friend class List< NODETYPE >; // make List a friend
public:
   ListNode( const NODETYPE & );  // constructor
   NODETYPE getData() const;    // return the data in the node
   void setNextPtr( ListNode *nPtr ) { nextPtr = nPtr; }
   ListNode *getNextPtr() const { return nextPtr; }
private:
   NODETYPE data;               // data
   ListNode *nextPtr;           // next node in the list
};

// Constructor
template< class NODETYPE >
ListNode< NODETYPE >::ListNode( const NODETYPE &info )
{
   data = info;
   nextPtr = 0;
}

// Return a copy of the data in the node
template< class NODETYPE >
NODETYPE ListNode< NODETYPE >::getData() const { return data; }

#endif
```

```
// Exercise 15.8 solution
#include <iostream>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
263
264 using std::cout;
265
266 #include <cstdlib>
267 #include <ctime>
268 #include "List2.h"
269
270 // Integer specific list sum
271 int sumList( List2< int > &listRef )
272 {
273    List2< int > temp( listRef );
274    int sum = 0, value;
275
276    while ( !temp.isEmpty() ) {
277       temp.removeFromFront( value );
278       sum += value;
279    }
280
281    return sum;
282 }
283
284 // Integer specific list average
285 double aveList( List2< int > &listRef )
286 {
287    List2< int > temp( listRef );
288    int sum = 0, value, count = 0;
289
290    while ( !temp.isEmpty() ) {
291       temp.removeFromFront( value );
292       ++count;
293       sum += value;
294    }
295
296    return static_cast< double >( sum ) / count;
297 }
298
299 int main()
300 {
301    srand( time( 0 ) );  // randomize the random number generator
302
303    List2< int > intList;
304
305    for ( int i = 1; i <= 25; ++i )
306       intList.insertInOrder( rand() % 101 );
307
308    intList.print();
309
310    cout << "The sum of the elements is: " << sumList( intList ) << '\n';
311    cout << "The average of the elements is: " << aveList( intList ) << '\n';
312
313    return 0;
314 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
The list is: 6 11 14 22 23 25 31 34 41 42 43 43 46 47 48 51 54 61 66 72 72 82 89
 94 95


All nodes destroyed

The sum of the elements is: 1212

All nodes destroyed

The average of the elements is: 48.48
Destroying nodes ...
6 11 14 22 23 25 31 34 41 42 43 43 46 47 48 51 54 61 66 72 72 82 89 94 95
All nodes destroyed
```

15.9 Write a program that creates a linked list object of 10 characters and then creates a second list object containing a copy of the first list, but in reverse order.

```
1  // LIST.H
2  // Template List class definition
3  // Added copy constructor to member functions (not included in chapter).
4  #ifndef LIST_H
5  #define LIST_H
6
7  #include <iostream>
8
9  using std::cout;
10
11 #include <cassert>
12 #include "listnd.h"
13
14 template< class NODETYPE >
15 class List {
16 public:
17    List();                              // default constructor
18    List( const List< NODETYPE > & );  // copy constructor
19    ~List();                             // destructor
20    void insertAtFront( const NODETYPE & );
21    void insertAtBack( const NODETYPE & );
22    bool removeFromFront( NODETYPE & );
23    bool removeFromBack( NODETYPE & );
24    bool isEmpty() const;
25    void print() const;
26 protected:
27    ListNode< NODETYPE > *firstPtr;  // pointer to first node
28    ListNode< NODETYPE > *lastPtr;   // pointer to last node
29
30    // Utility function to allocate a new node
31    ListNode< NODETYPE > *getNewNode( const NODETYPE & );
32 };
33
34 // Default constructor
35 template< class NODETYPE >
36 List< NODETYPE >::List() { firstPtr = lastPtr = 0; }
37
38 // Copy constructor
39 template< class NODETYPE >
40 List< NODETYPE >::List( const List<NODETYPE> &copy )
41 {
42    firstPtr = lastPtr = 0;  // initialize pointers
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
43
44       ListNode< NODETYPE > *currentPtr = copy.firstPtr;
45
46       while ( currentPtr != 0 ) {
47          insertAtBack( currentPtr -> data );
48          currentPtr = currentPtr -> nextPtr;
49       }
50    }
51
52    // Destructor
53    template< class NODETYPE >
54    List< NODETYPE >::~List()
55    {
56       if ( !isEmpty() ) {    // List is not empty
57          cout << "Destroying nodes ...\n";
58
59          ListNode< NODETYPE > *currentPtr = firstPtr, *tempPtr;
60
61          while ( currentPtr != 0 ) {  // delete remaining nodes
62             tempPtr = currentPtr;
63             cout << tempPtr -> data << ' ';
64             currentPtr = currentPtr -> nextPtr;
65             delete tempPtr;
66          }
67       }
68
69       cout << "\nAll nodes destroyed\n\n";
70    }
71
72    // Insert a node at the front of the list
73    template< class NODETYPE >
74    void List< NODETYPE >::insertAtFront( const NODETYPE &value )
75    {
76       ListNode<NODETYPE> *newPtr = getNewNode( value );
77
78       if ( isEmpty() )  // List is empty
79          firstPtr = lastPtr = newPtr;
80       else {           // List is not empty
81          newPtr -> nextPtr = firstPtr;
82          firstPtr = newPtr;
83       }
84    }
85
86    // Insert a node at the back of the list
87    template< class NODETYPE >
88    void List< NODETYPE >::insertAtBack( const NODETYPE &value )
89    {
90       ListNode< NODETYPE > *newPtr = getNewNode( value );
91
92       if ( isEmpty() )  // List is empty
93          firstPtr = lastPtr = newPtr;
94       else {           // List is not empty
95          lastPtr -> nextPtr = newPtr;
96          lastPtr = newPtr;
97       }
98    }
99
100   // Delete a node from the front of the list
101   template< class NODETYPE >
102   bool List< NODETYPE >::removeFromFront( NODETYPE &value )
103   {
104      if ( isEmpty() )             // List is empty
105         return false;             // delete unsuccessful
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
106    else {
107       ListNode< NODETYPE > *tempPtr = firstPtr;
108
109       if ( firstPtr == lastPtr )
110          firstPtr = lastPtr = 0;
111       else
112          firstPtr = firstPtr -> nextPtr;
113
114       value = tempPtr -> data;  // data being removed
115       delete tempPtr;
116       return true;              // delete successful
117    }
118 }
119
120 // Delete a node from the back of the list
121 template< class NODETYPE >
122 bool List< NODETYPE >::removeFromBack( NODETYPE &value )
123 {
124    if ( isEmpty() )
125       return false;   // delete unsuccessful
126    else {
127       ListNode< NODETYPE > *tempPtr = lastPtr;
128
129       if ( firstPtr == lastPtr )
130          firstPtr = lastPtr = 0;
131       else {
132          ListNode< NODETYPE > *currentPtr = firstPtr;
133
134          while ( currentPtr -> nextPtr != lastPtr )
135             currentPtr = currentPtr -> nextPtr;
136
137          lastPtr = currentPtr;
138          currentPtr -> nextPtr = 0;
139       }
140
141       value = tempPtr -> data;
142       delete tempPtr;
143       return true;   // delete successful
144    }
145 }
146
147 // Is the List empty?
148 template< class NODETYPE >
149 bool List< NODETYPE >::isEmpty() const { return firstPtr == 0; }
150
151 // Return a pointer to a newly allocated node
152 template< class NODETYPE >
153 ListNode< NODETYPE > *List< NODETYPE >::getNewNode( const NODETYPE &value )
154 {
155    ListNode< NODETYPE > *ptr = new ListNode< NODETYPE >( value );
156    assert( ptr != 0 );
157    return ptr;
158 }
159
160 // Display the contents of the List
161 template< class NODETYPE >
162 void List< NODETYPE >::print() const
163 {
164    if ( isEmpty() ) {
165       cout << "The list is empty\n\n";
166       return;
167    }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
168
169    ListNode< NODETYPE > *currentPtr = firstPtr;
170
171    cout << "The list is: ";
172
173    while ( currentPtr != 0 ) {
174       cout << currentPtr -> data << ' ';
175       currentPtr = currentPtr -> nextPtr;
176    }
177
178    cout << "\n\n";
179 }
180
181 #endif
```

```
182 // LISTND.H
183 // ListNode template definition
184 #ifndef LISTND_H
185 #define LISTND_H
186
187 template< class T > class List;  // forward declaration
188
189 template< class NODETYPE >
190 class ListNode {
191    friend class List< NODETYPE >; // make List a friend
192 public:
193    ListNode( const NODETYPE & );  // constructor
194    NODETYPE getData() const;    // return the data in the node
195    void setNextPtr( ListNode *nPtr ) { nextPtr = nPtr; }
196    ListNode *getNextPtr() const { return nextPtr; }
197 private:
198    NODETYPE data;               // data
199    ListNode *nextPtr;           // next node in the list
200 };
201
202 // Constructor
203 template< class NODETYPE >
204 ListNode< NODETYPE >::ListNode( const NODETYPE &info )
205 {
206    data = info;
207    nextPtr = 0;
208 }
209
210 // Return a copy of the data in the node
211 template< class NODETYPE >
212 NODETYPE ListNode< NODETYPE >::getData() const { return data; }
213
214 #endif
```

```
215 // Exercise 15.9 solution
216 #include <iostream>
217
218 using std::cout;
219
220 #include "list.h"
221
222 // Function template that takes two List objects as arguments
223 // and makes a copy of the second argument reversed in the first argument.
224 template< class T >
225 void reverseList( List< T > &first, List< T > &second )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   List< T > temp( second ); // create a copy of second
   T value;                  // variable to store removed item from temp

   while ( !temp.isEmpty() ) {
      temp.removeFromFront( value );  // remove value from temp list
      first.insertAtFront( value );   // insert at beginning of first list
   }
}

int main()
{
   List< char > list1, list2;

   for ( char c = 'a'; c <= 'g'; ++c )
      list1.insertAtBack( c );

   list1.print();

   reverseList( list2, list1 );
   cout << "After reversing:\n";
   list2.print();

   return 0;
}
```

```
The list is: a b c d e f g


All nodes destroyed

After reversing:
The list is: g f e d c b a

Destroying nodes ...
g f e d c b a
All nodes destroyed

Destroying nodes ...
a b c d e f g
All nodes destroyed
```

15.10 Write a program that inputs a line of text and uses a stack object to print the line reversed.

```
// STACK.H
// Definition of class Stack
// NOTE: This Stack class is a standalone Stack class template.
#ifndef STACK_H
#define STACK_H

#include <iostream>

using std::cout;

#include <cassert>
#include "stacknd.h"

template < class T >
class Stack {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
16 public:
17    Stack();              // default constructor
18    ~Stack();             // destructor
19    void push( T & );     // insert item in stack
20    T pop();              // remove item from stack
21    bool isEmpty() const; // is the stack empty?
22    void print() const;   // output the stack
23    StackNode< T > *getTopPtr() const { return topPtr; }
24 private:
25    StackNode< T > *topPtr;    // pointer to fist StackNode
26 };
27
28 // Member function definitions for class Stack
29 template < class T >
30 Stack< T >::Stack() { topPtr = 0; }
31
32 template < class T >
33 Stack< T >::~Stack()
34 {
35    StackNode< T > *tempPtr, *currentPtr = topPtr;
36
37    while ( currentPtr != 0 ) {
38       tempPtr = currentPtr;
39       currentPtr = currentPtr -> getNextPtr();
40       delete tempPtr;
41    }
42 }
43
44 template < class T >
45 void Stack< T >::push( T &d )
46 {
47    StackNode< T > *newPtr = new StackNode< T >( d, topPtr );
48
49    assert( newPtr != 0 );  // was memory allocated?
50    topPtr = newPtr;
51 }
52
53 template < class T >
54 T Stack< T >::pop()
55 {
56    assert( !isEmpty() );
57
58    StackNode< T > *tempPtr = topPtr;
59
60    topPtr = topPtr -> nextPtr;
61    T poppedValue = tempPtr -> data;
62    delete tempPtr;
63    return poppedValue;
64 }
65
66 template < class T >
67 bool Stack< T >::isEmpty() const { return topPtr == 0; }
68
69 template < class T >
70 void Stack< T >::print() const
71 {
72    StackNode< T > *currentPtr = topPtr;
73
74    if ( isEmpty() )          // Stack is empty
75       cout << "Stack is empty\n";
76    else {                    // Stack is not empty
77       cout << "The stack is:\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
78
79          while ( currentPtr != 0 ) {
80             cout << currentPtr -> data << ' ';
81             currentPtr = currentPtr -> nextPtr;
82          }
83
84          cout << '\n';
85       }
86    }
87
88    #endif
```

```
89    // STACKND.H
90    // Definition of template class StackNode
91    #ifndef STACKND_H
92    #define STACKND_H
93
94    template< class T > class Stack;  // forward declaration
95
96    template < class T >
97    class StackNode {
98       friend class Stack< T >;
99    public:
100      StackNode( const T & = 0, StackNode * = 0 );
101      T getData() const;
102      void setNextPtr( StackNode *nPtr ) { nextPtr = nPtr; }
103      StackNode *getNextPtr() const { return nextPtr; }
104   private:
105      T data;
106      StackNode *nextPtr;
107   };
108
109   // Member function definitions for class StackNode
110   template < class T >
111   StackNode< T >::StackNode( const T &d, StackNode< T > *ptr )
112   {
113      data = d;
114      nextPtr = ptr;
115   }
116
117   template < class T >
118   T StackNode< T >::getData() const { return data; }
119
120   #endif
```

```
121   // Exercise 15.10 solution
122   #include <iostream>
123
124   using std::cout;
125   using std::cin;
126
127   #include "stack.h"
128
129   int main()
130   {
131      Stack< char > charStack;
132      char c;
133
134      cout << "Enter a sentence:\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
135
136    while ( ( c = static_cast< char >( cin.get() ) ) != '\n' )
137       charStack.push( c );
138
139    cout << "\nThe sentence in reverse is:\n";
140
141    while ( !charStack.isEmpty() )
142       cout << charStack.pop();
143
144    cout << '\n';
145
146    return 0;
147 }
```

```
Enter a sentence:
Hello World!

The sentence in reverse is:
!dlroW olleH
```

15.11 Write a program that uses a stack object to determine if a string is a palindrome (i.e., the string is spelled identically backwards and forwards). The program should ignore spaces and punctuation.

```
1  // STACK.H
2  // Definition of class Stack
3  // NOTE: This Stack class is a standalone Stack class template.
4  #ifndef STACK_H
5  #define STACK_H
6
7  #include <iostream>
8
9  using std::cout;
10
11 #include <cassert>
12 #include "stacknd.h"
13
14 template < class T >
15 class Stack {
16 public:
17    Stack();              // default constructor
18    ~Stack();             // destructor
19    void push( T & );     // insert item in stack
20    T pop();              // remove item from stack
21    bool isEmpty() const; // is the stack empty?
22    void print() const;   // output the stack
23    StackNode< T > *getTopPtr() const { return topPtr; }
24 private:
25    StackNode< T > *topPtr;    // pointer to fist StackNode
26 };
27
28 // Member function definitions for class Stack
29 template < class T >
30 Stack< T >::Stack() { topPtr = 0; }
31
32 template < class T >
33 Stack< T >::~Stack()
34 {
35    StackNode< T > *tempPtr, *currentPtr = topPtr;
36
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
37       while ( currentPtr != 0 ) {
38          tempPtr = currentPtr;
39          currentPtr = currentPtr -> getNextPtr();
40          delete tempPtr;
41       }
42    }
43
44    template < class T >
45    void Stack< T >::push( T &d )
46    {
47       StackNode< T > *newPtr = new StackNode< T >( d, topPtr );
48
49       assert( newPtr != 0 );  // was memory allocated?
50       topPtr = newPtr;
51    }
52
53    template < class T >
54    T Stack< T >::pop()
55    {
56       assert( !isEmpty() );
57
58       StackNode< T > *tempPtr = topPtr;
59
60       topPtr = topPtr -> nextPtr;
61       T poppedValue = tempPtr -> data;
62       delete tempPtr;
63       return poppedValue;
64    }
65
66    template < class T >
67    bool Stack< T >::isEmpty() const { return topPtr == 0; }
68
69    template < class T >
70    void Stack< T >::print() const
71    {
72       StackNode< T > *currentPtr = topPtr;
73
74       if ( isEmpty() )          // Stack is empty
75          cout << "Stack is empty\n";
76       else {                    // Stack is not empty
77          cout << "The stack is:\n";
78
79          while ( currentPtr != 0 ) {
80             cout << currentPtr -> data << ' ';
81             currentPtr = currentPtr -> nextPtr;
82          }
83
84          cout << '\n';
85       }
86    }
87
88    #endif
```

```
89    // STACKND.H
90    // Definition of template class StackNode
91    #ifndef STACKND_H
92    #define STACKND_H
93
94    template< class T > class Stack;  // forward declaration
95
96    template < class T >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
97  class StackNode {
98     friend class Stack< T >;
99  public:
100    StackNode( const T & = 0, StackNode * = 0 );
101    T getData() const;
102    void setNextPtr( StackNode *nPtr ) { nextPtr = nPtr; }
103    StackNode *getNextPtr() const { return nextPtr; }
104 private:
105    T data;
106    StackNode *nextPtr;
107 };
108
109 // Member function definitions for class StackNode
110 template < class T >
111 StackNode< T >::StackNode( const T &d, StackNode< T > *ptr )
112 {
113    data = d;
114    nextPtr = ptr;
115 }
116
117 template < class T >
118 T StackNode< T >::getData() const { return data; }
119
120 #endif
```

```
121 // Exercise 15.11 solution
122 #include <iostream>
123
124 using std::cout;
125 using std::cin;
126
127 #include <cctype>
128
129 #include <cstring>
130 #include "stack.h"
131
132 int main()
133 {
134    Stack< char > charStack;
135    char c, string1[ 80 ], string2[ 80 ];
136    int i = 0;
137
138    cout << "Enter a sentence:\n";
139
140    while ( ( c = static_cast< char >( cin.get() ) ) != '\n' )
141       if ( isalpha( c ) ) {
142          string1[ i++ ] = c;
143          charStack.push( c );
144       }
145
146    string1[ i ] = '\0';
147
148    i = 0;
149
150    while ( !charStack.isEmpty() )
151       string2[ i++ ] = charStack.pop();
152
153    string2[ i ] = '\0';
154
155    if ( strcmp( string1, string2 ) == 0 )
156       cout << "\nThe sentence is a palindrome\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   else
      cout << "\nThe sentence is not a palindrome\n";

   return 0;
}
```

```
Enter a sentence:
oat y tao

The sentence is a palindrome
```

15.12 Stacks are used by compilers to help in the process of evaluating expressions and generating machine language code. In this and the next exercise, we investigate how compilers evaluate arithmetic expressions consisting only of constants, operators and parentheses.

Humans generally write expressions like **3 + 4** and **7 / 9** in which the operator (**+** or **/** here) is written between its operands—this is called *infix notation*. Computers "prefer" *postfix notation* in which the operator is written to the right of its two operands. The preceding infix expressions would appear in postfix notation as **3 4 +** and **7 9 /**, respectively.

To evaluate a complex infix expression, a compiler would first convert the expression to postfix notation and then evaluate the postfix version of the expression. Each of these algorithms requires only a single left-to-right pass of the expression. Each algorithm uses a stack object in support of its operation, and in each algorithm the stack is used for a different purpose.

In this exercise, you will write a C++ version of the infix-to-postfix conversion algorithm. In the next exercise, you will write a C++ version of the postfix expression evaluation algorithm. Later in the chapter, you will discover that code you write in this exercise can help you implement a complete working compiler.

Write a program that converts an ordinary infix arithmetic expression (assume a valid expression is entered) with single-digit integers such as

```
(6 + 2) * 5 - 8 / 4
```

to a postfix expression. The postfix version of the preceding infix expression is

```
6 2 + 5 * 8 4 / -
```

The program should read the expression into character array **infix**, and use modified versions of the stack functions implemented in this chapter to help create the postfix expression in character array **postfix**. The algorithm for creating a postfix expression is as follows:

1) Push a left parenthesis **'('** onto the stack.
2) Append a right parenthesis **')'** to the end of **infix**.
3) While the stack is not empty, read **infix** from left to right and do the following:
   If the current character in **infix** is a digit, copy it to the next element of **postfix**.
   If the current character in **infix** is a left parenthesis, push it onto the stack.
   If the current character in **infix** is an operator,
      Pop operators (if there are any) at the top of the stack while they have equal or higher precedence than the current operator, and insert the popped operators in **postfix**.
      Push the current character in **infix** onto the stack.
   If the current character in **infix** is a right parenthesis
      Pop operators from the top of the stack and insert them in **postfix** until a left parenthesis is at the top of the stack.
      Pop (and discard) the left parenthesis from the stack.

The following arithmetic operations are allowed in an expression:

- **+** addition
- **-** subtraction
- ***** multiplication
- **/** division
- **^** exponentiation

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

% modulus

The stack should be maintained with stack nodes that each contain a data member and a pointer to the next stack node.

Some of the functional capabilities you may want to provide are:

a) Function **convertToPostfix** that converts the infix expression to postfix notation.
b) Function **isOperator** that determines if **c** is an operator.
c) Function **precedence** that determines if the precedence of **operator1** is less than, equal to or greater than the precedence of **operator2**. The function returns -1, 0 and 1, respectively**.**
d) Function **push** that pushes a value onto the stack.
e) Function **pop** that pops a value off the stack.
f) Function **stackTop** that returns the top value of the stack without popping the stack.
g) Function **isEmpty** that determines if the stack is empty.
h) Function **printStack** that prints the stack.

```
// STACK.H
// Definition of class Stack
// NOTE: This Stack class is a standalone Stack class template.
#ifndef STACK_H
#define STACK_H

#include <iostream>

using std::cout;

#include <cassert>
#include "stacknd.h"

template < class T >
class Stack {
public:
   Stack();              // default constructor
   ~Stack();             // destructor
   void push( T & );     // insert item in stack
   T pop();              // remove item from stack
   bool isEmpty() const; // is the stack empty?
   void print() const;   // output the stack
   StackNode< T > *getTopPtr() const { return topPtr; }
private:
   StackNode< T > *topPtr;    // pointer to fist StackNode
};

// Member function definitions for class Stack
template < class T >
Stack< T >::Stack() { topPtr = 0; }

template < class T >
Stack< T >::~Stack()
{
   StackNode< T > *tempPtr, *currentPtr = topPtr;

   while ( currentPtr != 0 ) {
      tempPtr = currentPtr;
      currentPtr = currentPtr -> getNextPtr();
      delete tempPtr;
   }
}

template < class T >
void Stack< T >::push( T &d )
{
   StackNode< T > *newPtr = new StackNode< T >( d, topPtr );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
48
49    assert( newPtr != 0 );  // was memory allocated?
50    topPtr = newPtr;
51 }
52
53 template < class T >
54 T Stack< T >::pop()
55 {
56    assert( !isEmpty() );
57
58    StackNode< T > *tempPtr = topPtr;
59
60    topPtr = topPtr -> nextPtr;
61    T poppedValue = tempPtr -> data;
62    delete tempPtr;
63    return poppedValue;
64 }
65
66 template < class T >
67 bool Stack< T >::isEmpty() const { return topPtr == 0; }
68
69 template < class T >
70 void Stack< T >::print() const
71 {
72    StackNode< T > *currentPtr = topPtr;
73
74    if ( isEmpty() )          // Stack is empty
75       cout << "Stack is empty\n";
76    else {                    // Stack is not empty
77       cout << "The stack is:\n";
78
79       while ( currentPtr != 0 ) {
80          cout << currentPtr -> data << ' ';
81          currentPtr = currentPtr -> nextPtr;
82       }
83
84       cout << '\n';
85    }
86 }
87
88 #endif
```

```
89 // STACKND.H
90 // Definition of template class StackNode
91 #ifndef STACKND_H
92 #define STACKND_H
93
94 template< class T > class Stack;  // forward declaration
95
96 template < class T >
97 class StackNode {
98    friend class Stack< T >;
99 public:
100   StackNode( const T & = 0, StackNode * = 0 );
101   T getData() const;
102   void setNextPtr( StackNode *nPtr ) { nextPtr = nPtr; }
103   StackNode *getNextPtr() const { return nextPtr; }
104 private:
105   T data;
106   StackNode *nextPtr;
107 };
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
108
109 // Member function definitions for class StackNode
110 template < class T >
111 StackNode< T >::StackNode( const T &d, StackNode< T > *ptr )
112 {
113    data = d;
114    nextPtr = ptr;
115 }
116
117 template < class T >
118 T StackNode< T >::getData() const { return data; }
119
120 #endif
```

```
121 // STACK2
122 // Definition of class Stack2
123 #ifndef STACK2_H
124 #define STACK2_H
125
126 #include <iostream>
127
128 using std::cout;
129
130 #include <cassert>
131 #include "stacknd.h"
132 #include "stack.h"
133
134 template < class T >
135 class Stack2 : public Stack< T > {
136 public:
137    T stackTop() const;   // check the top value
138 };
139
140 template < class T >
141 T Stack2< T >::stackTop() const
142 { return !isEmpty() ? getTopPtr() -> getData() : static_cast< T >( 0 ); }
143
144 #endif
```

```
145 // Exercise 15.12 Solution
146 // Infix to postfix conversion
147 #include <iostream>
148
149 using std::cout;
150 using std::endl;
151 using std::cin;
152
153 #include <cctype>
154 #include <cstring>
155 #include "stack2.h"
156
157 void convertToPostfix( char * const, char * const );
158 bool isOperator( char );
159 bool precedence( char, char );
160
161 int main()
162 {
163    const int MAXSIZE = 100;
164    char c, inFix[ MAXSIZE ], postFix[ MAXSIZE ];
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   int pos = 0;

   cout << "Enter the infix expression.\n";

   while ( ( c = static_cast< char >( cin.get() ) ) != '\n' )
      if ( c != ' ' )
         inFix[ pos++ ] = c;

   inFix[ pos ] = '\0';

   cout << "The original infix expression is:\n" << inFix << '\n';
   convertToPostfix( inFix, postFix );
   cout << "The expression in postfix notation is:\n" << postFix << endl;

   return 0;
}

void convertToPostfix( char * const infix, char * const postfix )
{
   Stack2< char > charStack;
   int infixCount, postfixCount;
   bool higher;
   char popValue, leftParen = '(';

   // push a left paren onto the stack and add a right paren to infix
   charStack.push( leftParen );
   charStack.print();
   strcat( infix, ")" );

   // convert the infix expression to postfix
   for ( infixCount = 0, postfixCount = 0; charStack.stackTop();
         ++infixCount ) {

      if ( isdigit( infix[ infixCount ] ) )
         postfix[ postfixCount++ ] = infix[ infixCount ];
      else if ( infix[ infixCount ] == '(' ) {
         charStack.push( leftParen );
         charStack.print();
      }
      else if ( isOperator( infix[ infixCount ] ) ) {
         higher = true;   // used to store value of precedence test

         while ( higher ) {
            if ( isOperator( charStack.stackTop() ) )
               if ( precedence( charStack.stackTop(), infix[ infixCount ] ) ) {
                  postfix[ postfixCount++ ] = charStack.pop();
                  charStack.print();
               }
               else
                  higher = false;
            else
               higher = false;
         }

         charStack.push( infix[ infixCount ] );
         charStack.print();
      }
      else if ( infix[ infixCount ] == ')' ) {
         while ( ( popValue = charStack.pop() ) != '(' ) {
            charStack.print();
            postfix[ postfixCount++ ] = popValue;
         }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
227
228            charStack.print();
229         }
230      }
231
232      postfix[ postfixCount ] = '\0';
233   }
234
235   // check if c is an operator
236   bool isOperator( char c )
237   {
238      if ( c == '+' || c == '-' || c == '*' || c == '/' || c == '^' )
239         return true;
240      else
241         return false;
242   }
243
244   bool precedence( char operator1, char operator2 )
245   {
246      if ( operator1 == '^' )
247         return true;
248      else if ( operator2 == '^' )
249         return false;
250      else if ( operator1 == '*' || operator1 == '/' )
251         return true;
252      else if ( operator1 == '+' || operator1 == '-' )
253         if ( operator2 == '*' || operator2 == '/' )
254            return false;
255         else
256            return true;
257
258      return false;
259   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter the infix expression.
(6 + 2) * 5 - 8 / 4
The original infix expression is:
(6+2)*5-8/4
The stack is:
(
The stack is:
( (
The stack is:
+ ( (
The stack is:
( (
The stack is:
(
The stack is:
* (
The stack is:
(
The stack is:
- (
The stack is:
/ - (
The stack is:
- (
The stack is:
(
Stack is empty
The expression in postfix notation is:
62+5*84/-
```

15.13 Write a program that evaluates a postfix expression (assume it is valid) such as

```
6 2 + 5 * 8 4 / -
```

The program should read a postfix expression consisting of digits and operators into a character array. Using modified versions of the stack functions implemented earlier in this chapter, the program should scan the expression and evaluate it. The algorithm is as follows:

1) Append the null character (`'\0'`) to the end of the postfix expression. When the null character is encountered, no further processing is necessary.
2) While `'\0'` has not been encountered, read the expression from left to right.
   If the current character is a digit,
      Push its integer value onto the stack (the integer value of a digit character is its value in the computer's character set minus the value of `'0'` in the computer's character set).
   Otherwise, if the current character is an *operator*,
      Pop the two top elements of the stack into variables `x` and `y`.
      Calculate `y` *operator* `x`.
      Push the result of the calculation onto the stack.
3) When the null character is encountered in the expression, pop the top value of the stack. This is the result of the postfix expression.

Note: In step 2) above, if the operator is `'/'`, the top of the stack is `2` and the next element in the stack is `8`, then pop `2` into `x`, pop `8` into `y`, evaluate `8 / 2` and push the result, `4`, back onto the stack. This note also applies to operator `'-'`. The arithmetic operations allowed in an expression are:

`+` addition
`-` subtraction
`*` multiplication
`/` division
^ exponentiation

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

`%` modulus

The stack should be maintained with stack nodes that contain an **`int`** data member and a pointer to the next stack node. You may want to provide the following functional capabilities:

a) Function **`evaluatePostfixExpression`** that evaluates the postfix expression.
b) Function **`calculate`** that evaluates the expression **`op1 operator op2`**.
c) Function **`push`** that pushes a value onto the stack.
d) Function **`pop`** that pops a value off the stack.
e) Function **`isEmpty`** that determines if the stack is empty.
f) Function **`printStack`** that prints the stack.

```
// STACK.H
// Definition of class Stack
// NOTE: This Stack class is a standalone Stack class template.
#ifndef STACK_H
#define STACK_H

#include <iostream>

using std::cout;

#include <cassert>
#include "stacknd.h"

template < class T >
class Stack {
public:
   Stack();              // default constructor
   ~Stack();             // destructor
   void push( T & );     // insert item in stack
   T pop();              // remove item from stack
   bool isEmpty() const; // is the stack empty?
   void print() const;   // output the stack
   StackNode< T > *getTopPtr() const { return topPtr; }
private:
   StackNode< T > *topPtr;    // pointer to fist StackNode
};

// Member function definitions for class Stack
template < class T >
Stack< T >::Stack() { topPtr = 0; }

template < class T >
Stack< T >::~Stack()
{
   StackNode< T > *tempPtr, *currentPtr = topPtr;

   while ( currentPtr != 0 ) {
      tempPtr = currentPtr;
      currentPtr = currentPtr -> getNextPtr();
      delete tempPtr;
   }
}

template < class T >
void Stack< T >::push( T &d )
{
   StackNode< T > *newPtr = new StackNode< T >( d, topPtr );

   assert( newPtr != 0 );  // was memory allocated?
   topPtr = newPtr;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
52
53 template < class T >
54 T Stack< T >::pop()
55 {
56    assert( !isEmpty() );
57
58    StackNode< T > *tempPtr = topPtr;
59
60    topPtr = topPtr -> nextPtr;
61    T poppedValue = tempPtr -> data;
62    delete tempPtr;
63    return poppedValue;
64 }
65
66 template < class T >
67 bool Stack< T >::isEmpty() const { return topPtr == 0; }
68
69 template < class T >
70 void Stack< T >::print() const
71 {
72    StackNode< T > *currentPtr = topPtr;
73
74    if ( isEmpty() )          // Stack is empty
75       cout << "Stack is empty\n";
76    else {                  // Stack is not empty
77       cout << "The stack is:\n";
78
79       while ( currentPtr != 0 ) {
80          cout << currentPtr -> data << ' ';
81          currentPtr = currentPtr -> nextPtr;
82       }
83
84       cout << '\n';
85    }
86 }
87
88 #endif
```

```
89 // STACKND.H
90 // Definition of template class StackNode
91 #ifndef STACKND_H
92 #define STACKND_H
93
94 template< class T > class Stack;  // forward declaration
95
96 template < class T >
97 class StackNode {
98    friend class Stack< T >;
99 public:
100   StackNode( const T & = 0, StackNode * = 0 );
101   T getData() const;
102   void setNextPtr( StackNode *nPtr ) { nextPtr = nPtr; }
103   StackNode *getNextPtr() const { return nextPtr; }
104 private:
105   T data;
106   StackNode *nextPtr;
107 };
108
109 // Member function definitions for class StackNode
110 template < class T >
111 StackNode< T >::StackNode( const T &d, StackNode< T > *ptr )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
{
   data = d;
   nextPtr = ptr;
}

template < class T >
T StackNode< T >::getData() const { return data; }

#endif
```

```
// Exercise 15.13 Solution
// Using a stack to evaluate an expression in postfix notation
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstring>
using std::string;

#include <cctype>
#include <cmath>
#include "stack.h"

int evaluatePostfixExpression( char * const );
int calculate( int, int, char );

int main()
{
   char expression[ 100 ], c;
   int answer, i = 0;

   cout << "Enter a postfix expression:\n";

   while ( ( c = static_cast< char >( cin.get() ) ) != '\n')
      if ( c != ' ' )
         expression[ i++ ] = c;

   expression[ i ] = '\0';

   answer = evaluatePostfixExpression( expression );
   cout << "The value of the expression is: " << answer << endl;

   return 0;
}

int evaluatePostfixExpression( char * const expr )
{
   int i, popVal1, popVal2, pushVal;
   Stack< int > intStack;
   char c;

   strcat( expr, ")" );

   for ( i = 0; ( c = expr[ i ] ) != ')'; ++i )
      if ( isdigit( expr[ i ] ) ) {
         pushVal = c - '0';
         intStack.push( pushVal );
         intStack.print();
      }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
172         else {
173            popVal2 = intStack.pop();
174            intStack.print();
175            popVal1 = intStack.pop();
176            intStack.print();
177            pushVal = calculate( popVal1, popVal2, expr[ i ] );
178            intStack.push( pushVal );
179            intStack.print();
180         }
181
182      return intStack.pop();
183   }
184
185   int calculate( int op1, int op2, char oper )
186   {
187      switch( oper ) {
188         case '+':
189            return op1 + op2;
190         case '-':
191            return op1 - op2;
192         case '*':
193            return op1 * op2;
194         case '/':
195            return op1 / op2;
196         case '^':   // exponentiation
197            return static_cast< int >( pow( op1, op2 ) );
198      }
199
200      return 0;
201   }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 Enter a postfix expression:
6 2 + 5 * 8 4 / -
The stack is:
6
The stack is:
2 6
The stack is:
6
Stack is empty
The stack is:
8
The stack is:
5 8
The stack is:
8
Stack is empty
The stack is:
40
The stack is:
8 40
The stack is:
4 8 40
The stack is:
8 40
The stack is:
40
The stack is:
2 40
The stack is:
40
Stack is empty
The stack is:
38
The value of the expression is: 38
```

15.14 Modify the postfix evaluator program of Exercise 15.13 so that it can process integer operands larger than 9.

15.15 *(Supermarket simulation)* Write a program that simulates a checkout line at a supermarket. The line is a queue object. Customers (i.e., customer objects) arrive in random integer intervals of 1 to 4 minutes. Also, each customer is served in random integer intervals of 1 to 4 minutes. Obviously, the rates need to be balanced. If the average arrival rate is larger than the average service rate, the queue will grow infinitely. Even with "balanced" rates, randomness can still cause long lines. Run the supermarket simulation for a 12-hour day (720 minutes) using the following algorithm:

1) Choose a random integer between 1 and 4 to determine the minute at which the first customer arrives.
2) At the first customer's arrival time:
   Determine customer's service time (random integer from 1 to 4);
   Begin servicing the customer;
   Schedule arrival time of next customer (random integer 1 to 4 added to the current time).
3) For each minute of the day:
   If the next customer arrives,
      Say so,
      Enqueue the customer;
      Schedule the arrival time of the next customer;
   If service was completed for the last customer;
      Say so
      Dequeue next customer to be serviced
      Determine customer's service completion time
         (random integer from 1 to 4 added to the current time).

Now run your simulation for 720 minutes and answer each of the following:

a) What is the maximum number of customers in the queue at any time?

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

b) What is the longest wait any one customer experiences?
c) What happens if the arrival interval is changed from 1-to-4 minutes to 1-to-3 minutes?

15.16 Modify the program of Fig. 15.16 to allow the binary tree object to contain duplicates.

```
// TREE
// Definition of template class Tree
#ifndef TREE_H
#define TREE_H

#include <iostream>

using std::cout;

#include <cassert>
#include "treenode.h"

template< class NODETYPE >
class Tree {
public:
   Tree();
   void insertNode( const NODETYPE & );
   void preOrderTraversal() const;
   void inOrderTraversal() const;
   void postOrderTraversal() const;
protected:
   TreeNode<NODETYPE> *rootPtr;

   // utility functions
   void insertNodeHelper( TreeNode< NODETYPE > **, const NODETYPE & );
   void preOrderHelper( TreeNode< NODETYPE > * ) const;
   void inOrderHelper( TreeNode< NODETYPE > * ) const;
   void postOrderHelper( TreeNode< NODETYPE > * ) const;
};

template< class NODETYPE >
Tree< NODETYPE >::Tree() { rootPtr = 0; }

template< class NODETYPE >
void Tree< NODETYPE >::insertNode( const NODETYPE &value )
   { insertNodeHelper( &rootPtr, value ); }

// This function receives a pointer to a pointer so the
// pointer can be modified.
// NOTE: THIS FUNCTION WAS MODIFIED TO ALLOW DUPLICATES.
template< class NODETYPE >
void Tree< NODETYPE >::insertNodeHelper( TreeNode< NODETYPE > **ptr,
                                         const NODETYPE &value )
{
   if ( *ptr == 0 ) {                   // tree is empty
      *ptr = new TreeNode< NODETYPE >( value );
      assert( *ptr != 0 );
   }
   else                                 // tree is not empty
      if ( value <= ( *ptr ) -> data )
         insertNodeHelper( &( ( *ptr ) -> leftPtr ), value );
      else
         insertNodeHelper( &( ( *ptr ) -> rightPtr ), value );
}

template< class NODETYPE >
void Tree< NODETYPE >::preOrderTraversal() const { preOrderHelper( rootPtr ); }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
58
59  template< class NODETYPE >
60  void Tree< NODETYPE >::preOrderHelper( TreeNode< NODETYPE > *ptr ) const
61  {
62     if ( ptr != 0 ) {
63        cout << ptr -> data << ' ';
64        preOrderHelper( ptr -> leftPtr );
65        preOrderHelper( ptr -> rightPtr );
66     }
67  }
68
69  template< class NODETYPE >
70  void Tree< NODETYPE >::inOrderTraversal() const { inOrderHelper( rootPtr ); }
71
72  template< class NODETYPE >
73  void Tree< NODETYPE >::inOrderHelper( TreeNode< NODETYPE > *ptr ) const
74  {
75     if ( ptr != 0 ) {
76        inOrderHelper( ptr -> leftPtr );
77        cout << ptr -> data << ' ';
78        inOrderHelper( ptr -> rightPtr );
79     }
80  }
81
82  template< class NODETYPE >
83  void Tree< NODETYPE >::postOrderTraversal() const { postOrderHelper( rootPtr );
}
84
85  template< class NODETYPE >
86  void Tree< NODETYPE >::postOrderHelper( TreeNode< NODETYPE > *ptr ) const
87  {
88     if ( ptr != 0 ) {
89        postOrderHelper( ptr -> leftPtr );
90        postOrderHelper( ptr -> rightPtr );
91        cout << ptr -> data << ' ';
92     }
93  }
94
95  #endif
```

```
96  // TREENODE.H
97  // Definition of class TreeNode
98  #ifndef TREENODE_H
99  #define TREENODE_H
100
101 template< class T > class Tree;    // forward declaration
102
103 template< class NODETYPE >
104 class TreeNode {
105    friend class Tree< NODETYPE >;
106 public:
107    TreeNode( const NODETYPE & );  // constructor
108    NODETYPE getData() const;      // return data
109    TreeNode *getLeftPtr() const { return leftPtr; }
110    TreeNode *getRightPtr() const { return rightPtr; }
111    void setLeftPtr( TreeNode *ptr ) { leftPtr = ptr; }
112    void setRightPtr( TreeNode *ptr ) { rightPtr = ptr; }
113 private:
114    TreeNode *leftPtr;   // pointer to left subtree
115    NODETYPE data;
116    TreeNode *rightPtr;  // pointer to right subtree
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
117 };
118
119 // Constructor
120 template< class NODETYPE >
121 TreeNode< NODETYPE >::TreeNode( const NODETYPE &d )
122 {
123    data = d;
124    leftPtr = rightPtr = 0;
125 }
126
127 //Return a copy of the data value
128 template< class NODETYPE >
129 NODETYPE TreeNode< NODETYPE >::getData() const { return data; }
130
131 #endif
```

```
132 // Exercise 15.16 solution
133 // Driver to test class Tree
134 #include <iostream>
135
136 using std::cout;
137 using std::cin;
138 using std::ios;
139
140 #include <iomanip>
141
142 using std::setprecision;
143 using std::setiosflags;
144
145 #include "tree.h"
146
147 int main()
148 {
149    Tree< int > intTree;
150    int intVal, i;
151
152    cout << "Enter 10 integer values:\n";
153    for ( i = 0; i < 10; ++i ) {
154       cin >> intVal;
155       intTree.insertNode( intVal );
156    }
157
158    cout << "\nPreorder traversal\n";
159    intTree.preOrderTraversal();
160
161    cout << "\nInorder traversal\n";
162    intTree.inOrderTraversal();
163
164    cout << "\nPostorder traversal\n";
165    intTree.postOrderTraversal();
166
167    Tree< double > doubleTree;
168    double doubleVal;
169
170    cout << "\n\n\nEnter 10 double values:\n"
171         << setiosflags( ios::fixed | ios::showpoint )
172         << setprecision( 1 );
173    for ( i = 0; i < 10; ++i ) {
174       cin >> doubleVal;
175       doubleTree.insertNode( doubleVal );
176    }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
177
178    cout << "\nPreorder traversal\n";
179    doubleTree.preOrderTraversal();
180
181    cout << "\nInorder traversal\n";
182    doubleTree.inOrderTraversal();
183
184    cout << "\nPostorder traversal\n";
185    doubleTree.postOrderTraversal();
186
187    return 0;
188 }
```

```
Enter 10 integer values:
22 8 88 22 73 88 83 68 99 92

Preorder traversal
22 8 22 88 73 68 88 83 99 92
Inorder traversal
8 22 22 68 73 83 88 88 92 99
Postorder traversal
22 8 68 83 88 73 92 99 88 22


Enter 10 double values:
9.9 2.2 8.8 2.2 0.0 6.0 3.4 9.8 5.2 6.3

Preorder traversal
9.9 2.2 2.2 0.0 8.8 6.0 3.4 5.2 6.3 9.8
Inorder traversal
0.0 2.2 2.2 3.4 5.2 6.0 6.3 8.8 9.8 9.9
Postorder traversal
0.0 2.2 5.2 3.4 6.3 6.0 9.8 8.8 2.2 9.9
```

15.17 Write a program based on Fig. 15.16 that inputs a line of text, tokenizes the sentence into separate words (you may want to use the **strtok** library function), inserts the words in a binary search tree and prints the inorder, preorder and postorder traversals of the tree. Use an OOP approach.

```
1  // TREE
2  // Definition of template class Tree
3  #ifndef TREE_H
4  #define TREE_H
5
6  #include <iostream>
7
8  using std::cout;
9
10 #include <cassert>
11 #include "treenode.h"
12
13 template< class NODETYPE >
14 class Tree {
15 public:
16    Tree();
17    void insertNode( const NODETYPE & );
18    void preOrderTraversal() const;
19    void inOrderTraversal() const;
20    void postOrderTraversal() const;
21 protected:
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
22    TreeNode<NODETYPE> *rootPtr;
23
24    // utility functions
25    void insertNodeHelper( TreeNode< NODETYPE > **, const NODETYPE & );
26    void preOrderHelper( TreeNode< NODETYPE > * ) const;
27    void inOrderHelper( TreeNode< NODETYPE > * ) const;
28    void postOrderHelper( TreeNode< NODETYPE > * ) const;
29 };
30
31 template< class NODETYPE >
32 Tree< NODETYPE >::Tree() { rootPtr = 0; }
33
34 template< class NODETYPE >
35 void Tree< NODETYPE >::insertNode( const NODETYPE &value )
36    { insertNodeHelper( &rootPtr, value ); }
37
38 // This function receives a pointer to a pointer so the
39 // pointer can be modified.
40 // NOTE: THIS FUNCTION WAS MODIFIED TO ALLOW DUPLICATES.
41 template< class NODETYPE >
42 void Tree< NODETYPE >::insertNodeHelper( TreeNode< NODETYPE > **ptr,
43                                          const NODETYPE &value )
44 {
45    if ( *ptr == 0 ) {                    // tree is empty
46       *ptr = new TreeNode< NODETYPE >( value );
47       assert( *ptr != 0 );
48    }
49    else                                  // tree is not empty
50       if ( value <= ( *ptr ) -> data )
51          insertNodeHelper( &( ( *ptr ) -> leftPtr ), value );
52       else
53          insertNodeHelper( &( ( *ptr ) -> rightPtr ), value );
54 }
55
56 template< class NODETYPE >
57 void Tree< NODETYPE >::preOrderTraversal() const { preOrderHelper( rootPtr ); }
58
59 template< class NODETYPE >
60 void Tree< NODETYPE >::preOrderHelper( TreeNode< NODETYPE > *ptr ) const
61 {
62    if ( ptr != 0 ) {
63       cout << ptr -> data << ' ';
64       preOrderHelper( ptr -> leftPtr );
65       preOrderHelper( ptr -> rightPtr );
66    }
67 }
68
69 template< class NODETYPE >
70 void Tree< NODETYPE >::inOrderTraversal() const { inOrderHelper( rootPtr ); }
71
72 template< class NODETYPE >
73 void Tree< NODETYPE >::inOrderHelper( TreeNode< NODETYPE > *ptr ) const
74 {
75    if ( ptr != 0 ) {
76       inOrderHelper( ptr -> leftPtr );
77       cout << ptr -> data << ' ';
78       inOrderHelper( ptr -> rightPtr );
79    }
80 }
81
82 template< class NODETYPE >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
void Tree< NODETYPE >::postOrderTraversal() const { postOrderHelper( rootPtr );}

template< class NODETYPE >
void Tree< NODETYPE >::postOrderHelper( TreeNode< NODETYPE > *ptr ) const
{
   if ( ptr != 0 ) {
      postOrderHelper( ptr -> leftPtr );
      postOrderHelper( ptr -> rightPtr );
      cout << ptr -> data << ' ';
   }
}

#endif
```

```
// TREENODE.H
// Definition of class TreeNode
#ifndef TREENODE_H
#define TREENODE_H

template< class T > class Tree;    // forward declaration

template< class NODETYPE >
class TreeNode {
   friend class Tree< NODETYPE >;
public:
   TreeNode( const NODETYPE & );  // constructor
   NODETYPE getData() const;      // return data
   TreeNode *getLeftPtr() const { return leftPtr; }
   TreeNode *getRightPtr() const { return rightPtr; }
   void setLeftPtr( TreeNode *ptr ) { leftPtr = ptr; }
   void setRightPtr( TreeNode *ptr ) { rightPtr = ptr; }
private:
   TreeNode *leftPtr;   // pointer to left subtree
   NODETYPE data;
   TreeNode *rightPtr;  // pointer to right subtree
};

// Constructor
template< class NODETYPE >
TreeNode< NODETYPE >::TreeNode( const NODETYPE &d )
{
   data = d;
   leftPtr = rightPtr = 0;
}

//Return a copy of the data value
template< class NODETYPE >
NODETYPE TreeNode< NODETYPE >::getData() const { return data; }

#endif
```

```
// STRING2.H
// Definition of a String class
#ifndef STRING1_H
#define STRING1_H

#include <iostream>

using std::ostream;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
140 using std::istream;
141
142 class String {
143    friend ostream &operator<<( ostream &, const String & );
144    friend istream &operator>>( istream &, String & );
145 public:
146    String( const char * = "" ); // conversion constructor
147    String( const String & );    // copy constructor
148    ~String();                   // destructor
149    const String &operator=( const String & );  // assignment
150    String &operator+=( const String & );     // concatenation
151    bool operator!() const;                   // is String empty?
152    bool operator==( const String & ) const;  // test s1 == s2
153    bool operator!=( const String & ) const;  // test s1 != s2
154    bool operator<( const String & )  const;  // test s1 < s2
155    bool operator>( const String & )  const;  // test s1 > s2
156    bool operator>=( const String & ) const;  // test s1 >= s2
157    bool operator<=( const String & ) const;  // test s1 <= s2
158    char &operator[]( int );        // return char reference
159    String &operator()( int, int ); // return a substring
160    int getLength() const;          // return string length
161 private:
162    char *sPtr;                     // pointer to start of string
163    int length;                     // string length
164 };
165
166 #endif
```

```
167 // STRING2.CPP
168 // Member function definitions for class String.
169 // NOTE: The printing capabilities have been removed
170 // from the constructor and destructor functions.
171 #include <iostream>
172
173 using std::cout;
174 using std::ostream;
175 using std::istream;
176
177 #include <iomanip>
178
179 using std::setw;
180
181 #include <cstring>
182 using std::string;
183
184 #include <cassert>
185 #include "string2.h"
186
187 // Conversion constructor: Convert char * to String
188 String::String( const char *ptr )
189 {
190    length = strlen( ptr );          // compute length
191    sPtr = new char[ length + 1 ];    // allocate storage
192    assert( sPtr != 0 );              // terminate if memory not allocated
193    strcpy( sPtr, ptr );                // copy literal to object
194 }
195
196 // Copy constructor
197 String::String( const String &copy )
198 {
199    length = copy.length;         // copy length
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
200    sPtr = new char[ length + 1 ]; // allocate storage
201    assert( sPtr != 0 );           // ensure memory allocated
202    strcpy( sPtr, copy.sPtr );     // copy string
203 }
204
205 // Destructor
206 String::~String()
207 {
208    delete [] sPtr;              // reclaim string
209 }
210
211 // Overloaded = operator; avoids self assignment
212 const String &String::operator=( const String &right )
213 {
214    if ( &right != this ) {           // avoid self assignment
215       delete [] sPtr;                // prevents memory leak
216       length = right.length;         // new String length
217       sPtr = new char[ length + 1 ]; // allocate memory
218       assert( sPtr != 0 );           // ensure memory allocated
219       strcpy( sPtr, right.sPtr );    // copy string
220    }
221    else
222       cout << "Attempted assignment of a String to itself\n";
223
224    return *this;   // enables concatenated assignments
225 }
226
227 // Concatenate right operand to this object and
228 // store in this object.
229 String &String::operator+=( const String &right )
230 {
231    char *tempPtr = sPtr;          // hold to be able to delete
232    length += right.length;        // new String length
233    sPtr = new char[ length + 1 ]; // create space
234    assert( sPtr != 0 );           // terminate if memory not allocated
235    strcpy( sPtr, tempPtr );       // left part of new String
236    strcat( sPtr, right.sPtr );    // right part of new String
237    delete [] tempPtr;             // reclaim old space
238    return *this;                  // enables concatenated calls
239 }
240
241 // Is this String empty?
242 bool String::operator!() const { return length == 0; }
243
244 // Is this String equal to right String?
245 bool String::operator==( const String &right ) const
246    { return strcmp( sPtr, right.sPtr ) == 0; }
247
248 // Is this String not equal to right String?
249 bool String::operator!=( const String &right ) const
250    { return strcmp( sPtr, right.sPtr ) != 0; }
251
252 // Is this String less than right String?
253 bool String::operator<( const String &right ) const
254    { return strcmp( sPtr, right.sPtr ) < 0; }
255
256 // Is this String greater than right String?
257 bool String::operator>( const String &right ) const
258    { return strcmp( sPtr, right.sPtr ) > 0; }
259
260 // Is this String greater than or equal to right String?
261 bool String::operator>=( const String &right ) const
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
262    { return strcmp( sPtr, right.sPtr ) >= 0; }
263
264 // Is this String less than or equal to right String?
265 bool String::operator<=( const String &right ) const
266    { return strcmp( sPtr, right.sPtr ) <= 0; }
267
268 // Return a reference to a character in a String.
269 char &String::operator[]( int subscript )
270 {
271    // First test for subscript out of range
272    assert( subscript >= 0 && subscript < length );
273
274    return sPtr[ subscript ];  // creates lvalue
275 }
276
277 // Return a substring beginning at index and
278 // of length subLength as a reference to a String object.
279 String &String::operator()( int index, int subLength )
280 {
281    // ensure index is in range and substring length >= 0
282    assert( index >= 0 && index < length && subLength >= 0 );
283
284    String *subPtr = new String;   // empty String
285    assert( subPtr != 0 );     // ensure new String allocated
286
287    // determine length of substring
288    if ( ( subLength == 0 ) || ( index + subLength > length ) )
289       subPtr -> length = length - index + 1;
290    else
291       subPtr -> length = subLength + 1;
292
293    // allocate memory for substring
294    delete subPtr -> sPtr;        // delete character from object
295    subPtr -> sPtr = new char[ subPtr -> length ];
296    assert( subPtr -> sPtr != 0 ); // ensure space allocated
297
298    // copy substring into new String
299    strncpy( subPtr -> sPtr, &sPtr[ index ], subPtr -> length );
300    subPtr -> sPtr[ subPtr -> length ] = '\0'; // terminate new String
301
302    return *subPtr;           // return new String
303 }
304
305 // Return string length
306 int String::getLength() const { return length; }
307
308 // Overloaded output operator
309 ostream &operator<<( ostream &output, const String &s )
310 {
311    output << s.sPtr;
312    return output;   // enables concatenation
313 }
314
315 // Overloaded input operator
316 istream &operator>>( istream &input, String &s )
317 {
318    char temp[ 100 ];   // buffer to store input
319
320    input >> setw( 100 ) >> temp;
321    s = temp;         // use String class assignment operator
322    return input;     // enables concatenation
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}
```

```
// Exercise 15.17 solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <cstring>
using std::string;

#include "tree.h"
#include "string2.h"

int main()
{
   Tree< String > stringTree;
   char sentence[ 80 ], *tokenPtr;

   cout << "Enter a sentence:\n";
   cin.getline( sentence, 80 );

   tokenPtr = strtok( sentence, " " );

   while ( tokenPtr != 0 ) {
      String *newString = new String( tokenPtr );
      stringTree.insertNode( *newString );
      tokenPtr = strtok( 0, " " );
   }

   cout << "\nPreorder traversal\n";
   stringTree.preOrderTraversal();

   cout << "\nInorder traversal\n";
   stringTree.inOrderTraversal();

   cout << "\nPostorder traversal\n";
   stringTree.postOrderTraversal();

   cout << endl;

   return 0;
}
```

```
Enter a sentence:
ANSI/ISO C++ How to Program

Preorder traversal
ANSI/ISO C++ How to Program
Inorder traversal
ANSI/ISO C++ How Program to
Postorder traversal
Program to How C++ ANSI/ISO
```

15.18 In this chapter, we saw that duplicate elimination is straightforward when creating a binary search tree. Describe how you would perform duplicate elimination using only a single-subscripted array. Compare the performance of array-based duplicate elimination with the performance of binary-search-tree-based duplicate elimination.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

15.19 Write a function **depth** that receives a binary tree and determines how many levels it has.

```
// TREE
// Definition of template class Tree
#ifndef TREE_H
#define TREE_H

#include <iostream>

using std::cout;

#include <cassert>
#include "treenode.h"

template< class NODETYPE >
class Tree {
public:
   Tree();
   void insertNode( const NODETYPE & );
   void preOrderTraversal() const;
   void inOrderTraversal() const;
   void postOrderTraversal() const;
protected:
   TreeNode<NODETYPE> *rootPtr;

   // utility functions
   void insertNodeHelper( TreeNode< NODETYPE > **, const NODETYPE & );
   void preOrderHelper( TreeNode< NODETYPE > * ) const;
   void inOrderHelper( TreeNode< NODETYPE > * ) const;
   void postOrderHelper( TreeNode< NODETYPE > * ) const;
};

template< class NODETYPE >
Tree< NODETYPE >::Tree() { rootPtr = 0; }

template< class NODETYPE >
void Tree< NODETYPE >::insertNode( const NODETYPE &value )
   { insertNodeHelper( &rootPtr, value ); }

// This function receives a pointer to a pointer so the
// pointer can be modified.
// NOTE: THIS FUNCTION WAS MODIFIED TO ALLOW DUPLICATES.
template< class NODETYPE >
void Tree< NODETYPE >::insertNodeHelper( TreeNode< NODETYPE > **ptr,
                                         const NODETYPE &value )
{
   if ( *ptr == 0 ) {                    // tree is empty
      *ptr = new TreeNode< NODETYPE >( value );
      assert( *ptr != 0 );
   }
   else                                  // tree is not empty
      if ( value <= ( *ptr ) -> data )
         insertNodeHelper( &( ( *ptr ) -> leftPtr ), value );
      else
         insertNodeHelper( &( ( *ptr ) -> rightPtr ), value );
}

template< class NODETYPE >
void Tree< NODETYPE >::preOrderTraversal() const { preOrderHelper( rootPtr ); }

template< class NODETYPE >
void Tree< NODETYPE >::preOrderHelper( TreeNode< NODETYPE > *ptr ) const
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
61  {
62     if ( ptr != 0 ) {
63        cout << ptr -> data << ' ';
64        preOrderHelper( ptr -> leftPtr );
65        preOrderHelper( ptr -> rightPtr );
66     }
67  }
68
69  template< class NODETYPE >
70  void Tree< NODETYPE >::inOrderTraversal() const { inOrderHelper( rootPtr ); }
71
72  template< class NODETYPE >
73  void Tree< NODETYPE >::inOrderHelper( TreeNode< NODETYPE > *ptr ) const
74  {
75     if ( ptr != 0 ) {
76        inOrderHelper( ptr -> leftPtr );
77        cout << ptr -> data << ' ';
78        inOrderHelper( ptr -> rightPtr );
79     }
80  }
81
82  template< class NODETYPE >
83  void Tree< NODETYPE >::postOrderTraversal() const { postOrderHelper( rootPtr );
}
84
85  template< class NODETYPE >
86  void Tree< NODETYPE >::postOrderHelper( TreeNode< NODETYPE > *ptr ) const
87  {
88     if ( ptr != 0 ) {
89        postOrderHelper( ptr -> leftPtr );
90        postOrderHelper( ptr -> rightPtr );
91        cout << ptr -> data << ' ';
92     }
93  }
94
95  #endif
```

```
96  // TREENODE.H
97  // Definition of class TreeNode
98  #ifndef TREENODE_H
99  #define TREENODE_H
100
101 template< class T > class Tree;    // forward declaration
102
103 template< class NODETYPE >
104 class TreeNode {
105    friend class Tree< NODETYPE >;
106 public:
107    TreeNode( const NODETYPE & );  // constructor
108    NODETYPE getData() const;      // return data
109    TreeNode *getLeftPtr() const { return leftPtr; }
110    TreeNode *getRightPtr() const { return rightPtr; }
111    void setLeftPtr( TreeNode *ptr ) { leftPtr = ptr; }
112    void setRightPtr( TreeNode *ptr ) { rightPtr = ptr; }
113 private:
114    TreeNode *leftPtr;   // pointer to left subtree
115    NODETYPE data;
116    TreeNode *rightPtr;  // pointer to right subtree
117 };
118
119 // Constructor
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
120 template< class NODETYPE >
121 TreeNode< NODETYPE >::TreeNode( const NODETYPE &d )
122 {
123    data = d;
124    leftPtr = rightPtr = 0;
125 }
126
127 //Return a copy of the data value
128 template< class NODETYPE >
129 NODETYPE TreeNode< NODETYPE >::getData() const { return data; }
130
131 #endif
```

```
132 // TREE2.H
133 // Definition of template class Tree
134 // Modified to include getDepth and determineDepth member functions.
135 #ifndef TREE2_H
136 #define TREE2_H
137
138 #include <cassert>
139 #include "treenode.h"
140 #include "tree.h"
141
142 template< class NODETYPE >
143 class Tree2 : public Tree< NODETYPE > {
144 public:
145    int getDepth() const;
146 private:
147    void determineDepth( TreeNode< NODETYPE > *, int *, int * ) const;
148 };
149
150 template< class NODETYPE >
151 int Tree2< NODETYPE >::getDepth() const
152 {
153    int totalDepth = 0, currentDepth = 0;
154
155    determineDepth( rootPtr, &totalDepth, &currentDepth );
156
157    return totalDepth;
158 }
159
160 template< class NODETYPE >
161 void Tree2< NODETYPE >::determineDepth( TreeNode< NODETYPE > *ptr,
162                                         int *totPtr, int *currPtr ) const
163 {
164    if ( ptr != 0 ) {
165       ++( *currPtr );
166
167       if ( *currPtr > *totPtr )
168          *totPtr = *currPtr;
169
170       determineDepth( ptr -> getLeftPtr(), totPtr, currPtr );
171       determineDepth( ptr -> getRightPtr(), totPtr, currPtr );
172       --( *currPtr );
173    }
174 }
175
176 #endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 15.19 solution
#include <iostream>

using std::cout;
using std::cin;

#include "tree2.h"

int main()
{
   Tree2< int > intTree;
   int intVal;

   cout << "Enter 10 integer values:\n";

   for ( int i = 0; i < 10; ++i ) {
      cin >> intVal;
      intTree.insertNode( intVal );
   }

   cout << "\nPreorder traversal\n";
   intTree.preOrderTraversal();

   cout << "\nInorder traversal\n";
   intTree.inOrderTraversal();

   cout << "\nPostorder traversal\n";
   intTree.postOrderTraversal();

   cout << "\n\nThere are " << intTree.getDepth()
        << " levels in this binary tree\n";

   return 0;
}
```

```
Enter 10 integer values:
1 2 3 88 4 6 0 22 21 10

Preorder traversal
1 0 2 3 88 4 6 22 21 10
Inorder traversal
0 1 2 3 4 6 10 21 22 88
Postorder traversal
0 10 21 22 6 4 88 3 2 1

There are 9 levels in this binary tree
```

15.20 (*Recursively print a list backwards*) Write a member function **printListBackwards** that recursively outputs the items in a linked list object in reverse order. Write a test program that creates a sorted list of integers and prints the list in reverse order.

```
// LIST
// Template List class definition
// Added copy constructor to member functions (not included in chapter).
#ifndef LIST_H
#define LIST_H

#include <iostream>

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
using std::cout;

#include <cassert>
#include "Listnd.h"

template< class NODETYPE >
class List {
public:
   List();                              // default constructor
   List( const List< NODETYPE > & );  // copy constructor
   ~List();                             // destructor
   void insertAtFront( const NODETYPE & );
   void insertAtBack( const NODETYPE & );
   bool removeFromFront( NODETYPE & );
   bool removeFromBack( NODETYPE & );
   bool isEmpty() const;
   void print() const;
protected:
   ListNode< NODETYPE > *firstPtr;  // pointer to first node
   ListNode< NODETYPE > *lastPtr;   // pointer to last node

   // Utility function to allocate a new node
   ListNode< NODETYPE > *getNewNode( const NODETYPE & );
};

// Default constructor
template< class NODETYPE >
List< NODETYPE >::List() { firstPtr = lastPtr = 0; }

// Copy constructor
template< class NODETYPE >
List< NODETYPE >::List( const List<NODETYPE> &copy )
{
   firstPtr = lastPtr = 0;  // initialize pointers

   ListNode< NODETYPE > *currentPtr = copy.firstPtr;

   while ( currentPtr != 0 ) {
      insertAtBack( currentPtr -> data );
      currentPtr = currentPtr -> nextPtr;
   }
}

// Destructor
template< class NODETYPE >
List< NODETYPE >::~List()
{
   if ( !isEmpty() ) {    // List is not empty
      cout << "Destroying nodes ...\n";

      ListNode< NODETYPE > *currentPtr = firstPtr, *tempPtr;

      while ( currentPtr != 0 ) {  // delete remaining nodes
         tempPtr = currentPtr;
         cout << tempPtr -> data << ' ';
         currentPtr = currentPtr -> nextPtr;
         delete tempPtr;
      }
   }

   cout << "\nAll nodes destroyed\n\n";
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
71
72 // Insert a node at the front of the list
73 template< class NODETYPE >
74 void List< NODETYPE >::insertAtFront( const NODETYPE &value )
75 {
76    ListNode<NODETYPE> *newPtr = getNewNode( value );
77
78    if ( isEmpty() )  // List is empty
79       firstPtr = lastPtr = newPtr;
80    else {           // List is not empty
81       newPtr -> nextPtr = firstPtr;
82       firstPtr = newPtr;
83    }
84 }
85
86 // Insert a node at the back of the list
87 template< class NODETYPE >
88 void List< NODETYPE >::insertAtBack( const NODETYPE &value )
89 {
90    ListNode< NODETYPE > *newPtr = getNewNode( value );
91
92    if ( isEmpty() )  // List is empty
93       firstPtr = lastPtr = newPtr;
94    else {           // List is not empty
95       lastPtr -> nextPtr = newPtr;
96       lastPtr = newPtr;
97    }
98 }
99
100 // Delete a node from the front of the list
101 template< class NODETYPE >
102 bool List< NODETYPE >::removeFromFront( NODETYPE &value )
103 {
104    if ( isEmpty() )              // List is empty
105       return false;              // delete unsuccessful
106    else {
107       ListNode< NODETYPE > *tempPtr = firstPtr;
108
109       if ( firstPtr == lastPtr )
110          firstPtr = lastPtr = 0;
111       else
112          firstPtr = firstPtr -> nextPtr;
113
114       value = tempPtr -> data;  // data being removed
115       delete tempPtr;
116       return true;              // delete successful
117    }
118 }
119
120 // Delete a node from the back of the list
121 template< class NODETYPE >
122 bool List< NODETYPE >::removeFromBack( NODETYPE &value )
123 {
124    if ( isEmpty() )
125       return false;   // delete unsuccessful
126    else {
127       ListNode< NODETYPE > *tempPtr = lastPtr;
128
129       if ( firstPtr == lastPtr )
130          firstPtr = lastPtr = 0;
131       else {
132          ListNode< NODETYPE > *currentPtr = firstPtr;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
133
134            while ( currentPtr -> nextPtr != lastPtr )
135               currentPtr = currentPtr -> nextPtr;
136
137            lastPtr = currentPtr;
138            currentPtr -> nextPtr = 0;
139         }
140
141         value = tempPtr -> data;
142         delete tempPtr;
143         return true;   // delete successful
144      }
145   }
146
147   // Is the List empty?
148   template< class NODETYPE >
149   bool List< NODETYPE >::isEmpty() const { return firstPtr == 0; }
150
151   // Return a pointer to a newly allocated node
152   template< class NODETYPE >
153   ListNode< NODETYPE > *List< NODETYPE >::getNewNode( const NODETYPE &value )
154   {
155      ListNode< NODETYPE > *ptr = new ListNode< NODETYPE >( value );
156      assert( ptr != 0 );
157      return ptr;
158   }
159
160   // Display the contents of the List
161   template< class NODETYPE >
162   void List< NODETYPE >::print() const
163   {
164      if ( isEmpty() ) {
165         cout << "The list is empty\n\n";
166         return;
167      }
168
169      ListNode< NODETYPE > *currentPtr = firstPtr;
170
171      cout << "The list is: ";
172
173      while ( currentPtr != 0 ) {
174         cout << currentPtr -> data << ' ';
175         currentPtr = currentPtr -> nextPtr;
176      }
177
178      cout << "\n\n";
179   }
180
181   #endif
```

```
182   // LISTND.H
183   // ListNode template definition
184   #ifndef LISTND_H
185   #define LISTND_H
186
187   template< class T > class List;  // forward declaration
188
189   template< class NODETYPE >
190   class ListNode {
191      friend class List< NODETYPE >; // make List a friend
192   public:
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
193    ListNode( const NODETYPE & );  // constructor
194    NODETYPE getData() const;    // return the data in the node
195    void setNextPtr( ListNode *nPtr ) { nextPtr = nPtr; }
196    ListNode *getNextPtr() const { return nextPtr; }
197 private:
198    NODETYPE data;               // data
199    ListNode *nextPtr;           // next node in the list
200 };
201
202 // Constructor
203 template< class NODETYPE >
204 ListNode< NODETYPE >::ListNode( const NODETYPE &info )
205 {
206    data = info;
207    nextPtr = 0;
208 }
209
210 // Return a copy of the data in the node
211 template< class NODETYPE >
212 NODETYPE ListNode< NODETYPE >::getData() const { return data; }
213
214 #endif
```

```
215 // LIST2.H
216 // Template List class definition
217 #ifndef LIST2_H
218 #define LIST2_H
219
220 #include <iostream>
221
222 using std::cout;
223
224 #include <cassert>
225 #include "listnd.h"
226 #include "list.h"
227
228 template< class NODETYPE >
229 class List2 : public List< NODETYPE > {
230 public:
231    void recursivePrintReverse() const;
232 private:
233    void recursivePrintReverseHelper( ListNode< NODETYPE > * ) const;
234 };
235
236 // Print a List backwards recursively.
237 template< class NODETYPE >
238 void List2< NODETYPE >::recursivePrintReverse() const
239 {
240    cout << "The list printed recursively backwards is:\n";
241    recursivePrintReverseHelper( firstPtr );
242    cout << '\n';
243 }
244
245 // Helper for printing a list backwards recursively.
246 template< class NODETYPE >
247 void List2< NODETYPE >::recursivePrintReverseHelper(
248                          ListNode< NODETYPE > *currentPtr ) const
249 {
250    if ( currentPtr == 0 )
251       return;
252
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
253    recursivePrintReverseHelper( currentPtr -> getNextPtr() );
254    cout << currentPtr -> getData() << ' ';
255 }
256
257 #endif
```

```
258 // Exercise 15.20 solution
259
260 #include "list2.h"
261
262 int main()
263 {
264    List2< int > intList;
265
266    for ( int i = 1; i <= 10; ++i )
267       intList.insertAtBack( i );
268
269    intList.print();
270    intList.recursivePrintReverse();
271
272    return 0;
273 }
```

```
The list is: 1 2 3 4 5 6 7 8 9 10

The list printed recursively backwards is:
10 9 8 7 6 5 4 3 2 1
Destroying nodes ...
1 2 3 4 5 6 7 8 9 10
All nodes destroyed
```

15.21 (*Recursively search a list*) Write a member function **searchList** that recursively searches a linked list object for a specified value. The function should return a pointer to the value if it is found; otherwise, null should be returned. Use your function in a test program that creates a list of integers. The program should prompt the user for a value to locate in the list.

```
 1 // LIST
 2 // Template List class definition
 3 // Added copy constructor to member functions (not included in chapter).
 4 #ifndef LIST_H
 5 #define LIST_H
 6
 7 #include <iostream>
 8
 9 using std::cout;
10
11 #include <cassert>
12 #include "Listnd.h"
13
14 template< class NODETYPE >
15 class List {
16 public:
17    List();                              // default constructor
18    List( const List< NODETYPE > & );  // copy constructor
19    ~List();                             // destructor
20    void insertAtFront( const NODETYPE & );
21    void insertAtBack( const NODETYPE & );
22    bool removeFromFront( NODETYPE & );
23    bool removeFromBack( NODETYPE & );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
24       bool isEmpty() const;
25       void print() const;
26    protected:
27       ListNode< NODETYPE > *firstPtr;  // pointer to first node
28       ListNode< NODETYPE > *lastPtr;   // pointer to last node
29
30       // Utility function to allocate a new node
31       ListNode< NODETYPE > *getNewNode( const NODETYPE & );
32    };
33
34    // Default constructor
35    template< class NODETYPE >
36    List< NODETYPE >::List() { firstPtr = lastPtr = 0; }
37
38    // Copy constructor
39    template< class NODETYPE >
40    List< NODETYPE >::List( const List<NODETYPE> &copy )
41    {
42       firstPtr = lastPtr = 0;  // initialize pointers
43
44       ListNode< NODETYPE > *currentPtr = copy.firstPtr;
45
46       while ( currentPtr != 0 ) {
47          insertAtBack( currentPtr -> data );
48          currentPtr = currentPtr -> nextPtr;
49       }
50    }
51
52    // Destructor
53    template< class NODETYPE >
54    List< NODETYPE >::~List()
55    {
56       if ( !isEmpty() ) {    // List is not empty
57          cout << "Destroying nodes ...\n";
58
59          ListNode< NODETYPE > *currentPtr = firstPtr, *tempPtr;
60
61          while ( currentPtr != 0 ) {  // delete remaining nodes
62             tempPtr = currentPtr;
63             cout << tempPtr -> data << ' ';
64             currentPtr = currentPtr -> nextPtr;
65             delete tempPtr;
66          }
67       }
68
69       cout << "\nAll nodes destroyed\n\n";
70    }
71
72    // Insert a node at the front of the list
73    template< class NODETYPE >
74    void List< NODETYPE >::insertAtFront( const NODETYPE &value )
75    {
76       ListNode<NODETYPE> *newPtr = getNewNode( value );
77
78       if ( isEmpty() )  // List is empty
79          firstPtr = lastPtr = newPtr;
80       else {           // List is not empty
81          newPtr -> nextPtr = firstPtr;
82          firstPtr = newPtr;
83       }
84    }
85
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
86  // Insert a node at the back of the list
87  template< class NODETYPE >
88  void List< NODETYPE >::insertAtBack( const NODETYPE &value )
89  {
90     ListNode< NODETYPE > *newPtr = getNewNode( value );
91
92     if ( isEmpty() )  // List is empty
93        firstPtr = lastPtr = newPtr;
94     else {           // List is not empty
95        lastPtr -> nextPtr = newPtr;
96        lastPtr = newPtr;
97     }
98  }
99
100 // Delete a node from the front of the list
101 template< class NODETYPE >
102 bool List< NODETYPE >::removeFromFront( NODETYPE &value )
103 {
104    if ( isEmpty() )              // List is empty
105       return false;              // delete unsuccessful
106    else {
107       ListNode< NODETYPE > *tempPtr = firstPtr;
108
109       if ( firstPtr == lastPtr )
110          firstPtr = lastPtr = 0;
111       else
112          firstPtr = firstPtr -> nextPtr;
113
114       value = tempPtr -> data;  // data being removed
115       delete tempPtr;
116       return true;              // delete successful
117    }
118 }
119
120 // Delete a node from the back of the list
121 template< class NODETYPE >
122 bool List< NODETYPE >::removeFromBack( NODETYPE &value )
123 {
124    if ( isEmpty() )
125       return false;   // delete unsuccessful
126    else {
127       ListNode< NODETYPE > *tempPtr = lastPtr;
128
129       if ( firstPtr == lastPtr )
130          firstPtr = lastPtr = 0;
131       else {
132          ListNode< NODETYPE > *currentPtr = firstPtr;
133
134          while ( currentPtr -> nextPtr != lastPtr )
135             currentPtr = currentPtr -> nextPtr;
136
137          lastPtr = currentPtr;
138          currentPtr -> nextPtr = 0;
139       }
140
141       value = tempPtr -> data;
142       delete tempPtr;
143       return true;   // delete successful
144    }
145 }
146
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
147 // Is the List empty?
148 template< class NODETYPE >
149 bool List< NODETYPE >::isEmpty() const { return firstPtr == 0; }
150
151 // Return a pointer to a newly allocated node
152 template< class NODETYPE >
153 ListNode< NODETYPE > *List< NODETYPE >::getNewNode( const NODETYPE &value )
154 {
155    ListNode< NODETYPE > *ptr = new ListNode< NODETYPE >( value );
156    assert( ptr != 0 );
157    return ptr;
158 }
159
160 // Display the contents of the List
161 template< class NODETYPE >
162 void List< NODETYPE >::print() const
163 {
164    if ( isEmpty() ) {
165       cout << "The list is empty\n\n";
166       return;
167    }
168
169    ListNode< NODETYPE > *currentPtr = firstPtr;
170
171    cout << "The list is: ";
172
173    while ( currentPtr != 0 ) {
174       cout << currentPtr -> data << ' ';
175       currentPtr = currentPtr -> nextPtr;
176    }
177
178    cout << "\n\n";
179 }
180
181 #endif
```

```
182 // LISTND.H
183 // ListNode template definition
184 #ifndef LISTND_H
185 #define LISTND_H
186
187 template< class T > class List;  // forward declaration
188
189 template< class NODETYPE >
190 class ListNode {
191    friend class List< NODETYPE >; // make List a friend
192 public:
193    ListNode( const NODETYPE & );  // constructor
194    NODETYPE getData() const;    // return the data in the node
195    void setNextPtr( ListNode *nPtr ) { nextPtr = nPtr; }
196    ListNode *getNextPtr() const { return nextPtr; }
197 private:
198    NODETYPE data;               // data
199    ListNode *nextPtr;           // next node in the list
200 };
201
202 // Constructor
203 template< class NODETYPE >
204 ListNode< NODETYPE >::ListNode( const NODETYPE &info )
205 {
206    data = info;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   nextPtr = 0;
}

// Return a copy of the data in the node
template< class NODETYPE >
NODETYPE ListNode< NODETYPE >::getData() const { return data; }

#endif
```

```
// LIST2.H
// Template List class definition
#ifndef LIST2_H
#define LIST2_H

#include <iostream>

using std::cout;

#include <cassert>
#include "listnd.h"
#include "list.h"

template< class NODETYPE >
class List2 : public List< NODETYPE > {
public:
   void recursivePrintReverse() const;
   NODETYPE *recursiveSearch( NODETYPE & ) const;
private:
   // Utility functions
   void recursivePrintReverseHelper( ListNode< NODETYPE > * ) const;
   NODETYPE *recursiveSearchHelper( ListNode< NODETYPE > *, NODETYPE & ) const;
};

// Print a List backwards recursively.
template< class NODETYPE >
void List2< NODETYPE >::recursivePrintReverse() const
{
   cout << "The list printed recursively backwards is:\n";
   recursivePrintReverseHelper( firstPtr );
   cout << '\n';
}

// Helper for printing a list backwards recursively.
template< class NODETYPE >
void List2< NODETYPE >::recursivePrintReverseHelper(
                           ListNode< NODETYPE > *currentPtr ) const
{
   if ( currentPtr == 0 )
      return;

   recursivePrintReverseHelper( currentPtr -> nextPtr );
   cout << currentPtr -> data << ' ';
}

// Search a List recursively.
template< class NODETYPE >
NODETYPE *List2< NODETYPE >::recursiveSearch( NODETYPE &val ) const
   { return recursiveSearchHelper( firstPtr, val ); }

// Helper for searching a list recursively.
template< class NODETYPE >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
NODETYPE *List2< NODETYPE >::recursiveSearchHelper(
                   ListNode< NODETYPE > *currentPtr, NODETYPE &value ) const
{
   if ( currentPtr == 0 )
      return 0;

   if ( currentPtr -> getData() == value )
      return currentPtr -> getAddress();

   return recursiveSearchHelper( currentPtr -> getNextPtr(), value );
}

#endif
```

```
// Exercise 15.21 solution
#include <iostream>

using std::cout;
using std::cin;

#include "list2.h"

int main()
{
   List2< int > intList;

   for ( int i = 2; i <= 20; i += 2 )
      intList.insertAtBack( i );

   intList.print();

   int value, *ptr;

   cout << "Enter a value to search for: ";
   cin >> value;
   ptr = intList.recursiveSearch( value );

   if ( ptr != 0 )
      cout << *ptr << " was found\n";
   else
      cout << "Element not found\n";

   return 0;
}
```

```
The list is: 2 4 6 8 10 12 14 16 18 20

Enter a value to search for: 14
14 was found
Destroying nodes ...
2 4 6 8 10 12 14 16 18 20
All nodes destroyed
```

15.22 (*Binary tree delete*) In this exercise, we discuss deleting items from binary search trees. The deletion algorithm is not as straightforward as the insertion algorithm. There are three cases that are encountered when deleting an item—the item is contained in a leaf node (i.e., it has no children), the item is contained in a node that has one child or the item is contained in a node that has two children.

If the item to be deleted is contained in a leaf node, the node is deleted and the pointer in the parent node is set to null.

If the item to be deleted is contained in a node with one child, the pointer in the parent node is set to point to the child node

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

and the node containing the data item is deleted. This causes the child node to take the place of the deleted node in the tree.

The last case is the most difficult. When a node with two children is deleted, another node in the tree must take its place. However, the pointer in the parent node cannot be assigned to point to one of the children of the node to be deleted. In most cases, the resulting binary search tree would not adhere to the following characteristic of binary search trees (with no duplicate values): *The values in any left subtree are less than the value in the parent node, and the values in any right subtree are greater than the value in the parent node*.

Which node is used as a *replacement node* to maintain this characteristic? Either the node containing the largest value in the tree less than the value in the node being deleted, or the node containing the smallest value in the tree greater than the value in the node being deleted. Let us consider the node with the smaller value. In a binary search tree, the largest value less than a parent's value is located in the left subtree of the parent node and is guaranteed to be contained in the rightmost node of the subtree. This node is located by walking down the left subtree to the right until the pointer to the right child of the current node is null. We are now pointing to the replacement node, which is either a leaf node or a node with one child to its left. If the replacement node is a leaf node, the steps to perform the deletion are as follows:

1) Store the pointer to the node to be deleted in a temporary pointer variable (this pointer is used to delete the dynamically allocated memory)
2) Set the pointer in the parent of the node being deleted to point to the replacement node
3) Set the pointer in the parent of the replacement node to null
4) Set the pointer to the right subtree in the replacement node to point to the right subtree of the node to be deleted
5) Delete the node to which the temporary pointer variable points.

The deletion steps for a replacement node with a left child are similar to those for a replacement node with no children, but the algorithm also must move the child in to the replacement node's position in the tree. If the replacement node is a node with a left child, the steps to perform the deletion are as follows:

1) Store the pointer to the node to be deleted in a temporary pointer variable
2) Set the pointer in the parent of the node being deleted to point to the replacement node
3) Set the pointer in the parent of the replacement node to point to the left child of the replacement node
4) Set the pointer to the right subtree in the replacement node to point to the right subtree of the node to be deleted
5) Delete the node to which the temporary pointer variable points.

Write member function **`deleteNode`**, which takes as its arguments a pointer to the root node of the tree object and the value to be deleted. The function should locate in the tree the node containing the value to be deleted and use the algorithms discussed here to delete the node. If the value is not found in the tree, the function should print a message that indicates whether or not the value is deleted. Modify the program of Fig. 15.16 to use this function. After deleting an item, call the **`inOrder`**, **`preOrder`** and **`postOrder`** traversal functions to confirm that the delete operation was performed correctly.

15.23 (*Binary tree search*) Write member function **`binaryTreeSearch`**, which attempts to locate a specified value in a binary search tree object. The function should take as arguments a pointer to the root node of the binary tree and a search key to be located. If the node containing the search key is found, the function should return a pointer to that node; otherwise, the function should return a null pointer.

```
// TREE
// Definition of template class Tree
#ifndef TREE_H
#define TREE_H

#include <iostream>

using std::cout;

#include <cassert>
#include "treenode.h"

template< class NODETYPE >
class Tree {
public:
   Tree();
   void insertNode( const NODETYPE & );
   void preOrderTraversal() const;
   void inOrderTraversal() const;
   void postOrderTraversal() const;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
protected:
   TreeNode<NODETYPE> *rootPtr;

   // utility functions
   void insertNodeHelper( TreeNode< NODETYPE > **, const NODETYPE & );
   void preOrderHelper( TreeNode< NODETYPE > * ) const;
   void inOrderHelper( TreeNode< NODETYPE > * ) const;
   void postOrderHelper( TreeNode< NODETYPE > * ) const;
};

template< class NODETYPE >
Tree< NODETYPE >::Tree() { rootPtr = 0; }

template< class NODETYPE >
void Tree< NODETYPE >::insertNode( const NODETYPE &value )
   { insertNodeHelper( &rootPtr, value ); }

// This function receives a pointer to a pointer so the
// pointer can be modified.
// NOTE: THIS FUNCTION WAS MODIFIED TO ALLOW DUPLICATES.
template< class NODETYPE >
void Tree< NODETYPE >::insertNodeHelper( TreeNode< NODETYPE > **ptr,
                                         const NODETYPE &value )
{
   if ( *ptr == 0 ) {                    // tree is empty
      *ptr = new TreeNode< NODETYPE >( value );
      assert( *ptr != 0 );
   }
   else                                  // tree is not empty
      if ( value <= ( *ptr ) -> data )
         insertNodeHelper( &( ( *ptr ) -> leftPtr ), value );
      else
         insertNodeHelper( &( ( *ptr ) -> rightPtr ), value );
}

template< class NODETYPE >
void Tree< NODETYPE >::preOrderTraversal() const { preOrderHelper( rootPtr ); }

template< class NODETYPE >
void Tree< NODETYPE >::preOrderHelper( TreeNode< NODETYPE > *ptr ) const
{
   if ( ptr != 0 ) {
      cout << ptr -> data << ' ';
      preOrderHelper( ptr -> leftPtr );
      preOrderHelper( ptr -> rightPtr );
   }
}

template< class NODETYPE >
void Tree< NODETYPE >::inOrderTraversal() const { inOrderHelper( rootPtr ); }

template< class NODETYPE >
void Tree< NODETYPE >::inOrderHelper( TreeNode< NODETYPE > *ptr ) const
{
   if ( ptr != 0 ) {
      inOrderHelper( ptr -> leftPtr );
      cout << ptr -> data << ' ';
      inOrderHelper( ptr -> rightPtr );
   }
}

template< class NODETYPE >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
83  void Tree< NODETYPE >::postOrderTraversal() const { postOrderHelper( rootPtr );}
84
85  template< class NODETYPE >
86  void Tree< NODETYPE >::postOrderHelper( TreeNode< NODETYPE > *ptr ) const
87  {
88     if ( ptr != 0 ) {
89        postOrderHelper( ptr -> leftPtr );
90        postOrderHelper( ptr -> rightPtr );
91        cout << ptr -> data << ' ';
92     }
93  }
94
95  #endif
```

```
96  // TREENODE.H
97  // Definition of class TreeNode
98  #ifndef TREENODE_H
99  #define TREENODE_H
100
101 template< class T > class Tree;    // forward declaration
102
103 template< class NODETYPE >
104 class TreeNode {
105    friend class Tree< NODETYPE >;
106 public:
107    TreeNode( const NODETYPE & );  // constructor
108    NODETYPE getData() const;      // return data
109    TreeNode *getLeftPtr() const { return leftPtr; }
110    TreeNode *getRightPtr() const { return rightPtr; }
111    void setLeftPtr( TreeNode *ptr ) { leftPtr = ptr; }
112    void setRightPtr( TreeNode *ptr ) { rightPtr = ptr; }
113 private:
114    TreeNode *leftPtr;   // pointer to left subtree
115    NODETYPE data;
116    TreeNode *rightPtr;  // pointer to right subtree
117 };
118
119 // Constructor
120 template< class NODETYPE >
121 TreeNode< NODETYPE >::TreeNode( const NODETYPE &d )
122 {
123    data = d;
124    leftPtr = rightPtr = 0;
125 }
126
127 //Return a copy of the data value
128 template< class NODETYPE >
129 NODETYPE TreeNode< NODETYPE >::getData() const { return data; }
130
131 #endif
```

```
132 // TREE2.H
133 // Definition of template class Tree
134 #ifndef TREE2_H
135 #define TREE2_H
136
137 #include <iostream>
138
139 using std::cout;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
140
141 #include <cassert>
142 #include "treenode.h"
143 #include "tree.h"
144
145 template< class NODETYPE >
146 class Tree2 : public Tree< NODETYPE > {
147 public:
148    TreeNode< NODETYPE > *binarySearch( int ) const;
149 private:
150    TreeNode< NODETYPE > *binarySearchHelper( TreeNode< NODETYPE > *,
151                                              int ) const;
152 };
153
154 template< class NODETYPE >
155 TreeNode< NODETYPE > *Tree2< NODETYPE >::binarySearch( int val ) const
156    { return binarySearchHelper( rootPtr, val ); }
157
158 template< class NODETYPE >
159 TreeNode< NODETYPE > *Tree2< NODETYPE >::binarySearchHelper(
160                            TreeNode< NODETYPE > *ptr, int value ) const
161 {
162    if ( ptr == 0 )
163       return 0;
164
165    cout << "Comparing " << value << " to " << ptr -> getData();
166
167    if ( value == ptr -> getData() ) {    // match
168       cout << "; search complete\n";
169       return ptr;
170    }
171    else if ( value < ptr -> getData() ) { // search val less than current data
172       cout << "; smaller, walk left\n";
173       return binarySearchHelper( ptr -> getLeftPtr(), value );
174    }
175    else {                         // search val greater than current data
176       cout << "; larger, walk right\n";
177       return binarySearchHelper( ptr -> getRightPtr(), value );
178    }
179 }
180
181 #endif
```

```
182 // Exercise 15.23 solution
183 #include <iostream>
184
185 using std::cout;
186 using std::endl;
187 using std::cin;
188
189 #include <cstdlib>
190 #include <ctime>
191 #include "tree2.h"
192
193 int main()
194 {
195    srand( time( 0 ) );  // randomize the random number generator
196
197    Tree2< int > intTree;
198    int intVal;
199
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
200    cout << "The values being placed in the tree are:\n";
201
202    for ( int i = 1; i <= 15; ++i ) {
203       intVal = rand() % 100;
204       cout << intVal << ' ';
205       intTree.insertNode( intVal );
206    }
207
208    cout << "\n\nEnter a value to search for: ";
209    cin >> intVal;
210
211    TreeNode< int > *ptr = intTree.binarySearch( intVal );
212
213    if ( ptr != 0 )
214       cout << ptr -> getData() << " was found\n";
215    else
216       cout << "Element was not found\n";
217
218    cout << endl;
219
220    return 0;
221 }
```

```
The values being placed in the tree are:
96 96 58 31 44 0 12 61 99 32 29 92 79 55 1

Enter a value to search for: 1
Comparing 1 to 96; smaller, walk left
Comparing 1 to 96; smaller, walk left
Comparing 1 to 58; smaller, walk left
Comparing 1 to 31; smaller, walk left
Comparing 1 to 0; larger, walk right
Comparing 1 to 12; smaller, walk left
Comparing 1 to 1; search complete
1 was found
```

15.24 (*Level-order binary tree traversal*) The program of Fig. 15.16 illustrated three recursive methods of traversing a binary tree—inorder, preorder and postorder traversals. This exercise presents the *level-order traversal* of a binary tree in which the node values are printed level by level, starting at the root node level. The nodes on each level are printed from left to right. The level-order traversal is not a recursive algorithm. It uses a queue object to control the output of the nodes. The algorithm is as follows:

1) Insert the root node in the queue
2) While there are nodes left in the queue,
   Get the next node in the queue
   Print the node's value
   If the pointer to the left child of the node is not null
      Insert the left child node in the queue
   If the pointer to the right child of the node is not null
      Insert the right child node in the queue.

Write member function **`levelOrder`** to perform a level-order traversal of a binary tree object. Modify the program of Fig 15.16 to use this function. (Note: You will also need to modify and incorporate the queue-processing functions of Fig. 15.12 in this program.)

```
1  // TREE
2  // Definition of template class Tree
3  #ifndef TREE_H
4  #define TREE_H
5
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#include <iostream>

using std::cout;

#include <cassert>
#include "treenode.h"

template< class NODETYPE >
class Tree {
public:
   Tree();
   void insertNode( const NODETYPE & );
   void preOrderTraversal() const;
   void inOrderTraversal() const;
   void postOrderTraversal() const;
protected:
   TreeNode<NODETYPE> *rootPtr;

   // utility functions
   void insertNodeHelper( TreeNode< NODETYPE > **, const NODETYPE & );
   void preOrderHelper( TreeNode< NODETYPE > * ) const;
   void inOrderHelper( TreeNode< NODETYPE > * ) const;
   void postOrderHelper( TreeNode< NODETYPE > * ) const;
};

template< class NODETYPE >
Tree< NODETYPE >::Tree() { rootPtr = 0; }

template< class NODETYPE >
void Tree< NODETYPE >::insertNode( const NODETYPE &value )
   { insertNodeHelper( &rootPtr, value ); }

// This function receives a pointer to a pointer so the
// pointer can be modified.
// NOTE: THIS FUNCTION WAS MODIFIED TO ALLOW DUPLICATES.
template< class NODETYPE >
void Tree< NODETYPE >::insertNodeHelper( TreeNode< NODETYPE > **ptr,
                                         const NODETYPE &value )
{
   if ( *ptr == 0 ) {                    // tree is empty
      *ptr = new TreeNode< NODETYPE >( value );
      assert( *ptr != 0 );
   }
   else                                  // tree is not empty
      if ( value <= ( *ptr ) -> data )
         insertNodeHelper( &( ( *ptr ) -> leftPtr ), value );
      else
         insertNodeHelper( &( ( *ptr ) -> rightPtr ), value );
}

template< class NODETYPE >
void Tree< NODETYPE >::preOrderTraversal() const { preOrderHelper( rootPtr ); }

template< class NODETYPE >
void Tree< NODETYPE >::preOrderHelper( TreeNode< NODETYPE > *ptr ) const
{
   if ( ptr != 0 ) {
      cout << ptr -> data << ' ';
      preOrderHelper( ptr -> leftPtr );
      preOrderHelper( ptr -> rightPtr );
   }
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
68
69  template< class NODETYPE >
70  void Tree< NODETYPE >::inOrderTraversal() const { inOrderHelper( rootPtr ); }
71
72  template< class NODETYPE >
73  void Tree< NODETYPE >::inOrderHelper( TreeNode< NODETYPE > *ptr ) const
74  {
75     if ( ptr != 0 ) {
76        inOrderHelper( ptr -> leftPtr );
77        cout << ptr -> data << ' ';
78        inOrderHelper( ptr -> rightPtr );
79     }
80  }
81
82  template< class NODETYPE >
83  void Tree< NODETYPE >::postOrderTraversal() const { postOrderHelper( rootPtr );}
84
85  template< class NODETYPE >
86  void Tree< NODETYPE >::postOrderHelper( TreeNode< NODETYPE > *ptr ) const
87  {
88     if ( ptr != 0 ) {
89        postOrderHelper( ptr -> leftPtr );
90        postOrderHelper( ptr -> rightPtr );
91        cout << ptr -> data << ' ';
92     }
93  }
94
95  #endif
```

```
96  // TREENODE.H
97  // Definition of class TreeNode
98  #ifndef TREENODE_H
99  #define TREENODE_H
100
101 template< class T > class Tree;    // forward declaration
102
103 template< class NODETYPE >
104 class TreeNode {
105    friend class Tree< NODETYPE >;
106 public:
107    TreeNode( const NODETYPE & );  // constructor
108    NODETYPE getData() const;      // return data
109    TreeNode *getLeftPtr() const { return leftPtr; }
110    TreeNode *getRightPtr() const { return rightPtr; }
111    void setLeftPtr( TreeNode *ptr ) { leftPtr = ptr; }
112    void setRightPtr( TreeNode *ptr ) { rightPtr = ptr; }
113 private:
114    TreeNode *leftPtr;   // pointer to left subtree
115    NODETYPE data;
116    TreeNode *rightPtr;  // pointer to right subtree
117 };
118
119 // Constructor
120 template< class NODETYPE >
121 TreeNode< NODETYPE >::TreeNode( const NODETYPE &d )
122 {
123    data = d;
124    leftPtr = rightPtr = 0;
125 }
126
127 //Return a copy of the data value
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
template< class NODETYPE >
NODETYPE TreeNode< NODETYPE >::getData() const { return data; }

#endif
```

```
// TREE2.H
// Definition of template class Tree
#ifndef TREE2_H
#define TREE2_H

#include <iostream>

using std::cout;

#include <cassert>
#include "treenode.h"
#include "queue.h"
#include "tree.h"

template< class NODETYPE >
class Tree2 : public Tree< NODETYPE > {
public:
   void levelOrderTraversal();
};

template< class NODETYPE >
void Tree2< NODETYPE >::levelOrderTraversal()
{
   Queue< TreeNode< NODETYPE > * > queue;
   TreeNode< NODETYPE > *nodePtr;

   if ( rootPtr != 0 )
      queue.enqueue( rootPtr );

   while ( !queue.isEmpty() ) {
      nodePtr = queue.dequeue();
      cout << nodePtr -> getData() << ' ';

      if ( nodePtr -> getLeftPtr() != 0 )
         queue.enqueue( nodePtr -> getLeftPtr() );

      if ( nodePtr -> getRightPtr() != 0 )
         queue.enqueue( nodePtr -> getRightPtr() );
   }
}

#endif
```

```
// QUEUE.H
// Definition of class Queue
#ifndef QUEUE_H
#define QUEUE_H

#include <iostream>

using std::cout;

#include <new>
#include <cstdlib>
#include "queuend.h"
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
186
187 template < class T >
188 class Queue {
189 public:
190    Queue();              // default constructor
191    ~Queue();             // destructor
192    void enqueue( T );    // insert item in queue
193    T dequeue();          // remove item from queue
194    bool isEmpty() const; // is the queue empty?
195    void print() const;   // output the queue
196 private:
197    QueueNode< T > *headPtr;  // pointer to first QueueNode
198    QueueNode< T > *tailPtr;  // pointer to last QueueNode
199 };
200
201 // Member function definitions for class Queue
202 template < class T >
203 Queue< T >::Queue() { headPtr = tailPtr = 0; }
204
205 template < class T >
206 Queue< T >::~Queue()
207 {
208    QueueNode< T > *tempPtr, *currentPtr = headPtr;
209
210    while ( currentPtr != 0 ) {
211       tempPtr = currentPtr;
212       currentPtr = currentPtr -> nextPtr;
213       delete tempPtr;
214    }
215 }
216
217 template < class T >
218 void Queue< T >::enqueue( T d )
219 {
220    QueueNode< T > *newPtr = new QueueNode< T >( d );
221    assert( newPtr != 0 );
222
223    if ( isEmpty() )
224       headPtr = tailPtr = newPtr;
225    else {
226       tailPtr -> nextPtr = newPtr;
227       tailPtr = newPtr;
228    }
229 }
230
231 template < class T >
232 T Queue< T >::dequeue()
233 {
234    assert( !isEmpty() );
235
236    QueueNode< T > *tempPtr = headPtr;
237
238    headPtr = headPtr -> nextPtr;
239    T value = tempPtr -> data;
240    delete tempPtr;
241
242    if ( headPtr == 0 )
243       tailPtr = 0;
244
245    return value;
246 }
247
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
template < class T >
bool Queue< T >::isEmpty() const { return headPtr == 0; }

template < class T >
void Queue< T >::print() const
{
   QueueNode< T > *currentPtr = headPtr;

   if ( isEmpty() )          // Queue is empty
      cout << "Queue is empty\n";
   else {                    // Queue is not empty
      cout << "The queue is:\n";

      while ( currentPtr != 0 ) {
         cout << currentPtr -> data << ' ';
         currentPtr = currentPtr -> nextPtr;
      }

      cout << endl;
   }
}

#endif
```

```
// QUEUEND.H
// Definition of template class QueueNode
#ifndef QUEUEND_H
#define QUEUEND_H

template< class T > class Queue;  // forward declaration

template < class T >
class QueueNode {
   friend class Queue< T >;
public:
   QueueNode( const T & = 0 );
   T getData() const;
private:
   T data;
   QueueNode *nextPtr;
};

// Member function definitions for class QueueNode
template < class T >
QueueNode< T >::QueueNode( const T &d )
{
   data = d;
   nextPtr = 0;
}

template < class T >
T QueueNode< T >::getData() const { return data; }

#endif
```

```
// Exercise 15.24 solution
#include <iostream>
using std::cout;
using std::endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
305
306 #include <cstdlib>
307 #include <ctime>
308 #include "tree2.h"
309
310 int main()
311 {
312    srand( time( 0 ) );  // randomize the random number generator
313
314    Tree2< int > intTree;
315    int intVal;
316
317    cout << "The values being placed in the tree are:\n";
318
319    for ( int i = 1; i <= 15; ++i ) {
320       intVal = rand() % 100;
321       cout << intVal << ' ';
322       intTree.insertNode( intVal );
323    }
324
325    cout << "\n\nThe level order traversal is:\n";
326    intTree.levelOrderTraversal();
327
328    cout << endl;
329
330    return 0;
331 }
```

```
The values being placed in the tree are:
13 21 85 48 83 42 93 38 29 11 21 4 6 69 81

The level order traversal is:
13 11 21 4 21 85 6 48 93 42 83 38 69 29 81
```

15.25 (*Printing trees*) Write a recursive member function **outputTree** to display a binary tree object on the screen. The function should output the tree row by row, with the top of the tree at the left of the screen and the bottom of the tree toward the right of the screen. Each row is output vertically. For example, the binary tree illustrated in Fig. 15.19 is output as follows:

```
              99
         97
              92
    83
              72
         71
              69
49
              44
         40
              32
    28
              19
         18
              11
```

Note that the rightmost leaf node appears at the top of the output in the rightmost column and the root node appears at the left of the output. Each column of output starts five spaces to the right of the previous column. Function **outputTree** should receive an argument **totalSpaces** representing the number of spaces preceding the value to be output (this variable should start at zero so the

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

root node is output at the left of the screen). The function uses a modified inorder traversal to output the tree—it starts at the rightmost node in the tree and works back to the left. The algorithm is as follows:

While the pointer to the current node is not null
  Recursively call **outputTree** with the right subtree of the current node and
    totalSpaces + 5
  Use a **for** structure to count from 1 to **totalSpaces** and output spaces
  Output the value in the current node
  Set the pointer to the current node to point to the left subtree of the current node
  Increment **totalSpaces** by 5.

```
// TREE
// Definition of template class Tree
#ifndef TREE_H
#define TREE_H

#include <iostream>

using std::cout;

#include <cassert>
#include "treenode.h"

template< class NODETYPE >
class Tree {
public:
   Tree();
   void insertNode( const NODETYPE & );
   void preOrderTraversal() const;
   void inOrderTraversal() const;
   void postOrderTraversal() const;
protected:
   TreeNode<NODETYPE> *rootPtr;

   // utility functions
   void insertNodeHelper( TreeNode< NODETYPE > **, const NODETYPE & );
   void preOrderHelper( TreeNode< NODETYPE > * ) const;
   void inOrderHelper( TreeNode< NODETYPE > * ) const;
   void postOrderHelper( TreeNode< NODETYPE > * ) const;
};

template< class NODETYPE >
Tree< NODETYPE >::Tree() { rootPtr = 0; }

template< class NODETYPE >
void Tree< NODETYPE >::insertNode( const NODETYPE &value )
   { insertNodeHelper( &rootPtr, value ); }

// This function receives a pointer to a pointer so the
// pointer can be modified.
// NOTE: THIS FUNCTION WAS MODIFIED TO ALLOW DUPLICATES.
template< class NODETYPE >
void Tree< NODETYPE >::insertNodeHelper( TreeNode< NODETYPE > **ptr,
                                         const NODETYPE &value )
{
   if ( *ptr == 0 ) {                    // tree is empty
      *ptr = new TreeNode< NODETYPE >( value );
      assert( *ptr != 0 );
   }
   else                                  // tree is not empty
      if ( value <= ( *ptr ) -> data )
         insertNodeHelper( &( ( *ptr ) -> leftPtr ), value );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
52          else
53             insertNodeHelper( &( ( *ptr ) -> rightPtr ), value );
54    }
55
56    template< class NODETYPE >
57    void Tree< NODETYPE >::preOrderTraversal() const { preOrderHelper( rootPtr ); }
58
59    template< class NODETYPE >
60    void Tree< NODETYPE >::preOrderHelper( TreeNode< NODETYPE > *ptr ) const
61    {
62       if ( ptr != 0 ) {
63          cout << ptr -> data << ' ';
64          preOrderHelper( ptr -> leftPtr );
65          preOrderHelper( ptr -> rightPtr );
66       }
67    }
68
69    template< class NODETYPE >
70    void Tree< NODETYPE >::inOrderTraversal() const { inOrderHelper( rootPtr ); }
71
72    template< class NODETYPE >
73    void Tree< NODETYPE >::inOrderHelper( TreeNode< NODETYPE > *ptr ) const
74    {
75       if ( ptr != 0 ) {
76          inOrderHelper( ptr -> leftPtr );
77          cout << ptr -> data << ' ';
78          inOrderHelper( ptr -> rightPtr );
79       }
80    }
81
82    template< class NODETYPE >
83    void Tree< NODETYPE >::postOrderTraversal() const { postOrderHelper( rootPtr );}
84
85    template< class NODETYPE >
86    void Tree< NODETYPE >::postOrderHelper( TreeNode< NODETYPE > *ptr ) const
87    {
88       if ( ptr != 0 ) {
89          postOrderHelper( ptr -> leftPtr );
90          postOrderHelper( ptr -> rightPtr );
91          cout << ptr -> data << ' ';
92       }
93    }
94
95    #endif
```

```
96    // TREENODE.H
97    // Definition of class TreeNode
98    #ifndef TREENODE_H
99    #define TREENODE_H
100
101   template< class T > class Tree;    // forward declaration
102
103   template< class NODETYPE >
104   class TreeNode {
105      friend class Tree< NODETYPE >;
106   public:
107      TreeNode( const NODETYPE & );  // constructor
108      NODETYPE getData() const;      // return data
109      TreeNode *getLeftPtr() const { return leftPtr; }
110      TreeNode *getRightPtr() const { return rightPtr; }
111      void setLeftPtr( TreeNode *ptr ) { leftPtr = ptr; }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   void setRightPtr( TreeNode *ptr ) { rightPtr = ptr; }
private:
   TreeNode *leftPtr;   // pointer to left subtree
   NODETYPE data;
   TreeNode *rightPtr;  // pointer to right subtree
};

// Constructor
template< class NODETYPE >
TreeNode< NODETYPE >::TreeNode( const NODETYPE &d )
{
   data = d;
   leftPtr = rightPtr = 0;
}

//Return a copy of the data value
template< class NODETYPE >
NODETYPE TreeNode< NODETYPE >::getData() const { return data; }

#endif
```

```
// TREE2
// Definition of template class Tree
#ifndef TREE2_H
#define TREE2_H

#include <iostream>

using std::cout;

#include <cassert>
#include "treenode.h"
#include "tree.h"

template< class NODETYPE >
class Tree2 : public Tree< NODETYPE > {
public:
   void outputTree() const;
private:
   void outputTreeHelper( TreeNode< NODETYPE > *, int ) const;
};

template< class NODETYPE >
void Tree2< NODETYPE >::outputTree() const { outputTreeHelper( rootPtr, 0 ); }

template< class NODETYPE >
void Tree2< NODETYPE >::outputTreeHelper( TreeNode< NODETYPE > *ptr,
                                          int totalSpaces ) const
{
   if ( ptr != 0 ) {
      outputTreeHelper( ptr -> getRightPtr(), totalSpaces + 5 );

      for ( int i = 1; i <= totalSpaces; ++i )
         cout << ' ';

      cout << ptr -> getData() << '\n';
      outputTreeHelper( ptr -> getLeftPtr(), totalSpaces + 5 );
   }
}

#endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 15.25 solution
#include <iostream>

using std::cout;

#include <cstdlib>
#include <ctime>
#include "tree2.h"

int main()
{
   srand( time( 0 ) );  // randomize the random number generator

   Tree2< int > intTree;
   int intVal;

   cout << "The values being placed in the tree are:\n";

   for ( int i = 1; i <= 15; ++i ) {
      intVal = rand() % 100;
      cout << intVal << ' ';
      intTree.insertNode( intVal );
   }

   cout << "\n\nThe tree is:\n";
   intTree.outputTree();

   return 0;
}
```

```
The values being placed in the tree are:
12 14 56 18 12 97 12 82 96 27 99 90 22 87 15

The tree is:
                    99
               97
                         96
                              90
                                   87
                    82
          56
                    27
                         22
               18
                    15
     14
12
     12
          12
```

SPECIAL SECTION—BUILDING YOUR OWN COMPILER

In Exercises 5.18 and 5.19, we introduced Simpletron Machine Language (SML) and you implemented a Simpletron computer simulator to execute programs written in SML. In this section, we build a compiler that converts programs written in a high-level programming language to SML. This section "ties" together the entire programming process. You will write programs in this new high-level language, compile these programs on the compiler you build and run the programs on the simulator you built in Exercise 7.19. You should make every effort to implement your compiler in an object-oriented manner.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

15.26 (*The Simple Language*) Before we begin building the compiler, we discuss a simple, yet powerful, high-level language similar to early versions of the popular language BASIC. We call the language *Simple*. Every Simple *statement* consists of a *line number* and a Simple *instruction*. Line numbers must appear in ascending order. Each instruction begins with one of the following Simple *commands*: **rem**, **input**, **let**, **print**, **goto**, **if/goto** and **end** (see Fig. 15.20). All commands except **end** can be used repeatedly. Simple evaluates only integer expressions using the **+**, **-**, ***** and **/** operators. These operators have the same precedence as in C. Parentheses can be used to change the order of evaluation of an expression.

Our Simple compiler recognizes only lowercase letters. All characters in a Simple file should be lowercase (uppercase letters result in a syntax error unless they appear in a **rem** statement, in which case they are ignored). A *variable name* is a single letter. Simple does not allow descriptive variable names, so variables should be explained in remarks to indicate their use in a program. Simple uses only integer variables. Simple does not have variable declarations—merely mentioning a variable name in a program causes the variable to be declared and initialized to zero automatically. The syntax of Simple does not allow string manipulation (reading a string, writing a string, comparing strings, etc.). If a string is encountered in a Simple program (after a command other than **rem**), the compiler generates a syntax error. The first version of our compiler will assume that Simple programs are entered correctly. Exercise 15.29 asks the student to modify the compiler to perform syntax error checking.

Command	Example statement	Description
rem	**50 rem this is a remark**	Text following **rem** is for documentation purposes and is ignored by the compiler.
input	**30 input x**	Display a question mark to prompt the user to enter an integer. Read that integer from the keyboard and store the integer in **x**.
let	**80 let u = 4 * (j - 56)**	Assign **u** the value of **4 * (j - 56)**. Note that an arbitrarily complex expression can appear to the right of the equals sign.
print	**10 print w**	Display the value of **w**.
goto	**70 goto 45**	Transfer program control to line **45**.
if/goto	**35 if i == z goto 80**	Compare **i** and **z** for equality and transfer control to line **80** if the condition is true; otherwise, continue execution with the next statement.
end	**99 end**	Terminate program execution.

Fig. 15.20 Simple commands.

Simple uses the conditional **if/goto** statement and the unconditional **goto** statement to alter the flow of control during program execution. If the condition in the **if/goto** statement is true, control is transferred to a specific line of the program. The following relational and equality operators are valid in an **if/goto** statement: **<**, **>**, **<=**, **>=**, **==** and **!=**. The precedence of these operators is the same as in C++.

Let us now consider several programs that demonstrate Simple's features. The first program (Fig. 15.21) reads two integers from the keyboard, stores the values in variables **a** and **b** and computes and prints their sum (stored in variable **c**).

The program of Fig. 15.22 determines and prints the larger of two integers. The integers are input from the keyboard and stored in **s** and **t**. The **if/goto** statement tests the condition **s >= t**. If the condition is true, control is transferred to line **90** and **s** is output; otherwise, **t** is output and control is transferred to the **end** statement in line **99** where the program terminates.

Simple does not provide a repetition structure (such as C++'s **for**, **while** or **do/while**). However, Simple can simulate each of C++'s repetition structures using the **if/goto** and **goto** statements. Figure 15.23 uses a sentinel-controlled loop to calculate the squares of several integers. Each integer is input from the keyboard and stored in variable **j**. If the value entered is the sentinel
-9999, control is transferred to line **99**, where the program terminates. Otherwise, **k** is assigned the square of **j**, **k** is output to the screen and control is passed to line **20**, where the next integer is input.

```
1  10 rem   determine and print the sum of two integers
2  15 rem
```

Fig. 15.21 Simple program that determines the sum of two integers (part 1 of 2).

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 3   20 rem   input the two integers
 4   30 input a
 5   40 input b
 6   45 rem
 7   50 rem   add integers and store result in c
 8   60 let c = a + b
 9   65 rem
10   70 rem   print the result
11   80 print c
12   90 rem   terminate program execution
13   99 end
```

Fig. 15.21 Simple program that determines the sum of two integers (part 2 of 2).

```
 1   10 rem   determine the larger of two integers
 2   20 input s
 3   30 input t
 4   32 rem
 5   35 rem   test if s >= t
 6   40 if s >= t goto 90
 7   45 rem
 8   50 rem   t is greater than s, so print t
 9   60 print t
10   70 goto 99
11   75 rem
12   80 rem   s is greater than or equal to t, so print s
13   90 print s
14   99 end
```

Fig. 15.22 Simple program that finds the larger of two integers.

```
 1   10 rem   calculate the squares of several integers
 2   20 input j
 3   23 rem
 4   25 rem   test for sentinel value
 5   30 if j == -9999 goto 99
 6   33 rem
 7   35 rem   calculate square of j and assign result to k
 8   40 let k = j * j
 9   50 print k
10   53 rem
11   55 rem   loop to get next j
12   60 goto 20
13   99 end
```

Fig. 15.23 Calculate the squares of several integers.

Using the sample programs of Fig. 15.21, Fig. 15.22 and Fig. 15.23 as your guide, write a Simple program to accomplish each of the following:

a) Input three integers, determine their average and print the result.
b) Use a sentinel-controlled loop to input 10 integers and compute and print their sum.
c) Use a counter-controlled loop to input 7 integers, some positive and some negative, and compute and print their average.
d) Input a series of integers and determine and print the largest. The first integer input indicates how many numbers should be processed.
e) Input 10 integers and print the smallest.
f) Calculate and print the sum of the even integers from 2 to 30.
g) Calculate and print the product of the odd integers from 1 to 9.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

15.27 (*Building A Compiler; Prerequisite: Complete Exercises 5.18, 5.19, 15.12, 15.13 and 15.26*) Now that the Simple language has been presented (Exercise 15.26), we discuss how to build a Simple compiler. First, we consider the process by which a Simple program is converted to SML and executed by the Simpletron simulator (see Fig. 15.24). A file containing a Simple program is read by the compiler and converted to SML code. The SML code is output to a file on disk, in which SML instructions appear one per line. The SML file is then loaded into the Simpletron simulator, and the results are sent to a file on disk and to the screen. Note that the Simpletron program developed in Exercise 5.19 took its input from the keyboard. It must be modified to read from a file so it can run the programs produced by our compiler.



Fig. 15.24 Writing, compiling and executing a Simple language program.

The Simple compiler performs two *passes* of the Simple program to convert it to SML. The first pass constructs a *symbol table* (object) in which every *line number* (object), *variable name* (object) and *constant* (object) of the Simple program is stored with its type and corresponding location in the final SML code (the symbol table is discussed in detail below). The first pass also produces the corresponding SML instruction object(s) for each of the Simple statements (object, etc.). As we will see, if the Simple program contains statements that transfer control to a line later in the program, the first pass results in an SML program containing some "unfinished" instructions. The second pass of the compiler locates and completes the unfinished instructions, and outputs the SML program to a file.

First Pass

The compiler begins by reading one statement of the Simple program into memory. The line must be separated into its individual *tokens* (i.e., "pieces" of a statement) for processing and compilation (standard library function **`strtok`** can be used to facilitate this task). Recall that every statement begins with a line number followed by a command. As the compiler breaks a statement into tokens, if the token is a line number, a variable or a constant, it is placed in the symbol table. A line number is placed in the symbol table only if it is the first token in a statement. The **`symbolTable`** object is an array of **`tableEntry`** objects representing each symbol in the program. There is no restriction on the number of symbols that can appear in the program. Therefore, the **`symbolTable`** for a particular program could be large. Make the **`symbolTable`** a 100-element array for now. You can increase or decrease its size once the program is working.

Each **`tableEntry`** object contains three members. Member **`symbol`** is an integer containing the ASCII representation of a variable (remember that variable names are single characters), a line number or a constant. Member **`type`** is one of the following characters indicating the symbol's type: **`'C'`** for constant, **`'L'`** for line number and **`'V'`** for variable. Member **`location`** contains the Simpletron memory location (**`00`** to **`99`**) to which the symbol refers. Simpletron memory is an array of 100 integers in which SML instructions and data are stored. For a line number, the location is the element in the Simpletron memory array at which the SML instructions for the Simple statement begin. For a variable or constant, the location is the element in the Simpletron memory array in which the variable or constant is stored. Variables and constants are allocated from the end of Simpletron's memory backwards. The first variable or constant is stored in location at **`99`**, the next in location at **`98`**, etc.

The symbol table plays an integral part in converting Simple programs to SML. We learned in Chapter 5 that an SML instruction is a four-digit integer composed of two parts—the *operation code* and the *operand*. The operation code is determined by commands in Simple. For example, the simple command **`input`** corresponds to SML operation code **`10`** (read), and the Simple command **`print`** corresponds to SML operation code **`11`** (write). The operand is a memory location containing the data on which the operation code performs its task (e.g., operation code **`10`** reads a value from the keyboard and stores it in the memory location specified by the operand). The compiler searches **`symbolTable`** to determine the Simpletron memory location for each symbol so the corresponding location can be used to complete the SML instructions.

The compilation of each Simple statement is based on its command. For example, after the line number in a **`rem`** statement is inserted in the symbol table, the remainder of the statement is ignored by the compiler because a remark is for documentation purposes only. The **`input`**, **`print`**, **`goto`** and **`end`** statements correspond to the SML *read*, *write*, *branch* (to a specific location) and *halt* instructions. Statements containing these Simple commands are converted directly to SML (note that a **`goto`** statement may

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

contain an unresolved reference if the specified line number refers to a statement further into the Simple program file; this is sometimes called a forward reference).

When a **goto** statement is compiled with an unresolved reference, the SML instruction must be *flagged* to indicate that the second pass of the compiler must complete the instruction. The flags are stored in 100-element array **flags** of type **int** in which each element is initialized to **-1**. If the memory location to which a line number in the Simple program refers is not yet known (i.e., it is not in the symbol table), the line number is stored in array **flags** in the element with the same subscript as the incomplete instruction. The operand of the incomplete instruction is set to **00** temporarily. For example, an unconditional branch instruction (making a forward reference) is left as **+4000** until the second pass of the compiler. The second pass of the compiler is described shortly.

Compilation of **if/goto** and **let** statements is more complicated than other statements—they are the only statements that produce more than one SML instruction. For an **if/goto**, the compiler produces code to test the condition and to branch to another line if necessary. The result of the branch could be an unresolved reference. Each of the relational and equality operators can be simulated using SML's *branch zero* and *branch negative* instructions (or a combination of both).

For a **let** statement, the compiler produces code to evaluate an arbitrarily complex arithmetic expression consisting of integer variables and/or constants. Expressions should separate each operand and operator with spaces. Exercises 15.12 and 15.13 presented the infix-to-postfix conversion algorithm and the postfix evaluation algorithm used by compilers to evaluate expressions. Before proceeding with your compiler, you should complete each of these exercises. When a compiler encounters an expression, it converts the expression from infix notation to postfix notation and then evaluates the postfix expression.

How is it that the compiler produces the machine language to evaluate an expression containing variables? The postfix evaluation algorithm contains a "hook" where the compiler can generate SML instructions rather than actually evaluating the expression. To enable this "hook" in the compiler, the postfix evaluation algorithm must be modified to search the symbol table for each symbol it encounters (and possibly insert it), determine the symbol's corresponding memory location and *push the memory location onto the stack (instead of the symbol)*. When an operator is encountered in the postfix expression, the two memory locations at the top of the stack are popped and machine language for effecting the operation is produced using the memory locations as operands. The result of each subexpression is stored in a temporary location in memory and pushed back onto the stack so the evaluation of the postfix expression can continue. When postfix evaluation is complete, the memory location containing the result is the only location left on the stack. This is popped and SML instructions are generated to assign the result to the variable at the left of the **let** statement.

Second Pass

The second pass of the compiler performs two tasks: resolve any unresolved references and output the SML code to a file. Resolution of references occurs as follows:

a) Search the **flags** array for an unresolved reference (i.e., an element with a value other than **-1**).
b) Locate the object in array **symbolTable**, containing the symbol stored in the **flags** array (be sure that the type of the symbol is **'L'** for line number).
c) Insert the memory location from member **location** into the instruction with the unresolved reference (remember that an instruction containing an unresolved reference has operand **00**).
d) Repeat steps 1, 2 and 3 until the end of the **flags** array is reached.

After the resolution process is complete, the entire array containing the SML code is output to a disk file with one SML instruction per line. This file can be read by the Simpletron for execution (after the simulator is modified to read its input from a file). Compiling your first Simple program into an SML file and then executing that file should give you a real sense of personal accomplishment.

A Complete Example

The following example illustrates a complete conversion of a Simple program to SML as it will be performed by the Simple compiler. Consider a Simple program that inputs an integer and sums the values from 1 to that integer. The program and the SML instructions produced by the first pass of the Simple compiler are illustrated in Fig. 15.25. The symbol table constructed by the first pass is shown in Fig. 15.26.

Simple program	SML location and instruction	Description
`5 rem sum 1 to x`	*none*	**rem** ignored

Fig. 15.25 SML instructions produced after the compiler's first pass.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Simple program	SML location and instruction	Description
`10 input x`	`00 +1099`	read **x** into location **99**
`15 rem check y == x`	*none*	**rem** ignored
`20 if y == x goto 60`	`01 +2098`	load **y** (**98**) into accumulator
	`02 +3199`	sub **x** (**99**) from accumulator
	`03 +4200`	branch zero to unresolved location
`25 rem increment y`	*none*	**rem** ignored
`30 let y = y + 1`	`04 +2098`	load **y** into accumulator
	`05 +3097`	add **1** (**97**) to accumulator
	`06 +2196`	store in temporary location **96**
	`07 +2096`	load from temporary location **96**
	`08 +2198`	store accumulator in **y**
`35 rem add y to total`	*none*	**rem** ignored
`40 let t = t + y`	`09 +2095`	load **t** (**95**) into accumulator
	`10 +3098`	add **y** to accumulator
	`11 +2194`	store in temporary location **94**
	`12 +2094`	load from temporary location **94**
	`13 +2195`	store accumulator in **t**
`45 rem loop y`	*none*	**rem** ignored
`50 goto 20`	`14 +4001`	branch to location **01**
`55 rem output result`	*none*	**rem** ignored
`60 print t`	`15 +1195`	output **t** to screen
`99 end`	`16 +4300`	terminate execution

Fig. 15.25 SML instructions produced after the compiler's first pass.

Symbol	Type	Location
`5`	`L`	`00`
`10`	`L`	`00`
`'x'`	`V`	`99`
`15`	`L`	`01`
`20`	`L`	`01`
`'y'`	`V`	`98`
`25`	`L`	`04`
`30`	`L`	`04`
`1`	`C`	`97`
`35`	`L`	`09`
`40`	`L`	`09`
`'t'`	`V`	`95`

Fig. 15.26 Symbol table for program of Fig. 15.25 (part 1 of 2).

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Symbol	Type	Location
45	L	14
50	L	14
55	L	15
60	L	15
99	L	16

Fig. 15.26 Symbol table for program of Fig. 15.25 (part 2 of 2).

Most Simple statements convert directly to single SML instructions. The exceptions in this program are remarks, the **if/goto** statement in line **20** and the **let** statements. Remarks do not translate into machine language. However, the line number for a remark is placed in the symbol table in case the line number is referenced in a **goto** statement or an **if/goto** statement. Line **20** of the program specifies that if the condition **y == x** is true, program control is transferred to line **60**. Because line **60** appears later in the program, the first pass of the compiler has not as yet placed **60** in the symbol table (statement line numbers are placed in the symbol table only when they appear as the first token in a statement). Therefore, it is not possible at this time to determine the operand of the SML *branch zero* instruction at location **03** in the array of SML instructions. The compiler places **60** in location **03** of the **flags** array to indicate that the second pass completes this instruction.

We must keep track of the next instruction location in the SML array because there is not a one-to-one correspondence between Simple statements and SML instructions. For example, the **if/goto** statement of line **20** compiles into three SML instructions. Each time an instruction is produced, we must increment the *instruction counter* to the next location in the SML array. Note that the size of Simpletron's memory could present a problem for Simple programs with many statements, variables and constants. It is conceivable that the compiler will run out of memory. To test for this case, your program should contain a *data counter* to keep track of the location at which the next variable or constant will be stored in the SML array. If the value of the instruction counter is larger than the value of the data counter, the SML array is full. In this case, the compilation process should terminate and the compiler should print an error message indicating that it ran out of memory during compilation. This serves to emphasize that although the programmer is freed from the burdens of managing memory by the compiler, the compiler itself must carefully determine the placement of instructions and data in memory, and must check for such errors as memory being exhausted during the compilation process.

A Step-by-Step View of the Compilation Process

Let us now walk through the compilation process for the Simple program in Fig. 15.25. The compiler reads the first line of the program

```
5 rem sum 1 to x
```

into memory. The first token in the statement (the line number) is determined using **strtok** (see Chapters 5 and 16 for a discussion of C++'s string manipulation functions). The token returned by **strtok** is converted to an integer using **atoi** so the symbol **5** can be located in the symbol table. If the symbol is not found, it is inserted in the symbol table. Since we are at the beginning of the program and this is the first line, no symbols are in the table yet. So, **5** is inserted into the symbol table as type **L** (line number) and assigned the first location in SML array (**00**). Although this line is a remark, a space in the symbol table is still allocated for the line number (in case it is referenced by a **goto** or an **if/goto**). No SML instruction is generated for a **rem** statement, so the instruction counter is not incremented.

The statement

```
10 input x
```

is tokenized next. The line number **10** is placed in the symbol table as type **L** and assigned the first location in the SML array (**00** because a remark began the program so the instruction counter is currently **00**). The command **input** indicates that the next token is a variable (only a variable can appear in an **input** statement). Because **input** corresponds directly to an SML operation code, the compiler has to determine the location of **x** in the SML array. Symbol **x** is not found in the symbol table. So, it is inserted into the symbol table as the ASCII representation of **x**, given type **V**, and assigned location **99** in the SML array (data storage begins at **99** and is allocated backwards). SML code can now be generated for this statement. Operation code **10** (the SML read operation code) is multiplied by 100, and the location of **x** (as determined in the symbol table) is added to complete the instruction. The instruction is then stored in the SML array at location **00**. The instruction counter is incremented by 1 because a single SML

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

instruction was produced.

The statement

```
15 rem   check y == x
```

is tokenized next. The symbol table is searched for line number **15** (which is not found). The line number is inserted as type **L** and assigned the next location in the array, **01** (remember that **rem** statements do not produce code, so the instruction counter is not incremented).

The statement

```
20 if y == x goto 60
```

is tokenized next. Line number **20** is inserted in the symbol table and given type **L** with the next location in the SML array **01**. The command **if** indicates that a condition is to be evaluated. The variable **y** is not found in the symbol table, so it is inserted and given the type **V** and the SML location **98**. Next, SML instructions are generated to evaluate the condition. Since there is no direct equivalent in SML for the **if/goto**, it must be simulated by performing a calculation using **x** and **y** and branching based on the result. If **y** is equal to **x**, the result of subtracting **x** from **y** is zero, so the *branch zero* instruction can be used with the result of the calculation to simulate the **if/goto** statement. The first step requires that **y** be loaded (from SML location **98**) into the accumulator. This produces the instruction **01 +2098**. Next, **x** is subtracted from the accumulator. This produces the instruction **02 +3199**. The value in the accumulator may be zero, positive or negative. Since the operator is **==**, we want to *branch zero.* First, the symbol table is searched for the branch location (**60** in this case), which is not found. So, **60** is placed in the **flags** array at location **03**, and the instruction **03 +4200** is generated (we cannot add the branch location, because we have not assigned a location to line **60** in the SML array yet). The instruction counter is incremented to **04**.

The compiler proceeds to the statement

```
25 rem   increment y
```

The line number **25** is inserted in the symbol table as type **L** and assigned SML location **04**. The instruction counter is not incremented.

When the statement

```
30 let y = y + 1
```

is tokenized, the line number **30** is inserted in the symbol table as type **L** and assigned SML location **04**. Command **let** indicates that the line is an assignment statement. First, all the symbols on the line are inserted in the symbol table (if they are not already there). The integer **1** is added to the symbol table as type **C** and assigned SML location **97**. Next, the right side of the assignment is converted from infix to postfix notation. Then the postfix expression (**y 1 +**) is evaluated. Symbol **y** is located in the symbol table and its corresponding memory location is pushed onto the stack. Symbol **1** is also located in the symbol table and its corresponding memory location is pushed onto the stack. When the operator **+** is encountered, the postfix evaluator pops the stack into the right operand of the operator, pops the stack again into the left operand of the operator and then produces the SML instructions

```
04 +2098   (load y)
05 +3097   (add 1)
```

The result of the expression is stored in a temporary location in memory (**96**) with instruction

```
06 +2196   (store temporary)
```

and the temporary location is pushed on the stack. Now that the expression has been evaluated, the result must be stored in **y** (i.e., the variable on the left side of **=**). So, the temporary location is loaded into the accumulator and the accumulator is stored in **y** with the instructions

```
07 +2096   (load temporary)
08 +2198   (store y)
```

The reader will immediately notice that SML instructions appear to be redundant. We will discuss this issue shortly.

When the statement

```
35 rem   add y to total
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

is tokenized, line number **35** is inserted in the symbol table as type **L** and assigned location **09**.

The statement

```
40 let t = t + y
```

is similar to line **30**. The variable **t** is inserted in the symbol table as type **V** and assigned SML location **95**. The instructions follow the same logic and format as line **30**, and the instructions **09 +2095**, **10 +3098**, **11 +2194**, **12 +2094** and **13 +2195** are generated. Note that the result of **t + y** is assigned to temporary location **94** before being assigned to **t** (**95**). Once again, the reader will note that the instructions in memory locations **11** and **12** appear to be redundant. Again, we will discuss this shortly.

The statement

```
45 rem   loop y
```

is a remark, so line **45** is added to the symbol table as type **L** and assigned SML location **14**.

The statement

```
50 goto 20
```

transfers control to line **20**. Line number **50** is inserted in the symbol table as type **L** and assigned SML location **14**. The equivalent of **goto** in SML is the *unconditional branch* (**40**) instruction that transfers control to a specific SML location. The compiler searches the symbol table for line **20** and finds that it corresponds to SML location **01**. The operation code (**40**) is multiplied by 100, and location **01** is added to it to produce the instruction **14 +4001**.

The statement

```
55 rem   output result
```

is a remark, so line **55** is inserted in the symbol table as type **L** and assigned SML location **15**.

The statement

```
60 print t
```

is an output statement. Line number **60** is inserted in the symbol table as type **L** and assigned SML location **15**. The equivalent of **print** in SML is operation code **11** (*write*). The location of **t** is determined from the symbol table and added to the result of the operation code multiplied by 100.

The statement

```
99 end
```

is the final line of the program. Line number **99** is stored in the symbol table as type **L** and assigned SML location **16**. The **end** command produces the SML instruction **+4300** (**43** is *halt* in SML), which is written as the final instruction in the SML memory array.

This completes the first pass of the compiler. We now consider the second pass. The **flags** array is searched for values other than **-1**. Location **03** contains **60**, so the compiler knows that instruction **03** is incomplete. The compiler completes the instruction by searching the symbol table for **60**, determining its location and adding the location to the incomplete instruction. In this case, the search determines that line **60** corresponds to SML location **15**, so the completed instruction **03 +4215** is produced, replacing **03 +4200**. The Simple program has now been compiled successfully.

To build the compiler, you will have to perform each of the following tasks:

a) Modify the Simpletron simulator program you wrote in Exercise 5.19 to take its input from a file specified by the user (see Chapter 14). The simulator should output its results to a disk file in the same format as the screen output. Convert the simulator to be an object-oriented program. In particular, make each part of the hardware an object. Arrange the instruction types into a class hierarchy using inheritance. Then execute the program polymorphically by telling each instruction to execute itself with an **executeInstruction** message.

b) Modify the infix-to-postfix conversion algorithm of Exercise 15.12 to process multi-digit integer operands and single-letter variable name operands. (Hint: Standard library function **strtok** can be used to locate each constant and variable in an expression, and constants can be converted from strings to integers using standard library function **atoi**.) (Note: The data representation of the postfix expression must be altered to support variable names and integer constants.)

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

c) Modify the postfix evaluation algorithm to process multidigit integer operands and variable name operands. Also, the algorithm should now implement the "hook" discussed above so that SML instructions are produced rather than directly evaluating the expression. (Hint: Standard library function **strtok** can be used to locate each constant and variable in an expression, and constants can be converted from strings to integers using standard library function **atoi**.) (*Note:* The data representation of the postfix expression must be altered to support variable names and integer constants.)

d) Build the compiler. Incorporate parts (b) and (c) for evaluating expressions in **let** statements. Your program should contain a function that performs the first pass of the compiler and a function that performs the second pass of the compiler. Both functions can call other functions to accomplish their tasks. Make your compiler as object oriented as possible.

```
1  // STACKND.H
2  // Definition of template class StackNode
3  #ifndef STACKND_H
4  #define STACKND_H
5
6  template < class T > class Stack;
7
8  template < class T >
9  class StackNode {
10    friend class Stack< T >;
11 public:
12    StackNode( const T & = 0, StackNode * = 0 );
13    T getData() const;
14 private:
15    T data;
16    StackNode *nextPtr;
17 };
18
19 // Member function definitions for class StackNode
20 template < class T >
21 StackNode< T >::StackNode( const T &d, StackNode< T > *ptr )
22 {
23    data = d;
24    nextPtr = ptr;
25 }
26
27 template < class T >
28 T StackNode< T >::getData() const { return data; }
29
30 #endif
```

```
31 // STACK.H
32 // Definition of class Stack
33 #ifndef STACK_H
34 #define STACK_H
35
36 #include <iostream>
37 using std::cout;
38
39 #include <cassert>
40 #include "stacknd.h"
41
42 template < class T >
43 class Stack {

44 public:
45    Stack();              // default constructor
46    ~Stack();             // destructor
47    void push( T & );     // insert item in stack
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
48       T pop();              // remove item from stack
49       bool isEmpty() const;  // is the stack empty?
50       T stackTop() const;   // return the top element of stack
51       void print() const;   // output the stack
52    private:
53       StackNode< T > *topPtr;    // pointer to fist StackNode
54    };
55
56    // Member function definitions for class Stack
57    template < class T >
58    Stack< T >::Stack() { topPtr = 0; }
59
60    template < class T >
61    Stack< T >::~Stack()
62    {
63       StackNode< T > *tempPtr, *currentPtr = topPtr;
64
65       while ( currentPtr != 0 ) {
66          tempPtr = currentPtr;
67          currentPtr = currentPtr -> nextPtr;
68          delete tempPtr;
69       }
70    }
71
72    template < class T >
73    void Stack< T >::push( T &d )
74    {
75       StackNode< T > *newPtr = new StackNode< T >( d, topPtr );
76
77       assert( newPtr != 0 );  // was memory allocated?
78       topPtr = newPtr;
79    }
80
81    template < class T >
82    T Stack< T >::pop()
83    {
84       assert( !isEmpty() );
85
86       StackNode< T > *tempPtr = topPtr;
87
88       topPtr = topPtr -> nextPtr;
89       T poppedValue = tempPtr -> data;
90       delete tempPtr;
91       return poppedValue;
92    }
93
94    template < class T >
95    bool Stack< T >::isEmpty() const { return topPtr == 0; }
96
97    template < class T >
98    T Stack< T >::stackTop() const
99    { return !isEmpty() ? topPtr -> data : 0; }
100
101   template < class T >
102   void Stack< T >::print() const
103   {
104      StackNode< T > *currentPtr = topPtr;
105
106      if ( isEmpty() )           // Stack is empty
107         cout << "Stack is empty\n";
108      else {                     // Stack is not empty
109         cout << "The stack is:\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
110
111       while ( currentPtr != 0 ) {
112          cout << currentPtr -> data << ' ';
113          currentPtr = currentPtr -> nextPtr;
114       }
115
116       cout << '\n';
117    }
118 }
119
120 #endif
```

```
121 // compiler.h
122
123 const int MAXIMUM = 81;             // maximum length for lines
124 const int SYMBOLTABLESIZE = 100;    // maximum size of symbol table
125 const int MEMORYSIZE = 100;         // maximum Simpletron memory
126
127 // Definition of structure for symbol table entries
128 struct TableEntry {
129    int location;              // SML memory location 00 to 99
130    char type;                 // 'C' = constant, 'V' = variable,
131    int symbol;                // or 'L' = line number
132 };
133
134 // Function prototypes for compiler functions
135 int checkSymbolTable( TableEntry *, int, char );
136 int checkOperand( TableEntry *, char *, int *, int *, int * );
137 void addToSymbolTable( char, int, int, TableEntry *, int );
138 void addLineToFlags( int, int, int *, int *, const int * );
139 void compile( ifstream &, char * );
140 void printOutput( const int [], char * );
141 void lineNumber( char *, TableEntry *, int, int );
142 void initArrays( int *, int *, TableEntry * );
143 void firstPass( int *, int *, TableEntry *, ifstream & );
144 void secondPass( int *, int *, TableEntry * );
145 void separateToken( char *, int *, int *, TableEntry *, int *, int * );
146 void keyWord( char *, int *, int *, TableEntry *, int *, int * );
147 void keyLet( char *, int *, TableEntry *, int *, int * );
148 void keyInput( char *, int *, TableEntry *, int *, int * );
149 void keyPrint( char *, int *, TableEntry *, int *, int * );
150 void keyGoto( char *, int *, int *, TableEntry *, int * );
151 void keyIfGoto( char *, int *, int *, TableEntry *, int *, int * );
152 void evaluateExpression( int, int, char *, int *, TableEntry *,
153                          int *, int *, char * );
154 int createLetSML( int, int, int *, int *, int *, char );
155 void infixToPostfix( char *, char *, int, TableEntry *, int *, int *, int * );
156 void evaluatePostfix( char *, int *, int *, int *, int, TableEntry * );
157 bool isOperator( char );
158 bool precedence( char, char );
159
160 // Simpletron Machine Language (SML) Operation Codes
161 enum SMLOperationCodes { READ = 10, WRITE = 11, LOAD = 20, STORE = 21, ADD = 30,
162                          SUBTRACT = 31, DIVIDE = 32, MULTIPLY = 33, BRANCH = 40,
163                          BRANCHNEG = 41, BRANCHZERO = 42, HALT = 43 };
```

```
164 // Exercise 15.27 Solution
165 // Non-optimized version.
166 #include <iostream>
167
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
168 using std::cout;
169 using std::cin;
170 using std::ios;
171 using std::cerr;
172
173 #include <iomanip>
174
175 using std::setw;
176
177 #include <fstream>
178
179 using std::ifstream;
180 using std::ofstream;
181
182 #include <cstring>
183 #include <cctype>
184 #include <cstdlib>
185 #include "stack.h"
186
187 #include "compiler.h"
188
189 int main()
190 {
191    char inFileName[ 15 ] = "", outFileName[ 15 ] = "";
192    int last = 0;
193
194    cout << "Enter Simple file to be compiled: ";
195    cin >> setw( 15 ) >> inFileName;
196
197    while ( isalnum( inFileName[ last ] ) != 0 ) {
198       outFileName[ last ] = inFileName[ last ];
199       last++;            // note the last occurance
200    }
201
202    outFileName[ last ] = '\0';     // append a NULL character
203    strcat( outFileName, ".sml" );  // add .sml to name
204
205    ifstream inFile( inFileName, ios::in );
206
207    if ( inFile )
208       compile( inFile, outFileName );
209    else
210       cerr << "File not opened. Program execution terminating.\n";
211
212    return 0;
213 }
214
215 // compile function calls the first pass and the second pass
216 void compile( ifstream &input, char *outFileName )
217 {
218    TableEntry symbolTable[ SYMBOLTABLESIZE ]; // symbol table
219    int flags[ MEMORYSIZE ];           // array for forward references
220    int machineArray[ MEMORYSIZE ];    // array for SML instructions
221
222    initArrays( flags, machineArray, symbolTable );
223
224    firstPass( flags, machineArray, symbolTable, input );
225    secondPass( flags, machineArray, symbolTable );
226
227    printOutput( machineArray, outFileName );
228 }
229
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
230 // firstPass constructs the symbol table, creates SML, and flags unresolved
231 // references for goto and if/goto statements.
232 void firstPass( int flags[], int machineArray[], TableEntry symbolTable[],
233                 ifstream &input )
234 {
235    char array[ MAXIMUM ];              // array to copy a Simple line
236    int n = MAXIMUM;                  // required for fgets()
237    int dataCounter = MEMORYSIZE - 1; // 1st data location in machineArray
238    int instCounter = 0;              // 1st instruction location in machineArray
239
240    input.getline( array, n );
241
242    while ( !input.eof() ) {
243       separateToken( array, flags, machineArray, symbolTable, &dataCounter,
244                      &instCounter );
245       input.getline( array, n );
246    }
247 }
248
249 // Separate Tokens tokenizes a Simple statement, process the line number,
250 // and passes the next token to keyWord for processing.
251 void separateToken( char array[], int flags[], int machineArray[],
252                     TableEntry symbolTable[], int *dataCounterPtr,
253                     int *instCounterPtr )
254 {
255    char *tokenPtr = strtok( array, " " );     // tokenize line
256    lineNumber( tokenPtr, symbolTable, *instCounterPtr, *dataCounterPtr );
257    tokenPtr = strtok( 0, " \n" );      // get next token
258    keyWord( tokenPtr, flags, machineArray, symbolTable, dataCounterPtr,
259             instCounterPtr );
260 }
261
262 // checkSymbolTable searches the symbol table and returns
263 // the symbols SML location or a -1 if not found.
264 int checkSymbolTable( TableEntry symbolTable[], int symbol, char type )
265 {
266    for ( int loop = 0; loop < SYMBOLTABLESIZE; ++loop )
267       if ( ( symbol == symbolTable[ loop ].symbol ) &&
268            ( type == symbolTable[ loop ].type ) )
269          return symbolTable[ loop ].location;  // return SML location
270
271    return -1;                                  // symbol not found
272 }
273
274 // lineNumber processes line numbers
275 void lineNumber( char *tokenPtr, TableEntry symbolTable[],
276                  int instCounter, int dataCounter )
277 {
278    const char type = 'L';
279    int symbol;
280
281    if ( isdigit( tokenPtr[ 0 ] ) ) {
282       symbol = atoi( tokenPtr );
283
284       if ( -1 == checkSymbolTable( symbolTable, symbol, type ) )
285          addToSymbolTable( type, symbol, dataCounter, symbolTable,
286                            instCounter );
287    }
288 }
289
290 // keyWord determines the key word type and calls the appropriate function
291 void keyWord( char *tokenPtr, int flags[], int machineArray[],
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
292               TableEntry symbolTable[], int *dataCounterPtr,
293               int *instCounterPtr )
294 {
295    if ( strcmp( tokenPtr, "rem" ) == 0 )
296       ; // no instructions are generated by comments
297    else if ( strcmp( tokenPtr, "input" ) == 0 ) {
298       tokenPtr = strtok( 0, " " );  // assign pointer to next token
299       keyInput( tokenPtr, machineArray, symbolTable, dataCounterPtr,
300                 instCounterPtr );
301    }
302    else if ( strcmp( tokenPtr, "print" ) == 0 ) {
303       tokenPtr = strtok( 0, " " );  // assign pointer to next token
304       keyPrint( tokenPtr, machineArray, symbolTable, dataCounterPtr,
305                 instCounterPtr );
306    }
307    else if ( strcmp( tokenPtr, "goto" ) == 0 ) {
308       tokenPtr = strtok( 0, " " );  // assign pointer to next token
309       keyGoto( tokenPtr, flags, machineArray, symbolTable, instCounterPtr );
310    }
311    else if ( strcmp( tokenPtr, "if" ) == 0 ) {
312       tokenPtr = strtok( 0, " " );  // assign pointer to next token
313       keyIfGoto( tokenPtr, flags, machineArray, symbolTable, dataCounterPtr,
314                  instCounterPtr );
315    }
316    else if ( strcmp( tokenPtr, "end" ) == 0 ) {
317       machineArray[ *instCounterPtr ] = HALT * 100;
318       ++( *instCounterPtr );
319       tokenPtr = 0;       // assign tokenPtr to 0
320    }
321    else if ( strcmp( tokenPtr, "let" ) == 0 ) {
322       tokenPtr = strtok( 0, " " );  // assign pointer to next token
323       keyLet( tokenPtr, machineArray, symbolTable, dataCounterPtr,
324               instCounterPtr );
325    }
326 }
327
328 // keyInput process input keywords
329 void keyInput( char *tokenPtr, int machineArray[], TableEntry symbolTable[],
330                int *dataCounterPtr, int *instCounterPtr )
331 {
332    const char type = 'V';
333
334    machineArray[ *instCounterPtr ] = READ * 100;
335    int symbol = tokenPtr[ 0 ];
336    int tableTest = checkSymbolTable( symbolTable, symbol, type );
337
338    if ( -1 == tableTest ) {
339       addToSymbolTable( type, symbol, *dataCounterPtr, symbolTable,
340                         *instCounterPtr );
341       machineArray[ *instCounterPtr ] += *dataCounterPtr;
342       --( *dataCounterPtr );
343    }
344    else
345       machineArray[ *instCounterPtr ] += tableTest;
346
347    ++( *instCounterPtr );
348 }
349
350 // keyPrint process print keywords
351 void keyPrint( char *tokenPtr, int machineArray[], TableEntry symbolTable[],
352                int *dataCounterPtr, int *instCounterPtr )
353 {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
354    const char type = 'V';
355
356    machineArray[ *instCounterPtr ] = WRITE * 100;
357    int symbol = tokenPtr[ 0 ];
358    int tableTest = checkSymbolTable( symbolTable, symbol, type );
359
360    if ( -1 == tableTest ) {
361       addToSymbolTable( type, symbol, *dataCounterPtr, symbolTable,
362                         *instCounterPtr );
363       machineArray[*instCounterPtr] += *dataCounterPtr;
364       --( *dataCounterPtr );
365    }
366    else
367       machineArray[ *instCounterPtr ] += tableTest;
368
369    ++( *instCounterPtr );
370 }
371
372 // keyGoto process goto keywords
373 void keyGoto( char *tokenPtr, int flags[], int machineArray[],
374               TableEntry symbolTable[], int *instCounterPtr )
375 {
376    const char type = 'L';
377
378    machineArray[*instCounterPtr] = BRANCH * 100;
379    int symbol = atoi( tokenPtr );
380    int tableTest = checkSymbolTable( symbolTable, symbol, type );
381    addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
382    ++( *instCounterPtr );
383 }
384
385 // keyIfGoto process if/goto commands
386 void keyIfGoto( char *tokenPtr, int flags[], int machineArray[],
387                 TableEntry symbolTable[], int *dataCounterPtr,
388                 int *instCounterPtr )
389 {
390    int operand1Loc = checkOperand( symbolTable, tokenPtr, dataCounterPtr,
391                                    instCounterPtr, machineArray );
392
393    char *operatorPtr = strtok( 0, " " );   // get the operator
394
395    tokenPtr = strtok( 0, " " );  // get the right operand of comparison operator
396
397    int operand2Loc = checkOperand( symbolTable, tokenPtr, dataCounterPtr,
398                                    instCounterPtr, machineArray );
399
400    tokenPtr = strtok( 0, " " );  // read in the goto keyword
401
402    char *gotoLinePtr = strtok( 0, " " );  // read in the goto line number
403
404    evaluateExpression( operand1Loc, operand2Loc, operatorPtr, machineArray,
405                        symbolTable, instCounterPtr, flags, gotoLinePtr );
406 }
407
408 // checkOperand ensures that the operands of an if/goto statement are
409 // in the symbol table.
410 int checkOperand( TableEntry symbolTable[], char *symPtr, int *dataCounterPtr,
411                   int *instCounterPtr, int machineArray[] )
412 {
413    char type;
414    int tableTest, operand, temp;
415
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
416    if ( isalpha( symPtr[ 0 ] ) ) {
417       type = 'V';
418       operand = symPtr[ 0 ];
419       tableTest = checkSymbolTable( symbolTable, operand, type );
420
421       if ( tableTest == -1 ) {
422          addToSymbolTable( type, operand, *dataCounterPtr, symbolTable,
423                            *instCounterPtr );
424          temp = *dataCounterPtr;
425          --( *dataCounterPtr );
426          return temp;
427       }
428       else
429          return tableTest;
430    }
431    // if the symbol is a digit or a signed digit
432    else if ( isdigit( symPtr[ 0 ] ) ||
433              ( ( symPtr[ 0 ] == '-' || symPtr[ 0 ] == '+' ) &&
434              isdigit( symPtr[ 1 ] ) != 0 ) ) {
435       type = 'C';
436       operand = atoi( symPtr );
437       tableTest = checkSymbolTable( symbolTable, operand, type );
438
439       if ( tableTest == -1 ) {
440          addToSymbolTable( type, operand, *dataCounterPtr, symbolTable,
441                            *instCounterPtr );
442          machineArray[ *dataCounterPtr ] = operand;
443          temp = *dataCounterPtr;
444          --( *dataCounterPtr );
445          return temp ;
446       }
447       else
448          return tableTest;
449    }
450
451    return 0;       // default return for compilation purposes
452 }
453
454 // evaluateExpression creates SML for conditional operators
455 void evaluateExpression( int operator1Loc, int operator2Loc, char *operandPtr,
456                          int machineArray[], TableEntry symbolTable[],
457                          int *instCounterPtr, int flags[], char *gotoLinePtr )
458 {
459    const char type = 'L';
460    int tableTest, symbol;
461
462    if ( strcmp( operandPtr, "==" ) == 0 ) {
463       machineArray[ *instCounterPtr ] = LOAD * 100;
464       machineArray[ *instCounterPtr ] += operator1Loc;
465       ++( *instCounterPtr );
466
467       machineArray[ *instCounterPtr ] = SUBTRACT * 100;
468       machineArray[ *instCounterPtr ] += operator2Loc;
469       ++( *instCounterPtr );
470
471       machineArray[ *instCounterPtr ] = BRANCHZERO * 100;
472
473       symbol = atoi( gotoLinePtr );
474       tableTest = checkSymbolTable( symbolTable, symbol, type );
475       addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
476       ++( *instCounterPtr );
477    }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
478    else if ( strcmp( operandPtr, "!=" ) == 0 ) {
479       machineArray[ *instCounterPtr ] = LOAD * 100;
480       machineArray[ *instCounterPtr ] += operator2Loc;
481       ++( *instCounterPtr );
482
483       machineArray[ *instCounterPtr ] = SUBTRACT * 100;
484       machineArray[ *instCounterPtr ] += operator1Loc;
485       ++( *instCounterPtr );
486
487       machineArray[ *instCounterPtr ] = BRANCHNEG * 100;
488
489       symbol = atoi( gotoLinePtr );
490       tableTest = checkSymbolTable( symbolTable, symbol, type );
491
492       addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
493
494       ++( *instCounterPtr );
495
496       machineArray[ *instCounterPtr ] = LOAD * 100;
497       machineArray[ *instCounterPtr ] += operator1Loc;
498       ++( *instCounterPtr );
499
500       machineArray[ *instCounterPtr ] = SUBTRACT * 100;
501       machineArray[ *instCounterPtr ] += operator2Loc;
502       ++( *instCounterPtr );
503
504       machineArray[ *instCounterPtr ] = BRANCHNEG * 100;
505
506       symbol = atoi( gotoLinePtr );
507       tableTest = checkSymbolTable( symbolTable, symbol, type );
508
509       addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
510
511       ++( *instCounterPtr );
512    }
513    else if ( strcmp( operandPtr, ">" ) == 0 ) {
514       machineArray[ *instCounterPtr ] = LOAD * 100;
515       machineArray[ *instCounterPtr ] += operator2Loc;
516       ++( *instCounterPtr );
517
518       machineArray[ *instCounterPtr ] = SUBTRACT * 100;
519       machineArray[ *instCounterPtr ] += operator1Loc;
520       ++( *instCounterPtr );
521
522       machineArray[ *instCounterPtr ] = BRANCHNEG * 100;
523
524       symbol = atoi( gotoLinePtr );
525       tableTest = checkSymbolTable( symbolTable, symbol, type );
526
527       addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
528       ++( *instCounterPtr );
529    }
530    else if ( strcmp( operandPtr, "<" ) == 0 ) {
531       machineArray[ *instCounterPtr ] = LOAD * 100;
532       machineArray[ *instCounterPtr ] += operator1Loc;
533       ++( *instCounterPtr );
534
535       machineArray[ *instCounterPtr ] = SUBTRACT * 100;
536       machineArray[ *instCounterPtr ] += operator2Loc;
537       ++( *instCounterPtr );
538
539       machineArray[ *instCounterPtr ] = BRANCHNEG * 100;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
540
541         symbol = atoi( gotoLinePtr );
542         tableTest = checkSymbolTable( symbolTable, symbol, type );
543
544         addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
545         ++( *instCounterPtr );
546      }
547      else if ( strcmp( operandPtr, ">=" ) == 0 ) {
548         machineArray[ *instCounterPtr ] = LOAD * 100;
549         machineArray[ *instCounterPtr ] += operator2Loc;
550         ++( *instCounterPtr );
551
552         machineArray[ *instCounterPtr ] = SUBTRACT * 100;
553         machineArray[ *instCounterPtr ] += operator1Loc;
554         ++( *instCounterPtr );
555
556         machineArray[ *instCounterPtr ] = BRANCHNEG * 100;
557
558         symbol = atoi( gotoLinePtr );
559         tableTest = checkSymbolTable( symbolTable, symbol, type );
560
561         addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
562         ++( *instCounterPtr );
563
564         machineArray[ *instCounterPtr ] = BRANCHZERO * 100;
565
566         addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
567         ++( *instCounterPtr );
568      }
569      else if ( strcmp( operandPtr, "<=" ) == 0 ) {
570         machineArray[ *instCounterPtr ] = LOAD * 100;
571         machineArray[ *instCounterPtr ] += operator1Loc;
572         ++( *instCounterPtr );
573
574         machineArray[ *instCounterPtr ] = SUBTRACT * 100;
575         machineArray[ *instCounterPtr ] += operator2Loc;
576         ++( *instCounterPtr );
577
578         machineArray[ *instCounterPtr ] = BRANCHNEG * 100;
579
580         symbol = atoi( gotoLinePtr );
581         tableTest = checkSymbolTable( symbolTable, symbol, type );
582
583         addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
584         ++( *instCounterPtr );
585
586         machineArray[ *instCounterPtr ] = BRANCHZERO * 100;
587
588         addLineToFlags( tableTest, symbol, flags, machineArray, instCounterPtr );
589         ++( *instCounterPtr );
590      }
591   }
592
593   // secondPass resolves incomplete SML instructions for forward references
594   void secondPass( int flags[], int machineArray[], TableEntry symbolTable[] )
595   {
596      const char type = 'L';
597
598      for ( int loop = 0; loop < MEMORYSIZE; ++loop ) {
599         if ( flags[ loop ] != -1 ) {
600            int symbol = flags[ loop ];
601            int flagLocation = checkSymbolTable( symbolTable, symbol, type );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
602          machineArray[ loop ] += flagLocation;
603       }
604    }
605 }
606
607 // keyLet processes the keyword let
608 void keyLet( char *tokenPtr, int machineArray[], TableEntry symbolTable[],
609              int *dataCounterPtr, int *instCounterPtr )
610 {
611    const char type = 'V';
612    char infixArray[ MAXIMUM ] = "", postfixArray[ MAXIMUM ] = "";
613    int tableTest, symbol, location;
614    static int subscript = 0;
615
616    symbol = tokenPtr[ 0 ];
617    tableTest = checkSymbolTable( symbolTable, symbol, type );
618
619    if ( -1 == tableTest ) {
620       addToSymbolTable( type, symbol, *dataCounterPtr, symbolTable,
621                         *instCounterPtr );
622       location = *dataCounterPtr;
623       --( *dataCounterPtr );
624    }
625    else
626       location = tableTest;
627
628    tokenPtr = strtok( 0, " " );     // grab equal sign
629    tokenPtr = strtok( 0, " " );     // get next token
630
631    while ( tokenPtr != 0 ) {
632       checkOperand( symbolTable, tokenPtr, dataCounterPtr,
633                     instCounterPtr, machineArray );
634       infixArray[ subscript ] = tokenPtr[ 0 ];
635       ++subscript;
636       tokenPtr = strtok( 0, " " );  // get next token
637    }
638
639    infixArray[ subscript ] = '\0';
640
641    infixToPostfix( infixArray, postfixArray, location, symbolTable,
642                    instCounterPtr, dataCounterPtr, machineArray );
643
644    subscript = 0;    // reset static subscript when done
645 }
646
647 void addToSymbolTable( char type, int symbol, int dataCounter,
648                        TableEntry symbolTable[], int instCounter )
649 {
650    static int symbolCounter = 0;
651
652    symbolTable[ symbolCounter ].type = type;
653    symbolTable[ symbolCounter ].symbol = symbol;
654
655    if ( type == 'V' || type == 'C' )
656       symbolTable[ symbolCounter ].location = dataCounter;
657    else
658       symbolTable[ symbolCounter ].location = instCounter;
659
660    ++symbolCounter;
661 }
662
663 void addLineToFlags( int tableTest, int symbol, int flags[],
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
                      int machineArray[], const int *instCounterPtr )
{
   if ( tableTest == -1 )
      flags[ *instCounterPtr ] = symbol;
   else
      machineArray[ *instCounterPtr ] += tableTest;
}

void printOutput( const int machineArray[], char *outFileName )
{
   ofstream output( outFileName, ios::out );

   if ( !output )
      cerr << "File was not opened.\n";
   else                    // output every memory cell
      for ( int loop = 0; loop <= MEMORYSIZE - 1; ++loop )
         output << machineArray[ loop ] << '\n';
}

void initArrays( int flags[], int machineArray[], TableEntry symbolTable[] )
{
   TableEntry initEntry = { 0, 0, -1 };

   for ( int loop = 0; loop < MEMORYSIZE; ++loop ) {
      flags[ loop ] = -1;
      machineArray[ loop ] = 0;
      symbolTable[ loop ] = initEntry;
   }
}

////////////////////////////////////////////////////////////////////////////
// INFIX TO POSTFIX CONVERSION and POSTFIX EVALUATION FOR THE LET STATEMENT //
////////////////////////////////////////////////////////////////////////////

// infixToPostfix converts an infix expression to a postfix expression
void infixToPostfix( char infix[], char postfix[], int getsVariable,
                     TableEntry symbolTable[], int *instCounterPtr,
                     int *dataCounterPtr, int machineArray[] )
{
   Stack< int > intStack;
   int infixCount, postfixCount, popValue;
   bool higher;
   int leftParen = '(';   // made int

   // push a left paren onto the stack and add a right paren to infix
   intStack.push( leftParen );
   strcat( infix, ")" );

   // convert the infix expression to postfix
   for ( infixCount = 0, postfixCount = 0; intStack.stackTop();
         ++infixCount ) {

      if ( isalnum( infix[ infixCount ] ) )
         postfix[ postfixCount++ ] = infix[ infixCount ];
      else if ( infix[ infixCount ] == '(' )
         intStack.push( leftParen );
      else if ( isOperator( infix[ infixCount ] ) ) {
         higher = true;   // used to store value of precedence test

         while ( higher ) {
            if ( isOperator( static_cast< char >( intStack.stackTop() ) ) )
               if ( precedence( static_cast< char >( intStack.stackTop() ),
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
                     infix[ infixCount ] ) )

                  postfix[ postfixCount++ ] =
                                    static_cast< char >( intStack.pop() );
               else
                  higher = false;
            else
               higher = false;
         }

         // See chapter 21 for a discussion of reinterpret_cast
         intStack.push( reinterpret_cast< int & > ( infix[ infixCount ] ) );
      }
      else if ( infix[ infixCount ] == ')' )
         while ( ( popValue = intStack.pop() ) != '(' )
            postfix[ postfixCount++ ] = static_cast< char >( popValue );
   }

   postfix[ postfixCount ] = '\0';

   evaluatePostfix( postfix, dataCounterPtr, instCounterPtr,
                    machineArray, getsVariable, symbolTable );
}

// check if c is an operator
bool isOperator( char c )
{
   if ( c == '+' || c == '-' || c == '*' || c == '/' || c == '^' )
      return true;
   else
      return false;
}

// If the precedence of operator1 is >= operator2,
bool precedence( char operator1, char operator2 )
{
   if ( operator1 == '^' )
      return true;
   else if ( operator2 == '^' )
      return false;
   else if ( operator1 == '*' || operator1 == '/' )
      return true;
   else if ( operator1 == '+' || operator1 == '-' )
      if ( operator2 == '*' || operator2 == '/' )
         return false;
      else
         return true;

   return false;
}

// evaluate postfix expression and produce code
void evaluatePostfix( char *expr, int *dataCounterPtr,
                      int *instCounterPtr, int machineArray[],
                      int getsVariable, TableEntry symbolTable[] )
{
   Stack< int > intStack;
   int popRightValue, popLeftValue, accumResult, symbolLocation, symbol;
   char type, array[ 2 ] = "";
   int i;

   strcat( expr, ")" );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
788
789    for ( i = 0; expr[ i ] != ')'; ++i )
790       if ( isdigit( expr[ i ] ) ) {
791          type = 'C';
792          array[ 0 ] = expr[ i ];
793          symbol = atoi( array );
794
795          symbolLocation = checkSymbolTable( symbolTable, symbol, type );
796          intStack.push( symbolLocation );
797       }
798       else if ( isalpha( expr[ i ] ) ) {
799          type = 'V';
800          symbol = expr[ i ];
801          symbolLocation = checkSymbolTable( symbolTable, symbol, type );
802          intStack.push( symbolLocation );
803       }
804       else {
805          popRightValue = intStack.pop();
806          popLeftValue = intStack.pop();
807          accumResult = createLetSML( popRightValue, popLeftValue, machineArray,
808                                      instCounterPtr, dataCounterPtr,
809                                      expr[ i ] );
810          intStack.push( accumResult );
811       }
812
813       machineArray[ *instCounterPtr ] = LOAD * 100;
814       machineArray[ *instCounterPtr ] += intStack.pop();
815       ++( *instCounterPtr );
816       machineArray[ *instCounterPtr ] = STORE * 100;
817       machineArray[ *instCounterPtr ] += getsVariable;
818       ++( *instCounterPtr );
819 }
820
821 int createLetSML( int right, int left, int machineArray[],
822                   int *instCounterPtr, int *dataCounterPtr, char oper )
823 {
824    int location;
825
826    switch( oper ) {
827       case '+':
828          machineArray[ *instCounterPtr ] = LOAD * 100;
829          machineArray[ *instCounterPtr ] += left;
830          ++( *instCounterPtr );
831          machineArray[ *instCounterPtr ] = ADD * 100;
832          machineArray[ *instCounterPtr ] += right;
833          ++( *instCounterPtr );
834          machineArray[ *instCounterPtr ] = STORE * 100;
835          machineArray[ *instCounterPtr ] += *dataCounterPtr;
836          location = *dataCounterPtr;
837          --( *dataCounterPtr );
838          ++( *instCounterPtr );
839          return location;
840       case '-':
841          machineArray[ *instCounterPtr ] = LOAD * 100;
842          machineArray[ *instCounterPtr ] += left;
843          ++( *instCounterPtr );
844          machineArray[ *instCounterPtr ] = SUBTRACT * 100;
845          machineArray[ *instCounterPtr ] += right;
846          ++( *instCounterPtr );
847          machineArray[ *instCounterPtr ] = STORE * 100;
848          machineArray[ *instCounterPtr ] += *dataCounterPtr;
849          location = *dataCounterPtr;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
850          --( *dataCounterPtr );
851          ++( *instCounterPtr );
852          return location;
853       case '/':
854          machineArray[ *instCounterPtr ] = LOAD * 100;
855          machineArray[ *instCounterPtr ] += left;
856          ++( *instCounterPtr );
857          machineArray[ *instCounterPtr ] = DIVIDE * 100;
858          machineArray[ *instCounterPtr ] += right;
859          ++( *instCounterPtr );
860          machineArray[ *instCounterPtr ] = STORE * 100;
861          machineArray[ *instCounterPtr ] += *dataCounterPtr;
862          location = *dataCounterPtr;
863          --( *dataCounterPtr );
864          ++( *instCounterPtr );
865          return location;
866       case '*':
867          machineArray[ *instCounterPtr ] = LOAD * 100;
868          machineArray[ *instCounterPtr ] += left;
869          ++( *instCounterPtr );
870          machineArray[ *instCounterPtr ] = MULTIPLY * 100;
871          machineArray[ *instCounterPtr ] += right;
872          ++( *instCounterPtr );
873          machineArray[ *instCounterPtr ] = STORE * 100;
874          machineArray[ *instCounterPtr ] += *dataCounterPtr;
875          location = *dataCounterPtr;
876          --( *dataCounterPtr );
877          ++( *instCounterPtr );
878          return location;
879       default:
880          cerr << "ERROR: operator not recognized.\n";
881          break;
882    }
883
884    return 0;    // default return
885 }
```

15.28 (*Optimizing the Simple Compiler*) When a program is compiled and converted into SML, a set of instructions is generated. Certain combinations of instructions often repeat themselves, usually in triplets called *productions*. A production normally consists of three instructions such as *load*, *add* and *store*. For example, Fig. 15.27 illustrates five of the SML instructions that were produced in the compilation of the program in Fig. 15.25 The first three instructions are the production that adds **1** to **y**. Note that instructions **06** and **07** store the accumulator value in temporary location **96** and then load the value back into the accumulator so instruction **08** can store the value in location **98**. Often a production is followed by a load instruction for the same location that was just stored. This code can be *optimized* by eliminating the store instruction and the subsequent load instruction that operate on the same memory location, thus enabling the Simpletron to execute the program faster. Figure 15.28 illustrates the optimized SML for the program of Fig. 15.25. Note that there are four fewer instructions in the optimized code—a memory-space savings of 25%.

Modify the compiler to provide an option for optimizing the Simpletron Machine Language code it produces. Manually compare the nonoptimized code with the optimized code, and calculate the percentage reduction.

15.29 (*Modifications to the Simple compiler*) Perform the following modifications to the Simple compiler. Some of these modifications may also require modifications to the Simpletron Simulator program written in Exercise 5.19.

a) Allow the modulus operator (**%**) to be used in **let** statements. Simpletron Machine Language must be modified to include a modulus instruction.

b) Allow exponentiation in a **let** statement using **^** as the exponentiation operator. Simpletron Machine Language must be modified to include an exponentiation instruction.

```
1  04   +2098   (load)
2  05   +3097   (add)
```

Fig. 15.27 Nonoptimized code from the program of Fig. 15.25.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
3  06   +2196  (store)
4  07   +2096  (load)
5  08   +2198  (store)
```

Fig. 15.27 Nonoptimized code from the program of Fig. 15.25.

Simple program	SML location and instruction	Description
`5 rem sum 1 to x`	*none*	**rem** ignored
`10 input x`	`00 +1099`	read **x** into location **99**
`15 rem check y == x`	*none*	**rem** ignored
`20 if y == x goto 60`	`01 +2098`	load **y** (**98**) into accumulator
	`02 +3199`	sub **x** (**99**) from accumulator
	`03 +4211`	branch to location **11** if zero
`25 rem increment y`	*none*	**rem** ignored
`30 let y = y + 1`	`04 +2098`	load **y** into accumulator
	`05 +3097`	add **1** (**97**) to accumulator
	`06 +2198`	store accumulator in **y** (**98**)
`35 rem add y to total`	*none*	**rem** ignored
`40 let t = t + y`	`07 +2096`	load **t** from location (**96**)
	`08 +3098`	add **y** (**98**) accumulator
	`09 +2196`	store accumulator in **t** (**96**)
`45 rem loop y`	*none*	**rem** ignored
`50 goto 20`	`10 +4001`	branch to location **01**
`55 rem output result`	*none*	**rem** ignored
`60 print t`	`11 +1196`	output **t** (**96**) to screen
`99 end`	`12 +4300`	terminate execution

Fig. 15.28 Optimized code for the program of Fig. 15.25.

c) Allow the compiler to recognize uppercase and lowercase letters in Simple statements (e.g., **'A'** is equivalent to **'a'**). No modifications to the Simulator are required.

d) Allow **input** statements to read values for multiple variables such as **input x, y**. No modifications to the Simpletron Simulator are required.

e) Allow the compiler to output multiple values in a single **print** statement such as **print a, b, c**. No modifications to the Simpletron Simulator are required.

f) Add syntax-checking capabilities to the compiler so error messages are output when syntax errors are encountered in a Simple program. No modifications to the Simpletron Simulator are required.

g) Allow arrays of integers. No modifications to the Simpletron Simulator are required.

h) Allow subroutines specified by the Simple commands **gosub** and **return**. Command **gosub** passes program control to a subroutine, and command **return** passes control back to the statement after the **gosub**. This is similar to a function call in C++. The same subroutine can be called from many **gosub** commands distributed throughout a program. No modifications to the Simpletron Simulator are required.

i) Allow repetition structures of the form

```
for x = 2 to 10 step 2
    Simple statements
next
```

This **for** statement loops from **2** to **10** with an increment of **2**. The **next** line marks the end of the body of the **for** line. No modifications to the Simpletron Simulator are required.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

j) Allow repetition structures of the form

```
for x = 2 to 10
   Simple statements
next
```

This **for** statement loops from **2** to **10** with a default increment of **1**. No modifications to the Simpletron Simulator are required.

k) Allow the compiler to process string input and output. This requires the Simpletron Simulator to be modified to process and store string values. (Hint: Each Simpletron word can be divided into two groups, each holding a two-digit integer. Each two-digit integer represents the ASCII decimal equivalent of a character. Add a machine language instruction that will print a string beginning at a certain Simpletron memory location. The first half of the word at that location is a count of the number of characters in the string (i.e., the length of the string). Each succeeding half word contains one ASCII character expressed as two decimal digits. The machine language instruction checks the length and prints the string by translating each two-digit number into its equivalent character.)

l) Allow the compiler to process floating-point values in addition to integers. The Simpletron Simulator must also be modified to process floating-point values.

15.30 (*A Simple interpreter*) An interpreter is a program that reads a high-level language program statement, determines the operation to be performed by the statement and executes the operation immediately. The high-level language program is not converted into machine language first. Interpreters execute slowly because each statement encountered in the program must first be deciphered. If statements are contained in a loop, the statements are deciphered each time they are encountered in the loop. Early versions of the BASIC programming language were implemented as interpreters.

Write an interpreter for the Simple language discussed in Exercise 15.26. The program should use the infix-to-postfix converter developed in Exercise 15.12 and the postfix evaluator developed in Exercise 15.13 to evaluate expressions in a **let** statement. The same restrictions placed on the Simple language in Exercise 15.26 should be adhered to in this program. Test the interpreter with the Simple programs written in Exercise 15.26. Compare the results of running these programs in the interpreter with the results of compiling the Simple programs and running them in the Simpletron Simulator built in Exercise 5.19.

15.31 *(Insert/Delete Anywhere in a Linked List)* Our linked list class template allowed insertions and deletions at only the front and the back of the linked list. These capabilities were convenient for us when we used private inheritance and composition to produce a stack class template and a queue class template with a minimal amount of code by reusing the list class template. Actually, linked lists are more general that those we provided. Modify the linked list class template we developed in this chapter to handle insertions and deletions anywhere in the list.

```
1  // LIST.H
2  // Template List class definition
3  // Added copy constructor to member functions (not included in chapter).
4  #ifndef LIST_H
5  #define LIST_H
6
7  #include <iostream>
8
9  using std::cout;
10
11 #include <cassert>
12 #include "listnd.h"
13
14 template< class NODETYPE >
15 class List {
16 public:
17    List();                           // default constructor
18    List( const List< NODETYPE > & );  // copy constructor
19    ~List();                          // destructor
20    void insertAtFront( const NODETYPE & );
21    void insertAtBack( const NODETYPE & );
22    bool removeFromFront( NODETYPE & );
23    bool removeFromBack( NODETYPE & );
24    void insertInOrder( const NODETYPE & );
25    bool isEmpty() const;
26    void print() const;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
27 protected:
28    ListNode< NODETYPE > *firstPtr;  // pointer to first node
29    ListNode< NODETYPE > *lastPtr;   // pointer to last node
30
31    // Utility function to allocate a new node
32    ListNode< NODETYPE > *getNewNode( const NODETYPE & );
33 };
34
35 // Default constructor
36 template< class NODETYPE >
37 List< NODETYPE >::List() { firstPtr = lastPtr = 0; }
38
39 // Copy constructor
40 template< class NODETYPE >
41 List< NODETYPE >::List( const List<NODETYPE> &copy )
42 {
43    firstPtr = lastPtr = 0;  // initialize pointers
44
45    ListNode< NODETYPE > *currentPtr = copy.firstPtr;
46
47    while ( currentPtr != 0 ) {
48       insertAtBack( currentPtr -> data );
49       currentPtr = currentPtr -> nextPtr;
50    }
51 }
52
53 // Destructor
54 template< class NODETYPE >
55 List< NODETYPE >::~List()
56 {
57    if ( !isEmpty() ) {    // List is not empty
58       cout << "Destroying nodes ...\n";
59
60       ListNode< NODETYPE > *currentPtr = firstPtr, *tempPtr;
61
62       while ( currentPtr != 0 ) {  // delete remaining nodes
63          tempPtr = currentPtr;
64          cout << tempPtr -> data << ' ';
65          currentPtr = currentPtr -> nextPtr;
66          delete tempPtr;
67       }
68    }
69
70    cout << "\nAll nodes destroyed\n\n";
71 }
72
73 // Insert a node at the front of the list
74 template< class NODETYPE >
75 void List< NODETYPE >::insertAtFront( const NODETYPE &value )
76 {
77    ListNode<NODETYPE> *newPtr = getNewNode( value );
78
79    if ( isEmpty() )  // List is empty
80       firstPtr = lastPtr = newPtr;
81    else {          // List is not empty
82       newPtr -> nextPtr = firstPtr;
83       firstPtr = newPtr;
84    }
85 }
86
87 // Insert a node at the back of the list
88 template< class NODETYPE >
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
89  void List< NODETYPE >::insertAtBack( const NODETYPE &value )
90  {
91     ListNode< NODETYPE > *newPtr = getNewNode( value );
92
93     if ( isEmpty() )  // List is empty
94        firstPtr = lastPtr = newPtr;
95     else {           // List is not empty
96        lastPtr -> nextPtr = newPtr;
97        lastPtr = newPtr;
98     }
99  }
100
101 // Delete a node from the front of the list
102 template< class NODETYPE >
103 bool List< NODETYPE >::removeFromFront( NODETYPE &value )
104 {
105    if ( isEmpty() )              // List is empty
106       return false;              // delete unsuccessful
107    else {
108       ListNode< NODETYPE > *tempPtr = firstPtr;
109
110       if ( firstPtr == lastPtr )
111          firstPtr = lastPtr = 0;
112       else
113          firstPtr = firstPtr -> nextPtr;
114
115       value = tempPtr -> data;  // data being removed
116       delete tempPtr;
117       return true;              // delete successful
118    }
119 }
120
121 // Delete a node from the back of the list
122 template< class NODETYPE >
123 bool List< NODETYPE >::removeFromBack( NODETYPE &value )
124 {
125    if ( isEmpty() )
126       return false;   // delete unsuccessful
127    else {
128       ListNode< NODETYPE > *tempPtr = lastPtr;
129
130       if ( firstPtr == lastPtr )
131          firstPtr = lastPtr = 0;
132       else {
133          ListNode< NODETYPE > *currentPtr = firstPtr;
134
135          while ( currentPtr -> nextPtr != lastPtr )
136             currentPtr = currentPtr -> nextPtr;
137
138          lastPtr = currentPtr;
139          currentPtr -> nextPtr = 0;
140       }
141
142       value = tempPtr -> data;
143       delete tempPtr;
144       return true;   // delete successful
145    }
146 }
147

148 // Is the List empty?
149 template< class NODETYPE >
150 bool List< NODETYPE >::isEmpty() const { return firstPtr == 0; }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
151
152 // Return a pointer to a newly allocated node
153 template< class NODETYPE >
154 ListNode< NODETYPE > *List< NODETYPE >::getNewNode( const NODETYPE &value )
155 {
156    ListNode< NODETYPE > *ptr = new ListNode< NODETYPE >( value );
157    assert( ptr != 0 );
158    return ptr;
159 }
160
161 // Display the contents of the List
162 template< class NODETYPE >
163 void List< NODETYPE >::print() const
164 {
165    if ( isEmpty() ) {
166       cout << "The list is empty\n\n";
167       return;
168    }
169
170    ListNode< NODETYPE > *currentPtr = firstPtr;
171
172    cout << "The list is: ";
173
174    while ( currentPtr != 0 ) {
175       cout << currentPtr -> data << ' ';
176       currentPtr = currentPtr -> nextPtr;
177    }
178
179    cout << "\n\n";
180 }
181
182 template< class NODETYPE >
183 void List< NODETYPE >::insertInOrder( const NODETYPE &value )
184 {
185    if ( isEmpty() ) {
186       ListNode< NODETYPE > *newPtr = getNewNode( value );
187       firstPtr = lastPtr = newPtr;
188    }
189    else {
190       if ( firstPtr -> data > value )
191          insertAtFront( value );
192       else if ( lastPtr -> data < value )
193          insertAtBack( value );
194       else {
195          ListNode< NODETYPE > *currentPtr = firstPtr -> nextPtr,
196                               *previousPtr = firstPtr,
197                               *newPtr = getNewNode( value );
198
199          while ( currentPtr != lastPtr && currentPtr -> data < value ) {
200             previousPtr = currentPtr;
201             currentPtr = currentPtr -> nextPtr;
202          }
203
204          previousPtr -> nextPtr = newPtr;
205          newPtr -> nextPtr = currentPtr;
206       }
207    }
208 }
209
210 #endif
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// LISTND.H
// ListNode template definition
#ifndef LISTND_H
#define LISTND_H

template< class T > class List;  // forward declaration

template< class NODETYPE >
class ListNode {
   friend class List< NODETYPE >; // make List a friend
public:
   ListNode( const NODETYPE & );  // constructor
   NODETYPE getData() const;    // return the data in the node
   void setNextPtr( ListNode *nPtr ) { nextPtr = nPtr; }
   ListNode *getNextPtr() const { return nextPtr; }
private:
   NODETYPE data;               // data
   ListNode *nextPtr;           // next node in the list
};

// Constructor
template< class NODETYPE >
ListNode< NODETYPE >::ListNode( const NODETYPE &info )
{
   data = info;
   nextPtr = 0;
}

// Return a copy of the data in the node
template< class NODETYPE >
NODETYPE ListNode< NODETYPE >::getData() const { return data; }

#endif
```

```
// LIST2.H
// Template List class definition
// NOTE: This solution only provides the delete anywhere operation.

#ifndef LIST2_H
#define LIST2_H

#include <cassert>
#include "listnd.h"
#include "list.h"

template< class NODETYPE >
class List2 : public List< NODETYPE > {
public:
   bool deleteNode( const NODETYPE &, NODETYPE & );
};

// Delete a node from anywhere in the list
template< class NODETYPE >
bool List2< NODETYPE >::deleteNode( const NODETYPE &val, NODETYPE &deletedVal )
{
   if ( isEmpty() )
      return false;   // delete unsuccessful

   else {
      if ( firstPtr -> getData() == val ) {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
269          removeFromFront( deletedVal );
270          return true;  // delete successful
271       }
272       else if ( lastPtr -> getData() == val ) {
273          removeFromBack( deletedVal );
274          return true;  // delete successful
275       }
276       else {
277          ListNode< NODETYPE > *currentPtr = firstPtr -> getNextPtr(),
278                               *previousPtr = firstPtr;
279
280          while ( currentPtr != lastPtr && currentPtr -> getData() < val ) {
281             previousPtr = currentPtr;
282             currentPtr = currentPtr -> getNextPtr();
283          }
284
285          if ( currentPtr -> getData() == val ) {
286             ListNode< NODETYPE > *tempPtr = currentPtr;
287             deletedVal = currentPtr -> getData();
288             previousPtr -> setNextPtr( currentPtr -> getNextPtr() );
289             delete tempPtr;
290             return true;  // delete successful
291          }
292          else
293             return false;  // delete unsuccessful
294       }
295    }
296 }
297
298 #endif
```

```
299 // Exercise 15.31 solution
300 #include <iostream>
301
302 using std::cout;
303 using std::cin;
304
305 #include <cstdlib>
306 #include <ctime>
307 #include "list2.h"
308
309 int main()
310 {
311    srand( time( 0 ) );  // randomize the random number generator
312
313    List2< int > intList;
314
315    for ( int i = 1; i <= 10; ++i )
316       intList.insertInOrder( rand() % 101 );
317
318    intList.print();
319
320    int value, deletedValue;
321
322    cout << "Enter an integer to delete (-1 to end): ";
323    cin >> value;
324
325    while ( value != -1 ) {
326       if ( intList.deleteNode( value, deletedValue ) ) {
327          cout << deletedValue << " was deleted from the list\n";
328          intList.print();
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      }
      else
         cout << "Element was not found";

      cout << "Enter an integer to delete (-1 to end): ";
      cin >> value;
   }

   return 0;
}
```

```
The list is: 0 3 20 35 39 51 61 62 64 82

Enter an integer to delete (-1 to end): 8
Element was not foundEnter an integer to delete (-1 to end): 82
82 was deleted from the list
The list is: 0 3 20 35 39 51 61 62 64

Enter an integer to delete (-1 to end): -1
Destroying nodes ...
0 3 20 35 39 51 61 62 64
All nodes destroyed
```

15.32 *(List and Queues without Tail Pointers)* Our implementation of a linked list (Fig. 15.3) used both a **firstPtr** and a **lastPtr**. The **lastPtr** was useful for the **insertAtBack** and **removeFromBack** member functions of the **List** class. The **insertAtBack** function corresponds to the **enqueue** member function of the **Queue** class. Rewrite the **List** class so that it does not use a **lastPtr**. Thus, any operations on the tail of a list must begin searching the list from the front. Does this affect our implementation of the **Queue** class (Fig. 15.12)?

15.33 Use the composition version of the stack program (Fig. 15.11) to form a complete working stack program. Modify this program to **inline** the member functions. Compare the two approaches. Summarize the advantages and disadvantages of inlining member functions.

15.34 *(Performance of Binary Tree Sorting and Searching)* One problem with the binary tree sort is that the order in which the data are inserted affects the shape of the tree—for the same collection of data, different orderings can yield binary trees of dramatically different shapes. The performance of the binary tree sorting and searching algorithms is sensitive to the shape of the binary tree. What shape would a binary tree have if its data were inserted in increasing order? in decreasing order? What shape should the tree have to achieve maximal searching performance?

15.35 *(Indexed Lists)* As presented in the text, linked lists must be searched sequentially. For large lists, this can result in poor performance. A common technique for improving list searching performance is to create and maintain an index to the list. An index is a set of pointers to various key places in the list. For example, an application that searches a large list of names could improve performance by creating an index with 26 entries—one for each letter of the alphabet. A search operation for a last name beginning with 'Y' would then first search the index to determine where the 'Y' entries begin, and then "jump into" the list at that point and search linearly until the desired name is found. This would be much faster than searching the linked list from the beginning. Use the **List** class of Fig. 15.3 as the basis of an **IndexedList** class. Write a program that demonstrates the operation of indexed lists. Be sure to include member functions **insertInIndexedList**, **searchIndexedList** and **deleteFromIndexedList**.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

16

Bits, Characters, Strings and Structures Solutions

Solutions

16.6 Provide the definition for each of the following structures and unions:

a) Structure **Inventory** containing character array **partName[30]**, integer **partNumber**, floating-point **price**, integer **stock** and integer **reorder**.

ANS:

```
struct Inventory {
   char partName[ 30 ];
   int partNumber;
   double price;
   int stock;
   int reorder;
};
```

b) A structure called **Address** that contains character arrays **streetAddress[25]**, **city[20]**, **state[3]** and **zipCode[6]**.

ANS:

```
struct Address {
   char streetAddress[ 25 ];
   char city[ 20 ];
   char state[ 3 ];
   char zipCode[ 6 ];
};
```

c) Structure **Student** that contains arrays **firstName[15]** and **lastName[15]**, and variable **homeAddress** of type **struct Address** from part (b).

ANS:

```
struct Student {
   char firstName[ 15 ];
   char lastName[ 15 ];
   struct Address homeAddress;
};
```

d) Structure **Test** containing 16 bit fields with widths of 1 bit. The names of the bit fields are the letters **a** to **p**.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS:

```
struct Test {
   unsigned a:1, b:1, c:1, d:1, e:1, f:1, g:1, h:1,
            i:1, j:1, k:1, l:1, m:1, n:1, o:1, p:1;
};
```

16.7 Consider the following structure definitions and variable declarations,

```
struct Customer {
   char lastName[ 15 ];
   char firstName[ 15 ];
   int customerNumber;

   struct {
      char phoneNumber[ 11 ];
      char address[ 50 ];
      char city[ 15 ];
      char state[ 3 ];
      char zipCode[ 6 ];
   } personal;
} customerRecord, *customerPtr;

customerPtr = &customerRecord;
```

Write a separate expression that accesses the structure members in each of the following parts:

a) Member **lastName** of structure **customerRecord**.
ANS: customerRecord.lastName
b) Member **lastName** of the structure pointed to by **customerPtr**.
ANS: customerPtr->lastName
c) Member **firstName** of structure **customerRecord**.
ANS: customerRecord.firstName
d) Member **firstName** of the structure pointed to by **customerPtr**.
ANS: customerPtr->firstName
e) Member **customerNumber** of structure **customerRecord**.
ANS: customerRecord.customerNumber
f) Member **customerNumber** of the structure pointed to by **customerPtr**.
ANS: customerPtr->customerNumber
g) Member **phoneNumber** of member **personal** of structure **customerRecord**.
ANS: customerRecord.personal.phoneNumber
h) Member **phoneNumber** of member **personal** of the structure pointed to by **customerPtr**.
ANS: customerPtr->personal.phoneNumber
i) Member **address** of member **personal** of structure **customerRecord**.
ANS: customerRecord.personal.address
j) Member **address** of member **personal** of the structure pointed to by **customerPtr**.
ANS: customerPtr->personal.address
k) Member **city** of member **personal** of structure **customerRecord**.
ANS: customerRecord.personal.city
l) Member **city** of member **personal** of the structure pointed to by **customerPtr**.
ANS: customerPtr->personal.city
m) Member **state** of member **personal** of structure **customerRecord.**
ANS: customerRecord.personal.state
n) Member **state** of member **personal** of the structure pointed to by **customerPtr**.
ANS: customerPtr->personal.state
o) Member **zipCode** of member **personal** of structure **customerRecord**.
ANS: customerRecord.personal.zipCode
p) Member **zipCode** of member **personal** of the structure pointed to by **customerPtr**.
ANS: customerPtr->personal.zipCode

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

16.8 Modify the program of Fig. 16.14 to shuffle the cards using a high-performance shuffle as shown in Fig. 16.2. Print the resulting deck in two column format as in Fig. 16.3. Precede each card with its color.

```
// Exercise 16.8 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

#include <cstdlib>
#include <ctime>

struct bitCard {
   unsigned face : 4;
   unsigned suit : 2;
   unsigned color : 1;
};

typedef struct bitCard Card;

void fillDeck( Card * const );
void shuffle( Card * const );
void deal( const Card * const );

int main()
{
   Card deck[ 52 ];

   srand( 0 );

   fillDeck( deck );
   shuffle( deck );
   deal( deck );

   return 0;
}

void fillDeck( Card * const wDeck )
{
   for ( int i = 0; i < 52; ++i ) {
      wDeck[ i ].face = i % 13;
      wDeck[ i ].suit = i / 13;
      wDeck[ i ].color = i / 26;
   }
}

void shuffle( Card * const wDeck )
{
   int j;
   Card temp;

   for ( int i = 0; i < 52; ++i ) {
      j = rand() % 52;

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      temp = wDeck[ i ];
      wDeck[ i ] = wDeck[ j ];
      wDeck[ j ] = temp;
   }
}

void deal( const Card * const wDeck2 )
{
   char *face[] = { "Ace", "Deuce", "Three", "Four", "Five", "Six", "Seven",
                    "Eight", "Nine", "Ten", "Jack", "Queen", "King" },
        *suit[] = { "Hearts", "Diamonds", "Clubs", "Spades" },
        *color[] = { "Red", "Black" };

   for ( int i = 0; i < 52; ++i ) {

      cout << setw( 5 ) << color[ wDeck2[ i ].color ] << ": "
           << setw( 8 ) << face[ wDeck2[ i ].face ] << " of "
           << setiosflags( ios::left ) << setw( 8 )
           << suit[ wDeck2[ i ].suit ] << resetiosflags( ios::left );

      cout.put( ( i + 1 ) % 2 ? '\t' : '\n' );
   }
}
```

```
Black:     King of Clubs        Black:    Three of Clubs
Black:     Five of Clubs          Red:      Ten of Hearts
Black:    Deuce of Clubs          Red:     Four of Hearts
  Red:      Six of Hearts       Black:     Nine of Clubs
Black:    Seven of Clubs          Red:     Five of Hearts
Black:    Deuce of Spades         Red:    Eight of Diamonds
  Red:     Nine of Hearts         Red:     Nine of Diamonds
Black:    Three of Spades       Black:     Nine of Spades
  Red:    Seven of Diamonds       Red:     King of Diamonds
Black:      Six of Clubs          Red:     Jack of Diamonds
  Red:    Queen of Hearts       Black:      Ten of Clubs
  Red:    Deuce of Hearts         Red:      Six of Diamonds
Black:     Five of Spades       Black:     Four of Clubs
Black:     Jack of Clubs          Red:    Three of Diamonds
  Red:     Jack of Hearts         Red:      Ace of Hearts
  Red:      Ten of Diamonds     Black:    Eight of Clubs
Black:    Queen of Spades       Black:      Six of Spades
  Red:    Seven of Hearts       Black:      Ace of Spades
Black:    Seven of Spades         Red:     King of Hearts
Black:      Ten of Spades       Black:     Four of Spades
  Red:    Queen of Diamonds     Black:     Jack of Spades
Black:      Ace of Clubs        Black:     King of Spades
Black:    Eight of Spades       Black:    Queen of Clubs
  Red:    Eight of Hearts         Red:      Ace of Diamonds
  Red:     Four of Diamonds       Red:    Three of Hearts
  Red:     Five of Diamonds       Red:    Deuce of Diamonds
```

16.9 Write a program that right shifts an integer variable 4 bits. The program should print the integer in bits before and after the shift operation. Does your system place zeros or ones in the vacated bits?

```
// Exercise 16.9 Solution
#include <iostream>

using std::cout;
using std::endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;
using std::resetiosflags;

void displayBits( unsigned );

int main()
{
   unsigned val;

   cout << "Enter an integer: ";
   cin >> val;

   cout << "Before right shifting 4 bits is:\n";
   displayBits( val );
   cout << "After right shifting 4 bits is:\n";
   displayBits( val >> 4 );

   return 0;
}

void displayBits( unsigned value )
{
   const int SHIFT = 8 * sizeof( unsigned ) - 1;
   const unsigned MASK = 1 << SHIFT;
   cout << setw( 7 ) << value << " = ";

   for ( unsigned c = 1; c <= SHIFT + 1; c++ ) {
      cout << ( value & MASK ? '1' : '0' );
      value <<= 1;

      if ( c % 8 == 0 )
      cout << ' ';
   }

   cout << endl;
}
```

```
Enter an integer: 888
Before right shifting 4 bits is:
    888 = 00000000 00000000 00000011 01111000
After right shifting 4 bits is:
     55 = 00000000 00000000 00000000 00110111
```

16.10 If your computer uses 4-byte integers, modify the program of Fig. 16.5 so that it works with 4-byte integers.

16.11 Left shifting an **unsigned** integer by 1 bit is equivalent to multiplying the value by 2. Write function **power2** that takes two integer arguments **number** and **pow** and calculates

$$\texttt{number} * 2^{\texttt{pow}}$$

Use a shift operator to calculate the result. The program should print the values as integers and as bits.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 16.11 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;

#include <iomanip>

using std::setw;
using std::setprecision;

void displayBits( unsigned );
unsigned power2( unsigned, unsigned );

int main()
{
   unsigned number, pow, result;

   cout << "Enter two integers: ";
   cin >> number >> pow;

   cout << "number:\n";
   displayBits( number );
   cout << "\npower:\n";
   displayBits( pow );
   result = power2( number, pow );
   cout << '\n' << number << " * 2^" << pow << " = " << result << '\n';
   displayBits( result );

   return 0;
}

unsigned power2( unsigned n, unsigned p )  { return n << p; }

void displayBits( unsigned value )
{
   const int SHIFT = 8 * sizeof( unsigned ) - 1;
   const unsigned MASK = 1 << SHIFT;
   cout << setw( 7 ) << value << " = ";

   for ( unsigned c = 1; c <= SHIFT + 1; c++ ) {
      cout << ( value & MASK ? '1' : '0' );
      value <<= 1;

      if ( c % 8 == 0 )
      cout << ' ';
   }

   cout << endl;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter an integer: 888
Before right shifting 4 bits is:
    888 = 00000000 00000000 00000011 01111000
After right shifting 4 bits is:
     55 = 00000000 00000000 00000000 00110111



Enter two integers: 3 4
number:
      3 = 00000000 00000000 00000000 00000011

power:
      4 = 00000000 00000000 00000000 00000100

3 * 2^4 = 48
     48 = 00000000 00000000 00000000 00110000
```

16.12 The left-shift operator can be used to pack two character values into a 2-byte unsigned integer variable. Write a program that inputs two characters from the keyboard and passes them to function **packCharacters**. To pack two characters into an **unsigned** integer variable, assign the first character to the **unsigned** variable, shift the **unsigned** variable left by 8 bit positions and combine the **unsigned** variable with the second character using the bitwise inclusive-OR operator. The program should output the characters in their bit format before and after they are packed into the **unsigned** integer to prove that the characters are in fact packed correctly in the **unsigned** variable.

```
1  // Exercise 16.12 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <iomanip>
10
11 using std::setw;
12
13 unsigned packCharacters( char, char );
14 void displayBits( unsigned );
15
16 int main()
17 {
18    char a, b;
19    unsigned result;
20
21    cout << "Enter two characters: ";
22    cin.setf( ios::skipws );
23    cin >> a >> b;
24
25    cout << '\'' << a << '\'' << " in bits as an unsigned integers is:\n";
26    displayBits( a );
27
28    cout << '\'' << b << '\'' << " in bits as an unsigned integers is:\n";
29    displayBits( b );
30
31    result = packCharacters( a, b );
32
33    cout << "\n\'" << a << '\'' << " and " << '\'' << b << '\''
34         << " packed in an unsigned integer:\n";
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
35    displayBits( result );
36
37    return 0;
38 }
39
40 unsigned packCharacters( char x, char y )
41 {
42    unsigned pack = x;
43
44    pack <<= 8;
45    pack |= y;
46    return pack;
47 }
48
49 void displayBits( unsigned value )
50 {
51    const int SHIFT = 8 * sizeof( unsigned ) - 1;
52    const unsigned MASK = 1 << SHIFT;
53    cout << setw( 7 ) << value << " = ";
54
55    for ( unsigned c = 1; c <= SHIFT + 1; c++ ) {
56       cout << ( value & MASK ? '1' : '0' );
57       value <<= 1;
58
59       if ( c % 8 == 0 )
60       cout << ' ';
61    }
62
63    cout << endl;
64 }
```

```
Enter two characters: T N
'T' in bits as an unsigned integers is:
     84 = 00000000 00000000 00000000 01010100
'N' in bits as an unsigned integers is:
     78 = 00000000 00000000 00000000 01001110

'T' and 'N' packed in an unsigned integer:
  21582 = 00000000 00000000 01010100 01001110
```

16.13 Using the right-shift operator, the bitwise AND operator and a mask, write function **unpackCharacters** that takes the **unsigned** integer from Exercise 16.12 and unpacks it into two characters. To unpack two characters from an **unsigned** 2-byte integer, combine the unsigned integer with the mask **65280** (**11111111 00000000**) and right shift the result 8 bits. Assign the resulting value to a **char** variable. Then, combine the **unsigned** integer with the mask **255** (**00000000 11111111**). Assign the result to another **char** variable. The program should print the **unsigned** integer in bits before it is unpacked, and then print the characters in bits to confirm that they were unpacked correctly.

```
1  // Exercise 16.13 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6
7  #include <iomanip>
8
9  using std::setw;
10
11 void unpackCharacters( char * const, char * const, unsigned );
12 void displayBits( unsigned );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
13
14 int main()
15 {
16    char a, b;
17    unsigned packed = 16706;
18
19    cout << "The packed character representation is:\n";
20    displayBits( packed );
21    unpackCharacters( &a, &b, packed );
22    cout << "\nThe unpacked characters are \'" << a << "\' and \'" << b
23         << "\'\n";
24    displayBits( a );
25    displayBits( b );
26
27    return 0;
28 }
29
30 void unpackCharacters( char * const aPtr, char * const bPtr, unsigned pack )
31 {
32    unsigned mask1 = 65280, mask2 = 255;
33
34    *aPtr = static_cast< char >( ( pack & mask1 ) >> 8 );
35    *bPtr = static_cast< char >( pack & mask2 );
36 }
37
38 void displayBits( unsigned value )
39 {
40    const int SHIFT = 8 * sizeof( unsigned ) - 1;
41    const unsigned MASK = 1 << SHIFT;
42    cout << setw( 7 ) << value << " = ";
43
44    for ( unsigned c = 1; c <= SHIFT + 1; c++ ) {
45       cout << ( value & MASK ? '1' : '0' );
46       value <<= 1;
47
48       if ( c % 8 == 0 )
49          cout << ' ';
50    }
51
52    cout << endl;
53 }
```

```
The packed character representation is:
  16706 = 00000000 00000000 01000001 01000010

The unpacked characters are 'A' and 'B'
     65 = 00000000 00000000 00000000 01000001
     66 = 00000000 00000000 00000000 01000010
```

16.14 If your system uses 4-byte integers, rewrite the program of Exercise 16.12 to pack 4 characters.

16.15 If your system uses 4-byte integers, rewrite the function **unpackCharacters** of Exercise 16.13 to unpack 4 characters. Create the masks you need to unpack the 4 characters by left shifting the value 255 in the mask variable by 8 bits 0, 1, 2 or 3 times (depending on the byte you are unpacking).

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

16.16 Write a program that reverses the order of the bits in an **unsigned** integer value. The program should input the value from the user and call function **reverseBits** to print the bits in reverse order. Print the value in bits both before and after the bits are reversed to confirm that the bits are reversed properly.

```
// Exercise 16.16 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;

void reverseBits( unsigned * const );
void displayBits( unsigned );

int main()
{
   unsigned a;

   cout << "Enter an unsigned integer: ";
   cin >> a;

   cout << "\nBefore bits are reversed:\n";
   displayBits( a );
   reverseBits( &a );
   cout << "\nAfter bits are reversed:\n";
   displayBits( a );

   return 0;
}

void reverseBits( unsigned * const vPtr )
{
   const int SHIFT = 8 * sizeof( unsigned ) - 1;
   const unsigned MASK = 1;
   unsigned value = *vPtr;

   for ( int i = 0; i <= 15; ++i ) {
      *vPtr <<= 1;
      *vPtr |= ( value & MASK );
      value >>= 1;
   }
}
void displayBits( unsigned value )
{
   const int SHIFT = 8 * sizeof( unsigned ) - 1;
   const unsigned MASK = 1 << SHIFT;
   cout << setw( 7 ) << value << " = ";

   for ( unsigned c = 1; c <= SHIFT + 1; c++ ) {
      cout << ( value & MASK ? '1' : '0' );
      value <<= 1;

      if ( c % 8 == 0 )
         cout << ' ';
   }

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
58      cout << endl;
59   }
```

```
Enter an unsigned integer: 330

Before bits are reversed:
    330 = 00000000 00000000 00000001 01001010

After bits are reversed:
21648000 = 00000001 01001010 01010010 10000000
```

16.17 Write a program that demonstrates passing an array by value. (Hint: use a **struct**). Prove that a copy was passed by modifying the array copy in the called function.

16.18 Write a program that inputs a character from the keyboard and tests the character with each of the functions in the character handling library. The program should print the value returned by each function.

```
1   // Exercise 16.18 Solution
2   #include <iostream>
3
4   using std::cout;
5   using std::endl;
6   using std::cin;
7
8   #include <cctype>
9
10  int main()
11  {
12     char c;
13
14     cout << "Enter a character: ";
15     c = static_cast< char >( cin.get() );
16
17     cout << "isdigit(\'" << c << "\')  = " << isdigit( c )
18          << "\nisalpha(\'" << c << "\')  = " << isalpha( c )
19          << "\nisalnum(\'" << c << "\')  = " << isalnum( c );
20
21     cout << "\nisxdigit(\'" << c << "\') = " << isxdigit( c )
22          << "\nislower(\'" << c << "\')  = " << islower( c )
23          << "\nisupper(\'" << c << "\')  = " << isupper( c )
24          << "\ntolower(\'" << c << "\')  = " << tolower( c )
25          << "\ntoupper(\'" << c << "\')  = " << toupper( c )
26          << "\nisspace(\'" << c << "\')  = " << isspace( c );
27
28     cout << "\niscntrl(\'" << c << "\')  = " << iscntrl( c )
29          << "\nispunct(\'" << c << "\')  = " << ispunct( c )
30          << "\nisprint(\'" << c << "\')  = " << isprint( c )
31          << "\nisgraph(\'" << c << "\')  = " << isgraph( c ) << endl;
32
33     return 0;
34  }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter a character: ~
isdigit('~')  = 0
isalpha('~')  = 0
isalnum('~')  = 0
isxdigit('~') = 0
islower('~')  = 0
isupper('~')  = 0
tolower('~')  = 126
toupper('~')  = 126
isspace('~')  = 0
iscntrl('~')  = 0
ispunct('~')  = 16
isprint('~')  = 16
isgraph('~')  = 16
```

16.19 The following program uses function **multiple** to determine if the integer entered from the keyboard is a multiple of some integer **X**. Examine function **multiple**, and then determine the value of **X**.

```
1  // ex16_19.cpp
2  // This program determines if a value is a multiple of X
3  #include <iostream>
4
5  using std::cout;
6  using std::cin;
7  using std::endl;
8
9  bool multiple( int );
10
11 int main()
12 {
13    int y;
14
15    cout << "Enter an integer between 1 and 32000: ";
16    cin >> y;
17
18    if ( multiple( y ) )
19       cout << y << " is a multiple of X" << endl;
20    else
21       cout << y << " is not a multiple of X" << endl;
22
23    return 0;
24 }
25
26 bool multiple( int num )
27 {
28    bool mult = true;
29
30    for ( int i = 0, mask = 1; i < 10; i++, mask <<= 1 )
31       if ( ( num & mask ) != 0 ) {
32          mult = false;
33          break;
34       }
35
36    return mult;
37 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS: Determines if the number input is a multiple of X. The value of X is 1024.

16.20 What does the following program do?

```
// ex16_20.cpp
#include <iostream>

using std::cout;
using std::cin;
using std::endl;

int mystery( unsigned );

int main()
{
   unsigned x;

   cout << "Enter an integer: ";
   cin >> x;
   cout << "The result is " << mystery( x ) << endl;

   return 0;
}

int mystery( unsigned bits )
{
   const int SHIFT = 8 * sizeof( unsigned ) - 1;
   const unsigned MASK = 1 << SHIFT;
   unsigned total = 0;

   for ( int i = 0; i < SHIFT + 1; i++, bits <<= 1 )
      if ( ( bits & MASK ) == MASK )
         ++total;

   return !( total % 2 );
}
```

ANS: The program prints **0** if the total number of 1s in the bit representation is odd, and prints a **1** if the number of bits is even.

16.21 Write a program that inputs a line of text with **istream**member function **getline** (see Chapter 11) into character array **s[100]**. Output the line in uppercase letters and lowercase letters.

```
// Exercise 16.21 Solution
#include <iostream>

using std::cout;
using std::cin;

#include <cctype>

const int SIZE = 100;

int main()
{
   char s[ SIZE ];
   int i;

   cout << "Enter a line of text:\n";
   cin.getline( s, SIZE );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
18
19     cout << "\nThe line in uppercase is:\n";
20
21     for ( i = 0; s[ i ] != '\0'; ++i )
22        cout.put( static_cast< char >( toupper( s[ i ] ) ) );
23
24     cout << "\n\nThe line in lowercase is:\n";
25
26     for ( i = 0; s[ i ] != '\0'; ++i )
27        cout.put( static_cast< char >( tolower( s[ i ] ) ) );
28
29     return 0;
30  }
```

```
Enter a line of text:
CPPHTP2 Instructor's Manual

The line in uppercase is:
CPPHTP2 INSTRUCTOR'S MANUAL

The line in lowercase is:
cpphtp2 instructor's manual
```

16.22 Write a program that inputs four strings that represent integers, converts the strings to integers sums the values, and prints the total of the four values.

```
1  // Exercise 16.22 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <cstdlib>
9
10 const int SIZE = 6;
11
12 int main()
13 {
14    char stringValue[ SIZE ];
15    int sum = 0;
16
17    for ( int i = 1; i <= 4; ++i ) {
18       cout << "Enter an integer string: ";
19       cin >> stringValue;
20       sum += atoi( stringValue );
21    }
22
23    cout << "The total of the values is " << sum << endl;
24
25    return 0;
26 }
```

```
Enter an integer string: 11
Enter an integer string: 22
Enter an integer string: 44
Enter an integer string: 88
The total of the values is 165
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

16.23 Write a program that inputs four strings that represent floating-point values, converts the strings to double values, sums the values and prints the total of the four values.

```
// Exercise 16.23 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;

#include <cstdlib>

const int SIZE = 15;

int main()
{
   char stringValue[ SIZE ];
   double sum = 0.0;

   for ( int i = 1; i <= 4; ++i ) {
      cout << "Enter a double point string: ";
      cin >> stringValue;
      sum += atof( stringValue );
   }

   cout.setf( ios::fixed | ios::showpoint );
   cout << "\nThe total of the values is " << setprecision( 3 ) << sum
        << endl;

   return 0;
}
```

```
Enter a double point string: 1.1
Enter a double point string: 1.2
Enter a double point string: 1.3
Enter a double point string: 1.4

The total of the values is 5.000
```

16.24 Write a program that inputs a line of text and a search string from the keyboard. Using function **strstr**, locate the first occurrence of the search string in the line of text, and assign the location to variable **searchPtr** of type **char ***. If the search string is found, print the remainder of the line of text beginning with the search string. Then, use **strstr** again to locate the next occurrence of the search string in the line of text. If a second occurrence is found, print the remainder of the line of text beginning with the second occurrence. (Hint: The second call to **strstr** should contain the expression **searchPtr + 1** as its first argument.)

```
// Exercise 16.24 Solution
#include <iostream>

using std::cout;
using std::cin;

#include <cstring>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 8
 9  const int SIZE1 = 80, SIZE2 = 15;
10
11  int main()
12  {
13     char text[ SIZE1 ], search[ SIZE2 ], *searchPtr;
14
15     cout << "Enter a line of text:\n";
16     cin.get( text, SIZE1 );
17     cout << "Enter a search string: ";
18     cin >> search;
19     searchPtr = strstr( text, search );
20
21     if ( searchPtr ) {
22        cout << "\nThe remainder of the line beginning with\n"
23             << "the first occurrence of\n\"" << search << "\":\n"
24             << searchPtr << '\n';
25
26        searchPtr = strstr( searchPtr + 1, search );
27
28        if ( searchPtr )
29           cout << "\nThe remainder of the line beginning with"
30                << "\nthe second occurrence of\n\"" << search << "\":\n"
31                << searchPtr << '\n';
32        else
33           cout << "The search string appeared only once.\n";
34     }
35     else
36        cout << "\"" << search << "\" not found.\n";
37
38     return 0;
39  }
```

```
Enter a line of text:
alphabet soup tastes good
Enter a search string: be

The remainder of the line beginning with
the first occurrence of
"be":
bet soup tastes good
The search string appeared only once.
```

16.25 Write a program based on the program of Exercise 16.24 that inputs several lines of text and a search string, and uses function **strstr** to determine the total number of occurrences of the string in the lines of text. Print the result.

```
 1  // Exercise 16.25 Solution
 2  #include <iostream>
 3
 4  using std::cout;
 5  using std::endl;
 6  using std::cin;
 7
 8  #include <iomanip>
 9
10  using std::setw;
11  using std::setprecision;
12  using std::setiosflags;
13  using std::resetiosflags;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
14
15  #include <cstring>
16  #include <cctype>
17
18  const int SIZE1 = 80, SIZE2 = 20;
19
20  int main()
21  {
22     char text[ 3 ][ SIZE1 ], search[ SIZE2 ], *searchPtr;
23     int count = 0, i;
24
25     cout << "Enter three lines of text:\n";
26
27     for ( i = 0; i <= 2; ++i )
28        cin.getline( &text[ i ][ 0 ], SIZE1 );
29
30     // make all characters lowercase
31     for ( i = 0; i <= 2; ++i )
32        for ( int j = 0; text[ i ][ j ] != '\0'; ++j ) {
33           char c = static_cast< char >( tolower( text[ i ][ j ] ) );
34           text[ i ][ j ] = c;
35        }
36
37     cout << "\nEnter a search string: ";
38     cin >> search;
39
40     for ( i = 0; i <= 2; ++i ) {
41        searchPtr = &text[ i ][ 0 ];
42
43        while ( searchPtr = strstr( searchPtr, search ) ) {
44           ++count;
45           ++searchPtr;
46        }
47     }
48
49     cout << "\nThe total occurrences of \"" << search
50          << "\" in the text is:" << setw( 3 ) << count << endl;
51
52     return 0;
53  }
```

```
Enter three lines of text:
first line of text
second line of text
third line of text

Enter a search string: in

The total occurrences of "in" in the text is:  3
```

16.26 Write a program that inputs several lines of text and a search character and uses function **strchr** to determine the total number of occurrences of the character in the lines of text.

```
1  // Exercise 16.26 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
 7
 8  #include <iomanip>
 9
10  using std::setw;
11
12  #include <cstring>
13  #include <cctype>
14
15  const int SIZE = 80;
16
17  int main()
18  {
19     char text[ 3 ][ SIZE ], search, *searchPtr;
20     int count = 0, i;
21
22     cout << "Enter three lines of text:\n";
23
24     for ( i = 0; i <= 2; ++i )
25        cin.getline( &text[ i ][ 0 ], SIZE );
26
27     // convert all letters to lowercase
28     for ( i = 0; i <= 2; ++i )
29        for ( int j = 0; text[ i ][ j ] != '\0'; ++j ) {
30           char c = static_cast< char >( tolower( text[ i ][ j ] ) );
31           text[ i ][ j ] = c;
32        }
33
34     cout << "\nEnter a search character: ";
35     cin >> search;
36
37     for ( i = 0; i <= 2; ++i ) {
38        searchPtr = &text[ i ][ 0 ];
39
40        while ( searchPtr = strchr( searchPtr, search ) ) {
41           ++count;
42           ++searchPtr;
43        }
44     }
45
46     cout << "The total occurrences of \'" << search << "\' in the text is:"
47          << setw( 3 ) << count << endl;
48
49     return 0;
50  }
```

```
Enter three lines of text:
one line of text
two lines of text
three lines of text

Enter a search character: e
The total occurrences of 'e' in the text is:  9
```

16.27 Write a program based on the program of Exercise 16.26 that inputs several lines of text and uses function **strchr** to determine the total number of occurrences of each letter of the alphabet in the text. Uppercase and lowercase letters should be counted together. Store the totals for each letter in an array, and print the values in tabular format after the totals have been determined.

```
1  // Exercise 16.27 Solution
2  #include <iostream>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  #include <iomanip>
9
10 using std::setw;
11
12 #include <cstring>
13 #include <cctype>
14
15 const int SIZE1 = 80, SIZE2 = 26;
16
17 int main()
18 {
19    char text[ 3 ][ SIZE1 ], *searchPtr;
20    int characters[ SIZE2 ] = { 0 }, count = 0;
21
22    cout << "Enter three lines of text:\n";
23
24    for ( int i = 0; i <= 2; ++i )
25       cin.getline( &text[ i ][ 0 ], SIZE1 );
26
27    // convert letters to lowercase
28    for ( int k = 0; k <= 2; ++k )
29       for ( int j = 0; text[ k ][ j ] != '\0'; ++j ) {
30          char c = static_cast< char >( tolower( text[ k ][ j ] ) );
31          text[ k ][ j ] = c;
32       }
33
34    for ( int q = 0; q < SIZE2; ++q ) {
35       count = 0;
36
37       for ( int j = 0; j <= 2; ++j ) {
38          searchPtr = &text[ j ][ 0 ];
39
40          while ( searchPtr = strchr( searchPtr, 'a' + q ) ) {
41             ++count;
42             ++searchPtr;
43          }
44       }
45
46       characters[ q ] = count;
47    }
48
49    cout << "\nThe total occurrences of each character:\n";
50
51    for ( int w = 0; w < SIZE2; ++w )
52       cout << setw( 3 ) << static_cast< char >( 'a' + w ) << ':' << setw( 3 )
53            << characters[ w ] << '\n';
54
55    return 0;
56 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter three lines of text:
The yak ran away
A giant parrot flew by
The cat pounced on the rat

The total occurrences of each character:
  a:  9
  b:  1
  c:  2
  d:  1
  e:  5
  f:  1
  g:  1
  h:  3
  i:  1
  j:  0
  k:  1
  l:  1
  m:  0
  n:  4
  o:  3
  p:  2
  q:  0
  r:  4
  s:  0
  t:  7
  u:  1
  v:  0
  w:  2
  x:  0
  y:  3
  z:  0
```

16.28 The chart in Appendix B shows the numeric code representations for the characters in the ASCII character set. Study this chart, and then state whether each of the following is *true* or *false*:

a) The letter "**A**" comes before the letter "**B**".
b) The digit "**9**" comes before the digit "**0**".
c) The commonly used symbols for addition, subtraction, multiplication and division all come before any of the digits.
d) The digits come before the letters.
e) If a sort program sorts strings into ascending sequence, then the program will place the symbol for a right parenthesis before the symbol for a left parenthesis.

```
1  // Exercise 16.28 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9
10 const int SIZE = 20;
11
12 int main()
13 {
14    char array[ 5 ][ SIZE ];
15    int i;
16
17    for ( i = 0; i <= 4; ++i ) {
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cout << "Enter a string: ";
      cin.getline( &array[ i ][ 0 ], SIZE );
   }

   cout << "The strings starting with 'b' are:\n";

   for ( i = 0; i <= 4; ++i )
      if ( array[ i ][ 0 ] == 'b' )
         cout << &array[ i ][ 0 ] << '\n';

   return 0;
}
```

```
Enter a string: c++
Enter a string: apple
Enter a string: burger
Enter a string: band
Enter a string: bag
The strings starting with 'b' are:
burger
band
bag
```

16.29 Write a program that reads a series of strings and prints only those strings beginning with the letter "**b**".

```
// Exercise 16.29 Solution
#include <iostream>

using std::cout;
using std::cin;


const int SIZE = 20;

int main()
{
   char array[ 5 ][ SIZE ];
   int i;

   for ( i = 0; i <= 4; ++i ) {
      cout << "Enter a string: ";
      cin.getline( &array[ i ][ 0 ], SIZE );
   }

   cout << "The strings starting with 'b' are:\n";

   for ( i = 0; i <= 4; ++i )
      if ( array[ i ][ 0 ] == 'b' )
         cout << &array[ i ][ 0 ] << '\n';

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Enter a string: MOVED
Enter a string: SAW
Enter a string: RAN
Enter a string: CARVED
Enter a string: PROVED

The strings ending with "ED" are:
MOVED
CARVED
PROVED
```

16.30 Write a program that reads a series of strings and prints only those strings that end with the letters "**ED**"Write a program that inputs an ASCII code and prints the corresponding character. Modify this program so that it generates all possible three-digit codes in the range 000 to 255 and attempts to print the corresponding characters. What happens when this program is runUsing the ASCII character chart in Appendix B as a guide, write your own versions of the character handling functions in Fig. 16.16.

```
1  // Exercise 16.30 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6
7  #include <cstring>
8
9  const int SIZE = 20;
10
11 int main()
12 {
13    int length, i;
14    char array[ 5 ][ SIZE ];
15
16    for ( i = 0; i <= 4; ++i ) {
17       cout << "Enter a string: ";
18       cin.getline( &array[ i ][ 0 ], SIZE );
19    }
20
21    cout << "\nThe strings ending with \"ED\" are:\n";
22
23    for ( i = 0; i <= 4; ++i ) {
24       length = strlen( &array[ i ][ 0 ] );
25
26       if ( strcmp( &array[ i ][ length - 2 ], "ED" ) == 0 )
27          cout << &array[ i ][ 0 ] << '\n';
28    }
29
30    return 0;
31 }
```

```
Enter an ASCII character code (EOF to end): 44
The corresponding character is ','

Enter an ASCII character code (EOF to end): 77
The corresponding character is 'M'

Enter an ASCII character code (EOF to end): 26
The corresponding character is '

...
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

16.31 Write your own versions of the functions in Fig. 16.20 for converting strings to numbers.

```
// Exercise 16.31 Solution
// NOTE: This solution is easily modified to print all
// possible three digit codes.
#include <iostream>

using std::cout;
using std::cin;


int main()
{
   int c;

   cout << "Enter an ASCII character code (EOF to end): ";
   cin >> c;

   while ( c != EOF ) {
      if ( c >= 0 && c <= 255 )
         cout << "The corresponding character is '"
              << static_cast< char > ( c ) << "\'\n";
      else
         cout << "Invalid character code\n";

      cout << "\nEnter an ASCII character code (EOF to end): ";
      cin >> c;
   }

   return 0;
}
```

```
Enter an ASCII character code (EOF to end): 44
The corresponding character is ','

Enter an ASCII character code (EOF to end): 77
The corresponding character is 'M'

Enter an ASCII character code (EOF to end): 26
The corresponding character is '

...
```

16.32 Write your own versions of the functions in Fig. 16.27 for searching strings.

```
// Exercise 16.32 Solution
#include <iostream>

using std::cout;
using std::cin;

int isDigit( int );
int isAlpha( int );
int isAlNum( int );
int isLower( int );
int isUpper( int );
int isSpace( int );
int isPunct( int );
int isPrint( int );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
15 int isGraph( int );
16 int toLower( int );
17 int toUpper( int );
18
19 int main()
20 {
21    int v;
22    char a, header[] = "According to",
23            *names[] = { "isDigit ", "isAlpha ", "isAlNum ",
24                         "isLower ", "isUpper ", "isSpace ",
25                         "isPunct ", "isPrint ", "isGraph ",
26                         "toLower ", "toUpper " },
27            *names2[] = { "digit", "letter", "letter/digit", "lowercase",
28                          "uppercase", "space", "punctuation", "print", "graph",
29                          "converted lowercase", "converted uppercase" };
30    int ( *f[] )( int ) = { isDigit, isAlpha, isAlNum, isLower,
31                            isUpper, isSpace, isPunct, isPrint,
32                            isGraph, toLower, toUpper };
33
34    cout << "Enter a character: ";
35    cin >> a;
36
37    for ( int k = 0; k < 11; ++k ) {
38       v = ( *f[ k ] )( static_cast< int >( a ) );
39       cout.write( header, 13 );
40       cout << names[ k ] << a << ( !v ? " is not a " : " is a " )
41            << names2[ k ] << " character\n";
42    }
43
44    return 0;
45 }
46
47 // Normally these would return bool, but int return type
48 // is consistent with the ctype library.
49 int isDigit( int c )
50 {
51    return ( c >= 48 && c <= 57 ) ? 1 : 0;
52 }
53
54 int isAlpha( int c )
55 {
56    return ( ( c >= 65 && c <= 90 ) || ( c >= 97 && c <= 122 ) ) ? 1 : 0;
57 }
58
59 int isAlNum( int c )
60 {
61    return ( isDigit( c ) == 1 || isAlpha( c ) == 1 ) ? 1 : 0;
62 }
63
64 int isLower( int c )
65 {
66    return ( c >= 97 && c <= 122 ) ? 1 : 0;
67 }
68
69 int isUpper( int c )
70 {
71    return ( c >= 65 && c <= 90 ) ? 1 : 0;
72 }
73
74 int isSpace( int c )
75 {
76    return ( ( c == 32 ) || ( c >= 9 && c <= 13 ) ) ? 1 : 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
77  }
78
79  int isPunct( int c )
80  {
81     return ( isAlNum( c ) == 0 && isSpace( c ) == 0 ) ? 1 : 0;
82  }
83
84  int isPrint( int c )
85  {
86     return ( c >= 32 && c <= 126 ) ? 1 : 0;
87  }
88
89  int isGraph( int c )
90  {
91     return ( c >= 33 && c <= 126 ) ? 1 : 0;
92  }
93
94  int toLower( int c )
95  {
96     return ( isUpper( c ) == 1 ) ? c + 32 : c;
97  }
98
99  int toUpper( int c )
100 {
101    return ( isLower( c ) == 1 ) ? c - 32 : c;
102 }
```

```
Enter a character: U
According to isDigit U is not a digit character
According to isAlpha U is a letter character
According to isAlNum U is a letter/digit character
According to isLower U is not a lowercase character
According to isUpper U is a uppercase character
According to isSpace U is not a space character
According to isPunct U is not a punctuation character
According to isPrint U is a print character
According to isGraph U is a graph character
According to toLower U is a converted lowercase character
According to toUpper U is a converted uppercase character
```

16.33 Write your own versions of the functions in Fig. 16.34 for manipulating blocks of memory.

16.34 *(Project: A Spelling Checker)* Many popular word-processing software packages have built-in spell checkers. We used spell-checking capabilities in preparing this book and discovered that no matter how careful we thought we were in writing a chapter, the software was always able to find a few more spelling errors than we were able to catch manually.

In this project, you are asked to develop your own spell-checker utility. We make suggestions to help get you started. You should then consider adding more capabilities. You may find it helpful to use a computerized dictionary as a source of words.

Why do we type so many words with incorrect spellings? In some cases, it is because we simply do not know the correct spelling, so we make a "best guess." In some cases, it is because we transpose two letters (e.g., "defualt" instead of "default"). Sometimes we double type a letter accidentally (e.g., "hanndy" instead of "handy"). Sometimes we type a nearby key instead of the one we intended (e.g., "biryhday" instead of "birthday"). And so on.

Design and implement a spell-checker program. Your program maintains an array **wordList** of character strings. You can either enter these strings or obtain them from a computerized dictionary.

Your program asks a user to enter a word. The program then looks up that word in the **wordList** array. If the word is present in the array, your program should print "**Word is spelled correctly.**"

If the word is not present in the array, your program should print "**Word is not spelled correctly.**" Then your program should try to locate other words in **wordList** that might be the word the user intended to type. For example, you can try all possible single transpositions of adjacent letters to discover that the word "default" is a direct match to a word in **wordList**.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Of course, this implies that your program will check all other single transpositions, such as "edfault," "dfeault," "deafult," "defalut" and "defautl." When you find a new word that matches one in **`wordList`**, print that word in a message such as "**`Did you mean "default?"`**."

Implement other tests such as replacing each double letter with a single letter and any other tests you can develop to improve the value of your spell checker.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

17

The Preprocessor Solutions

Solutions

17.4 Write a program that defines a macro with one argument to compute the volume of a sphere. The program should compute the volume for spheres of radius 1 to 10, and print the results in tabular format. The formula for the volume of a sphere is

$$(4.0 / 3) * \pi * r^3$$

where π is **3.14159**.

```
// Exercise 17.4 Solution
#include <iostream>

using std::cout;
using std::ios;


#include <iomanip>

using std::setw;
using std::setprecision;

#define PI 3.14159

// define macro for sphere volume
#define SPHEREVOLUME( r ) ( 4.0 / 3.0 * PI * ( r ) * ( r ) * ( r ) )

int main()
{
   // print header
   cout << setw( 10 ) << "Radius" << setw( 10 ) << "Volume\n";

   cout.setf( ios::fixed | ios::showpoint );
   for ( int i = 1; i <= 10; ++i )
      cout << setw( 10 ) << i << setw( 10 ) << setprecision( 3 )
           << SPHEREVOLUME( i ) << '\n';

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   return 0;
}
```

```
Radius   Volume
     1     4.189
     2    33.510
     3   113.097
     4   268.082
     5   523.598
     6   904.778
     7  1436.754
     8  2144.659
     9  3053.625
    10  4188.787
```

17.5 Write a program that produces the following output:

```
The sum of x and y is 13
```

The program should define macro **SUM** with two arguments, **x** and **y**, and use **SUM** to produce the output.

```
// Exercise 17.5 Solution
#include <iostream>

using std::cout;
using std::endl;

#define SUM( x, y ) ( ( x ) + ( y ) )

int main()
{
   cout << "The sum of 6 and 7 is " << SUM( 6, 7 ) << endl;
   return 0;
}
```

```
The sum of 6 and 7 is 13
```

17.6 Write a program that uses macro **MINIMUM2** to determine the smallest of two numeric values. Input the values from the keyboard.

```
// Exercise 17.6 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;

#define MINIMUM2( X, Y ) ( ( X ) < ( Y ) ? ( X ) : ( Y ) )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
15
16 int main()
17 {
18    int a, b;
19    double c, d;
20
21    cout << "Enter two integers: ";
22    cin >> a >> b;
23    cout << "The minimum of " << a << " and " << b << " is " << MINIMUM2( a, b )
24         << "\n\n";
25
26    cout << "Enter two doubles: ";
27    cin >> c >> d;
28
29    cout.setf( ios::fixed | ios::showpoint );
30    cout << "The minimum of " << setprecision( 2 ) << c << " and " << d
31         << " is " << MINIMUM2( c, d ) << '\n';
32
33    return 0;
34 }
```

```
Enter two integers: 8 22
The minimum of 8 and 22 is 8

Enter two doubles: 73.46 22.22
The minimum of 73.46 and 22.22 is 22.22
```

17.7 Write a program that uses macro **MINIMUM3** to determine the smallest of three numeric values. Macro **MINIMUM3** should use macro **MINIMUM2** defined in Exercise 17.6 to determine the smallest number. Input the values from the keyboard.

```
1  // Exercise 17.7 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <iomanip>
10
11 using std::setw;
12 using std::setprecision;
13
14 #define MINIMUM2( X, Y ) ( ( X ) < ( Y ) ? ( X ) : ( Y ) )
15 #define MINIMUM3( U, V, W ) ( MINIMUM2( W, MINIMUM2( U, V ) ) )
16
17 int main()
18 {
19    int a, b, c;
20    double d, e, f;
21
22    cout << "Enter three integers: ";
23    cin >> a >> b >> c;
24    cout << "The minimum of " << a << ", " << b << ", and " << c
25         << " is " << MINIMUM3( a, b, c ) << "\n\nEnter three doubles: ";
26
27    cin >> d >> e >> f;
28    cout.setf( ios::fixed | ios::showpoint );
29    cout << "The minimum of " << setprecision( 2 ) << d << ", "
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
         << e << ", and " << f << " is " << MINIMUM3( d, e, f ) << '\n';

   return 0;
}
```

```
Enter three integers: 44 2 55
The minimum of 44, 2, and 55 is 2

Enter three doubles: 9.5 7.3 3.22
The minimum of 9.50, 7.30, and 3.22 is 3.22
```

17.8 Write a program that uses macro **PRINT** to print a string value.

```
// Exercise 17.8 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#define PRINT( s ) cout << ( s )
#define SIZE 20

int main()
{
   char text[ SIZE ];

   PRINT( "Enter a string: " );
   cin >> text;

   PRINT( "The string entered was: " );
   PRINT( text );
   PRINT( endl );

   return 0;
}
```

```
Enter a string: HELLO
The string entered was: HELLO
```

17.9 Write a program that uses macro **PRINTARRAY** to print an array of integers. The macro should receive the array and the number of elements in the array as arguments.

```
// Exercise 17.9 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <iomanip>

using std::setw;

#define PRINTARRAY( A, N )  for ( int i = 0; i < ( N ); ++i ) \
                               cout << setw( 3 ) << A[ i ]
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```

#define SIZE 10

int main()
{
   int b[ SIZE ] = { 2, 4, 6, 8, 10, 12, 14, 16, 18, 20 };

   cout << "The array values are:\n";
   PRINTARRAY( b, SIZE );
   cout << endl;
   return 0;
}
```

```
The array values are:
 2  4  6  8 10 12 14 16 18 20
```

17.10 Write a program that uses macro **SUMARRAY** to sum the values in a numeric array. The macro should receive the array and the number of elements in the array as arguments.

```
// Exercise 17.10 Solution
#include <iostream>

using std::cout;
using std::endl;

#define SUMMARRAY( A, S )  for ( int c = 0; c < S; ++c )   \
                              sum += A[ c ];
#define SIZE 10

int main()
{
   int array[ SIZE ] = { 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 }, sum = 0;

   SUMMARRAY( array, SIZE );
   cout << "Sum is " << sum << endl;
   return 0;
}
```

```
Sum is 55
```

17.11 Rewrite the solutions to Exercises 17.4 to 17.10 as **inline** functions.

```
// Exercise 17.11 Solution
// NOTE: Exercises 17.9 and 17.10 cannot be
// expanded inline because they require the
// use of for repitition structures
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#define PI 3.14159

inline double sphereVolume( int r )
   { return 4.0 / 3.0 * PI * ( r ) * ( r ) * ( r ); }
inline int sum( int x, int y ) { return x + y; }
inline int minimum2( int x, int y ) { return x < y ? x : y; }
inline int minimum3( int x, int y, int z )
   { return minimum2( z, minimum2( x, y ) ); }
inline void print( char const * const cPtr ) { cout << cPtr; }

int main()
{
   // print header
   cout << "Function sphereVolume as an inline function:\n"
        << setw( 10 ) << "Radius" << setw( 10 ) << "Volume\n";

   cout.setf( ios::fixed | ios::showpoint );
   for ( int i = 1; i <= 10; ++i )
      cout << setw( 10 ) << i << setw( 10 ) << setprecision( 3 )
           << sphereVolume( i ) << '\n';

   int x = 6, y = 7;
   cout << "\nFunction sum as an inline function:\n"
        << "The sum of " << x << " and " << y << " is "
        << sum( 6, 7 ) << '\n';

   cout << "\nFunction minimum2 as an inline function:\n"
        << "The minimum of " << x << " and " << y << " is "
        << minimum2( x, y ) << '\n';

   int z = 4;
   cout << "\nFunction minimum3 as an inline function:\n"
        << "The minimum of " << x << ", " << y << " and " << z << " is "
        << minimum3( x, y, z ) << '\n';

   char s[] = "string...";
   cout << "\nFunction print as an inline function:\n"
        << "The output of print is: ";
   print( s );
   cout << endl;

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Function sphereVolume as an inline function:
   Radius    Volume
        1     4.189
        2    33.510
        3   113.097
        4   268.082
        5   523.598
        6   904.778
        7  1436.754
        8  2144.659
        9  3053.625
       10  4188.787

Function sum as an inline function:
The sum of 6 and 7 is 13

Function minimum2 as an inline function:
The minimum of 6 and 7 is 6

Function minimum3 as an inline function:
The minimum of 6, 7 and 4 is 4

Function print as an inline function:
The output of print is: string...
```

17.12 For each of the following macros, identify the possible problems (if any) when the preprocessor expands the macros:

a) `#define SQR( x ) x * x`

ANS: When `x` is an expression, such as `z - y`.

b) `#define SQR( x ) ( x * x )`

ANS: When `x` is an expression, such as `z - y`.

c) `#define SQR( x ) ( x ) * ( x )`

ANS: When `SQR( x )` is used in an expression such as `12 / SQR( 2 )`.

d) `#define SQR( x ) ( ( x ) * ( x ) )`

ANS: No problems.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

18

C Legacy Code Topics Solutions

Solutions

18.2 Write a program that calculates the product of a series of integers that are passed to function **product** using a variable-length argument list. Test your function with several calls, each with a different number of arguments.

```
// Exercise 18.2 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <cstdarg>

int sum( int, ... );

int main()
{
   int a = 1, b = 2, c = 3, d = 4, e = 5;

   cout << "a = " << a << ", b = " << b << ", c = " << c << ", d = " << d
        << ", e = " << e << "\n\n";

   cout << "The sum of a and b is: " << sum( 2, a, b )
        << "\nThe sum of a, b, and c is: " << sum( 3, a, b, c )
        << "\nThe sum of a, b, c, and d is: " << sum( 4, a, b, c, d )
        << "\nThe sum of a, b, c, d, and e is: " << sum( 5, a, b, c, d, e )
        << endl;

   return 0;
}

int sum( int i, ... )
{
   int total = 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
32     va_list ap;
33
34     va_start( ap, i );
35
36     // calculate total
37     for ( int j = 1; j <= i; ++j )
38        total += va_arg( ap, int );
39
40     va_end( ap );
41     return total;
42  }
```

```
a = 1, b = 2, c = 3, d = 4, e = 5

The sum of a and b is: 3
The sum of a, b, and c is: 6
The sum of a, b, c, and d is: 10
The sum of a, b, c, d, and e is: 15
```

18.3 Write a program that prints the command-line arguments of the program.

```
1  // Exercise 18.3 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7
8  using std::ios;
9
10 int main( int argc, char *argv[] )
11 {
12    cout << "The command line arguments are:\n";
13
14    for ( int i = 0; i < argc; ++i )
15       cout << argv[ i ] << ' ';
16
17    return 0;
18 }
```

```
c:\>p18_03.exe arg1 arg2 arg3
The command line arguments are:
p18_03.exe arg1 arg2 arg3
```

18.4 Write a program that sorts an integer array into ascending order or descending order. The program should use command-line arguments to pass either argument **-a** for ascending order or **-d** for descending order. (Note: This is the standard format for passing options to a program in UNIX.)

```
1  // Exercise 18.4 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::cin;
6
7  #include <iomanip>
8  using std::setw;
9
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
10  const int SIZE = 100;
11
12  void swap( int * const, int * const );
13
14  int main( int argc, char *argv[] )
15  {
16     int a[ SIZE ];
17     bool order;
18
19     if ( argc != 2 )
20        cout << "Usage: p18_4 -option\n";
21     else {
22        cout << "Enter up to " << SIZE << " integers (EOF to end input): ";
23
24        for ( int count = 0; !( cin.eof() ) && count < SIZE; ++count )
25           cin >> a[ count ];
26
27        // count is incremented before for loop continuation fails
28        --count;
29        order = ( argv[ 1 ][ 1 ] == 'd' ) ? true : false;
30
31        for ( int i = 1; i < count; ++i )
32           for ( int j = 0; j < count - 1; ++j )
33              if ( order ) {
34                 if ( a[ i ] > a[ j ] )
35                    swap( &a[ i ], &a[ j ] );
36              }
37              else if ( a[ i ] < a[ j ] )
38                 swap( &a[ j ], &a[ i ] );
39
40        cout << "\n\nThe sorted array is:\n";
41
42        for ( int j = 0; j < count; ++j )
43           cout << setw( 3 ) << a[ j ];
44
45        cout << '\n';
46     }
47
48     return 0;
49  }
50
51  void swap( int * const xPtr, int * const yPtr )
52  {
53     int temp;
54
55     temp = *xPtr;
56     *xPtr = *yPtr;
57     *yPtr = temp;
58  }
```

```
c:\>p18_04.exe -d
Enter up to 100 integers (EOF to end input): 77 2 -8 9 44 8 76 41 99
The sorted array is:
99 77 76 44 41  9  8  2 -8
```

18.5 Read the manuals for your system to determine what signals are supported by the signal-handling library (**csignal**). Write a program with signal handlers for the signals **SIGABRT** and **SIGINT**. The program should test the trapping of these signals by calling function **abort** to generate a signal of type **SIGABRT** and by pressing *Ctrl c* to generate a signal of type **SIGINT**.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

18.6 Write a program that dynamically allocates an array of integers. The size of the array should be input from the keyboard. The elements of the array should be assigned values input from the keyboard. Print the values of the array. Next, reallocate the memory for the array to half of the current number of elements. Print the values remaining in the array to confirm that they match the first half of the values in the original array.

```
// Exercise 18.6 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>
using std::setw;
using std::setprecision;
using std::setiosflags;

#include <cstdlib>

int main()
{
   int count, *array;

   cout << "This program dynamically allocates an array of integers."
        << "\nEnter the number of elements in the array: ";
   cin >> count;

   // allocate memory
   array = static_cast< int * >( calloc( count, sizeof( int ) ) );

   for ( int i = 0; i < count; ++i ) {
      cout << "Enter an integer: ";
      cin >> array[ i ];
   }

   cout << "\nThe elements of the array are:\n";

   for ( int j = 0; j < count; ++j )
      cout << setw( 3 ) << array[ j ];

   // reallocate to half the original size
   realloc( array, count / 2 * sizeof( int ) );
   cout << "\n\nThe elements of the array after reallocation are:\n";

   for ( int k = 0; k < count / 2; ++k )
      cout << setw( 3 ) << array[ k ];

   cout << '\n';

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
This program dynamically allocates an array of integers.
Enter the number of elements in the array: 5
Enter an integer: 1
Enter an integer: 2
Enter an integer: 3
Enter an integer: 4
Enter an integer: 5

The elements of the array are:
  1  2  3  4  5

The elements of the array after reallocation are:
  1  2
```

18.7 Write a program that takes two file names as command-line arguments, reads the characters from the first file one at a time and writes the characters in reverse order to the second file.

```
// Exercise 18.7 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;
using std::cerr;
using std::istream;
using std::ostream;

#include <fstream>

using std::ofstream;
using std::ifstream;

void reverseFile( istream&, ostream& );

int main( int argc, char *argv[] )
{
   ifstream inFile( argv[ 1 ], ios::in );
   ofstream outFile( argv[ 2 ], ios::out );

   if ( argc != 3 )
      cout << "Usage: copy infile outfile\n";
   else
      if ( inFile )
         if ( outFile )
            reverseFile( inFile, outFile );
         else
            cerr << "File \"" << argv[ 2 ] << "\" could not be opened\n";
      else
         cerr << "File \"" << argv[ 1 ] << "\" could not be opened\n";

   return 0;
}

void reverseFile( istream &in, ostream &out )
{
   int c;

   if ( ( c = in.get() ) != EOF )
      reverseFile( in, out );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   else
      return;  // do not write EOF character

   out.put( static_cast< char > ( c ) );
}
```

```
c:\>p18_07.exe test.txt copy.txt
```

18.8 Write a program that uses **goto** statements to simulate a nested looping structure that prints a square of asterisks as follows:

```
*****
*   *
*   *
*   *
*****
```

The program should use only the following three output statements:

```
cout << '*';
cout << ' ';
cout << endl;
```

```
// Exercise 18.8 Solution
#include <iostream>

using std::cout;
using std::cin;



int main()
{
   int size, row = 0, col;

   cout << "Enter the side length of the square: ";
   cin >> size;

   start:               // label
      ++row;
      cout << '\n';

      if ( row > size )
         goto end;

      col = 1;

      innerLoop:        // label
         if ( col > size )
            goto start;

         cout << ( row == 1 || row == size || col == 1 ||
                   col == size ? '*' : ' ' );

         ++col;
         goto innerLoop;

   end:                 // label
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
36
37       return 0;
38    }
```

```
Enter the side length of the square: 5

*****
*   *
*   *
*   *
*****
```

18.9 Provide the definition for **union Data** containing **char c**, **short s**, **long l**, **float f** and **double d**.

ANS:

```
union Data {
   char c;
   short s;
   long l;
   float f;
   double d;
};
```

18.10 Create **union Integer** with members **char c**, **short s**, **int i** and **long l**. Write a program that inputs values of type **char**, **short**, **int** and **long** and stores the values in **union** variables of type **union Integer**. Each **union** variable should be printed as a **char**, a **short**, an **int** and a **long**. Do the values always print correctly?

```
1  // Exercise 18.10 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  union Integer {
10    char c;
11    short s;
12    int i;
13    long l;
14 };
15
16 void printUnion( Integer );
17
18 int main()
19 {
20    Integer value;
21
22    cout << "Enter a character: ";
23    value.c = static_cast< char >( cin.get() );
24    printUnion( value );
25
26    cout << "Enter a short: ";
27    cin >> value.s;
28    printUnion( value );
29
30    cout << "Enter an int: ";
31    cin >> value.i;
32    printUnion( value );
33
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   cout << "Enter a long: ";
   cin >> value.l;
   printUnion( value );

   return 0;
}

void printUnion( Integer x )
{
    cout << "Current values in union Integer are:\n"
         << "char c  = " << x.c
         << "\nshort s = " << x.s
         << "\nint i   = " << x.i
         << "\nlong l  = " << x.l << "\n\n";
}
```

```
Enter a character: w
Current values in union Integer are:
char c  = w
short s = -13193
int i   = -858993545
long l  = -858993545

Enter a short: 5
Current values in union Integer are:
char c  = ?
short s = 5
int i   = -859045883
long l  = -859045883

Enter an int: 9999
Current values in union Integer are:
char c  = ¤
short s = 9999
int i   = 9999
long l  = 9999

Enter a long: 1000000
Current values in union Integer are:
char c  = @
short s = 16960
int i   = 1000000
long l  = 1000000
```

18.11 Create **union FloatingPoint** with members **float f**, **double d** and **long double l**. Write a program that inputs value of type **float**, **double** and **long double** and stores the values in **union** variables of type **union FloatingPoint**. Each **union** variable should be printed as a **float**, a **double** and a **long double**. Do the values always print correctly?

```
// Exercise 18.11 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

union FloatingPoint {
   float f;
   double d;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   long double l;
};

void printUnion( FloatingPoint );

int main()
{
   FloatingPoint value;

   cout << "Enter a float: ";
   cin >> value.f;
   printUnion( value );

   cout << "Enter a double: ";
   cin >> value.d;
   printUnion( value );

   cout << "Enter a long double: ";
   cin >> value.l;
   printUnion( value );

   return 0;
}

void printUnion( FloatingPoint x )
{
    cout << "Current values in union Integer are:\n"
         << "float f  = " << x.f
         << "\ndouble d = " << x.d
         << "\nlong double l  = " << x.l << "\n\n";
}
```

```
Enter a float: 4.567
Current values in union Integer are:
float f  = 4.567
double d = -9.25596e+061
long double l  = -9.25596e+061

Enter a double: 9998888.765
Current values in union Integer are:
float f  = 3.24255e-024
double d = 9.99889e+006
long double l  = 9.99889e+006

Enter a long double: 5e306
Current values in union Integer are:
float f  = 0.0210515
double d = 5e+306
long double l  = 5e+306
```

18.12 Given the **union**

```
union A {
   double y;
   char *z;
};
```

which of the following are correct statements for initializing the **union**?

a) **A p = B; // B is of same type as A**

ANS: Correct.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

b) `A q = x;  // x is a double`
ANS: Incorrect.
c) `A r = 3.14159;`
ANS: Incorrect.
d) `A s = { 79.63 };`
ANS: Correct.
e) `A t = { "Hi There!" };`
ANS: Incorrect.
f) `A u = { 3.14159, "Pi" };`
ANS: Incorrect.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

19

Class `string` and String Stream Processing Solutions

Solutions

19.4 Fill in the blanks in each of the following:

a) Functions _____, _____ and _____ convert **`string`**s to C-style strings.

ANS: **`data`**, **`c_str`**, **`copy`**

b) Function _____ is used for assignment.

ANS: **`assign`**

c) _____ is the return type of function **`rbegin`**.

ANS: **`string::reverse_iterator`**

d) Function _____ is used to retrieve a substring.

ANS: **`substr`**

19.5 State which of the following statements are true and which are false. If a statement is false, explain why.

a) **`string`**s are null terminated.

ANS: False. **`string`**s are not necessarily null terminated.

b) Function **`max_size`** returns the maximum size for a **`string`**.

ANS: True.

c) Function **`at`** is capable of throwing an **`out_of_range`** exception.

ANS: True.

d) Function **`begin`** returns an **`iterator`**.

ANS: True (**`string::iterator`** is more precise).

e) **`string`**s are passed by reference by default.

ANS: False. By default, **`string`**s are passed by value.

19.6 Find any error(s) in each of the following and explain how to correct it (them):

a)
```
std::cout << s.data() << std::endl;  // s is "hello"
```

ANS: The array returned by **`data`** is not null terminated.

b)
```
erase( s.rfind( "x" ), 1 );  // s is "xenon"
```

ANS: Function **`erase`** is a **`string`** class member function (i.e., **`erase`** must be called by an object of type **`string`**).

c)
```
string& foo( void )
{
   string s( "Hello" );
   ...   // other statements of function
   return;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS: A value is not being returned from the function (i.e., the **`return`** statement should be **`return s;`**). The **`return`** type should be **`string`** not **`string&`**.

19.7 (*Simple Encryption*) Some information on the Internet may be encrypted with a simple algorithm known as "rot13"—which rotates each character by 13 positions in the alphabet. Thus, **`'a'`** corresponds to **`'n'`**, and **`'x'`** corresponds to **`'k'`**. rot13 is an example of *symmetric key encryption*. With symmetric key encryption, both the encrypter and decrypter use the same key.

a) Write a program that encrypts a message using rot13.
b) Write a program that decrypts the scrambled message using 13 as the key.
c) After writing the programs of part (a) and part (b) briefly answer the following question: If you did not know the key for part (b), how difficult do you think it would be to break the code using any resources available? What if you had access to substantial computing power (e.g., Cray supercomputers)? In Exercise 19.27 we ask you to write a program to accomplish this.

```
// Execise 19.07 Part A Solution
// When solving Part B of this exercise, you
// might find it more convenient to only use
// uppercase letters for you input.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;
using std::getline;

int main()
{
   string m;
   int key = 13;  // Our key for encryption

   cout << "Enter a string:";
   getline( cin, m );

   string::iterator mi = m.begin();

   while ( mi != m.end() ) {
      *mi += key;
      ++mi;
   }

   cout << "\nEncypted string is:" << m << endl;

   return 0;
}
```

```
Enter a string:JAMES BOND IS 007
Encypted string is:WNZR`-O\[Q-V`-==D
```

```
// Execise 19.07 Part B Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
#include <string>
using std::string;
using std::getline;

int main()
{
   string m;
   int key = 13;  // Our key for decryption

   cout << "Enter encrypted string:";
   getline( cin, m );

   string::iterator mi = m.begin();

   while ( mi != m.end() ) {
      *mi -= key;
      ++mi;
   }

   cout << "\nDecypted string is:" << m << endl;

   return 0;
}
```

```
Enter encrypted string:WNZR`-O\[Q-V`-==D
Decypted string is:JAMES BOND IS 007
```

19.8 Write a program using iterators that demonstrates the use of functions **rbegin** and **rend**.

```
// Exercise 19.8 Solution
// Program demonstrates rend and rbegin.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;

int main()
{
   string s( "abcdefghijklmnopqrstuvwxyz" );
   string::reverse_iterator re = s.rend(),
                            rb = s.rbegin();

   cout << "Using rend() string is: ";
   while ( re >= s.rbegin() ) {
      cout << *re;
      --re;
   }

   cout << "\nUsing rbegin() string is: ";
   while ( rb != s.rend() ) {
      cout << *rb;
      ++rb;
   }

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   cout << endl;

   return 0;
}
```

```
Using rend() string is:  abcdefghijklmnopqrstuvwxyz
Using rbegin() string is: zyxwvutsrqponmlkjihgfedcba
```

19.9 Write your own versions of functions **data** and **c_str**.

19.10 Write a program that reads in several **string**s and prints only those ending in "**r**" or "**ay**". Only lowercase letters should be considered.

```
// Exercise 19.10 Solution
// Program determines if string ends in 'r'
// or "ay".
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;

int main()
{
   string s[ 5 ];

   for ( int i = 0; i < 5; ++i ) {
      cout << "Enter a word: ";
      cin >> s[ i ];
   }

   for ( int j = 0; j < 5; ++j ) {
      if ( ( ( s[ j ].rfind( "ay" ) == s[ j ].length() - 2 ) )
          || ( s[ j ].rfind( "r" ) == s[ j ].length() - 1 ) )
         cout << s[ j ] << endl;
   }

   return 0;
}
```

```
Enter a word: bicycle
Enter a word: car
Enter a word: tree
Enter a word: canary
Enter a word: iron
car
```

19.11 Write a program that demonstrates passing a **string** both by reference and by value.

```
// Exercise 19.11 Solution
// Program passes a string by value and
// passes a string by reference.
#include <iostream>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
5
6  using std::cout;
7  using std::endl;
8  using std::cin;
9  using std::ios;
10
11 #include <string>
12 using std::string;
13
14 void byValue( string );
15 void byReference( string& );
16
17 int main()
18 {
19    string s = "Standard C++ draft standard";
20
21    cout << "Original string: " << s;
22
23    byValue( s );
24    cout << "\nAfter calling byValue: " << s;
25
26    byReference( s );
27    cout << "\nAfter calling byReference: " << s << endl;
28
29    return 0;
30 }
31
32 void byValue( string s )
33 {
34    s.erase( 0, 4 );
35 }
36
37 void byReference( string& sRef )
38 {
39    sRef.erase( 0, 9 );
40 }
```

```
Original string: Standard C++ draft standard
After calling byValue: Standard C++ draft standard
After calling byReference: C++ draft standard
```

19.12 Write a program that separately inputs a first name and a last name and then concatenates the two into a new **string**.

```
1  // Exercise 19.12 Solution
2  // Program reads a first name and
3  // last name and concatenates the two.
4  #include <iostream>
5  using std::cout;
6  using std::endl;
7  using std::cin;
8  using std::ios;
9
10 #include <string>
11 using std::string;
12
13 #include <iomanip>
14
15 using std::setw;
16 using std::setprecision;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
using std::setiosflags;

int main()
{
   string first, last;

   cout << "Enter first name: ";
   cin >> first;

   cout << "Enter last name: ";
   cin >> last;

   first.append( " " ).append( last );
   cout << "The full name is: " << first << endl;

   return 0;
}
```

```
Enter first name: Hans
Enter last name: Gruber
The full name is: Hans Gruber
```

19.13 Write a program that plays the game of hangman. The program should pick a word (which is either coded directly into the program or read from a text file) and display the following:

```
Guess the word:    XXXXXX
```

Each **X** represents a letter. If the user guesses correctly, the program should display:

```
Congratulations!!! You guessed my word. Play again? yes/no
```

The appropriate response **yes** or **no** should be input. If the user guesses incorrectly, display the appropriate body part.

After seven incorrect guesses, the user should be hanged. The display should look like

```
  O
 /|\
  |
 / \
```

After each guess you want to display all their guesses.

```
// Exercise 19.13 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;

#include <cctype>

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
19
20 #include <cstdlib>
21
22 int main()
23 {
24    string response;  // "yes"/"no" input from user
25    int w = 0;        // index for current word
26    const int WORDS = 4;   // total number of words
27
28    do {
29       const char body[] = " o/|\\|/\\";  // body parts
30       string words[ WORDS ] = { "MACAW", "SADDLE",
31                                 "TOASTER", "XENOCIDE" };
32       string xword( words[ w ].length(), '?' ); // masked display
33       string::iterator i, ix = xword.begin();
34       char letters[ 26 ] = { '\0' };  // letters guessed
35       int n = 0, xcount = xword.length();
36       bool found = false, solved = false;
37       int offset = 0, bodyCount = 0;
38       bool hung = false;
39
40       // clear window; system is a stdlib function
41       system( "cls" );  // "cls" for DOS; "clear" for unix
42
43       do {
44          cout << "\n\nGuess a letter (case does"
45               << " not matter):  " << xword << "\n?";
46          char temp;
47          cin >> temp;  // letter guessed
48
49          if ( !isalpha( temp ) ) {  // validate for letters
50             cout << "\nLETTERS ONLY PLEASE\n";
51             continue; // next iteration of do/while
52          }
53
54          letters[ n ] = toupper( temp ); // convert to uppercase
55
56          system( "cls" );  // "cls" for DOS; "clear" for unix
57
58          // seach word for letters
59          i = words[ w ].begin(); // initialize iterator to beginning
60          found = false;          // assume letter is not found in word
61          offset = 0;             // initial position set to 0
62
63          // replace letter in mask string in all the necessary
64          // places. decrement count of characters masked such
65          // that we know when word is solved.
66          while ( i != words[ w ].end() ) {
67
68             if ( *i == letters[ n ] ) {
69                *( ix + offset ) = *i;
70                found = true;
71
72                if ( --xcount == 0 )
73                   solved = true;
74             }
75
76             ++i;
77             ++offset;
78          }
79
80          if ( !found )   // if the letter was not found
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
81             ++bodyCount; // increment our count of incorrect guesses.
82
83          // graphically draw the pieces of the body
84          // based upon the number of incorrect answers.
85          bool newline = false;
86          for ( int q = 1; q <= bodyCount; ++q ) {
87             if ( q == 1 || q == 5 || q == 7 ) {
88                newline = true;
89                cout << body[ 0 ];   // output space
90             }
91             else if ( q == 4 )
92                newline = true;
93             else
94                newline = false;
95
96             cout << body[ q ];
97
98             if ( newline )
99                cout << '\n';
100         }
101
102         // test to see if guesses were exceeded.
103         if ( bodyCount == 7 ) {
104            cout << "\n\n...GAME OVER...\n";
105            hung = true;
106            break;
107         }
108
109         // display all guesses. note we did not provide
110         // the code that would politely refuse duplicates.
111         cout << "\n\n\nYour guesses:\n";
112         for ( int k = 0; k <= n; k++ )
113            cout << setw( 2 ) << letters[ k ];
114
115         ++n;
116      } while ( !solved );
117
118      cout << "\n\nWord: " << words[ w ] << "\n\n";
119
120      if ( !hung )
121         cout << "\nCongratulations!!! You guessed "
122              << "my word.\n";
123
124      // if we are out of words, then time to exit loop
125      if ( ++w >= WORDS )
126         break;
127
128      cout << "Play again (yes/no)? ";
129      cin >> response;
130
131   } while ( !response.compare( "yes" ) );
132
133   cout << "\nThank you for playing hangman." << endl;
134
135   return 0;
136 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
Your guesses:
 M

Guess a letter (case does not matter):  M????
?a

Your guesses:
 M A
...
 o
/|\
 |
/


Your guesses:
 M A E I O U N K C W

Word: MACAW


Congratulations!!! You guessed my word.
Play again (yes/no)? n

Thank you for playing hangman.
```

19.14 Write a program that inputs a **string** and prints the **string** backwards. Convert all uppercase characters to lowercase and all lowercase characters to uppercase.

```
1  // Exercise 19.14 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <string>
10 using std::string;
11
12 #include <cctype>
13
14 int main()
15 {
16    string s;
17
18    cout << "Enter a string: ";
19    getline( cin, s, '\n' );
20
21    string::reverse_iterator r = s.rbegin();
22
23    while ( r != s.rend() ) {
24       *r = ( isupper( *r ) ? tolower( *r ): toupper( *r ) );
25       cout << *( r++ );
26    }
27
28    cout << endl;
29
30    return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}
```

```
Enter a string: The sinking of HMS Titanic
CINATIt smh FO GNIKNIS EHt
```

19.15 Write a program that uses the comparison capabilities introduced in this chapter to alphabetize a series of animal names. Only uppercase letters should be used for the comparisons.

```
// Exercise 19.15 Solution
// NOTE: The problem description should have asked
// the programmer to use a quicksort.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;

void output( const string const *, const int );
void quickSort( string [], int, int );

int main()
{
   string animals[] = { "Macaw", "Lion", "Tiger",
                        "Bear", "Toucan", "Zebra",
                        "Puma", "Cat", "Yak", "Boar",
                        "Fox", "Ferret", "Crocodile",
                        "Alligator", "Elk", "Ox",
                        "Horse", "Eagle", "Hawk" };

   cout << "before:";
   output( animals, 19 );

   quickSort( animals, 0, 19 );

   cout << "\nafter:";
   output( animals, 19 );

   return 0;
}

void output( const string * const ani, const int length )
{
   for ( int j = 0; j < length; ++j )
      cout << ( j % 10 ? ' ': '\n' ) << ani[ j ];

   cout << endl;
}

void quickSort( string a[], int first, int last )
{
   int partition( string [], int, int );
   int currentLocation;

   if ( first >= last )
      return;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
52
53       currentLocation = partition( a, first, last );
54       quickSort( a, first, currentLocation - 1 );
55       quickSort( a, currentLocation + 1, last );
56    }
57
58    int partition( string b[], int left, int right )
59    {
60       int pos = left;
61
62       while ( true ) {
63
64          while ( b[ pos ] <= b[ right ] && pos != right )
65             --right;
66
67          if ( pos == right )
68             return pos;
69
70          if ( b[ pos ] > b[ right ] ) {
71             b[ pos ].swap( b[ right ] );
72             pos = right;
73          }
74
75          while ( b[ left ] <= b[ pos ] && pos != left )
76             ++left;
77
78          if ( pos == left )
79             return pos;
80
81          if ( b[ left ] > b[ pos ] ) {
82             b[ pos ].swap( b[ left ] );
83             pos = left;
84          }
85       }
86    }
```

```
before:
Macaw Lion Tiger Bear Toucan Zebra Puma Cat Yak Boar
Fox Ferret Crocodile Alligator Elk Ox Horse Eagle Hawk

after:
Alligator Bear Boar Cat Crocodile Eagle Elk Ferret Fox Hawk
Horse Lion Macaw Ox Puma Tiger Toucan Yak Zebra
```

19.16 Write a program that creates a cryptogram out of a **string**. A cryptogram is a message or word where each letter is replaced with another letter. For example the **string**

The birds name was squawk

might be scrambled to form

xms kbypo zhqs fho obrhfu

Note that spaces are not scrambled. In this particular case, **'T'** was replaced with **'x'**, each **'a'** was replaced with **'h'**, etc. Uppercase letters and lowercase letters should be treated the same. Use techniques similar to those in Exercise 19.7.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
// Exercise 19.16 Solution
// Program creates a cryptogram from a string.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;
using std::getline;

#include <cstdlib>
#include <ctime>
#include <cctype>

void convertToLower( string::iterator,
                     string::iterator );

int main()
{
   string s, alpha = "ABCDEFGHIJKLMNOPQRSTUVWXYZ";
   string::iterator is, is2, is3;

   srand( time( 0 ) );
   cout << "Enter a string: ";
   getline( cin, s, '\n' ); // allow white space to be read

   is = s.begin();
   convertToLower( is, s.end() );
   string s2( s ); // instantiate s2

   is3 = s2.begin();

   do {
      is2 = is3;  // position location on string s2

      // do not change spaces
      if ( *is == ' ' ) {
         is++;
         continue;
      }

      int x = rand() % alpha.length(); // pick letter
      char c = alpha.at( x );  // get letter
      alpha.erase( x, 1 );     // remove picked letter

      // iterate along s2 doing replacement
      while ( is2 != s2.end() ) {
         if ( *is2 == *is )
            *is2 = c;

         ++is2;
      }

      ++is3;  // position to next element
      ++is;   // position to next element
   } while ( is != s.end() );

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   // change s2 to lowercase
   is3 = s2.begin();
   convertToLower( is3, s2.end() );

   // output strings
   cout << "Original string:      " << s
        << "\nCryptogram of string: " << s2 << endl;

   return 0;
}

void convertToLower( string::iterator i,
                     string::iterator e )
{
   while ( i != e ) {
      *i = tolower( *i );
      ++i;
   }
}
```

```
Enter a string: a cold hard rain fell
Original string:      a cold hard rain fell
Cryptogram of string: k yivu rkou okdj cmvv
```

19.17 Modify the previous exercise to allow a user to solve the cryptogram by inputting two characters. The first character specifies the letter in the cryptogram and the second letter specifies the user's guess. For example, if the user inputs **r g**, then the user is guessing that the letter **r** is really a **g**.

19.18 Write a program that inputs a sentence and counts the number of palindromes in the sentence. A palindrome is a word that reads the same backwards and forwards. For example, **"tree"** is not a palindrome but **"noon"** is.

19.19 Write a program that counts the total number of vowels in a sentence. Output the frequency of each vowel.

19.20 Write a program that inserts the characters **"*******"** in the exact middle of a **string**.

19.21 Write a program that erases the sequences **"by"** and **"BY"** from a **string**.

```
// Exercise 19.21 Solution
// Program erases "by" or "BY" from strings.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;

void deleteBy( string&, string );

int main()
{
   string s;

   cout << "Enter a word:";
   cin >> s;

   deleteBy( s, "by" );
   deleteBy( s, "BY" );

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   cout << s << endl;

   return 0;
}


void deleteBy( string& sRef, string z )
{
   int x = sRef.find( z );
   while ( x <= sRef.length() ) {
      sRef.erase( x, 2 );
      x = sRef.find( z );
   }
}
```

```
Enter a word:DERBY
DER
```

19.22 Write a program that inputs a line of text, replaces all punctuation marks with spaces and then uses the C-string library function **strtok** to tokenize the **string** into individual words.

19.23 Write a program that inputs a line of text and prints the text backwards. Use iterators in your solution.

```
// Exercise 19.23 Solution
// Program prints a string backwards.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;
using std::getline;

int main()
{
   string s;

   cout << "Enter a string: ";
   getline( cin, s, '\n' );
   string::reverse_iterator rb = s.rbegin();

   while ( rb != s.rend() ) {
      cout << *rb;
      ++rb;
   }

   cout << endl;

   return 0;
}
```

```
Enter a string: PRINT THIS BACKWARDS
SDRAWKCAB SIHT TNIRP
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

19.24 Write a recursive version of Exercise 19.23.

```
// Exercise 19.23 Solution
// Program recursively prints a string backwards.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;
using std::getline;

void printBackwards( const string::reverse_iterator,
                     string::reverse_iterator );

int main()
{
   string s;

   cout << "Enter a string: ";
   getline( cin, s );
   string::reverse_iterator r = s.rend();

   printBackwards( s.rbegin(), r - 1 );
   cout << endl;

   return 0;
}

void printBackwards( const string::reverse_iterator s,
                     string::reverse_iterator rb )
{
   if ( rb == s - 1 )
      return;

   printBackwards( s, rb - 1 );
   cout << *rb;
}
```

```
Enter a string: automobile
elibomotua
```

19.25 Write a program that demonstrates the use of the **`erase`** functions that take **`iterator`** arguments.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

19.26 Write a program that generates from the **`string "abcdefghijklmnopqrstuvwxyz{"`** the following:

```
                    a
                   bcb
                  cdedc
                 defgfed
                efghihgfe
               fghijkjihgf
              ghijklmlkjihg
             hijklmnonmlkjih
            ijklmnopqponmlkji
           jklmnopqrsrqponmlkj
          klmnopqrstutsrqponmlk
         lmnopqrstuvwvutsrqponml
        mnopqrstuvwxyxwvutsrqponm
       nopqrstuvwxyz{zyxwvutsrqpon
```

```
1  // Exercise 19.26 Solution
2  // Program prints a pyramid from a string.
3  #include <iostream>
4
5  using std::cout;
6  using std::endl;
7  using std::cin;
8  using std::ios;
9
10 #include <string>
11 using std::string;
12
13 int main()
14 {
15    string alpha = "abcdefghijklmnopqrstuvwxyz{";
16    string::const_iterator x = alpha.begin(), x2;
17
18    for ( int p = 1; p <= 14; ++p ) {
19       int w, count = 0;  // set to 0 each iteration
20
21       // output spaces
22       for ( int k = 13; k >= p; --k )
23          cout << ' ';
24
25       x2 = x;  // set starting point
26
27       // output first half of characters
28       for ( int c = 1; c <= p; ++c ) {
29          cout << *x2;
30          x2++;       // move forwards one letter
31          count++;    // keep count of iterations
32       }
33
34       // output back half of characters
35       for ( w = 1, x2 -= 2; w < count; ++w ) {
36          cout << *x2;
37          --x2;   // move backwards one letter
38       }
39
40       x++;   // next letter
41       cout << '\n';
42    }
43
44    return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
45 }
```

```
            a
           bcb
          cdedc
         defgfed
        efghihgfe
       fghijkjihgf
      ghijklmlkjihg
     hijklmnonmlkjih
    ijklmnopqponmlkji
   jklmnopqrsrqponmlkj
  klmnopqrstutsrqponmlk
 lmnopqrstuvwvutsrqponml
mnopqrstuvwxyxwvutsrqponm
nopqrstuvwxyz{zyxwvutsrqpon
```

19.27 In Exercise 19.7 we asked you to write a simple encryption algorithm. Write a program that will attempt to decrypt a "rot13" message using simple frequency substitution (assume you do not know the key). The most frequent letters in the encrypted phrase should be substituted with the most commonly used English letters (a, e, i, o, u, s, t, r, etc.). Write the possibilities to a file. What made the code breaking easy? How can the encryption mechanism be improved?

19.28 Write a version of the bubble sort routine that sorts **`string`**s. Use function **`swap`** in your solution.

```
1  // Exercise 19.28 Solution
2  #include <iostream>
3
4  using std::cout;
5  using std::endl;
6  using std::cin;
7  using std::ios;
8
9  #include <string>
10  using std::string;
11
12 void output( const string const *, const int );
13 void bubbleSort( string [], const int );
14
15 int main()
16 {
17    string animals[] = { "Macaw", "Lion", "Tiger",
18                         "Bear", "Toucan", "Zebra",
19                         "Puma", "Cat", "Yak", "Boar",
20                         "Fox", "Ferret", "Crocodile",
21                         "Alligator", "Elk", "Ox",
22                         "Horse", "Eagle", "Hawk" };
23
24    cout << "before:";
25    output( animals, 19 );
26
27    bubbleSort( animals, 19 );
28
29    cout << "\nafter:";
30    output( animals, 19 );
31
32    return 0;
33 }
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
34
35 void output( const string * const ani, const int length )
36 {
37    for ( int j = 0; j < length; ++j )
38       cout << ( j % 10 ? ' ': '\n' ) << ani[ j ];
39
40    cout << endl;
41 }
42
43 void bubbleSort( string mals[], const int length )
44 {
45   for ( int pass = 1; pass < length; ++pass )
46      for ( int comp = 0; comp < length - pass; ++comp )
47         if ( mals[ comp ] > mals[ comp + 1 ] )
48            mals[ comp ].swap( mals[ comp + 1 ] );
49 }
```

```
before:
Macaw Lion Tiger Bear Toucan Zebra Puma Cat Yak Boar
Fox Ferret Crocodile Alligator Elk Ox Horse Eagle Hawk

after:
Alligator Bear Boar Cat Crocodile Eagle Elk Ferret Fox Hawk
Horse Lion Macaw Ox Puma Tiger Toucan Yak Zebra
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

20

Standard Template Library (STL) Solutions

Solutions

20.14 Write a function template **palindrome** that takes as a parameter a **const vector** and returns **true** or **false** depending upon whether the **vector** does or does not read the same forwards as backwards (e.g., a **vector** containing 1, 2, 3, 2, 1 is a palindrome and a **vector** containing 1, 2, 3, 4 is not).

```
// Exercise 20.14 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::ios;

#include <vector>

template < class X >
bool palindrome( const std::vector< X > &vec )
{
   std::vector< X >::const_reverse_iterator r = vec.rbegin();
   std::vector< X >::const_iterator i = vec.begin();

   while ( r != vec.rend() && i != vec.end() )  {
      if ( *r != *i )
         return false;

      ++r;
      ++i;
   }

   return true;
}

template < class Y >
void printVector( const std::vector< Y > &vec )
{
   std::vector< Y >::const_iterator i;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
31
32       for ( i = vec.begin(); i != vec.end(); ++i )
33          cout << *i << ' ';
34    }
35
36    int main()
37    {
38       std::vector< int > iv;
39       std::vector< char > ic;
40       int x = 0;
41
42       for ( int i = 75; i >= 65; --i ) {
43          iv.push_back( i );
44          ic.push_back( static_cast< char > ( i + x ) );
45
46          if ( i <= 70 )
47             x += 2;
48       }
49
50       printVector( iv );
51       cout << ( palindrome( iv ) ? " is " : " is not " )
52            << "a palindrome\n";
53
54       printVector( ic );
55       cout << ( palindrome( ic ) ? " is " : " is not " )
56            << "a palindrome" << endl;
57
58       return 0;
59    }
```

```
75 74 73 72 71 70 69 68 67 66 65  is not a palindrome
K J I H G F G H I J K  is a palindrome
```

20.15 Modify the program of Fig. 20.29, the Sieve of Eratosthenes, so that if the number the user inputs into the program is not prime, the program displays the prime factors of the number. Remember that a prime number's factors are only 1 and the prime number itself. Every number that is not prime has a unique prime factorization. For example, consider the number 54. The factors of 54 are 2, 3, 3 and 3. When these values are multiplied together, the result is 54. For the number 54, the prime factors output should be 2 and 3.

```
1   // Exercise 20.15 Solution
2   #include <iostream>
3
4   using std::cout;
5   using std::endl;
6   using std::cin;
7   using std::ios;
8
9   #include <iomanip>
10
11  using std::setw;
12  using std::setprecision;
13  using std::setiosflags;
14
15  #include <bitset>
16
17  using std::bitset;
18
19  #include <cmath>
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
20
21 int main()
22 {
23    const int size = 1024;
24    int i, value, counter;
25    bitset< size > sieve;
26
27    sieve.flip();
28
29    // perform Sieve of Eratosthenes
30    int finalBit = sqrt( sieve.size() ) + 1;
31
32    for ( i = 2; i < finalBit; ++i )
33       if ( sieve.test( i ) )
34          for ( int j = 2 * i; j < size; j += i )
35             sieve.reset( j );
36
37    cout << "The prime numbers in the range 2 to 1023 are:\n";
38
39    for ( i = 2, counter = 0; i < size; ++i )
40       if ( sieve.test( i ) ) {
41          cout << setw( 5 ) << i;
42
43          if ( ++counter % 12 == 0 )
44             cout << '\n';
45       }
46
47    cout << endl;
48
49    // get a value from the user to determine if it is prime
50    cout << "\nEnter a value from 1 to 1023 (-1 to end): ";
51    cin >> value;
52
53    while ( value != -1 ) {
54       if ( sieve[ value ] )
55          cout << value << " is a prime number\n";
56       else {
57          cout << value << " is not a prime number\n"
58               << "prime factor(s): ";
59
60          bool print = true;
61
62          for ( int f = 2; f < size; )
63             if ( sieve.test( f ) && value % f == 0 ) {
64                if ( print )
65                   cout << f << ' '; // output factor
66
67                value /= f;       // modify value
68
69                if ( value <= 1 ) // time to stop
70                   break;
71
72                print = false;
73             }
74             else {
75                ++f;  // move to next prime
76                print = true;
77             }
78
79          cout << '\n';
80       }
81
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
      cout << "\nEnter a value from 2 to 1023 (-1 to end): ";
      cin >> value;
   }

   return 0;
}
```

```
The prime numbers in the range 2 to 1023 are:
    2    3    5    7   11   13   17   19   23   29   31   37
   41   43   47   53   59   61   67   71   73   79   83   89
   97  101  103  107  109  113  127  131  137  139  149  151
  157  163  167  173  179  181  191  193  197  199  211  223
  227  229  233  239  241  251  257  263  269  271  277  281
  283  293  307  311  313  317  331  337  347  349  353  359
  367  373  379  383  389  397  401  409  419  421  431  433
  439  443  449  457  461  463  467  479  487  491  499  503
  509  521  523  541  547  557  563  569  571  577  587  593
  599  601  607  613  617  619  631  641  643  647  653  659
  661  673  677  683  691  701  709  719  727  733  739  743
  751  757  761  769  773  787  797  809  811  821  823  827
  829  839  853  857  859  863  877  881  883  887  907  911
  919  929  937  941  947  953  967  971  977  983  991  997
 1009 1013 1019 1021

Enter a value from 1 to 1023 (-1 to end): 8
8 is not a prime number
prime factor(s): 2

Enter a value from 2 to 1023 (-1 to end): 444
444 is not a prime number
prime factor(s): 2 3 37

Enter a value from 2 to 1023 (-1 to end): -1
```

20.16 Modify Exercise 20.15 so that if the number the user inputs into the program is not prime, the program displays the prime factors of the number and the number of times that prime factor appears in the unique prime factorization. For example, the output for the number 54 should be **`The unique prime factorization of 54 is: 2 * 3 * 3 * 3`**

```
// Exercise 20.16 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <iomanip>

using std::setw;
using std::setprecision;
using std::setiosflags;

#include <bitset>

using std::bitset;

#include <cmath>


```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
int main()
{
   const int size = 1024;
   int i, value, counter;
   bitset< size > sieve;

   sieve.flip();

   // perform Sieve of Eratosthenes
   int finalBit = sqrt( sieve.size() ) + 1;

   for ( i = 2; i < finalBit; ++i )
      if ( sieve.test( i ) )
         for ( int j = 2 * i; j < size; j += i )
            sieve.reset( j );

   cout << "The prime numbers in the range 2 to 1023 are:\n";

   for ( i = 2, counter = 0; i < size; ++i )
      if ( sieve.test( i ) ) {
         cout << setw( 5 ) << i;

         if ( ++counter % 12 == 0 )
            cout << '\n';
      }

   cout << endl;

   // get a value from the user to determine if it is prime
   cout << "\nEnter a value from 1 to 1023 (-1 to end): ";
   cin >> value;

   while ( value != -1 ) {
      if ( sieve[ value ] )
         cout << value << " is a prime number\n";
      else {
         cout << value << " is not a prime number\n"
              << "prime factor(s): ";

         for ( int f = 2; f < size; )
            if ( sieve.test( f ) && value % f == 0 ) {
               cout << f << ' '; // output factor
               value /= f;       // modify value

               if ( value <= 1 ) // time to stop
                  break;
            }
            else
               ++f;  // move to next prime

         cout << '\n';
      }

      cout << "\nEnter a value from 2 to 1023 (-1 to end): ";
      cin >> value;
   }

   return 0;
}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
The prime numbers in the range 2 to 1023 are:
    2    3    5    7   11   13   17   19   23   29   31   37
   41   43   47   53   59   61   67   71   73   79   83   89
   97  101  103  107  109  113  127  131  137  139  149  151
  157  163  167  173  179  181  191  193  197  199  211  223
  227  229  233  239  241  251  257  263  269  271  277  281
  283  293  307  311  313  317  331  337  347  349  353  359
  367  373  379  383  389  397  401  409  419  421  431  433
  439  443  449  457  461  463  467  479  487  491  499  503
  509  521  523  541  547  557  563  569  571  577  587  593
  599  601  607  613  617  619  631  641  643  647  653  659
  661  673  677  683  691  701  709  719  727  733  739  743
  751  757  761  769  773  787  797  809  811  821  823  827
  829  839  853  857  859  863  877  881  883  887  907  911
  919  929  937  941  947  953  967  971  977  983  991  997
 1009 1013 1019 1021

Enter a value from 1 to 1023 (-1 to end): 99
99 is not a prime number
prime factor(s): 3 3 11

Enter a value from 2 to 1023 (-1 to end): 888
888 is not a prime number
prime factor(s): 2 2 2 3 37

Enter a value from 2 to 1023 (-1 to end): -1
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

21

Standard C++ Language Additions Solutions

Solutions

21.3 Fill in the blanks for each of the following:

a) Operator _____ is used to determine an object's type at run-time.

ANS: **`typeid`** or **`dynamic_cast`**

b) Keyword _____ specifies that a **`namespace`** or **`namespace`** member is being used.

ANS: **`using`**

c) Operator _____ is the operator keyword for logical OR.

ANS: **`or`**

d) Storage specifier _____ allows a member of a **`const`** object to be modified.

ANS: **`mutable`**

21.4 State which of the following are true and which are false. If a statement is false, explain why.

a) The validity of a **`static_cast`** operation is checked at compile-time.

ANS: True.

b) The validity of a **`dynamic_cast`** operation is checked at run-time.

ANS: True.

c) The name **`typeid`** is a keyword.

ANS: True.

d) Keyword **`explicit`** may be applied to constructors, member functions and data members.

ANS: False. Keyword **`explicit`** can only be used with constructors.

21.5 What does each expression evaluate to? (*Note:* Some expressions may generate errors; if so, say what the cause of the error is.)

a)
```
cout << false;
```
ANS: 0 is output.

b)
```
cout << ( bool b = 8 );
```
ANS: Error. Most compilers will not allow a variable to be declared in this manner. If the compiler permits the expression, 1 is output.

c)
```
cout << ( a = true );   // a is of type int
```
ANS: 1 is output.

d)
```
cout << ( *ptr + true && p );   // *ptr is 10 and p is 8.88
```
ANS: 1 is output.

e)
```
// *ptr is 0 and m is false
bool k = ( *ptr * 2 || ( true + 24 ) );
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

ANS: **k** is assigned 1.

f) **bool s = true + false;**

ANS: **true** is assigned to **s**.

g) **cout << boolalpha << false << setw(3) << true;**

ANS: **falsetrue** is output.

21.6 Write a **namespace Currency** which defines constant members **ONE**, **TWO**, **FIVE**, **TEN**, **TWENTY**, **FIFTY** and **HUNDRED**. Write two short programs that use **Currency**. One program should make all constants available and the other program should only make **FIVE** available.

```
// Exercise 21.6 Part A Solution
// Program makes namespace members accessible.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

namespace Currency {
   enum Money { ONE = 1, TWO, FIVE = 5, TEN = 10,
                TWENTY = 20, FIFTY = 50,
                HUNDRED = 100 };
}

int main()
{
   using namespace Currency;

   cout << "TWO's value is: " << TWO
        << "\nTEN's value is: " << TEN << endl;

   return 0;
}
```

```
TWO's value is: 2
TEN's value is: 10
```

```
// Exercise 21.6 Part B Solution
// Program makes one namespace member accessible.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

namespace Currency {
   enum Money { ONE = 1, TWO, FIVE = 5, TEN = 10,
                TWENTY = 20, FIFTY = 50,
                HUNDRED = 100 };
}

int main()
{
   using Currency::FIVE;

   cout << "FIVE's value is: " << FIVE << endl;

}
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
   return 0;
}
```

```
FIVE's value is: 5
```

21.7 Write a program that uses the **reinterpret_cast** operator to cast different pointer types to **int**. Do any conversions result in syntax errors?

```
// Exercise 21.7 Solution
// Program exercises reinterpret cast
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

#include <string>
using std::string;

int main()
{
   // declare variables
   int x;
   double d;
   float f;
   long l;
   short s;
   string z;
   char c;

   // declare and initialize pointers
   int *xPtr = &x;
   double *dPtr = &d;
   float *fPtr = &f;
   long *lPtr = &l;
   short *sPtr = &s;
   string *zPtr = &z;
   char *cPtr = &c;
   void *vPtr = &z;

   // test reinterpret_cast
   cout << "reinterpret_cast< int > ( xPtr ) = "
        << reinterpret_cast< int > ( xPtr )
        << "\nreinterpret_cast< int > ( dPtr ) = "
        << reinterpret_cast< int > ( dPtr )
        << "\nreinterpret_cast< int > ( fPtr ) = "
        << reinterpret_cast< int > ( fPtr ) ;

   cout << "\nreinterpret_cast< int > ( lPtr ) = "
        << reinterpret_cast< int > ( lPtr )
        << "\nreinterpret_cast< int > ( sPtr ) = "
        << reinterpret_cast< int > ( sPtr )
        << "\nreinterpret_cast< int > ( zPtr ) = "
        << reinterpret_cast< int > ( zPtr )
        << "\nreinterpret_cast< int > ( cPtr ) = "
        << reinterpret_cast< int > ( cPtr )
        << "\nreinterpret_cast< int > ( vPtr ) = "
        << reinterpret_cast< int > ( vPtr ) << endl;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
52
53       return 0;
54    }
```

```
reinterpret_cast< int > ( xPtr ) = 1245040
reinterpret_cast< int > ( dPtr ) = 1245032
reinterpret_cast< int > ( fPtr ) = 1245024
reinterpret_cast< int > ( lPtr ) = 1245020
reinterpret_cast< int > ( sPtr ) = 1245016
reinterpret_cast< int > ( zPtr ) = 1245000
reinterpret_cast< int > ( cPtr ) = 1244996
reinterpret_cast< int > ( vPtr ) = 1245000
```

21.8 Write a program that uses the **static_cast** operator to cast some fundamental data types to **int**. Does the compiler allow the casts to **int**?

```
1  // Exercise 21.8 Solution
2  // Program exercises static casting.
3  #include <iostream>
4
5  using std::cout;
6  using std::endl;
7  using std::cin;
8  using std::ios;
9
10 int main()
11 {
12    // declare variables
13    int x = 8;
14    double d = 22.22;
15    float f = 33.33f;  // floating point representation
16    long l = 888888;
17    short s = 32000;
18    unsigned u = 65000;
19    char c = 'U';   // ascii of 85
20    long double ld = 999999999.00;
21    unsigned char uc = 250;
22    unsigned long ul = 777777;
23    unsigned short us = 55555;
24
25    // test static_cast
26    cout << "static_cast< int > ( x ) = "
27         << static_cast< int > ( x )
28         << "\nstatic_cast< int > ( d ) = "
29         << static_cast< int > ( d )
30         << "\nstatic_cast< int > ( f ) = "
31         << static_cast< int > ( f );
32
33    cout << "\nstatic_cast< int > ( l ) = "
34         << static_cast< int > ( l )
35         << "\nstatic_cast< int > ( s ) = "
36         << static_cast< int > ( s )
37         << "\nstatic_cast< int > ( u ) = "
38         << static_cast< int > ( u );
39
40    cout << "\nstatic_cast< int > ( c ) = "
41         << static_cast< int > ( c )
42         << "\nstatic_cast< int > ( ld ) = "
43         << static_cast< int > ( ld )
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
         << "\nstatic_cast< int > ( uc ) = "
         << static_cast< int > ( uc );

   cout << "\nstatic_cast< int > ( ul ) = "
        << static_cast< int > ( ul )
        << "\nstatic_cast< int > ( us ) = "
        << static_cast< int > ( us ) << endl;

   return 0;
}
```

```
static_cast< int > ( x ) = 8
static_cast< int > ( d ) = 22
static_cast< int > ( f ) = 33
static_cast< int > ( l ) = 888888
static_cast< int > ( s ) = 32000
static_cast< int > ( u ) = 65000
static_cast< int > ( c ) = 85
static_cast< int > ( ld ) = 999999999
static_cast< int > ( uc ) = 250
static_cast< int > ( ul ) = 777777
static_cast< int > ( us ) = 55555
```

21.9 Write a program that demonstrates upcasting from a derived class to a base class. Use the **`static_cast`** operator to perform the upcast.

```
// Exercise 21.9 Solution
// Program upcasts with static_cast.
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

class Base {
public:
   void print() const { cout << "BASE"; }
};

class Derived : public Base {
public:
   void print() const { cout << "DERIVED"; }
};

int main()
{
   Base *bPtr;    // base class pointer
   Derived d, *dPtr;

   dPtr = &d;  // point to d

   // upcast from Derived * to Base *
   bPtr = static_cast< Base * > ( dPtr );
   bPtr -> print();  // invoke function print

   cout << endl;

   return 0;
```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
}
```

```
BASE
```

21.10 Write a program that creates an **explicit** constructor that takes two arguments. Does the compiler permit this? Remove **explicit** and attempt an implicit conversion. Does the compiler permit this?

21.11 What is the benefit of an **explicit** constructor?
ANS: An **explicit** constructor prevents arguments from being implicitly converted.

21.12 Write a program that creates a class containing two constructors. One constructor should take a single **int** argument. The second constructor should take one **char *** argument. Write a driver program that constructs several different objects, each object having a different type passed into the constructor. Do not use **explicit**. What happens? Now use **explicit** only for the constructor that takes one **int**. What happens?

21.13 Given the following **namespace**s, answer whether or not each statement is *true* or *false*. Explain any *false* answers.

```
#include <string>
namespace Misc {
   using namespace std;
   enum Countries { POLAND, SWITZERLAND, GERMANY,
                    AUSTRIA, CZECH_REPUBLIC };
   int kilometers;
   string s;

   namespace Temp {
      short y = 77;
      Car car;   // assume definition exists
   }
}

namespace ABC {
   using namespace Misc::Temp;
   void *function( void *, int );
}
```

a) Variable **y** is accessible within **namespace ABC**.
ANS: True.
b) Object **s** is accessible within **namespace Temp**.
ANS: True.
c) Constant **POLAND** is not accessible within **namespace Temp**.
ANS: False.
d) Constant **GERMANY** is accessible within **namespace ABC**.
ANS: False.
e) Function **function** is accessible to **namespace Temp**.
ANS: False.
f) Namespace **ABC** is accessible to **Misc**.
ANS: False.
g) Object **car** is accessible to **Misc**.
ANS: True.

21.14 Compare and contrast **mutable** and **const_cast**. Give at least one example of when one might be preferred over the other. Note: This exercise does not require any code to be written.

ANS: Operator **const_cast** is used to cast away **const** or **volatile** qualifications. Users of a class usually will not be aware of **const_cast** operations, because this implementation is typically hidden. Storage class specifier **mutable** allows a variable to be modified even if the object is **const**. Users of the class are not likely to be aware of a **mutable** member. Members that are **mutable** usually correspond to some "secret" implementation. **mutable** members are always modifiable, whereas **const_cast** operations are confined to the line where the cast is performed.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

21.15 Write a program that uses **const_cast** to modify a **const** variable. (*Hint:* Use a pointer in your solution to point to the **const** identifier.)

```
// Exercise 21.15 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

int main()
{
   const char c = 'A';
   const char *ptr = &c;

   cout << "c is " << *ptr;

   *const_cast< char * > ( ptr ) = 'Z';

   cout << "\nc is " << *ptr << endl;

   return 0;
}
```

```
c is A
c is Z
```

21.16 What problem does **virtual** base classes solve?

ANS: **virtual** base classes solve the problem of "diamond inheritance" where a derived class recieves duplicate subobjects from its base classes. With **virtual** base classes, only one copy of the subobject is inherited into the derived class (at the bottom of the diamond).

21.17 Write a program that uses **virtual** base classes. The class at the top of the hierarchy should provide a constructor that takes at least one argument (i.e., do not provide a default constructor). What challenges does this present for the inheritance hierarchy?

```
// Exercise 21.17 Solution
#include <iostream>

using std::cout;
using std::endl;
using std::cin;
using std::ios;

class Base {
public:
   Base( int n ) { num = n; }
   void print() const { cout << num; }
private:
   int num;
};

class D1 : virtual public Base {
public:
   D1(): Base( 3 ) {}
};

```

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

```
22  class D2 : virtual public Base {
23  public:
24     D2(): Base( 5 ) {}
25  };
26
27  class Multi : public D1, D2 {
28  public:
29     Multi( int a ): Base( a ) {}
30  };
31
32  int main()
33  {
34     Multi m( 9 );
35
36     m.print();
37
38     cout << endl;
39
40     return 0;
41  }
```

```
9
```

21.18 Find the error(s) in each of the following. When possible, explain how to correct each error.

a)
```
namespace Name {
      int x, y;
      mutable int z;
   };
```
ANS: A **mutable** member can only belong to a class.

b)
```
int integer = const_cast< int >( double );
```
ANS: Operator **const_cast** cannot be used to convert a **float** to an **int**. Either **static_cast** or **reinterpret_cast** should be used. Note: The keyword **double** in parentheses should be a floating-point value.

c)
```
namespace PCM( 111, "hello" );    // construct namespace
```
ANS: A **namespace** cannot be constructed, because it only defines a scope.

d)
```
explicit int x = 99;
```
ANS: Keyword **explicit** can only be applied to a constructor definition.

©2000. Deitel & Associates, Inc. and Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net

Appendix

C++ Multimedia Cyber Classroom: Solutions Provided on CD

This appendix contains the complete list of solutions provided on the *C++ Multimedia Cyber Classroom* CD-ROM. This will help instructors avoid the exercises for which students have solutions if they purchase the Cyber Classroom product. Note that key exercises like the Simpletron Simulator (Chapter 5) and the compiler (Chapter 15) are not provided on the CD.

Chapter 1: 1.11, 1.13, 1.16, 1.19, 1.21, 1.24, 1.25, 1.30, 1.31, 1.34, 1.37

Chapter 2: 2.14, 2.16, 2.18, 2.20, 2.24, 2.26, 2.29, 2.31, 2.33, 2.37a/b, 2.40, 2.43, 2.45, 2.48, 2.49, 2.54, 2.58, 2.60, 2.63

Chapter 3: 3.12, 3.13, 3.16, 3.18, 3.20, 3.22, 3.27, 3.29, 3.33, 3.35, 3.38, 3.40, 3.44, 3.48, 3.53, 3.56, 3.58

Chapter 4: 4.10, 4.12, 4.15, 4.20, 4.23, 4.29, 4.30, 4.33, 4.36, 4.38

Chapter 5: 5.9, 5.12, 5.22, 5.25, 5.26, 5.27, 5.30, 5.31, 5.33, 5.37, 5.42a/b/c, 5.46

Chapter 6: 6.5, 6.7, 6.8, 6.12, 6.16

Chapter 7: 7.7, 7.8

Chapter 8: 8.12, 8.15, 8.19

Chapter 9: 9.10, 9.12

Chapter 10: 10.6, 10.7, 10.14

Chapter 11: 11.7, 11.9, 11.10, 11.12, 11.15, 11.18

Chapter 12: 12.3, 12.7, 12.9, 12.14, 12.15, 12.19, 12.23

Chapter 13: 13.21, 13.27, 13.29, 13.31, 13.34, 13.42, 13.43

Chapter 14: 14.7, 14.12, 14.14

Chapter 15: 15.6, 15.8, 15.10, 15.11, 15.17, 15.20, 15.24

Chapter 16: 16.9, 16.12, 16.21, 16.22, 16.26, 16.30

Chapter 17: 17.4, 17.6, 17.8 ,17.10

Chapter 18: 18.3, 18.8, 18.10

Chapter 19: 19.4, 19.5, 19.8, 19.11, 19.12, 19.21, 19.23

Chapter 20: 20.15

Chapter 21: 21.3, 21.4, 21.7, 21.8, 21.13, 21.15

©2000. Deitel & Associates, Inc. & Prentice Hall. All Rights Reserved.

http://librosysolucionarios.net